MASTER
FILE COPY
BUREAU OF RECLAMATION
HYDRAULIC LABORATORY
NOT TO BE REMOVED FROM FILES

HYD 135

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION

- - -

HYDRAULIC LABORATORY REPORT NO. 135

- - -

HYDRAULIC MODEL STUDIES FOR THE REDESIGN OF THE 58-INCH BALANCED OUTLET VALVES, SHOSHONE DAM, SHOSHONE PROJECT - WYOMING

By

J. W. BALL

- - -

Denver, Colorado
Oct. 12, 1943

PREFACE

The redesign of the outlets at Shoshone Dam, to prevent severe damage by cavitation, was evolved from aerodynamic and hydraulic studies conducted in the hydraulic laboratory of the Bureau of Reclamation, Denver, Colorado, from October 1942 to April 1943.

The plans for the 1- to 8-2/3-scale hydraulic model of the balanced valve and for the alterations to the field structure were prepared in the mechanical section of the Bureau by B. H. Statts, Engineer, under the direction of P. A. Kinzie and W. C. Beatty, Senior Engineers. The laboratory investigation was conducted and this report prepared under the direction of J. E. Warnock, Senior Engineer in charge of the hydraulic laboratory. Credit is due D. J. Hebert, Associate Engineer, and Fred Locher, Assistant Engineer, who contributed to the study.

All laboratories of the Bureau of Reclamation in Denver, Colorado, are in the Materials, Testing and Control Division, under R. F. Blanks, Senior Engineer. All design work is under J. L. Savage, Chief Designing Engineer, and all work of the Bureau is directed by S. O. Harper, Chief Engineer. The activities of the Bureau are directed by H. W. Bashore, Commissioner.

CONTENTS

Section	Page
Preface	
List of Figures	
Introduction	
1. Bureau of Reclamation structures using the balanced outlet valve	1
2. Operating difficulties at the balanced-valve installations	1
3. Description and history of the Shoshone outlet works	5
Purpose of Model Studies	
4. Scope of tests	11
5. Summary of results	13
Interpretation of Results	
6. Transference of model results to prototype	14
Special Aerodynamic Studies	
7. Air versus water as a test medium	17
8. Comparison of hydraulic and thermodynamic equations for computing the flow of air through an orifice	20
Investigation of the Shoshone Outlet by Aerodynamic Model	
9. Description of 1 to 6 aerodynamic model	25
10. Study of proposed redesign outlet	27
11. Study of present outlet installation	30
Investigation of the Shoshone Outlet by Hydraulic Model	
12. Description of 1- to 8-2/3-scale hydraulic model	31
13. Hydraulic operation of the valve plunger - Proposed redesign outlet	33
14. Study of pressures in the proposed redesign outlet	33
15. Calibration of proposed redesign outlet	35
16. Hydraulic operation of valve plunger of present outlet installation	38
17. Study of pressures in the present outlet installation	38
18. Calibration of present outlet installation	43
19. Study of air vent size for the modified design outlet	43
20. Study of pressures in the modified design outlet	45
21. Calibration of modified design outlet	48
22. Status of repairs and alterations	48
23. Conclusions	50

LIST OF FIGURES

Figure		Page
1	Typical balanced valve installation	2
2	Lower outlet tunnel - Shoshone Dam	6
3	Original installation and 1931 revisions - Shoshone Dam 58-inch balanced valve outlets	8
4	Balanced valves - Lower outlet tunnel - Shoshone Dam	9
5	Balanced valves - Lower outlet tunnel - Shoshone Dam	10
6	Balanced valves - Lower outlet tunnel - Shoshone Dam	12
7	Discharge coefficients for small valves using air and water as fluids	18
8	Comparison of pressure factors - Proposed redesign outlet and present design outlet - Air versus water	21
9	Error introduced by using hydraulic instead of thermodynamic equation for obtaining flow of air through an intake orifice	24
10	Assembly and details of aerodynamic model	26
11	Pressures in valves and conduits - Aerodynamic model	29
12	Assembly and details of hydraulic model	32
13	Unbalanced closing thrust for present field installation - Proposed redesign and modified design	34
14	Pressures in valves and conduits (hydraulic model)	36
15	Coefficient and discharge curves - Proposed redesign outlets	37
16	Critical opening range - Various degrees of aeration - Present field installation	39
17	Coefficient and discharge curves - Present field installation	44
18	Air manifold pressures and air demand for model of modified design outlet	46
19	Installation assembly - Modified design - Removal of throat liner and air pipes and installation of air ducts	47
20	Coefficient and discharge curves - Modified design outlets	49

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION

Branch of Design and Construction
Engineering and Geological Control
and Research Division
Denver, Colorado
October 12, 1943

Laboratory Report No. 135
Hydraulic Laboratory
Compiled by: J. W. Ball

Reviewed by: J. E. Warnock

Subject: Model studies for the redesign of the 58-inch balanced valves - Shoshone outlet works, Shoshone Dam, Shoshone Project.

INTRODUCTION

1. Bureau of Reclamation structures using the balanced outlet valve. Several high-pressure outlet structures, designed by the Bureau of Reclamation in the early part of the twentieth century, employed the Ensign balanced valve for flow regulation. The outlets at the Roosevelt, Pathfinder, Arrowrock, Elephant Butte, and Shoshone Dams were typical installations (figure 1). The structures were similarly arranged, and, in all except the Shoshone and the Elephant Butte installations, the valves were placed on the upstream faces of the dams where they were subjected to full reservoir head. At Elephant Butte Dam the valves were placed in wells near the upstream face of the dam with the water reaching them through passages from the reservoir, while at Shoshone Dam they were placed in a tunnel bypassing the left end of the dam. Except for the 60-inch valves at Elephant Butte Dam, all were of the 58-inch size. Flow from the valves discharged into conduits downstream. Though the lengths of these conduits varied in the different structures and numerous details were dissimilar, the installations were sufficiently alike to possess similar operating characteristics, even to mechanical and physical difficulties. The mechanical problems were usually of a nature easily overcome by small changes in design, while those of a physical nature, mainly damage to the valve needles and discharge conduits by a destructive pitting action, were more troublesome. Although similar, the damage at the different structures varied in severity.

2. Operating difficulties at the balanced-valve installations. A report on Bureau of Reclamation installations, "High-Pressure Reservoir Outlets," by J. M. Gaylord and J. L. Savage, published in 1923, describes the outlet structures at the dams referred to in paragraph 1 in detail and recounts the difficulties experienced at each. The report directs attention to the seriousness of the damages resulting from operation of the outlets and discusses measures taken to repair or eliminate them.

The major difficulties encountered in all these structures, namely, the pitting by cavitation of the valve needles and discharge conduits, are discussed in detail in the report, which, on page 8, summarizes them as follows:



TYPICAL BALANCED VALVE INSTALLATION

FIGURE 1

"... Most of the difficulties with the outlets built by the Bureau of Reclamation can be attributed to the effect of vacuum in the conduits below the regulating devices. Generally the damage to the conduits has been more serious than to the valves, although under extreme conditions the valves have also been seriously damaged.

"In valves and conduits carrying water at high velocities an irregular pitting or cavitation of the lining is often observed. This appears first as a slight blemish on the surface, but if allowed to continue, the material becomes honeycombed to a considerable depth and is ultimately destroyed. The surface is not worn away by attrition or sandblast action, but is roughened as though attacked by chemical action."

The Gaylord-Savage report contains only limited discussion of the Shoshone installation since it was one of the last using the balanced-type valve and had not been required to release large quantities under high heads for prolonged periods; thus the destructive action had not developed to the critical stage. However, the nature and extent of the damage to this structure during subsequent seasonal operation are clearly depicted by the following excerpts concerning the other installations, taken from the report.

On page 59, extracts from a report dated October 19, 1913, from I. C. Harris to O. H. Ensign concerning the inspection of the 58-inch balanced-valve installation at the Roosevelt Dam, are, in part:

"We found the tire steel seats of the valves in bad shape, and the first section of the discharge pipe, which is bolted to the grillage frame, is also deteriorating very fast. ... The seats and pipes are going the same way rapidly. The seats are in bad shape. In some places they are cut so that the retaining ring for the packing is half gone. .... It does not act like ordinary wear, for the metal is 'honeycombed' in peculiar shapes."

On page 60, quotations from the project superintendent's report of July 29, 1915, concerning the inspection of the Roosevelt outlets state:

"... The first length of pipe next the valve is very seriously pitted, and I do not think they will stand up another year without relining. ..... Two years ago these pipes showed the same pitting. At that time the abrazed part was filled with Smooth-on, leaving a satisfactory surface on the inside of the pipe. The inspection showed that this pipe was in very good condition the first of this season, but they have been discharging under such a high head that this filling seems to have worn away, and the metal itself is beginning to disappear. Where the pipes discharge into the tunnel, the No. 3 valve (the farthest

from the vent in the north side) has commenced cutting into the concrete lining of the tunnel very seriously."

On pages 89 and 90, the damage by operation of the 58-inch balanced valves at the Pathfinder Dam in 1913 and 1914 is depicted as follows:

"... At the end of the season several yards of concrete were gone from the concrete conduits of Nos. 1, 4, 5, and 6. .... The damage to the concrete conduits indicated a shattering of the mass rather than an abrasion, as the concrete surfaces were jagged and rough. .... At the close of the season of 1913 it was not considered necessary to make any extensive repairs, the only work done being to plug up the holes in the concrete conduit with a rich concrete and fill the pitted places in the cast-iron linings with Smooth-on. .... After a few days operation of the balanced valves (1914) the patches in the concrete conduits began to go out, and by the end of the season there were large holes in the conduits, the damage being much greater than in the previous season, probably due to the increased use of the outlet. The damage to the cast-iron conduit linings had also increased. There were holes entirely through the 1-1/2-inch shell in many places, and the surface presented a spongy appearance. This damage was believed to be caused by the formation of a vacuum around the jet issuing from the valves."

The damage caused by the operation of the 58-inch balanced valves at Arrowrock Dam is described on page 112 in the following manner:

"... Annual inspections of the outlets have been made since the valves were first installed. The wear on the conduits was very slow at first, and the condition of the valves and conduits in the fall of 1920 was reported to be practically as good as when first installed. In the fall of 1921, however, the throat liners and the concrete conduits below the semisteel linings were found to be considerably worn. .... The pitting of the throat pieces had the peculiar, rough, honeycomb appearance noted in many of the other outlets of the service and was most severe immediately below the V-guides of the balanced valves."

While the foregoing extracts do not concern the outlets at Shoshone Dam, they vividly portray the operational difficulties encountered at this project since the report was made.

Although the theory of cavitation at the time the Gaylord-Savage report was written differs materially from that accepted by present-day hydraulicians, the condition described in the foregoing excerpts is still attributed to the same phenomenon. As was the case then, the most prac-

tical remedy to be applied to the discharge conduits is considered to be the introduction of air immediately below the regulating devices. The admission of air to the discharge conduit was employed in many instances during the first few years of operation, but, in view of air requirement tests made in recent years on both model and prototype structures, it is doubtful if the air supply in most cases was adequate. The location of the air inlets to the conduits is often more important than the size. Thus improper location might have been one of the main factors contributing toward failure of some of the early vent systems.

Streamlining the needle tips is considered the only practicable means of eliminating damage to this part of the valve. However, this damage could be reduced to a minimum by limiting the valve operation to noncritical openings.

3. Description and history of the Shoshone outlet works. In May 1915 two 58-inch Ensign balanced valves were installed in the lower outlet tunnel in the south canyon wall downstream from the Shoshone Dam, located in the Shoshone River about eight miles west of Cody, Wyoming (figure 2). Although this type of valve had necessitated considerable maintenance work in the installations at the Roosevelt and Pathfinder Dams, it was adopted because of the lack of a better design. The valves were furnished by Joshua Hendy Iron Works under an extension of specifications No. 266, contract No. 548, dated June 5, 1914, which was negotiated originally for 20 valves for Arrowrock Dam.

The valves were in operation but a few seasons when it became evident that seasonal maintenance similar to that required at the older installations would be required to keep the outlets in condition for releasing irrigation water. Pitting of the downstream faces of the valve needles and severe damage to the discharge conduit walls immediately below the valves occurred during extended periods of operation.

Attempts were made to prevent further damage by patching the pitted areas. A material known as Smooth-on proved unsatisfactory; so the cavities in the needles were filled by arc-welding various metals into them. With few exceptions the patches eroded more rapidly than the parent materials and were, at best, only temporary. The bond between the new and the parent materials was none too reliable and there was always the danger that the patches would be torn out, allowing the areas to become pitted to a greater depth, possibly rendering the release system useless until extensive repairs could be made.

It was realized that the pitting was an action accompanying subatmospheric pressures, but the cause was not completely understood. At first the pitting was believed to be a direct result of the making and breaking of the vacuum in the immediate vicinity and then considered the result of cavitation.

FIGURE 2



HD-135

An attempt was made in the winter of 1930-31 to relieve the condition at Shoshone Dam by admitting air through a system of vents to the conduits below the valves. The conduits were repaired by patching, then lengthened and provided with twenty-four 2-inch pipes and an 8-inch duct below each valve (figure 3). Each was constricted two inches in diameter at the downstream end. A marked increase in the intensity of the noise accompanying the discharging water resulted, and the experiment was considered unsuccessful. The 8-inch vents were closed with wooden plugs when investigations disclosed them to be the main source of the increased noise. Because of the apparent failure of the vent system, resort was made to the original method of maintenance and the valves used as little as possible, being closed whenever sufficient water to meet downstream requirements passed through a notch in the spillway crest. It was realized that the pitting was serious and that repairs by the usual method were inadequate; however, a more practical method of repair was not apparent at the time.

The development of lands downstream and recent requests to control floods to prevent damage to crops along the river necessitated the release of more water through the outlet valves. Damage to the outlet structure was increased severely by these requirements and the problem of maintenance became critical, so much so that an inspection of the outlet structure was requested by the field at the end of the 1942 season, after the valves had operated at near full capacity over an extended period to regulate flood flow. In response to this request an inspection was made by Engineer J. E. Warnock of the Denver office hydraulic laboratory on October 10 and 11, 1942. Incurred damages were reported in a memorandum to the Chief Engineer by Mr. Warnock, dated October 30, 1942, as follows:

> "The concrete for several feet downstream from the metal lining in each conduit has been severely eroded and the majority of the twenty-four 2-inch pipes embedded in the conduit during the revision in 1931 have been torn out and washed away in the eroded areas. The leakage around the west valve in the closed position is abnormal, indicating the seat packing is missing and a leakage through the needle face on the west valve has increased in size since it was noticed in December 1941.
>
> "In the east valve conduit, seven of the twenty-four 2-inch pipes are still intact, the remainder being torn out as shown in figures 4 and 5. The concrete is stripped out from 6 to 10 feet downstream from the metal liner on the left side (figure 4) 10 feet on the bottom, and 3 to 6 feet on the right side. In the bottom, the maximum depth of erosion was 11 inches below the original invert. The 8-inch pipe in the crown, which was plugged since the trials on its effectiveness in 1931, is still intact but the concrete is torn from around it. The semisteel conduit liner below the valve is severely pitted due to cavitation as

FIGURE 3



HYD-135

Figure 4

B. Remains of 8-inch air pipes in vent of 58-inch conduit looking downstream from east valve.



D. Severe pitting due to cavitation on conduit liner immediately below east 58-inch balanced valve.

A. Outlets of 58-inch balanced valves in South Canyon Wall.

C. Two-inch air pipes laid bare by destruction of concrete downstream from east 58-inch balanced valve.

Balanced Valves - Lower Outlet Tunnel - Shoshone Dam

Balanced Valves - Lower Outlet Tunnel - Shoshone Dam



A. Pitting on metal liner near seat on east 58-inch balanced valve.



B. Remains of 2-inch air pipes in east conduit. Extensive welding on needle face is apparent. End of metal liner cut off in 1931 when present installation was made.



C. Remains of 2-inch air pipes and 8-inch vent and deep hole cut in right side of 52-inch conduit downstream from west 58-inch balanced valve.



D. Face of needle in west 58-inch valve, showing extensive welding and exposure of air vent pipes downstream from metal liner.

Figure 5

shown in figure 4. The severity of the pitting can be judged by a study of figure 5.

"The east valve closes satisfactorily, but there is an extensive pitted area on the sealing ring at the invert. The face of the needle has pitted areas on which several kinds of metal have been tried, such as Wilson 17, Airco nickel, 25-12 stainless steel and Hobart cast iron. None has been satisfactory. Figures 5 and 6 show the extensive welding on the face of the needle. The areas of greatest pitting were directly below and above the respective valve guides. In those areas only 3/4 of an inch of the original two inches of parent metal remains.

"The conduit downstream from the west valve is not as extensively eroded as the east valve but it is more severe in spots. Twelve of the twenty-four 2-inch pipes are still intact, the others being ripped from their embedment. Figure 5 shows the remains of these pipes and a hole in the concrete approximately 15 inches deep. In this conduit, the plug in the outlet of the 8-inch air pipe had been torn out."

In view of the findings of this inspection and similar previous occurrences at this and other installations, hydraulic model tests were believed to be the only practicable means of solving the problem, and a comprehensive test program was instigated immediately to enable repairs before the start of the 1943 irrigation season.

PURPOSE OF MODEL STUDIES

4. Scope of tests. The main purpose of constructing a model of the Shoshone outlet valve was to evolve a means of minimizing or eliminating the severe damage to the outlet structure, thereby reducing the unreasonably high seasonal maintenance costs and removing the danger of a possible failure in the water release system. This problem involved an extensive study of the pressure distribution in the valves and discharge conduits, first, on a 1-to-6-scale aerodynamic model representing a one-eighth sector through a valve and discharge conduit, to expedite the redesign so that purchase of the necessary materials might be made in time for completing repairs before the 1943 irrigation season; and then on a 1-to-8-2/3-scale hydraulic model of one valve and discharge conduit to verify the air model tests, study refinements in design, and determine the adequacy of the aeration system in both the original and the proposed designs. In addition, studies concerning the actuating pressures for the valve plunger were made. After it was found impossible to obtain materials for the new needle tips and air intake manifolds required for the proposed changes, due to restrictions by the War Production Board, tests were conducted to ascertain valve-opening ranges of safe operation to minimize damage by limited operation until materials became available.

Figure 6

B. Extent of erosion in east valve of December 17, 1941, showing 2-inch pipe uncovered in crown and left side of conduit.

D. Extensive welding on face of needle and leakage through needle - December 17, 1941.



A. Severe pitting of metal liner and concrete in crown of conduit immediately downstream from west 58-inch balanced valve.

C. Two-inch pipe openings in conduit on December 17, 1941.

Balanced valves - Lower Outlet - Shoshone Dam

Also, a study was instigated to ascertain the possibility of obtaining acceptable conditions by minor alterations to the present field structure. The model studies included tests to determine the reliability of using air as a fluid instead of water and investigations to ascertain limitations and disadvantages of the aerodynamic model. In connection with these tests, an examination was made of hydraulic and aerodynamic equations to ascertain the error induced when using the simpler hydraulic equation in determining the flow of air through an orifice.

5. Summary of results. A satisfactory solution to the problem of relieving the severe subatmospheric pressures on the valve needles and discharge conduit walls to prevent the occurrence of the cavitation phenomenon, thereby eliminating the destructive pitting action to these parts of the structure, was obtained through the model studies subsequently described.

The model tests indicated that either of two methods might be employed to give satisfactory operation. One included major changes in the valve needles and air-supply system and required the purchase of heavy metal castings, while the other involved the streamlining of the sealing edge of the plunger, removal of a portion of the bronze sealing ring by chipping and grinding, removal of the throat liner, and revamping the air-supply system. Aeration equivalent to three 12-inch ducts was found to be adequate in this arrangement, but slightly more area was recommended as a factor of safety because of the limited information available on the air requirement in high-velocity flow.

The model tests showed that the present prototype vent system is inadequate to prevent cavitation for all except a very small range of valve opening. Insufficient air is supplied at openings between 23 and 70 percent, and some of the 2-inch vent pipes on the invert and crown become ineffective at openings above 85 percent, due to eddies forming immediately downstream from the V-guides. These conditions precluded safe operation of the present installation at ranges of valve opening other than 70 to 85 percent.

Model studies of the present field design indicated that the pitting of the prototype valve needles has been the result of operating at valve openings between 14 and 25 percent and that damage to the conduits resulted between 23 and 70 percent valve opening. No doubt the damage to the conduit at these openings rendered the air-supply system ineffective and aggravated the destructive action for larger valve openings. Discharge coefficients and capacity curves, which will assist the project operating personnel to determine the flow being released by the outlet works before and after the outlets have been revised, were prepared from the model data.

The use of an aerodynamic model constructed of molding plaster proved an extremely useful expedient in determining the feasibility of

the proposed redesign. The tests on aerodynamic models of the Shoshone valve and on two other small valves, using air and water as flow media, indicated that it is possible to obtain reliable pressure and calibration data from air models providing the tests are conducted carefully and proper interpretation of the results is made.

Investigation of hydraulic and thermodynamic equations for computing the quantity of air discharging from an orifice disclosed that the simpler hydraulic equations may be used without introducing noticeable errors only when the pressure differential through the orifice remains small.

INTERPRETATION OF RESULTS

6. Transference of model results to prototype. It is generally accepted by present-day hydraulicians that cavitation in a hydraulic passage occurs only when the pressure at some point within it approaches or reaches the vapor pressure of the flowing medium. In view of this concept, pressures equal to the vapor pressure of water would have to exist in the outlets at Shoshone Dam before damage to the valve needles and discharge conduits would result. Interpretation of the pressure data obtained from the Shoshone outlet models was based on this concept. Because the aerodynamic tests were limited to a small range in head by the lack of air-blower capacity, the following discussion is directed principally to hydraulic models using a liquid as a test medium.

Whether or not the pressure at various points in the prototype can be accurately predicted from model results depends on the conditions existing during the operation of the prototype. If the pressures at all points within the prototype are above the vapor pressure of the fluid, the problem is simple and the usual similitude transfer relations are valid. However, if the pressure at any point becomes equal to the vapor pressure of the fluid and cavitation is present, the problem is more involved and accurate evaluation of pressures may become impossible unless the model is enclosed in a partial vacuum such that a true scale exists between the vapor and artificial atmospheric pressures of the model and the vapor and natural atmospheric pressures at the prototype.

If, at the scale heads, over a certain operating range, neglecting the relative difference in model and prototype friction due to different Reynolds numbers, the scaled model pressures at any point within the valve do not extend below the vapor pressure of the prototype, the pressure at any corresponding point on the prototype may be found by the usual model-to-prototype transfer expression

$$P_p = N P_m$$

where P_p and P_m are prototype and model pressures, respectively, and

N is the model scale.

However, if the scaled value at any point extends below the vapor pressure, which condition indicates that cavitation will occur on the prototype, it is not possible by this method to predict the correct pressure for any point on the prototype other than that corresponding to the lowest existing on the model and possibly the pressure which controls the discharge, as that in the throat below the seal ring of the Shoshone valve. To assume all pressures with such scaled magnitudes to be equal to the vapor pressure on the prototype (the lowest obtainable prototype pressure) is erroneous, particularly if the values are for widely separated points and both are not of the same intensity. Pressures obtained in the usual manner for any point in the prototype other than the control or lowest pressure will therefore be too low, and the percent of error will be proportional to the deviation of the scaled pressure from the vapor pressure. When this condition obtains, another method must be employed to evaluate the prototype pressures.

If the model and prototype have definite controlling pressures at the same relative location and the boundary contour upstream from this point is sufficiently streamlined to preclude any change in the shape of the stream tubes due to changes in head, that is, the coefficient of discharge, C in the equation

$$Q = CA\sqrt{2gh_t}$$

remains constant, the ratio of the difference in head between any two points in this region to the total difference (upstream to control pressure) is constant and may be termed a pressure factor for predicting the prototype values at corresponding locations. This method of predicting prototype pressures is also applicable where the scaled model pressures are above the vapor pressure of the prototype as explained above, providing, of course, that the stream tubes do not change shape when the head is varied. If the model is to be used in determining the control pressures, care must be taken to construct the model to give the correct scaled values of these pressures. Otherwise the operating characteristics of the full-sized structure may or may not be indicated by the model.

Since the pressure surrounding the vena contracta of a jet issuing from a valve influences its discharge rate and hence the pressures at all points within it, the total change of head through a valve should be taken as that from the upstream side to the vena contracta. Neglecting the relative difference in model and prototype friction because of the difference in Reynolds number, the stream tubes will remain geometrically similar and the same relation will exist in the prototype as in the model. Thus, knowing the control pressure on the prototype and the pressure-drop ratios (pressure factors, F) for the points in question, it is possible to predict quite accurately the pressures at these points by using the expression

$$P_p = FD_t + P_c$$

where P_p is the prototype pressure in feet of water for the point in question; P_c is the prototype control pressure (negative and equal to the vapor pressure of water at the prototype when the scaled value equals or exceeds the vapor pressure) expressed in feet of water above or below atmosphere, as the case may be; D_t is the total head difference in feet of water on the prototype, from the upstream side of the valve to the control pressure; and F is the factor for the point in question obtained from the model tests.

Though the application of this method to cases where the stream tubes change appreciably with changes in head, as in the present field design of the Shoshone valve, is incorrect and the model should be enclosed in a partial vacuum to give true pressure values, it may be used to a limited extent. In regions where the boundary surface of the main flow does not change appreciably, the values obtained by this method will be reasonably correct while those obtained for regions where the boundary change is considerable, as at the downstream edge of a low-pressure zone where the main flow separates from the solid boundary, will be substantially in error.

As there were two low-pressure zones in the Shoshone outlet model where the scaled pressures for certain valve openings extended below the vapor pressure of water at the prototype structure, about -28 feet of water, the pressures in these regions were taken as criteria in establishing the critical range of opening for the present prototype valve. Since it was desired to determine the existence of cavitation pressures and not the pressure distribution in the valve or the location where damage would result from the collapse of the cavities, the transfer of model data to prototype was not so involved. However, both methods outlined above were used.

The transference of the aerodynamic model data to prototype was made by pressure factors in a manner similar to that described previously. However, two variations of the method were employed; one, using factors based on the head on the valve, above atmosphere, expressed above or below atmosphere as indicated by the piezometer, being considered; and the other, using factors based on the total head difference but expressed above the aeration (control) pressure, obtained from the tests on the 1-to 8-2/3-scale hydraulic model. Those expressed in percent of the head above atmosphere were adequate for determining the pressures in the proposed redesign, since the aeration of the valve was sufficient to make any change from the small negative pressures at the vena contracta negligible. This is not the case in designs like the present field structure where substantial subatmospheric pressures exist.

Pressures obtained in this manner, for instances where the scaled

values exceed the vapor pressure and are assumed to be equal to it, as in the redesign when unaerated, or in the present installation when partially aerated, are incorrect, the results being similar to those obtained in a hydraulic model when the familiar similitude relationship is used and the same assumption is made. Critical pressures are indicated over a greater portion of the outlet and for a wider range of valve opening than should be the case.

The second variation mentioned above was expected to give pressures more closely representing those for the prototype structure; thus it was employed in recomputing the prototype pressures in all aerodynamic tests after the aeration pressure had been determined by the hydraulic model. Excellent agreement resulted between the hydraulic and the aerodynamic data for the proposed redesign, but discrepancies of appreciable magnitude, attributed partly to different degrees of separation of the two flow media from the bounding surfaces and partly to limitations of the aerodynamic model, were noted for the present field design.

SPECIAL AERODYNAMIC STUDIES

7. Air versus water as a test medium. The failure of discharge data taken from 45-degree sector aerodynamic models to agree within the limits of experimental error with that obtained from complete hydraulic models, in tests made previous to those on the Shoshone outlets, led to investigations to ascertain whether the difference was introduced by using air as a flow medium or by using sector models of one scale for air and complete models of another scale for water. It was concluded from the tests described subsequently that errors are more likely to result from the latter.

Two small valves (figure 7), one a 3-inch hollow-jet and the other a 2.8-inch needle, for which the laboratory air-blower capacity was sufficient to give reliable measurements, were calibrated, first with air, then with water.

There was very poor agreement between the aerodynamic and the hydraulic data from both models when first compared. The discharge coefficients for each valve were inconsistent regardless of the medium employed, and the results obtained by using air were in poor agreement with those using water. Better comparison was obtained for the needle valve than for the hollow-jet valve.

In the initial tests on the needle valve, the exit edge of the valve was rounded similarly to the design used in the Boulder Dam outlets. Apparently this exit shape did not give constant degrees of separation at the rounded edge for a given head. It seemed that the flowing media would at times cling to the curved surface, causing a recovery of head which was not included in the reading of a piezometer located one pipe diameter upstream from the valve. At other times the flow would be

FIGURE 7



A. NEEDLE VALVE
3.200" DIA. INLET - 2.574" DIA. SHARP-EDGED EXIT



LEGEND
× = AIR
○ = WATER



B. HOLLOW-JET VALVE
3.023" DIA. INLET - 4.662" DIA. EXIT



DISCHARGE COEFFICIENTS FOR SMALL VALVES
USING AIR AND WATER AS FLUIDS

HYD-135

free from this action. To eliminate any variation from this source the valve exit was changed to the sharp-edged type. The results obtained from this arrangement were considered excellent when the discharge coefficients obtained by using the two flow media were plotted against Reynolds number based on the entrance diameter of the valve (figure 7A). The altered exit shape eliminated the abrupt changes in direction at the boundary of the flow passage and gave coefficients which did not vary with the head. Though the agreement between the aerodynamic and the hydraulic tests was good, the comparison would have been more convincing if the capacity of the air blower had been sufficient to obtain the same Reynolds number as for water, without necessitating the operation of the valve at extremely low heads where the accuracy of head and discharge measurements with water were questionable.

The first attempts to compare the aerodynamic and the hydraulic data from the 3-inch hollow-jet valve were discouraging, for the discharge coefficients obtained by using air, measuring the head on the valve with atmospheric pressure as a datum and not considering the negative pressure on the interior of the valve downstream from the outer edge of the needle, were considerably in excess of those obtained by using water. After investigating the pressures in the downstream portion of the valve near the outer edge of the needle where appreciable subatmospheric pressures were found to exist, the disagreement was attributed to improper measurement of the head on the valve in the aerodynamic tests. At times, the subatmospheric pressure in this region was almost equal to the pressure above atmosphere recorded by the piezometer located one pipe diameter upstream from the valve. The subatmospheric pressure at the same point was negligible when water was passing through the valve; thus the head obtained for the hydraulic t e s t had been nearer the correct value than that for the aerodynamic tests. When the head on the valve was taken as total change in pressure from a point one diameter upstream to one immediately downstream from the outer edge of the needle, very good agreement resulted between the aerodynamic and the hydraulic tests (figure 7B). These tests demonstrated that care must be exercised in conducting aerodynamic testing of hydraulic devices. Pressures bounding a jet of water may be insignificant, while those at the same boundary when air is used may represent a large percentage of the total head.

Also, it was concluded that the discharge characteristics as well as the pressure distribution for most hydraulic devices can be obtained from an aerodynamic model if the tests are made with extreme care and the results are properly interpreted. It would be practically impossible to predict pressures in the present Shoshone outlet structure by aerodynamic studies without first making hydraulic studies to obtain the aeration pressure or measuring the prototype pressures and using corresponding pressures on the model.

Even with the aeration pressures known, the problem would be a difficult one, for the abrupt changes in direction of the flow passage in this

design would cause separation of the main flow from the boundary and the amount of separation would vary with the head on the valve. The difference in the physical properties of air and water would also influence the separation; thus poor agreement between tests using air and those using water as a flow medium might be expected. The difference in pressure factors obtained at various valve openings on the aerodynamic and the hydraulic models of the present field design (figure 8B) might be explained in this manner.

The pressures for the proposed design of the Shoshone outlets could be predicted accurately from the air tests, since the subatmospheric pressure at the control was negligible and sufficient aeration to obtain comparable model pressures could be provided by removing the model discharge conduit. In addition, the positive control immediately downstream from the seat assures against any appreciable change in the stream tubes to effect the pressure factors (figure 8A).

8. Comparison of hydraulic and thermodynamic equations for computing the flow of air through an orifice. When aerodynamic tests for the redesign of the Shoshone outlet works were instigated, it was realized that numerous computations of the air discharge through a standard intake orifice would be required during the study. This work could be facilitated if the hydraulic equation $Q = CA\sqrt{2gh}$ was used instead of the more complex thermodynamic equation

$$Q = CA\sqrt{2g\frac{k}{k-1}\left[P_a V_a - P_{ds} V_{ds}\right]}\ .$$

Moreover, the information would be useful in future aerodynamic tests. A comprehensive comparison was made of the two equations, based on both the upstream and the downstream pressures.

The hydraulic equation for flow through an orifice when based on atmospheric pressure may be expressed as:

$$Q_{ha} = CA\sqrt{2g}\quad\sqrt{(P_a - P_d)V_a}$$

and the thermodynamic equation as:



A. PROPOSED REDESIGN



B. EXISTING INSTALLATION

SHOSHONE DAM

COMPARISON OF PRESSURE FACTORS
PROPOSED REDESIGN AND EXISTING OUTLET
AIR VERSUS WATER

$$Q_{ta} = CA\sqrt{2g}\sqrt{\frac{k}{k-1}\left[P_a V_a - P_d V_d\right]\frac{V_a}{V_d}}$$

where

Q_{ha} and Q_{ta} are quantities in cubic feet per second at atmospheric pressure, obtained by the hydraulic and thermodynamic equations;

C is the discharge coefficient of the orifice;

A is the area of the orifice in square feet;

g is the acceleration due to gravity;

P_d is the downstream pressure in pounds per square inch absolute;

V_a is specific volume of the fluid at atmospheric pressure, cubic feet per pound;

V_d is specific volume at the downstream pressure; and

k, 1.405 for air, is the constant for adiabatic change of state, a change in which the system neither receives nor gives out heat.

The comparison was accomplished through the use of the ratio $\frac{Q_{ha}}{Q_{ta}}$, since it expressed the discharge obtained by using the hydraulic formula in terms of the correct amount given by the thermodynamic relationship.

From the two equations,

$$\frac{Q_{ha}}{Q_{ta}} = \frac{\sqrt{(P_a - P_d)V_a}}{\sqrt{\frac{k}{k-1}\left[P_a V_a - P_d V_d\right]\frac{V_a}{V_d}}} \quad \text{.....(1)}$$

Squaring both sides,

$$\frac{Q_{ha}^2}{Q_{ta}^2} = \frac{(P_a - P_d)\,V_a}{\frac{k}{k-1}\left[P_a V_a - P_d V_d\right]\frac{V_a^2}{V_d^2}} \quad \ldots\ldots\ldots\ldots\ldots(2)$$

Using $P_1 V_1^k = P_2 V_2^k = P_3 V_3^k$ from which $V_a = V_d \left(\frac{P_d}{P_a}\right)^{\frac{1}{k}}$,

substituting for V_a in (2) and dividing both numerator and denominator by P_a, the ratio becomes

$$\frac{\left(\frac{P_d}{P_a}\right)^{\frac{1}{k}} - \left(\frac{P_d}{P_a}\right)^{\frac{k+1}{k}}}{\frac{k}{k-1}\left[\left(\frac{P_d}{P_a}\right)^{\frac{3}{k}} - \left(\frac{P_d}{P_a}\right)^{\frac{k+2}{k}}\right]}$$

Assuming values of $\frac{P_d}{P_a}$, the ratio of $\frac{Q_{ha}^2}{Q_{ta}^2}$ can be obtained and the square root gives $\frac{Q_{ha}}{Q_{ta}}$ from which the amount Q_{ha} is greater or smaller than Q_{ta} can be determined.

When the assumed values for $\frac{P_d}{P_a}$ of 0.85, 0.90, 0.95, 0.97, and 0.99 were used to obtain the ratio of quantities and the results were plotted (figure 9), it was found that substantial errors could be introduced by using the hydraulic formula; that these errors would always be positive when the hydraulic equation, based on either P_a or P_d, was used instead of the thermodynamic equation based on P_a; that they would be negative when the hydraulic equation, based on P_a, was used instead of the thermodynamic equation based on P_d; and that they would be positive when the hydraulic equation, based on P_d, was used instead of the thermodynamic one based on P_d.

FIGURE 9



Variation from quantity obtained by Thermodynamic equation based on specific volume at P_d.

Variation from quantity obtained by Thermodynamic equation based on specific volume at P_a.

ERROR INTRODUCED BY USING HYDRAULIC INSTEAD OF THERMODYNAMIC EQUATION FOR OBTAINING FLOW OF AIR THROUGH AN INTAKE ORIFICE

In all cases the error was substantial for large differences in head, decreasing to a negligible amount as the difference became small and the ratio $\frac{P_d}{P_a}$ approached unity.

From this inspection it was concluded that the hydraulic equation may not be used without introducing an appreciable error unless the head differential through the orifice is small. Since the difference did not exceed 0.35 feet in the Shoshone tests, giving a value of $\frac{P_d}{P_a}$ of 0.99, and the error did not exceed 0.5 percent, the hydraulic equation based on atmospheric pressure was used in all computations to obtain the discharge of air through the standard measuring orifice attached to the intake of the blower.

INVESTIGATION OF THE SHOSHONE OUTLET BY AERODYNAMIC MODEL

9. Description of 1 to 6 aerodynamic model. A model having a scale of 1 to 6, representing a one-eighth sector through the valve and discharge conduit and using air as a test medium, was employed as an expedient in determining the feasibility of proposed changes in the present field installation of the Shoshone outlet to enable the revision of the prototype structure before the start of the 1943 irrigation season. The model consisted of a section of 12-inch diameter metal pipe; a transition from 12-inch diameter to a 45-degree, 12-inch radius, circular segment; a 45-degree V-shaped channel with one side of fiber wood and the other of transparent plastic; and 45-degree plaster sectors of the valve and discharge conduit (figure 10A).

Metal templates fastened to a sliding frame fitted to the edge of a smooth flat-topped table were used in forming the sectors of the tunnel and discharge conduit. Mortar, prepared by sifting dry molding plaster into a vessel of water until it was just covered by the water and stirring it in a manner to prevent entrainment of air, was placed on the table as it reached the proper consistency, and the templates moved back and forth across it. The model segments were shaped through a process of building up and scraping off the surplus plaster as it obtained its set.

The valve needle, housing, and support ring were shaped by templates which were revolved about fixed centers. The plaster mortar was placed in V-troughs with sides shaped approximately to the section profiles of the needle and housing, and the templates, centered at the ends, swung back and forth across the troughs.

The section representing the valve support ring was constructed by a metal template revolved about a center on the flat-top table, shaping

HYD-135



SHOSHONE DAM
58-INCH BALANCED VALVE
MODEL STUDIES - 1 TO 6 SCALE
ASSEMBLY AND DETAILS OF AERODYNAMIC MODEL

FIGURE 10

the setting plaster as explained above.

Except for the movable needle, which was controlled by an L-shaped rod with one end inserted into a metal tube installed within the needle and the other passing upstream through a groove in the bottom of the transparent-sided V-channel, all the plaster segments were fitted and bolted to the channel. Airtight joints were obtained by placing a fillet of modeling clay along the seams inside the model. Air was supplied to the model by a 4-inch positive-displacement blower of limited capacity, a type not as well adapted to aerodynamic studies as the centrifugal or axial-flow type due to its almost constant output against various pressures.

Piezometers were installed by drilling small holes into the model segments and inserting small copper or brass tubes for attaching to a water manometer. The connections between the model and the metal tubes were made airtight by placing plaster mortar around them.

The needle actuating rod, mentioned previously, and a scale of valve openings etched on a strip of transparent plastic and cemented to the plastic wall of the V-channel, enabled accurate setting of the valve for testing.

A water manometer was used to measure the difference in piezometric pressures between the piezometer indicating the head on the valve and any particular piezometer. This procedure was followed to avoid reading extremely small differences in head when critical areas were being investigated, which would have been necessary had atmospheric pressure been selected as the datum.

10. Study of proposed redesign outlet. The usual procedure of first constructing and testing a model of the original design to ascertain its characteristics and then altering it to obtain improvement was not followed in the Shoshone outlet study, principally because the completion of the model tests on the proposed redesign was necessary if revision of the prototype was to be accomplished before the 1943 irrigation season. Insufficient time remained to complete both tests. Moreover, the reliability of results from air tests on a design of this type was questionable because of the magnitude of the subatmospheric pressures involved. The behavior of the model was expected to be similar to that experienced in tests conducted in the hydraulic laboratory on models of other valves. The pressures near the two zones where damage occurred on the prototype were certain to be subatmospheric sufficiently to indicate cavitation, a condition considered to exist when the scaled model pressures exceed the prototype vapor pressure.

Since subatmospheric pressures in outlet structures like those at Shoshone Dam become more severe as the head is increased, the pressures predicted from the model tests were based on the maximum prototype head,

approximately 220 feet. By using the pressure factors and conducting tests to determine the variation of the control pressure with head, it would be possible to ascertain those for greater or lesser heads. The present design is an undesirable one; so an extensive program to study the variation of the control pressure with the head did not seem justified when this investigation was made.

When the proposed redesign (figure 10C) was tested without aeration and the data transferred to prototype by using pressure factors based on the static head on the valve (above atmosphere) and expressed as being above or below atmosphere, the pressures near the seat on the support ring and in the discharge conduit were severely subatmospheric (as much as 42 percent of the static head on the valve), indicating that cavitation would result to the redesign if the outlets were improperly aerated (figure 11A).

With the aeration to be provided to the prototype valve by the air-intake manifold and an air duct of approximately six square feet of area, pressures near atmosphere were expected to exist in the space surrounding the jet immediately downstream of the valve; thus the conduit sector below the model valve (area 1, figure 10C) was removed to acquire representative conditions. Tests on this arrangement disclosed that the admission of air to the region immediately below the valve was still hampered by the downstream edge of the support ring. The aeration pressure was too low so the downstream portion of the support ring (area 2, figure 10C) was removed. The negative pressure at piezometer 9 (figure 11D) was negligible for all positions of the model plunger.

The clearance-ring pressure (piezometer 16, figure 11D) was equal to or greater than any on the needle, thus indicating no trouble in closing the valve from the wide-open position as had been the case with the present field installation.

Pressure measurements for the complete range of valve opening indicated satisfactory conditions at all points in the valve except on the needle and the support-ring surfaces (piezometer 8, figure 11D) immediately below the seat where a divergent passage formed as the valve neared the closed position. To alleviate this condition, the continuous curve below the valve seat on the support ring was replaced by a short tangent, diverging one-half of one degree from the needle angle (figure 10C). Complete pressure measurements, including those downstream from the V-guides, were again taken (figures 11E and F). Though the pressures remained subatmospheric for openings of less than six percent, they were not of a magnitude indicating cavitation (figure 11G), and the design was considered satisfactory insofar as the aerodynamic investigation was concerned. Construction drawings for the changes were prepared on the basis of these findings (appendix I), but it was believed advisable to corroborate the results by hydraulic tests on the 1-to 8-2/3-scale model before the plans were

FIGURE 11



A. UNAERATED WITH PRESSURE FACTORS BASED ON HEAD ABOVE ATMOSPHERIC PRESSURE
TEST 1

B. UNAERATED WITH PRESSURE FACTORS BASED ON TOTAL HEAD DIFFERENCE AND ABOVE CONTROL PRESSURE
TEST 1



PRESSURES IN PRESENT FIELD INSTALLATION



C. PRESSURES WITH CONTINUOUS CURVE BELOW VALVE SEAT AND NO AERATION
TEST 3

NOTE
Location of piezometers shown on figure 10.

D. PRESSURES WITH CONTINUOUS CURVE BELOW VALVE SEAT AND AERATION
TEST 5





E. PRESSURES BETWEEN SUPPORTING RIBS WITH TANGENT BELOW SEAT
TEST 7



F. PRESSURES DOWNSTREAM FROM V-GUIDE VANE WITH TANGENT BELOW SEAT
TEST 8

CONTINUOUS CURVE
TEST 5

TANGENT BELOW SEAT
TEST 7



G. COMPARISON OF PRESSURES BELOW VALVE SEAT
TEST 5 AND TEST 7

PRESSURES IN PROPOSED REDESIGN OUTLET

SHOSHONE DAM
58-INCH BALANCED VALVE
AERODYNAMIC MODEL STUDIES-1:6 SCALE
PRESSURES IN VALVES AND CONDUITS

adopted, particularly since aerodynamic testing was comparatively new to the laboratory personnel. The aerodynamic tests later proved to be a valuable expedient when almost identical results were obtained from the hydraulic model requiring many times as long to construct.

11. Study of present outlet installation. As the parts of the aerodynamic model were constructed easily, the model was altered to include the present field design, except for the aeration system and the downstream end of the discharge conduit (figure 10B). The model was not aerated, as the prototype aeration pressures were unknown. Moreover, it would have been difficult to aerate properly the aerodynamic model to represent these pressures had their correct magnitude been known. A high-velocity air jet transports the surrounding air more readily than a water jet of the same size and velocity; thus considerably more vent area is required to obtain corresponding pressures at the vena contracta of the air jet and the area could be determined only by trial and error. The model tests indicated lower pressures at all points than would have been the case had proper aeration been supplied, a fact later verified by the hydraulic model.

The pressures in the outlet were as anticipated, severely subatmospheric on the outer edge of the plunger needle and in the conduit downstream. The pressures (figure 11A), computed by using pressure factors based on the head above atmosphere on the valve and expressed as percentages of this differential above or below atmosphere, were found to deviate markedly from those obtained subsequently from the 1- to 8-2/3-scale hydraulic model. Apparently the prototype pressures could not be predicted accurately by this procedure. Examination disclosed that the results were similar to those obtained in hydraulic models when employing the usual model-to-prototype transfer expression discussed in section 6 of this memorandum, and assuming that all scaled values exceeding the vapor pressure were constant and equal to it. The pressures were recomputed using pressure factors based on the total change in head through the valve but expressed as a percentage of the change above the control pressure, obtained from the hydraulic tests (figure 11B). Better agreement was obtained between the aerodynamic and the hydraulic tests when the latter method was used.

The clearance-ring pressure at full opening was not subatmospheric, as had been expected, but was substantially positive, 190 feet of water or about 20 feet lower than the pressure in the tunnel immediately above the valves. Thus little would be gained to improve the operation of the valve at large openings by altering the clearance ring. Pressures on certain parts of the needle were greater than the clearance-ring pressure for openings above 95 percent, indicating that the valve could not be closed hydraulically by the clearance-ring pressure from these openings (figure 11A and B).

Although the present field design was not represented correctly by

the aerodynamic model, due to the short section of discharge conduit and improper aeration, the tests were believed to give some clue as to the conditions causing the damage to the outlet during the 1942 season. Moreover, the model represented the prototype structure as it existed before the discharge conduits were lengthened and the aeration systems added in 1931 and the pressures, no doubt, were closely representative of those causing considerable damage prior to that date. The tests were important in that they furnished useful information concerning aerodynamic tests and interpretation of the test data.

INVESTIGATION OF THE SHOSHONE OUTLET BY HYDRAULIC MODEL

12. Description of the 1- to 8-2/3-scale hydraulic model. The hydraulic model of one valve and discharge conduit of the Shoshone outlet works, constructed to verify the results from the 1- to 6-scale aerodynamic model, study refinements in design, investigate hydraulic operating characteristics of the valve, and determine the adequacy of the aeration system of the proposed redesign, present field installation, and a modified design, consisted of a high-pressure steel head tank, a 1- to 8-2/3-scale bronze model valve, and a section of transparent plastic pipe representing the discharge conduit of the east outlet (figure 12A).

The model valve was made geometrically similar to the prototype to permit a study of its operating characteristics when the plunger actuated hydraulically and to investigate methods of increasing the effectiveness of the actuating mechanism when the valve plunger neared the open position. Piezometers were located on the needle tip and in the conduit wall immediately downstream from the valve to determine whether or not the pressures in these regions were sufficiently subatmospheric to induce cavitation. The piezometers were not installed until manual controls were provided, since their presence would interfere with the hydraulic operation of the valve. Two needle tips and two throat sections were provided. The bronze needle tips, representing those of the proposed redesign and the present field design, were made removable to facilitate changing from one design to the other. The two throat sections, one representing the air intake manifold of the proposed redesign and the other the valve seal and throat liner of the present field design, were machined from bronze castings and were interchangeable. The section representing that of the present field structure was remachined for tests on the modified design.

The portion of the discharge conduit beyond the throat liner of the prototype valve was represented by a length of transparent plastic pipe to permit observation of the flow conditions in the conduit. Twenty-four 0.234-inch holes were provided in the wall of this pipe to represent the 2-inch vent pipes on the present prototype installation. Water and mercury manometers were used to record the piezometric pressures.

FIGURE 12



A. 6" MODEL ASSEMBLY



B. PROPOSED REDESIGN (DESIGN 3)



HALF SECTION A-A



C. PRESENT FIELD INSTALLATION (DESIGN 1) AND MODIFIED DESIGN (DESIGN 2)

SHOSHONE DAM
58-INCH BALANCED VALVE
MODEL STUDIES - 1:8 SCALE
ASSEMBLY AND DETAILS OF HYDRAULIC MODEL

HYD-135

13. Hydraulic operation of the valve plunger - Proposed redesign outlet. Tests pertaining to the hydraulic operation of the valve were made for the proposed redesign outlet (figure 12B) before piezometers were installed, since their presence would interfere with the free movement of the valve plunger, preventing a correct measurement of the friction. Moreover, they would have been of little value since the operation of the valve at definite openings would have been difficult and the data would have appeared inconsistent. The pressure tests were performed at the conclusion of this investigation after positive mechanical control of the plunger had been provided and exact openings could be established.

Initial operation of the model valve disclosed that an abnormally high pressure (about two feet of water on the model valve center line) was necessary to overcome the friction on the plunger; thus it could not be actuated by the clearance-ring pressure over much of the opening range. Changes in alinement of the V-guides reduced this value to about 0.65 foot of water. A pressure of 0.55 foot of water on the back area of the valve was required to keep the valve in motion during the closing cycle. This value was assumed to be that required to keep the plunger in motion during the opening cycle when thrust computations were made. With the reduced friction, the plunger of the proposed redesign could be operated hydraulically by pressure from the clearance ring, providing it was not allowed to reach the wide-open position. Investigation indicated that its failure to operate at this position resulted when a seal formed between the machined surfaces of the back of the plunger and the inside of the valve housing, preventing the pressure from the bull-ring cylinder from reaching the back end of the plunger. Once this seal was broken, the clearance-ring pressure was sufficient to actuate the valve at all openings. To ascertain if the clearance-ring pressure was sufficient to actuate the valve from the wide-open position and whether the failure to start closure was due entirely to the seal, grooves were cut through the bull-ring seat at the back of the plunger. The clearance-ring pressure was transmitted to the back end of the piston through these grooves and hydraulic operation of the valve was possible at all openings. Though it is not indicated by the thrust diagram (figure 13), the force to close from the wide-open position is available since the pressure on the needle surface below the V-guides at large valve openings is less than on the remaining portion of the needle and these were not considered in the thrust computations. The proposed redesign of the field structure should therefore be operable at all openings by the clearance-ring pressure, providing the friction between the valve plunger and bull-ring cylinder is not too great and a seal similar to that observed on the model does not form on the prototype.

14. Study of pressures in the proposed redesign outlet. After the operating characteristics of the proposed redesign outlet had been studied and the clearance-ring pressure found adequate for actuating the plunger when the friction between the plunger and the bull-ring cylinder was not too great and the seal back of the bull ring eliminated, the mechanical



SHOSHONE DAM

58-INCH BALANCED VALVE

AERODYNAMIC - 1:6 SCALE

AND HYDRAULIC MODEL STUDIES - 1:8⅔ SCALE

UNBALANCED CLOSING THRUST FOR EXISTING INSTALLATION, PROPOSED REDESIGN, AND MODIFIED DESIGN

operating mechanism and the piezometer connections were installed. The pressures on the needle and in the conduit were recorded for small openings as well as for each 10-percent increment of valve opening and the flow conditions for each noted.

The jet from the valve was reasonably smooth with the downstream end of the discharge conduit filling and operating under pressure when the plunger neared the wide-open position.

The pressures on the needle and the support ring were positive for all except very small openings where a slightly diverging passage formed downstream from the seat causing them to become negative. Though these pressures were substantial, they were not of a magnitude indicating cavitation and the design was considered satisfactory.

The pressure in the air-intake manifold was only slightly subatmospheric over the entire range of opening, indicating adequate aeration for the design.

A comparison of these pressures with those obtained from the aerodynamic model disclosed them to be in good agreement, even to the subatmospheric pressures existing at extremely small openings (figures 11E and 14C) and the design (appendix I) was recommended. Invitations for bids were prepared, but due to restrictions by the War Production Board, the decision was made to repair the outlets and continue the test program to ascertain the feasibility of minor alterations requiring a minimum of strategic materials.

15. Calibration of proposed redesign outlet. Prototype discharge curves (figure 15) for a single valve operating at different openings and for one valve fully open and the other at various openings was prepared from model calibration data. The curves show a substantial reduction in capacity from the present field installation - that for one valve at the maximum head being approximately 1,120 second-feet, a reduction of about 300 second-feet (figures 15 and 17).

Head losses from the reservoir to the valves were computed for various quantities flowing in the tunnel and were plotted below a horizontal line representing the reservoir elevation. The descending (loss) curve obtained in this manner represented the available head at the valves for the given reservoir elevation and various quantities of water passing through the tunnel. Plotted against discharge, the losses are the same regardless of reservoir elevation. Discharge curves for different openings of the valves, obtained from coefficients based on the total head on the valves, were plotted on the same graph. The discharge for a given valve opening and reservoir elevation is that shown by the intersection of these curves with the loss curve for the reservoir elevation. To determine the quantity of water being released when the reservoir elevation and the valve opening are known, enter the graph on the loss

FIGURE 14



A. PRESENT FIELD INSTALLATION WITH 24 VENTS (DESIGN 1)

B. MODIFIED DESIGN OF OUTLET (DESIGN 2)

C. PRESSURES BETWEEN SUPPORTING RIBS

D. PRESSURES DOWNSTREAM FROM V-GUIDE

REDESIGN OF OUTLET (DESIGN 3)

SHOSHONE DAM

58-INCH BALANCED VALVE
HYDRAULIC MODEL STUDIES - 1:8 SCALE
PRESSURES IN VALVES AND CONDUITS



DISCHARGE CURVES



COEFFICIENT CURVE

SHOSHONE DAM

58-INCH BALANCED VALVE

HYDRAULIC MODEL STUDIES-SCALE 1 TO 8⅔

COEFFICIENT AND DISCHARGE CURVES

PROPOSED REDESIGN OUTLETS

HYD-135

curve for the known reservoir level, follow along this curve until it intersects the discharge curve for the given valve opening, and read the discharge scale vertically below this intersection. The outlet discharge for intermediate reservoir elevations may be found by interpolation.

Comparison of the discharge coefficients (figure 15) shows slightly more capacity for the air model than for the hydraulic model. The reason for this difference was not ascertained, but it might have been the result of errors inherent in constructing and assembling the V-shapes used in the aerodynamic model or the operation of the aerodynamic model at smaller Reynolds numbers. A more elaborate model than that used in the air study would have assured correct shapes and no doubt would have resulted in closer agreement.

16. Hydraulic operation of the valve plunger of present outlet installation. The pressures tending to open the model valve were greater than the clearance-ring pressure over much of the surface area of the needle tip; thus for certain openings the force exerted on the end of the plunger by the clearance-ring pressure was insufficient to move it (figures 13 and 14A). This unfavorable pressure distribution existed over the range of valve opening from 95 to 100 percent and precluded successful closing of the valve by the clearance-ring pressure at these openings. This condition, which was also obtained from the aerodynamic tests, no doubt explains the difficulty experienced by the project in closing the prototype valves when they are operated near the wide-open position.

17. Study of pressures in the present outlet installation. As soon as it was learned that materials for the new needle tips and air-intake manifolds of the proposed redesign could not be purchased, an extensive test program was initiated to investigate; (1) the pressure conditions in the present design to ascertain the possibility of minimizing the pitting resulting from cavitation by limiting operation of the valves to noncritical openings, and (2) to attempt to discover a method for eliminating the destructive action in the present structure by minor modifications not involving the purchase of strategic war materials. Tests for comparison with those obtained from the aerodynamic model were also made.

There were two low-pressure zones in the Shoshone outlet model where the pressures at certain valve openings when transferred to the prototype reached the vapor pressure of water, about -28 feet of water. The pressures in these regions (zones A and B, figure 16) were taken as criteria in establishing the noncritical range of openings for the prototype valve. Since it was desired to determine the existence of cavitation pressures by these tests and not the pressure distribution in the valve or the location where damage would result from the collapse of the cavities, the transfer of model data to prototype was simplified. However, both methods outlined previously were used and the pressure distribution for the field conditions investigated.

FIGURE 16



CRITICAL VALVE OPENING RANGE
Based on -20 feet of water gage pressure



SHOSHONE DAM
58" BALANCED VALVE
HYDRAULIC MODEL STUDIES - SCALE 1:8⅔
CRITICAL OPENING RANGE - VARIOUS DEGREES OF AERATION
PRESENT FIELD INSTALLATION

J.W.B.-H.R.S.

It was intended to use prototype measurements made in 1931 as the control pressures for the model in predicting the minimum pressures in zone A of the prototype. However, when scaled to the prototype, the model pressures in the conduit below the valve were not in agreement, being nearer the vapor pressure for all valve openings than the prototype measurements, even with all twenty-four 0.234-inch holes open. To ascertain whether this discrepancy was due to a deficiency of air resulting from aeration by the holes instead of pipes of the same diameter and the scaled length, the capacities of the two systems were compared. Computed discharges, using the same pressure difference, showed the quantity of air from the holes to be about 1.42 times that for an equal number of pipes, and it was concluded that the difference was not due to the method of aerating the model. Damage to the field structure also indicated more severe pressures than those tabulated in a report from the Project Superintendent to the Chief Engineer, dated December 11, 1931, for with pressures of this magnitude cavitation could not have occurred unless aeration was not effective upstream from where the pipes entered the discharge conduit, and the model studies did not indicate this to be the case. The control pressures in zone B for predicting those in other parts of the prototype were therefore obtained from scaled model pressures. The minimum pressure in zone B for each 10-percent increment of the plunger travel and maximum head was obtained and scaled to prototype by the similitude relationship,

$$P_p = N P_m .$$

When values obtained in this manner were above the vapor pressure for the prototype (about -28 feet of water at Shoshone Dam), they were used directly. When below this value (numerically larger), they were assumed to remain constant at -28 feet of water. The pressure in zone B, obtained in this manner, was added to the static head for the corresponding valve opening to obtain the total head difference across the valve. The static head was obtained from a head loss-discharge curve computed for the outlet tunnel.

The minimum pressure in zone A on the needle for each valve opening was then obtained from the relationship

$$P_A = F D_t + P_B$$

Since the destructive action in the field structure indicated the subatmospheric pressures in the discharge conduit to be more severe than those measured on the prototype in 1931, and since the model pressures near the vents in the crown of the discharge conduit were not in agreement with them, it was considered necessary to determine the effect of different degrees of aeration on their magnitude. Pressures in the model were observed for four degrees of aeration which were obtained by varying the number of open supply ports (0.234-inch holes) to the discharge con-

duit. The model was operated with 24, 17, and 12 of these ports open and with all of them closed. As the supply ports were approximately 1.42 times as effective as pipes of scaled length and the same diameter, the aeration of the first three arrangements was equivalent to 34, 24, and 17 two-inch pipes.

Some criterion as to the allowable magnitude of the minimum pressures in zones A and B to prevent cavitation had to be adopted to establish the noncritical range of valve opening. A value of -20 feet of water, above which conditions were considered satisfactory, was chosen for these studies, and the ranges of valve opening subsequently referred to as critical are based on this value.

When the model pressures in the conduit and on the needle for heads representing approximately reservoir elevation 5364 and valve openings from 20 to 100 percent were transferred to prototype, as outlined in section six of this memorandum, the results indicated that the pressures in zones A and B would reach the vapor pressure of water over certain ranges of valve opening.

There was practically no change in the minimum pressures in zone A on the needle for the different degrees of aeration. Only by closing the vents or by reducing the number until the hydraulic jump moved upstream to cover them was it possible to discern any change in these pressures. Even so, the change was slight, increasing by two percent the upper limit of the critical range of valve opening for the needle, making it 14 to 27 percent instead of 14 to 25 percent (figure 16). Severe atmospheric pressures in zone A on the present prototype design may therefore be expected over a range of opening from 14 to 25 percent. Roughness of the surface in this zone might extend the critical range, but because of the rapid rate of increase in pressure at the upper limit, any change from this source is expected to be negligible. The different degrees of aeration produced no appreciable change in the critical range or the magnitude of the pressures in this zone. It was considered doubtful if they would become less critical even with complete aeration of zone B. Thus it might be impossible to operate the valve in this range without damaging the needle. Later tests on this valve, with minor modifications to the needle and with zone B well aerated, corroborated this belief.

Because of the peculiar expansion of the jet as it emerged from the end of the needle, the discharge conduit of the model flowed full after the valve plunger completed approximately 25 percent of its travel toward the open position. Zone B was aerated by air flowing upstream along the crown of the conduit until the needle reached this position and the pressures in this region were not severely subatmospheric for any of the degrees of aeration. As the valve approached 25 percent open and the flow of air from downstream was cut off, the pressures dropped rapidly, reaching the vapor pressure when scaled to the prototype.

When the aeration was equivalent to thirty-four 2-inch pipes, the model indicated that the minimum pressure in zone B would remain at the vapor pressure for a range of valve opening between 25 and 47 percent, then begin a gradual rise to about -8 feet of water when fully open (figure 16). With aeration equivalent to twenty-four 2-inch pipes, the range over which the pressure remained at -28 feet of water was extended to about 58 percent, from where it rose to approximately -12 feet of water at 100 percent open. The upper limit of this range was increased to approximately 76 percent when the aeration was reduced to the equivalent of seventeen 2-inch pipes. The pressure at 100-percent opening reached about -18 feet of water. Without aeration, the pressures remained at the vapor pressure through the range from 23 to 100 percent. From these results it was concluded that the critical range of valve opening for the conduit in the present field installation, aerated by twenty-four 2-inch pipes, based on -20 feet of water, gage pressure, will be from 23 to 70 percent open.

During operation of the model valve, with aeration representing the twenty-four 2-inch pipes, eddies were observed to form downstream from the V-guides as the valve approached 90 percent open, covering the ends of some of the air vents on the crown and the invert of the discharge conduit, thereby decreasing the amount of air reaching the throat of the discharge conduit and lowering the pressure in that region. Because of the danger of obtaining subatmospheric pressures of sufficient magnitude to cause the hydraulic jump in the pipe to move upstream and cover the remaining openings, thus producing cavitation pressures on the throat liner, it was recommended that the maximum valve opening for the present installation be limited to 85 percent.

The severe subatmospheric pressures prevalent in the model of the present outlet design (figure 14A) were attributed to inadequate aeration resulting principally from improper location of the delivery ends of the air ducts, but due also to the small aeration area. The peculiar shape of the jet beyond the end of the needle tip no doubt contributed to the severity of these pressures. The stream expanded abruptly to fill the conduit at approximately 25-percent opening, with the action continuing throughout the upper range.

The model tests indicated that operation of the Shoshone outlet valves to obtain any appreciable amount of flow regulation without damage to the discharge conduit was impractible and that damage to the needle could be avoided only by limiting the valve operation to openings greater than 25 percent.

To ascertain the reliability of the aerodynamic tests on this design, the discharge conduit of the hydraulic model was shortened to correspond to that studied on the air model. Comparison of the results from the two models revealed poorer agreement than had been anticipated, but the difference was not sufficient to prove the aerodynamic tests un-

reliable. Part of the disagreement was attributed to the variation in the physical properties of air and water which it is believed caused different degrees of separation from the solid boundary where abrupt changes in direction of flow took place, as at the outer edge of the plunger needle when in a partially open position.

18. Calibration of present outlet installation. The model was calibrated to ascertain the discharge characteristics of the present installation. Discharge coefficients for the various openings were obtained and capacity curves prepared in the same manner as for the proposed redesign outlet, for a single valve and for both valves operating simultaneously (figure 17). From these curves it may be shown that the rate of increase in discharge decreases materially as the valve plunger approaches the open position. With the reservoir at elevation 5360, the increase obtained by opening the valve from 80 to 90 percent is approximately 3-1/2 percent of that for full opening, while that obtained by opening the valve from 90 percent to full opening is about 2-1/2 percent. Thus, opening the valve another 10 percent in the upper region increases the discharge only slightly. That excellent agreement existed between the model and the prototype capacity is evident from a comparison of model and prototype discharges for both valves operating at 90 percent open (figure 17).

19. Study of air vent size for the modified outlet design. After it was found impossible to purchase materials for the revisions required in the proposed redesign outlet and pressure conditions for the present field design were found to be extremely critical for practically all ranges of valve opening, it was deemed advisable to continue the model studies in an attempt to discover a satisfactory means of alleviating the condition inducing cavitation by making minor modifications requiring a minimum of strategic materials. It was believed that a solution might result from alterations consisting of streamlining the exposed corners of the bronze sealing ring in the conduit and the seat ring on the valve plunger by chipping and grinding; removing part of the throat liner; and modifying the air-vent system to provide more air to the outlet conduit at the proper location. The model was modified to include these changes (figure 12C). Aeration, equivalent to three 12-inch air ducts on the prototype, was provided. It was intended that three openings would be installed; one at the crown and two at the sides of the conduit liner in the throat. However, the openings were inadvertently placed 45 degrees counterclockwise from the intended positions. Tests were conducted on this arrangement since it was believed that the jet of water discharging from the valve would be completely surrounded by air and thus the pressure within this region would be equalized. This was found to be the case for the smaller valve openings. However, eddies forming downstream from the V-guides divided the air space into two sections at the larger valve openings and the aeration of these two compartments was unequal. Since the piezometers in the throat were in the section supplied by one vent and the pressures in this region were satisfactory, the arrangement was not changed. Moreover, the top vent would have been ineffective because



DISCHARGE CURVES



COEFFICIENT CURVE

SHOSHONE DAM

58-INCH BALANCED VALVE

HYDRAULIC MODEL STUDIES - SCALE 1 TO 8 2/3

COEFFICIENT AND DISCHARGE CURVES

EXISTING INSTALLATION

JWB-HRS-REMCD

of the eddies below the V-guides had it been placed at the crown as planned. From the model tests on the present field design and this modified design, it was concluded that air vents to the balanced valve should not enter at the crown or invert of the conduit downstream from the V-guides.

Each of the vent openings on the model was provided with a 4-inch diameter by 1.5-foot long measuring section in which standard air-measuring orifices were installed for determining the air requirements and studying the air-duct size of the modified design outlet. Three orifice sizes were used - 1/2-, 1-, and 1-1/2-inch diameters.

Pressures in the throat and on the needle were investigated for the three orifice sizes to ascertain the adequacy of the contemplated vent system. The three vent openings, when fitted with the 1/2-, 1-, or 1-1/2-inch orifices were approximately equivalent to prototype openings of 7-1/2, 15, and 23 inches, diameter, respectively. The throat pressures were severely subatmospheric for the smallest orifice, but quite small for the other two. The maximum negative pressures in the model were -6.0, -1.4, and -0.8 feet of water for the small, medium, and large-size orifices, respectively. Air measurements for various valve openings and heads were made for all three orifices and a curve $\frac{Q_a}{Q_w}$ versus opening plotted (figure 18).

20. Study of pressures in the modified design. A peculiar condition was noted on the needle during the initial tests on this modified design. The pressure at piezometer 1 was recorded as being positive, a condition not existing before the seat ring on the plunger had been streamlined. Apparently the flow did not spring free from the edge as before and the boundary layer entered the groove, producing positive pressure at piezometer 1. Piezometers 2 and 3 showed severe subatmospheric pressure, indicating this to be the case. Removal of the 1/4- by 1-inch wedge (detail D, figure 19) from the needle corrected this condition, and, although subatmospheric pressures still existed, their magnitude was decreased.

The condition of not being able to close the valves at openings above 95 percent by the clearance-ring pressure still existed, but as pointed out previously, this is not critical since the last 10 percent of opening results in an increase of discharge of less than 3 percent of the total for full opening.

Pressures on the needle, using the 1-1/2-inch orifices, were found to be positive for all openings above 23 percent (figure 14B). For smaller openings the pressures on the surface of the needle near its outer edge were severely subatmospheric, indicating that cavitation would occur on the prototype. Since the critical pressure existed over such a small range of opening and damage to the needle could be eliminated by avoiding operations in this region, and since it was impossible to streamline the corner of the plunger sufficiently to relieve this condition without a

FIGURE 18



SHOSHONE DAM

58-INCH BALANCED VALVE

HYDRAULIC MODEL STUDIES - 1:8 2/3 SCALE

AIR MANIFOLD PRESSURES AND AIR DEMAND FOR MODEL OF MODIFIED DESIGN OUTLET


FIGURE 17
SECTION B-B
SECTION A-A
3/8" Plate air duct
Cut 2'-6" x 2'-0" opening in old concrete with 4" radius in corners
4" R
Grout
Air supply
FLOW
3/8" Plate liner
SECTION C-C
Remove throat liner
DETAIL "D"
DETAIL "E"
UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
SHOSHONE PROJECT - WYOMING
SHOSHONE DAM
38" BALANCED VALVE
INSTALLATION ASSEMBLY-MODIFIED DESIGN
REMOVAL OF THROAT LINER AND AIR PIPES
AND INSTALLATION OF AIR DUCTS
DRAWN
SUBMITTED
TRACED
RECOMMENDED
CHECKED
APPROVED
DENVER, COLORADO, MAY 7, 1943
26-D-1610

major revision of the valve, the modified outlet design was recommended for installation during the 1943-44 winter season. The modification prepared from the model findings, considering structural and construction difficulties, was prepared by the design section (figure 19).

21. Calibration of modified outlet design. The outlet was calibrated and a discharge graph for various reservoir elevations prepared for one valve discharging and for both valves discharging, one at 90 percent and the other at various openings (figure 20). The graph may be used to determine water releases after the modified design is placed in operation.

22. Status of repairs and alterations. The original proposal on the repairs of the 58-inch outlet valves was to so modify the design as to eliminate all of the adverse pressures which occur in the original design. Based on the results of the model studies in the hydraulic laboratory, a satisfactory design was prepared, and invitations for bids were requested.

Application for Priority Assistance on Form PD-20C was made to the War Production Board for the extension of preference rating AA-2x to obtain prompt delivery of the materials covered by these specifications. Inasmuch as the extension of the rating was permissible only on qualification by this office that the work was necessary to prevent an impending breakdown, the decision was made to proceed instead with the repair of the valves to permit operation during the season of 1943. The project was so informed by office letter of January 15, 1943, and the suggestion was made that the valves be inspected not later than July 15, 1943. If further repairs and revamping of the valves were then shown to be necessary, there would be sufficient time to obtain priority and to purchase and install these parts before the start of the 1944 irrigation season.

During the period from December 1942 to March 1943, necessary repairs were made on both valves, under the supervision of Master Mechanic Wm. J. Montgomery, to restore them to their condition prior to the irrigation season of 1942. The east valve was dismantled except for the base and cylinder; the poorly bonded weld metal on the valve piston shell or needle was removed and new metal placed, using 1/8-inch "Ferroweld" arc-welding electrode; and the valve parts were cleaned and repaired. The pitted areas on the piston shells and throat liners on both valves were filled by welding. The 2-inch air-vent pipes and reinforcing steel in both conduits torn out during the 1942 season were replaced, and the conduits relined with concrete by pressure grouting. The damaged packing-ring seat in the west valve was replaced by a new one. The valves were under pressure and ready for operation on March 26. Late in March work was started on filling the notch in the spillway. Master Mechanic Wm. J. Montgomery was on the job from December 30, 1942, to February 19, 1943.

Subsequent to the decision to repair rather than revise the valves

FIGURE 20



DISCHARGE CURVES



COEFFICIENT CURVE

SHOSHONE DAM

58-INCH BALANCED VALVE

HYDRAULIC MODEL STUDIES - SCALE 1 TO 8⅔

COEFFICIENT AND DISCHARGE CURVES

MODIFIED DESIGN OUTLETS

HYD-135

during the winter of 1942-43, laboratory tests were made on a model of the original design of the valve. During these studies a partial revision was developed which would require much less critical material and would permit the operation of the valve from 23 to 95 percent open without the adverse subatmospheric pressures now so prevalent. This partial revision (drawing No. 26-D-1610, figure 19) entails the removal of the throat liner and the downstream end of the conduit liner; streamlining the exposed corner of the bronze sealing ring by chipping and grinding; streamlining of the exposed corner of the bronze seat on the piston; and the provision of an adequate air conduit which can later be incorporated in the complete revision shown in specifications No. 1681-D.

By letter of August 10, 1943, the project superintendent gave the following report on the condition of the valves and conduits:

> "The 58" balanced valves and their conduits were inspected on August 7. The west valve has been operated 35 days this season at 0.75 opening. The valve itself shows no visible evidence of additional pitting. A minimum amount of pitting has occurred, however, in the extreme top of the discharge conduit. A square foot or so of concrete is gone where it covered the capped 8" air vent and lapped over onto the pitted discharge liner. This exposes part of the capped 8" air vent. Then at odd intervals of about one foot apart are pitted areas not over two inches deep which extend out the discharge conduit for about ten feet. None of the 2-inch air vent pipes are exposed. Except for the spotted pitting in the top of the discharge conduit, no other damage to the concrete lining can be observed. It is planned to patch the small damaged areas before the valve is again put in operation.
>
> "The east valve has been operated for only 8½ hours this season at 0.30 opening. The plunger needle on this valve and the concrete lining in the discharge tunnel look the same as when repair work was completed last spring.
>
> "The opening of the west valve so far this season has been in the non-critical range as pointed out in the Chief Engineer's letter of April 17, 1943. It appears that it will soon be necessary to use one of the valves for the release of water from the reservoir and it will probably be necessary to operate it in the critical range if stored water is to be conserved for the generation of power this winter. It is therefore probable that the greatest amount of damage to the discharge conduits, etc., this season will occur during the remainder of the irrigation season."

23. Conclusions. From the model studies of the Shoshone outlets, it was concluded that the damage to the structure in past years had

resulted from cavitation, a phenomenon which takes place when the pressure at some point within a flow passage reaches the vapor pressure of the flowing medium. The presence of cavitation pressures in the prototype, a condition producing the damage observed on the field structure, was indicated by the subatmospheric pressures on the model whose scaled values were equal to or lower than the vapor pressure for the prototype.

It would be difficult to operate the present valves to obtain an appreciable amount of regulation without damaging the outlet structure. Pitting of the needles is expected when the valves operate between 14 and 25 percent open and in the conduit between 23 and 70 percent open; also, there will be danger at openings greater than 85 percent, since the ends of several of the 2-inch air-supply pipes will be covered by eddies forming below the V-guides. Little damage to the present installation should result when the valves are operated between 70 and 85 percent open.

The severe subatmospheric pressures on the needles at small valve openings can be reduced by streamlining the outer corner of the seat ring on the plunger, but they cannot be eliminated without a major revision similar to that included in the proposed redesign outlet.

The present aeration system is inadequate, as well as improperly located, to relieve the pressures inducing cavitation in the present installation. The 8-inch vents, which have been plugged in previous years, would tend to relieve the critical pressures in the conduit but would be inadequate to eliminate them, even though they do not become covered by the hydraulic jump in the conduit or by eddies downstream from the V-guides. If they were properly located, the additional air reaching the critical pressure zone in the throat would offer considerable relief.

Should the friction (by restriction or roughness) in the downstream portion of the discharge conduit be relatively greater on the prototype than on the model and cause the hydraulic jump to move upstream over the 2-inch vents as the valve plunger approaches the wide-open position, severe subatmospheric conditions inducing cavitation and consequently destructive pitting would result.

The damage to the needle during the 1942 season was the result of operating the valves from 22 to 48 percent open during the last few weeks of the season. The damage to the conduits first resulted from operating between 46 and 52 percent during the first one and one-half months and was then aggravated by operating at 90 percent open after the initial damage had reduced the effectiveness of the 2-inch vent pipes.

The presence of pressures on the valve needles, which exceed the clearance-ring pressure at valve openings in excess of 95 percent, prevent closure of the valves by this pressure when the plungers are in

this region.

Though the subatmospheric pressures tend to lessen as the head on the valve decreases, a substantial reduction would be necessary to alleviate the damaging action on the present field design.

From the model calibration data on the present field installation it was found that the increase in flow is small compared with the increase in the valve plunger movement when the plunger operates near full opening, the increase in discharge being 3-1/2 percent when open between 80 and 90 percent and 2-1/2 percent when open between 90 and 100 percent. Since 97-1/2 percent of the maximum discharge through the valves can be obtained at 90 percent opening, it is not important that the valves operate beyond this point, particularly since it is difficult to close the valves when this opening is exceeded.

Damage by cavitation on the valve needles and discharge conduits can be entirely eliminated by revising the needle tips, the valve seat, the conduit throat, and the aeration system (appendix I). This solution would be applicable to similar outlet installations. Maintenance cost would be reduced to a minimum by this revision and valves could be operated at any desired opening without the fear of damage due to subatmospheric pressures. The aeration system for the proposed redesign is satisfactory, probably over-adequate. The outlet capacity, however, will be substantially reduced, and consideration should be given to this fact when future revisions are planned.

Damage to the conduit can be eliminated in the present design by streamlining the exposed edge of the bronze sealing ring, removing the throat liner, and providing an adequate air-supply system at the location as shown on figure 19. However, operation of this modified design at openings smaller than 23 percent would have to be avoided to prevent damage to the needle.

Openings into an area of low pressure, such as those to the throat of the Shoshone outlet, should not be placed too near the surface of the flowing water, for this condition constricts the flow of air and prevents complete aeration of the jet. For example, the same size opening into the outlet throat will provide more aeration when the throat liner is removed. An air-supply duct equivalent to three 12-inch diameter openings into the throat of the outlet should provide ample quantities of air at all valve openings in the modified design. The modified outlet is likely to be noisy since the air taken into the conduit via the aeration system will be under pressure when released at the conduit exit, and explosive reports may accompany its expansion.

Transference of model pressures to prototype, by assuming all scaled values exceeding the vapor pressure to be equal to it, is incorrect. The pressure distribution, when such conditions exist, does not correctly

represent that of the prototype, for all pressures obtained in this manner (except the control pressure) are too low. It is not possible to predict accurately the pressure distribution in cases where the scaled values exceed vapor pressure and the stream tubes change with the head unless the model is enclosed in a partial vacuum to give the proper relation between the artificial atmospheric pressure of the model and the natural atmospheric pressure of the prototype.

It is difficult, and in many cases impossible, to determine control pressures in a hydraulic structure from air tests alone. This means that the control pressures must be known or must be determined by computation or from a carefully constructed hydraulic model before the prototype pressure distribution can be predicted accurately.

Aerodynamic models are extremely useful as an expedient in testing preliminary designs of hydraulic devices with closed-conduit flow. The models can be constructed easily and quickly and the tests can be conducted rapidly and without the cumbersome piezometer boards and connections. Calibration data as well as pressure data may be obtained, providing extreme care is taken to assure that the model is being tested under comparable conditions. It is necessary to make radical alterations to the aerodynamic model in some cases to attain the required effect. The removal of the downstream portion of the model of the proposed redesign outlet to give desired pressures is an example.

The positive-displacement rotary blower used in the aerodynamic tests had insufficient capacity and was too inflexible to permit extensive tests by this method. This type of blower is not as well adapted to aerodynamic studies as the centrifugal or axial-flow types which deliver large quantities at low pressures. The 4-inch positive-type blower in the laboratory is inadequate for all except small scale models and larger scale sector models which are difficult to construct and operate.

When the difference in head across a standard air-measuring orifice is small, the hydraulic equation $Q = CA\sqrt{2gh}$ may be used, since the error introduced is negligible.

- - -

APPENDIX I



SUGGESTED METHOD OF ASSEMBLY

1. Remove valve cover, piston shell and old valve seat in base, leaving base and valve cylinder undisturbed
2. Chip out old discharge pipe and concrete as shown on drawings 26-D-1647 and 1648
3. a. Insert conduit liner 4 thru opening in base.
   b. Assemble air inlet manifold 1 inside conduit opening and bolt securely to base.
   c. Insert manifold shell 6 and weld to air inlet manifold 1
   d. Assemble drain pipe 8 and weld to manifold shell 6.
   e. Weld manifold segments 7 to manifold shell 6 and conduit liner 4
   f. Cut openings in manifold shell 6 as shown on Dwg. 26-D-1647 and weld air hoods 9R and 9L to manifold shell 6
   g. Place 3/4" bolts 17 with a coating of heavy grease on threads, in manifold shell 6.
   h. Insert manifold liner 5 and weld in place.
   i. Needle seat 2 can then be fitted to base and bolted.
   j. Complete pouring of first stage concrete.
   k. Complete second stage concrete and all grouting.
   l. Remove bolts 17 thru openings in air inlet manifold 1.

NOTE

Parts 1 to 17 inclusive required to complete this repair.

FIGURE 2


SEC. B-B
54" Dia
12-1¼" Drills thru. equally spaced. spotface 3¼" F.S. for 12
72" B.C.
Three segments Match mark
4-1⅛" Drills thru. spotface 2¼" F.S. for 11.
76½" Dia
73⅛" Turn
58" Dia
52" Dia
53¼" Bore
56" Dia
74¾" Dia
73⅛" Turn
⅜" Chamfer
SECTION A-A
12-4¾ x ¼ x 0'-6" Pls Grind to sound metal and weld plate over each opening
3-1½" Std pipe taps for 15
1" R
Turned groove for 16
DETAIL E
1⅛" C.B.
SEC. D-D
3'-7¼"
3'-6"
5 Ls 3x2x¼
5 1⅛" Dia Max
52" Dia
53¼" Dia
1½" Std pipe tap for 15
Pl. ¾
Note: Not more than two longitudinal welds are desired in ¾" plate.
CONDUIT LINER
STEEL
ONE REQUIRED - MARK 1648-4
Pl. ¾
2'-6"
52" Dia
53¼" Dia
MANIFOLD LINER
STEEL
ONE REQUIRED - MARK 1648-5
AIR INLET MANIFOLD
CAST STEEL
ONE REQUIRED - MARK 1648-1
FIELD NOTE
Install seat with this ℄ 20° from vertical and cut new 1¼" taps in Base for 12.
12-1 1/16" Drills thru. spaced as shown and counterbore as shown in Section C-C for 12.
72" B.C.
65" Dia
Three segments Match mark
9 Ribs equally spaced
19.489"
20.250" R.
38.750"
66¼" Turn
56.944" Dia
54" Dia
56¼" Dia
58" Turn
65¼"
1" Chamfer
SEC. C-C
60-1 1/16" Drills thru. equally spaced and counterbore as shown in Section D-D for 13
59¼" B.C.
1" Drill for drain
NEEDLE SEAT
CAST MANGANESE BRONZE
ONE REQUIRED - MARK 1648-2
NOTE
* Indicates nominal dimension. Exact figure to be supplied later from field measurements.
3'-6"
3'-0½"
2'-5⅞"
3.175"
39¼" R.
35" R.
5.500" R.
62¼" Turn
56¼" C.B.
55⅛" Dia
1" Chamfer
50" Dia
Cast smooth
Finish this surface smooth and run out on cast surface without ridge.
NEEDLE TIP
CAST STEEL
ONE REQUIRED - MARK 1648-3
FINISH MARKS
SYMBOL | TYPE OF FINISH
Rough
Average
Smooth
UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
SHOSHONE PROJECT - WYOMING
SHOSHONE DAM
58" BALANCED VALVE
NOVEMBER 194 REPAIRS
REGULATING AND FULL DISCHARGE VALVES
MANIFOLD - LINERS - NEEDLE SEAT
DRAWN J.P.
TRACED J.M.P.
CHECKED
SUBMITTED
RECOMMENDED
APPROVED
DENVER, COLORADO, AUG. 27, 1944
SHEET 4 OF 3
26-D-1648