

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE		Page 1 of 2	
2. AMENDMENT/MODIFICATION NO. 0001		3. EFFECTIVE DATE 09/13/2006		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO. <i>(If applicable)</i>	
6. ISSUED BY Bureau of Reclamation - PNRO 1150 N Curtis Rd, Ste 100 Boise, ID 83706-1234				7. ADMINISTERED BY <i>(If other than Item 6)</i> Bureau of Reclamation - PNRO 1150 N Curtis Rd, Ste 100 Boise, ID 83706-1234			
8. NAME AND ADDRESS OF CONTRACTOR <i>(No., street, county, State and Zip Code)</i> No Contractor Information Available				(X)		9A. AMENDMENT OF SOLICITATION NO. 06SQ101641	
				(X)		9B. DATED <i>(SEE ITEM 11)</i> 08/31/2006	
						10A. MODIFICATION OF CONTRACT/ORDER NO.	
						10B. DATED <i>(SEE ITEM 13)</i>	
CODE				FACILITY CODE			

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

☒ The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers ☐ is extended, ☒ is not extended.

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:

(a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)*

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS.

IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
<input type="checkbox"/>	
<input type="checkbox"/>	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
<input type="checkbox"/>	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
<input type="checkbox"/>	D. OTHER <i>(Specify type of modification and authority)</i>

E. IMPORTANT: Contractor ☐ is not, ☐ is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*
Change of line item 003 summary and scope of work

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER <i>(Type or print)</i>		16A. NAME AND TITLE OF CONTRACTING OFFICER <i>(Type or print)</i> DARLENE LARRONDO	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. United States of America BY _____	16C. DATE SIGNED
<i>(Signature of person authorized to sign)</i>		<i>(Signature of Contracting Officer)</i>	

Line Item Summary		Document Number	Title			Page
		06SQ101641/0001	Becker Testing @ Tieton Dam			2 of 2
Line Item Number	Description	Delivery Date (Start date to End date)	Quantity	Unit of Issue	Unit Price	Total Cost
Solicitation No. 06SQ101641 Becker Investigations at Tieton Dam Yakima Project, Washington						
0003	Becker Testing-BPT Hole with Continuous PDA Data Collection Change in Description, Extended Description (w/knock-off bit and backfill w/BENTONITE CHIPS OR SLURRY.	11/16/2006	0.00	ft	\$ _____	\$ _____

**BECKER INVESTIGATIONS AT
TIETON DAM
YAKIMA PROJECT, WASHINGTON**

Table of Contents

1. General.....	2
2. Location.....	2
3. Scope of Work.....	3
3.1. Personnel.....	3
3.1.1 BPT Contractor	3
3.1.2 Engineering Contractor	3
3.2. Mobilization of Equipment for Use in Field Testing Program ...	3
3.3. Equipment Furnished by the Contractor	3
3.3.1 Drilling and Sampling Equipment	3
3.3.2 Pullback Testing.....	4
3.3.3 Becker PDA.....	4
3.3.4 Products.....	4
3.4 Becker Drilling.....	4
3.4.1 General	4
3.4.2 BPT Soundings	5
3.4.3 Record Keeping	5
3.4.4 Completion of Becker Soundings	5
3.5 Becker Holes	5
3.6 Pull Back Testing	5
3.7 Work Schedule	5
3.8 Safety Requirements	5
3.9 Drilling Permits, Licenses, and Permission to Drill.....	6
4. Cessation of Work	6
5. Access to Drilling Area	6
6. Materials and Service to be Provided for by the Government	6
7. Project Completion and Deliverables.....	6
7.1 BPT Contractor	6
7.2 Engineering Contractor	7
8. Site Security	7
Table 1 – Becker Sample Hole Summary	9
Table 2 – DH-05-1 Water Levels Measured During Drilling.....	10

3.3.1.5 The BPT soundings shall be advanced with a 6-5/8-inch outside diameter (O. D.), 8-tooth crowd-out, closed-end bit with a machined end plug for the purpose of collecting blow counts to specified depths and for subsequent tremmie backfilling.

3.3.1.6 A 1/4-inch N.P.T. T-fitting from the bounce chamber pressure gage, which is to allow for the connection of an electric transducer and automated data collection system provided by the Government. The hose between the bounce chamber and the energy monitor shall remain free of obstructions, including oil and other debris at all times. This unobstructed hose shall be maintained by blowing out the hose with compressed air or by other means prior to each Becker hole and as directed by Reclamation's Field Representative.

3.3.2 Pullback Testing

Provide pullback force and displacement measurement equipment for Standard Penetration testing developed by GRL, Inc. for the Federal Highway Administration. The strain (force) transducers will be monitored by signal conditioning units and fed into a laptop computer. The displacement will be monitored with a string/tape extensometer/potentiometer. The equipment is commercially available and does not require special fabrication.

3.3.3 Becker PDA

Provide PDA equipment suitable for obtaining continuous data to estimate the energy transferred to the top of the Becker Hammer drive casing and to correct to Nb_{30} for each one-foot drive interval. PDA measurements are to be taken with force and acceleration transducers on the drill string by an instrumented pipe section with a Pile Dynamics, Inc. pile driving analyzer. This dynamic measurement system cannot be used to measure static pullback forces. The PDA procedure compiles data to be used by the CAPWAP.

Provide equipment and labor to perform CAPWAP analyses, using the recorded PDA data from each respective BPT borehole sounding. CAPWAP analyses shall be presented within the report, including the rationale for selecting the BPT hole intervals for which the CAPWAP analyses are performed. The intervals for CAPWAP analysis shall be selected by Reclamation TSC representative with the assistance of the contractor. Results from the CAPWAP analyses will be used in the conversion of Becker Hammer penetration resistance data into equivalent Standard Penetration Test (SPT) resistance $N1(60)$ values.

3.3.4 Products

3.3.4.1 Backfill materials: medium size bentonite chips, or for deeper holes bentonite for pumped slurry.

3.4 Becker Drilling

3.4.1 General

The Becker geotechnical investigation program shall be conducted at the locations described in Tables 1 **and 2** below, as conditions allow. Reclamation's Field Representative will choose the order in which the boreholes will be investigated. **This requirement is for drilling through an estimated 5-ft thickness of riprap armor on the face of the dam in each of the holes. The Contractor will be responsible for this drilling activity and can use any suitable drilling method for advancing the hole through the riprap, subject to approval by the COTR. The Contractor will not be required to perform Becker hammer tests in this portion of the hole.** All locations shown in Tables 1 are an estimate of hole locations and depths.

High resistance may be encountered during drilling due to encountering cobbles and boulders. Each BPT sounding shall be advanced at least 5 feet into bedrock, to refusal, or as determined by Reclamation's Field Representative present at the site. Estimated depths to bedrock and elevations for each hole are listed in Table 1. Refusal is defined as 1-inch advancement of the drive casing after 200 blows at maximum effort. Refusal prior to reaching bedrock depth may require abandoning the BPT sounding and retesting at an adjacent location. Refusal criteria for penetrations within the bedrock will be determined by Reclamation's Field Representative in the field, but will not be more stringent than that mentioned above.

Table 2. DH-05-1 – Water Levels Measured During Drilling

The test hole locations are all sited on the upstream or reservoir face of the dam on access roads previously constructed by Reclamation. Reclamation has limited water level data from one hole (DH-05-1) drilled in this area last year. Water levels generally reflected the corresponding level of the reservoir with a slight time lag as the reservoir water drained from the embankment materials. Water levels in that hole varied from 0.0 to 63.5 ft below ground surface in that hole, but typically ranged from 0.0 to 17.1 ft. Individual water level readings measured in this hole are tabulated below.

2005 Date	Casing Depth (ft)	Hole Depth (ft)	Water Level BGS (ft)
10-3	17.5	19.0	Dry
10-4	26.3	30.3	Dry
10-5	46.3	47.8	4.1
10-12	58.8	60.3	Dry
10-13	68.8	70.3	37.1
10-14	76.3	80.3	27.1
10-15	88.8	90.3	0.0
10-17	101.3	102.8	0.0
10-18	108.3	111.3	4.5
10-19	123.8	125.3	3.1
10-20	136.3	137.8	2.1
10-21	146.3	147.8	2.3
10-22	156.3	157.8	17.1
10-24	166.3	167.8	0.0
10-25	176.3	177.8	0.0
10-26	186.3	187.8	0.0
10-31	201.3	201.3	63.5
11-1	201.3	202.8	6.1
11-2	221.3	221.3	7.3
11-3	241.1	241.6	6.7

Note: The water level was measured at the start of each daily shift.