



Arrowrock Dam Outlet Works Rehabilitation

Final Environmental Impact Statement

U.S. Bureau of Reclamation
Pacific Northwest Region
Snake River Area Office
Boise, Idaho

March 2001

Final Environmental Impact Statement

Arrowrock Dam Outlet Works Rehabilitation

Prepared by: Bureau of Reclamation
Pacific Northwest Region
Snake River Area Office
Boise Idaho

Abstract:

The Bureau of Reclamation proposes to rehabilitate the Arrowrock Dam outlet works by removing the 10 lower level Ensign valves and replacing those valves with 10 clamshell gates. The 10 upper level conduits controlled by Ensign valves and the 5 sluice outlets controlled by slide gates would be abandoned but left in place. Rehabilitation would require three construction seasons in a 4-year period and operational changes of the Boise River/reservoir system. Two alternatives have been identified that differ only in the timing of reservoir drawdown and the elevation of Arrowrock Reservoir and Lucky Peak Lake in the third construction season. During the first two construction seasons Arrowrock Reservoir would be held at a fairly high level and Lucky Peak Lake would be held at low level (both within normal operating levels). In the third construction season, Arrowrock Reservoir would be drawn down to a very low level for 5 months in the fall and winter (under Alternative A which is the Preferred and Environmentally Preferred Alternative) or to near run-of-river for 9 weeks (Alternative B). These low levels would be comparable with extreme drought conditions and levels required in the past for maintenance of the lower Ensign valves. The probability of sluice gates use would be only 15 percent with Alternative; use is required under Alternative B. Lucky Peak Lake, which at full pool elevations rises about 100 feet above the toe of Arrowrock Dam would be held at a low level (within normal operating levels) during this construction season. Although the Lucky Peak Lake elevation would be within normal operating ranges, it would be low for a longer period than normal.

This Final EIS has been developed to comply with the requirements of the National Environmental Policy Act and Bureau of Reclamation procedures and is intended to serve environmental review and consultation requirements pursuant to all appropriate Executive Orders, National Historical Preservation Act (Section 106), Fish and Wildlife Coordination Act, and Endangered Species Act (Section 7c). It also provides the public review required under Executive Order 11988 (Floodplain Management) and Executive Order 11990 (Protection of Wetlands). This Final EIS will be used by decision-makers in the Bureau of Reclamation and is provided for public information. A record of decision (ROD) will be signed after the 30-day waiting period and following publication of the *Federal Register* notice of availability of the Final EIS.

For Further Information Contact:

John Tiedeman,
Bureau of Reclamation,
1150 North Curtis Road, Boise
Idaho 83705-1234
Telephone: (208) 378-5034

Acronyms and Abbreviations

°C	degrees Celsius
°F	degrees Fahrenheit
BA	Biological Assessment
BO	Biological Opinion
BPA	Bonneville Power Administration
BPBOC	Boise Project Board of Control
CL	Center line
CAR	Coordination Act Report (Fish and Wildlife)
CEQ	Council on Environmental Quality
CFR	Codified Federal Regulations
cfs	cubic feet per second
Corps	United States Army Corps of Engineers
CWA	Clean Water Act
DEIS	Draft Environmental Impact Statement
EIS	Environmental Impact Statement
ESA	Endangered Species Act
FERC	Federal Energy Regulatory Commission
FWCA	Fish and Wildlife Coordination Act
HAER	Historic American Engineering Record
IDAPA	Idaho Administrative Procedures Act
IDEQ	Idaho Department of Environmental Quality
IDFG	Idaho Department of Fish and Game
IDPR	Idaho Department of Parks and Recreation
IDWR	Idaho Department of Water Resources
ITA	Indian Trust Asset
kW	kilowatt
kWh	kilowatt-hour
mg/L	milligrams per liter
M&I	Municipal and Industrial
MODSIM	Model Simulation (a computer program)
MW	megawatt
MWh	megawatt-hour
NAGPRA	Native American Graves Protection and Repatriation Act
NED	National Economic Development
NEPA	National Environmental Policy Act
NHPA	National Historic Preservation Act
NMFS	National Marine Fisheries Service
OM&R	Operations, Maintenance, and Replacement
OHV	Off-highway vehicle
Reclamation	Bureau of Reclamation
RPM	Reasonable and prudent measure
SHPO	State Historical Preservation Office (or Officer)
SRAO	Snake River Area Office (Bureau of Reclamation)
SOP	Standing operating procedures

TDG	Total dissolved gases
TMDL	Total maximum daily load
TSS	Total suspended sediment
USFWS	United States Fish and Wildlife Service
USFS	United States Forest Service
VE	Value engineering

Table of Contents

	Page
SUMMARY	
1 PURPOSE AND NEED FOR ACTION	1-1
Proposed Action	1-1
Need for Action	1-1
Background	1-2
Location and Setting	1-2
Arrowrock Dam and the Boise River Storage System Operation	1-3
Arrowrock Dam Facilities	1-3
Arrowrock Dam Maintenance	1-4
Scoping	1-5
Federal Register Notices	1-6
Scoping Document	1-6
Scoping Meetings	1-6
Results of Scoping	1-6
Additional Public Involvement	1-7
Related Actions and Activities	1-8
ESA Section 7 Consultation on Reclamation Operation and Maintenance	
Activities in the Snake River Basin Above Lower Granite Reservoir	1-8
Bull Trout Research, North Fork of the Boise River	1-9
Arrowrock Dam Parapet Wall Replacement	1-9
Arrowrock Bridge Replacement	1-9
Arrowrock Dam Telephone Line Replacement	1-10
Hydropower Development at Arrowrock Dam	1-10
Atlanta Road Improvement Project	1-10
Legal Authorities and Constraints	1-10
Document Organization	1-11
2 ALTERNATIVES	2-1
Formulation of Alternatives	2-1
No Action Alternative	2-2
Facilities	2-2
Maintenance and Replacement Schedule and Reservoir Drawdown	2-3
Staging, Materials, and Waste Materials	2-4
Reservoir Operation in Years Between Scheduled Maintenance	2-5
Costs	2-5
Alternative A (Preferred Alternative) – Replace Lower Row of Ensign Valves with Clamshell Gates, Arrowrock Reservoir Elevation 3027 Feet in Construction Year 3	2-5
Construction	2-5
Staging, Materials, and Waste Materials	2-7
Future Operation, Maintenance, and Replacement	2-7

Table of Contents

	Page
Costs	2-8
Alternative B – Replace Lower Row of Ensign Valves with Clamshell Gates, Reservoir	
Elevation 3007 Feet in Construction Year 3	2-8
Construction	2-8
Staging, Materials, and Waste Materials	2-9
Operation, Maintenance, and Replacement	2-9
Costs	2-9
Alternatives Eliminated from Further Consideration	2-10
Summary of Alternatives	2-11
 3 AFFECTED ENVIRONMENT AND ENVIRONMENTAL CONSEQUENCES	3-1
Introduction	3-1
Resources Not Affected by the Alternatives	3-2
 Water/Reservoir Operations	3-3
Affected Environment	3-3
River/Reservoir System	3-3
Arrowrock Dam and Reservoir	3-5
Lucky Peak Dam and Lake	3-5
Anderson Ranch Dam and Reservoir	3-6
Reservoir Data Summary	3-6
Storage System Active Space	3-6
Reservoir System Operations	3-7
General System Operation	3-7
System Flood Control Operations	3-8
System Irrigation Operations	3-9
System Winter Minimum Flows and Reservoir Contents	3-9
Salmon Flow Augmentation	3-10
Operation of Individual Facilities	3-11
Boise River Below Lucky Peak Dam	3-14
Environmental Consequences	3-15
Impact Indicators/Methods for Evaluating Impacts	3-15
No Action Alternative	3-16
Arrowrock Reservoir	3-16
Lucky Peak Lake	3-17
Lower Boise River	3-18
Anderson Ranch Reservoir and South Fork Boise River	3-18
Alternative A (Preferred Alternative)	3-19
Arrowrock Reservoir	3-19
Lucky Peak Lake	3-20
Lower Boise River	3-21
Anderson Ranch and South Fork Boise River	3-21

Table of Contents

	Page
Alternative B	3-22
Arrowrock Reservoir	3-22
Lucky Peak Lake	3-22
Lower Boise River	3-23
Anderson Ranch Reservoir and South Fork Boise River	3-23
Water Quality	3-24
Affected Environment	3-24
River Reaches Upstream of Arrowrock Reservoir	3-25
Arrowrock Reservoir	3-26
Lucky Peak Lake	3-26
Boise River Downstream of Lucky Peak Dam	3-27
Lake Lowell	3-28
Environmental Consequences	3-28
Impact Indicator/Methods for Evaluating Impacts	3-28
No Action Alternative	3-29
Arrowrock Reservoir	3-29
Lucky Peak Lake	3-30
Lower Boise River	3-31
Anderson Ranch Reservoir	3-32
South Fork Boise River	3-32
Mitigation and Residual Effects	3-32
Alternative A (Preferred Alternative)	3-32
Arrowrock Reservoir	3-32
Lucky Peak Lake	3-34
Lower Boise River	3-35
Anderson Ranch Reservoir	3-35
South Fork Boise River	3-35
Mitigation and Residual Effects	3-35
Alternative B	3-36
Arrowrock Reservoir	3-36
Lucky Peak Lake	3-36
Lower Boise River	3-37
Anderson Ranch Reservoir	3-37
South Fork Boise River	3-38
Mitigation and Residual Effects	3-38
Fish	3-39
Affected Environment	3-39
Arrowrock Reservoir	3-39
Lucky Peak Lake	3-39
Boise River Downstream of Lucky Peak Dam	3-40
Anderson Ranch Reservoir and South Fork Boise River	3-40

Table of Contents

	Page
Environmental Consequences	3-40
Impact Indicators/Methods for Evaluating Impacts	3-41
No Action Alternative	3-42
Arrowrock Reservoir	3-42
Lucky Peak Lake	3-43
Lower Boise River	3-43
South Fork Boise River	3-43
Mitigation and Residual Effects	3-44
Alternative A (Preferred Alternative)	3-44
Arrowrock Reservoir	3-44
Lucky Peak Lake	3-45
Lower Boise River	3-46
South Fork Boise River	3-46
Mitigation and Residual Effects	3-46
Alternative B	3-47
Arrowrock Reservoir	3-47
Lucky Peak Lake	3-47
Lower Boise River	3-47
South Fork Boise River	3-48
Mitigation and Residual Effects	3-48
Vegetation and Wildlife	3-49
Affected Environment	3-49
Vegetation	3-49
Wildlife	3-49
Environmental Consequences	3-50
Impact Indicators/Methods for Evaluating Impacts	3-50
No Action	3-50
Arrowrock Reservoir	3-50
Lucky Peak Lake	3-51
Lower Boise River	3-52
Anderson Ranch Reservoir/South Fork Boise River	3-52
Mitigation and Residual Effects	3-52
Alternative A (Preferred Alternative)	3-52
Arrowrock Reservoir	3-52
Lucky Peak Lake	3-53
Anderson Ranch Reservoir and South Fork Boise River	3-53
Mitigation and Residual Effect	3-53
Alternative B	3-53
Arrowrock Reservoir	3-53
Lucky Peak Reservoir	3-54

Table of Contents

	Page
Lower Boise River	3-54
Anderson Ranch Reservoir and South Fork Boise River	3-54
Mitigation and Residual Effects	3-54
 Threatened and Endangered Species	3-55
Affected Environment	3-55
Bull Trout	3-55
Life History and Habitat	3-55
Bull Trout Status in the Boise River	3-56
USFWS Biological Opinion on Reclamation's Operation and Maintenance Activities	3-58
Bald Eagle	3-59
Gray Wolf	3-61
Ute Ladies'-Tresses	3-61
Snake River Salmon and Steelhead	3-62
Environmental Consequences	3-62
Bull Trout	3-62
Impact Indicators/Methods of Evaluation	3-63
No Action Alternative	3-63
Alternative A (Preferred Alternative)	3-65
Alternative B	3-68
Bald Eagle	3-69
Impact Indicators/Methods of Evaluation	3-69
No Action	3-69
Alternative A (Preferred Alternative)	3-70
Alternative B	3-72
Gray Wolf	3-73
Ute Ladies'-Tresses	3-73
Snake River Salmon and Steelhead	3-73
 Recreation	3-74
Affected Environment	3-74
Arrowrock Reservoir	3-75
Facilities	3-75
Recreation Activities	3-75
Recreation Use and Season of Use	3-76
Factors Affecting Use	3-76
Lucky Peak Lake	3-77
Facilities	3-78
Recreation Activities	3-79
Recreation Use	3-80
Season of Use	3-81
Factors Affecting Use	3-82

Table of Contents

	Page
Lower Boise River	3-82
Recreation Facilities	3-83
Recreation Activities	3-84
Recreation Use and Season of Use	3-84
Factors Affecting Use	3-86
Anderson Ranch Reservoir	3-86
Recreation Facilities	3-86
Recreation Activities	3-87
Recreation Use and Season of Use	3-87
Factors Affecting Use	3-87
South Fork Boise River	3-87
Recreation Facilities	3-88
Recreation Activities	3-88
Recreation Use and Season of Use	3-89
Factors Affecting Use	3-89
Environmental Consequences	3-89
Impact Indicators/Methods for Evaluating Impacts	3-89
No Action	3-90
Arrowrock Reservoir	3-90
Lucky Peak Lake	3-91
Lower Boise River	3-92
Anderson Ranch Reservoir	3-93
South Fork Boise River	3-93
Mitigation and Residual Effects	3-93
Alternative A (Preferred Alternative)	3-93
Arrowrock Reservoir	3-93
Lucky Peak Lake	3-94
Lower Boise River	3-95
Anderson Ranch Reservoir	3-96
South Fork Boise River	3-96
Mitigation and Residual Effects	3-96
Alternative B	3-97
Arrowrock Reservoir	3-97
Lucky Peak Lake	3-97
Lower Boise River	3-98
Anderson Ranch Reservoir	3-99
South Fork Boise River	3-99
Mitigation and Residual Effects	3-100

Table of Contents

	Page
Economics	3-101
Affected Environment	3-101
Population and Income	3-101
Agricultural Economy Information	3-103
Hydropower	3-105
Environmental Consequences	3-106
Agriculture	3-106
Impact Indicators and Methods of Evaluation	3-106
Irrigation Shortages	3-107
Economic Impacts to Spaceholders	3-109
Financial Impacts to Arrowrock Spaceholders	3-109
Recreation	3-111
Impact Indicators/ Methods of Evaluation	3-111
No Action	3-112
Alternative A (Preferred Alternative)	3-112
Alternative B	3-112
Recreation Economics Summary	3-113
Hydropower	3-114
Impact Indicators/Methods of Evaluation	3-114
Generation	3-115
Mitigation and Residual Effects	3-118
Cultural Resources	3-119
Affected Environment	3-119
Overview	3-119
Previous Investigations and Identified Cultural Resources	3-120
Potential for Unrecorded Cultural Resource Sites	3-122
Environmental Consequences	3-122
Impact Indicators/Methods of Evaluation	3-122
No Action	3-123
Arrowrock Reservoir	3-123
Arrowrock Dam	3-124
Mitigation and Residual Effects	3-124
Alternative A (Preferred Alternative)	3-126
Arrowrock Reservoir	3-126
Arrowrock Dam	3-126
Mitigation and Residual Effects	3-126
Alternative B	3-127
Arrowrock Reservoir	3-127
Arrowrock Dam	3-127
Mitigation and Residual Effects	3-127

Table of Contents

	Page
Indian Sacred Sites	3-128
Affected Environment	3-128
Environmental Consequences	3-128
Impact Indicators/Methods of Evaluation	3-128
No Action	3-129
Environmental Consequences	3-129
Mitigation and Residual Effects	3-129
Alternative A (Preferred Alternative)	3-130
Environmental Consequences	3-130
Mitigation and Residual Effects	3-130
Alternative B	3-130
Environmental Consequences	3-130
Mitigation and Residual Effects	3-130
Indian Trust Assets	3-131
Affected Environment	3-131
Environmental Consequences	3-132
Impact Indicators/Methods of Evaluation	3-132
Environmental Consequences	3-132
Cumulative Impacts	3-133
Pertinent Activities, Events, and Trends	3-134
Water Resources	3-134
Water Quality	3-135
Fish	3-135
Vegetation and Wildlife	3-136
Threatened and Endangered Species	3-136
Recreation	3-137
Economics	3-137
Cultural Resources	3-138
Indian Sacred Sites	3-138
Indian Trust Assets	3-138
Unavoidable Adverse Effects	3-139
Irreversible and Irretrievable Commitments of Resources	3-140

Table of Contents

	Page
4 CONSULTATION AND COORDINATION	4-1
Public Scoping and Involvement	4-1
Coordination with Federal and State Agencies	4-2
Fish and Wildlife Coordination Act	4-2
Endangered Species Act	4-2
National Historic Preservation Act	4-3
Coordination with Native Americans	4-3
5 BIBLIOGRAPHY	5- 1
6 LIST OF PREPARERS	6-1
7 GLOSSARY	7-1
8 INDEX	8-1

Appendices

- Appendix A. Summary of Scoping Comments
- Appendix B. Engineering and Summary of Plan Concepts and Potential Elements
- Appendix C. Water Quality Data and Monitoring Plan
- Appendix D. Hydrology Studies
- Appendix E. Environmental Commitments
- Appendix F. U.S. Fish and Wildlife Service Final Coordination Act Report Extract, Reclamation Extract, Reclamation Response, Draft BO Reasonable and Prudent Measures, and Endangered Species Act List
- Appendix G. List of Correspondence and Meetings with Tribes
- Appendix H. Distribution List
- Appendix I. Supplemental Biological Assessment and Bull Trout Mitigation Plan
- Appendix J. Financial Impact Tables
- Appendix K. Comments and Responses

Tables

Table S-1. Summary of Alternatives	Summary-12
Table 1-1. Historical and Recent Maintenance of Lower Ensign Valves and Sluice Gates	1-5
Table 1-2. Identified Issues and Concerns	1-7
Table 2-2. No Action Reservoir Operation During Maintenance Years	2-3
Table 2-3. No Action Maintenance Schedule	2-3
Table 2-4. Construction Schedule for Alternative A (Preferred Alternative)	2-7
Table 2-5. Construction Schedule for Alternative B	2-9

Table of Contents

	Page
Table 2-6. Summary of Alternative Facilities, Reservoir Elevations and Costs	2-12
Table 3-1. Modified River Mile Index for the Boise River	3-4
Table 3-2. Data for Boise River Reservoirs	3-6
Table 3-3. Boise River Reservoir Active Space (Acre-Feet)	3-7
Table 3-4. Source of Boise River Water for Salmon Flow Augmentation (1993-1999) . . .	3-11
Table 3-5. Arrowrock Valve Rehabilitation/Replacement Hydrology Summary) .. follows	3-16
Table 3-6. Water Quality Impacted Waterbodies Upstream and Downstream of Arrowrock Reservoir	3-25
Table 3-7. Designated Beneficial Uses for the Boise River Downstream of Lucky Peak Dam	3-27
Table 3-9. Alternative A (Preferred Alternative) Probability of Using Sluice Gates	3-33
Table 3-10. Alternative A (Preferred Alternative), Construction Season 3 Potential Sediment Movement From Arrowrock Reservoir and Deposition in Lucky Peak Lake With a 5-10 Year Flood	3-34
Table 3-11. Arrowrock Reservoir Recreation Facilities	3-75
Table 3-12. Lucky Peak Lake Boat Ramps	3-79
Table 3-13. Lucky Peak Lake Recreation Visits	3-80
Table 3-14. Lucky Peak Lake - Use by Activity	3-81
Table 3-15. Lucky Peak Lake Use by Month	3-81
Table 3-16. Estimated 1999 Visitation on Boise River Downstream of Boise River Diversion Dam	3-85
Table 3-17. Lucky Peak State Park (Sandy Point Beach & Discovery State Park Units) Use By Month	3-85
Table 3-18. Lower Boise River Flow Parameters for Floating, Fishing, and Green Belt Use (Barber Park to Glenwood Bridge)	3-90
Table 3-19. South Fork Boise River Flow Parameters for White Water Rafting and Fishing	3-90
Table 3-20. No Action Alternative, Arrowrock Reservoir Elevation and Boat Ramp Usability	3-91
Table 3-21. No Action Alternative, Lucky Peak Lake Elevations and Boat Ramps Available in an Average Water Year	3-91
Table 3-22. Alternative A (Preferred Alternative), Arrowrock Reservoir Elevations and Boat Ramp Usability Construction Seasons 1 and 2	3-94
Table 3-23. Alternative A (Preferred Alternative), Arrowrock Reservoir Elevations and Boat Ramp Usability Construction Season 3	3-94
Table 3-24. Alternative A (Preferred Alternative), Lucky Peak Lake Elevations and Boat Ramps Available in Construction Seasons 1-3 with an Average Water Year	3-95
Table 3-25. Alternative A (Preferred Alternative), Lower Boise River Flows in Construction Seasons 1 and 2 with Average and Wet Water Years	3-95
Table 3-26. Alternative A (Preferred Alternative), Lower Boise River Flows in Construction Season 3 with Average and Wet Water Years	3-96
Table 3-27. Alternative B, Arrowrock Reservoir Elevations and Boat Ramp Usability Construction Season 3	3-97

Table of Contents

	Page
Table 3-28. Alternative B, Lucky Peak Lake Elevation and Boat Ramps Available in Construction Season 3 with an Average or Wet Water Year	3-98
Table 3-29. Alternative B, Lower Boise River Flows in Construction Season 3 with Average and Wet Water Years	3-99
Table 3-30. 1998 Population and Income	3-102
Table 3-31. Employment by Sector (1996)	3-103
Table 3-32. Arrowrock Reservoir Spaceholder Contracts	3-104
Table 3-33. 1997 Census of Agriculture Data	3-105
Table 3-34. Irrigation Shortages Over a 4-year Sequence (Acre-Feet)	3-107
Table 3-35. Irrigation Shortages for a 4-Year Dry Period (1988-1991) (Acre-Feet)	3-108
Table 3-36. Alternative B, Economic Impacts at Lucky Peak Lake	3-113
Table 3-37. Direct Recreation Impacts During Construction	3-113
Table 3-38. Marginal Cost of Power by Month in Pacific Northwest (Dollars per MWh) ..	3-115
Table 3-39. Hydropower Generation, Over a 4-Year Impact Period (MWh)	3-115
Table 3-40. Value of Incremental Generation Change Compared to No Action	3-117

Figures and Maps

Boise River Basin Location	Frontispiece
Figure S-1. Reservoir Elevations, Arrowrock Dam Cross Section	follows Summary-4
Figure 1-1. View inside the trashrack structure of the lower row of Ensign valves..	follows 1-2
Figure 1-2. Arrowrock Dam and Reservoir. Aerial photograph looking upstream showing discharge from the spillway and some of the upper level outlets..	follows 1-4
Figure 1-3. Cross-section of Arrowrock Dam from original design drawings.	follows 1-4
Figure 1-4. View of the upstream side of Arrowrock Dam during construction..	follows 1-4
Figure 2-1. No Action Alternative – Arrowrock Dam cross section with selected reservoir elevations.	follows 2-4
Figure 2-2. No Action Alternative – Arrowrock Reservoir showing areal extent of selected elevations.	follows 2-4
Figure 2-3. View of Arrowrock Dam looking upstream.....	follows 2-4
Figure 2-4. Looking downstream (west) at Arrowrock Dam from the north bank of the main stem Boise River	follows 2-4
Figure 2-5. Looking upstream (east) along the Boise River from the face of Arrowrock Dam.	follows 2-4
Figure 2-6. Alternative A – Arrowrock Dam cross section with selected reservoir elevations.	follows 2-6
Figure 2-7. Alternative A – Arrowrock Reservoir showing areal extent of selected elevations.	follows 2-6
Figure 2-8. Construction staging areas	follows 2-8

Table of Contents

	Page
Figure 2-9. Alternative B – Arrowrock Dam cross section with selected reservoir elevations.	follows 2-8
Figure 2-10. Alternative B – Arrowrock Reservoir showing areal extent of selected elevations.	follows 2-8
Figure 3-1. Typical content and outflow of Boise Project Reservoirs	follows 3-12
Figure 3-2. Idaho Counties	3-101
Figure 3-3. Average Monthly Generation At Anderson Ranch Powerplant for a 4-Year Impact Period	3-116
Figure 3-4. Average Monthly Generation at Lucky Peak Powerplant for a 4-Year Impact Period	3-116