


ANNUAL OPERATING PLAN

ANNUAL OPERATING PLAN

NIOBRARA, LOWER PLATTE, AND KANSAS RIVER BASINS 1975 - 1976



DEPARTMENT OF THE INTERIOR
Thomas S. Kleppe, Secretary

Bureau of Reclamation

Gilbert G. Stamm, Commissioner



Department of the Interior

Bureau of Reclamation

Lower Missouri Region • Denver, Colorado

ANNUAL OPERATING PLAN

**NIOBRARA, LOWER PLATTE, AND
KANSAS RIVER BASINS**

**1975 OPERATIONS
1976 OUTLOOK**

CONTENTS

	<u>Page</u>
SYNOPSIS	1
CHAPTER I - INTRODUCTION	5
Purpose of This Report	5
Operational Responsibilities	5
Tables and Exhibits.	6
Water Supply	6
Reservoir Operations	6
Major Features	6
Irrigation Districts	7
Municipal and Industrial Water	7
Fish Hatchery.	7
Environmental Considerations	7
CHAPTER II - NIOBRARA AND LOWER PLATTE RIVER BASINS.	8
Mirage Flats Project in Nebraska	8
Ainsworth Unit, Sandhills Division in Nebraska	9
Sargent Unit, Middle Loup Division in Nebraska	10
Farwell Unit, Middle Loup Division in Nebraska	10
CHAPTER III - REPUBLICAN RIVER BASIN	13
Armel Unit, Upper Republican Division in Colorado.	13
Frenchman Unit, Frenchman-Cambridge Division in Nebraska	14
Meeker-Driftwood, Red Willow, and Cambridge Units, Frenchman-Cambridge Division in Nebraska	15
Almena Unit, Kanaska Division in Kansas.	17
Franklin, Superior-Courtland, and Courtland Units, Bostwick Division in Nebraska and Kansas.	18
CHAPTER IV - SMOKY HILL RIVER BASIN.	21
Kirwin Unit, Solomon Division in Kansas.	21
Webster Unit, Solomon Division in Kansas	21
Glen Elder Unit, Solomon Division in Kansas.	24
Cedar Bluff Unit, Smoky Hill Division in Kansas.	25

LIST OF TABLES

- 1 - Capacity Allocation--Reservoirs in Niobrara, Lower Platte and Kansas River Basins
- 2 - Summary of 1975 Operations:
 - Mirage Flats Project and Sandhills, Middle Loup, and Upper Republican Divisions, Sheet 1 of 4
 - Frenchman-Cambridge Division, Sheet 2 of 4
 - Kanaska and Bostwick Divisions, Sheet 3 of 4
 - Solomon and Smoky Hill Divisions, Sheet 4 of 4
- 3 - Acres Irrigated in 1975 and Estimates for 1976
- 4 - Operation Estimates--1976:
 - Box Butte Reservoir, Sheet 1 of 15
 - Merritt Reservoir, Sheet 2 of 15
 - Sherman Reservoir, Sheet 3 of 15
 - Bonny Reservoir, Sheet 4 of 15
 - Swanson Lake, Sheet 5 of 15
 - Enders Reservoir, Sheet 6 of 15
 - Hugh Butler Lake, Sheet 7 of 15
 - Harry Strunk Lake, Sheet 8 of 15
 - Norton Reservoir, Sheet 9 of 15
 - Harlan County Reservoir, Sheet 10 of 15
 - Lovewell Reservoir, Sheet 11 of 15
 - Kirwin Reservoir, Sheet 12 of 15
 - Webster Reservoir, Sheet 13 of 15
 - Waconda Lake, Sheet 14 of 15
 - Cedar Bluff Reservoir, Sheet 15 of 15
- 5 - Flood Damages Prevented by Kansas River Projects Reservoirs
- 6 - Other Uses at Federally Constructed Storage and Diversion Dams--Niobrara, Lower Platte and Kansas River Basins

LIST OF EXHIBITS

Operation Hydrographs:

- 1 - Box Butte Reservoir
- 2 - Merritt Reservoir
- 3 - Sherman Reservoir
- 4 - Bonny Reservoir
- 5 - Swanson Lake
- 6 - Enders Reservoir
- 7 - Hugh Butler Lake
- 8 - Harry Strunk Lake
- 9 - Norton Reservoir
- 10 - Harlan County Reservoir
- 11 - Lovewell Reservoir
- 12 - Kirwin Reservoir
- 13 - Webster Reservoir
- 14 - Waconda Lake
- 15 - Cedar Bluff Reservoir

Canal Diversions and Acres Irrigated:

- 16 - All Districts in Niobrara, Lower Platte and
Kansas River Basins
- 17 - Mirage Flats Irrigation District
- 18 - Ainsworth Irrigation District
- 19 - Sargent Irrigation District
- 20 - Farwell Irrigation District
- 21 - Frenchman Valley Irrigation District
- 22 - H & RW Irrigation District
- 23 - Frenchman-Cambridge Irrigation District
- 24 - Almena Irrigation District
- 25 - Bostwick Irrigation District in Nebraska
- 26 - Kansas-Bostwick Irrigation District
- 27 - Kirwin Irrigation District
- 28 - Webster Irrigation District
- 29 - Cedar Bluff Irrigation District

Map - Irrigation and Flood Control Facilities

SYNOPSIS

GENERAL

This is the twenty-third consecutive year that an Annual Operating Plan has been prepared for the federally owned reservoirs serving an irrigation function in the Niobrara, Lower Platte, and Kansas River Basins. There are 15 dams and reservoirs in Colorado, Nebraska and Kansas. These reservoirs with 10 diversion dams, 10 pumping plants, and 22 canal systems serve approximately 268,600 acres of project lands in Nebraska and Kansas. A map in the back of this report shows the location of these features. The reservoirs in the Niobrara and Lower Platte River Basins are operated by either irrigation or reclamation districts, and the reservoirs in the Kansas River Basin are operated by either the Bureau of Reclamation or the Corps of Engineers. The diversion dams, pumping plants, and canal systems are operated by either irrigation or reclamation districts.

In addition to irrigation, these features serve flood control, municipal and industrial water, recreation, and fish and wildlife purposes.

The "Headlines 75" following this Synopsis is indicative of the awareness of local people of natural resource development and conservation in the Niobrara, Lower Platte, and Kansas River Basins.

1975 SUMMARY

Climatic Conditions. The total precipitation during 1975 ranged from 65 to 128 percent of normal over the operating area. The temperatures during the irrigation season were generally normal.

Storage Reservoirs.

- A. Conservation Operations - The 1975 inflows were within the range of forecasted dry, normal or wet years for all reservoirs with the exception of Lovewell, which was slightly above the wet-year forecast, and Box Butte and Merritt which were slightly below the dry-year forecast. The active conservation storage was evacuated from Box Butte and Sherman Reservoirs in 1975. The carryover storage in Box Butte and Norton Reservoirs and the available inflows and streamflows below these dams were inadequate to fully supply the irrigation requirements of the project lands served by the reservoirs.
- B. Flood Control Operations - Harlan County and Waconda Lakes, Lovewell, Kirwin, Webster, and Cedar Bluff Reservoirs prevented an estimated \$2,779,000 flood damages on the lower Republican and Kansas Rivers. The following table gives an individual breakdown by reservoir:

<u>Lake or Reservoir</u>	<u>Calendar Year 1975</u>		<u>Accumulated Actual Benefits from 1950 Through 1975 (\$1,000)</u>
	<u>Storage Used for Flood Control (Acre-Feet)</u>	<u>Damage Prevented (\$1,000)</u>	
Harlan County	---	200	13,226
Lovewell	7,860	98	2,532
Kirwin	26,830	618	2,290
Webster	31,000	385	2,832
Waconda	44,000	967	5,660
Cedar Bluff	2,900	11	8,942
Total		2,779	

The accumulated flood control benefits for the years 1951 through 1975 by the facilities covered in this report total \$42,643,000. (See Table 5.)

Water Service. There were 567,109 acre-feet of water diverted to irrigate 245,813 acres of project lands in 13 irrigation districts. The project water supply was inadequate for 16,230 acres of lands irrigated in the Mirage Flats and Almena Irrigation Districts. Arrangements were made in these two districts with owners of private irrigation wells for a supplemental water supply to district lands. The project water supplies for the other units mentioned in this report were adequate in 1975.

The water requirements of three municipalities, two industrial companies, and a Federal fish hatchery were furnished from storage releases or natural flows.

Under a long-term contract, 32,045 acre-feet were diverted to irrigate 13,694 acres of non-project lands in the Middle Loup Public Power and Irrigation District.

Irrigation Production. The crop yields from project lands in 1975 were higher on the average than in 1974. Corn, the principal crop, rose from 107 bushel per acre average to 111 bushel per acre. In 1975, the unit prices for all commodities were much lower than those in 1974. The 1975 gross crop value of \$65,660,125 was 85% of the 1974 gross crop value, and the gross average decreased from \$324.58 per acre in 1974 to \$267.12 per acre in 1975.

Fish and Wildlife and Recreation Benefits. The operations in 1975 were favorable for the recreation and fish and wildlife uses.

The Youth Conservation Corps camps at McCook, Nebraska, and Hays, Kansas, performed work on recreation and wildlife facilities which enhanced the visitations at Enders, Swanson, Hugh Butler, Norton, Cedar Bluff, Webster and Kirwin Public Use Areas.

1976 OUTLOOK

The irrigation and reclamation districts estimate that 245,700 acres of project land will be irrigated in 1976. The operation studies indicate that if 1976

is a dry year, the project water supplies will be inadequate for the irrigation of 79,600 acres in Mirage Flats, H & RW, Frenchman Valley, Almena, and Farwell Irrigation Districts. Farwell and Mirage Flats also show a shortage under normal-year conditions. As in past years, the Mirage Flats and Almena Irrigation Districts plan to use water from private irrigation wells to supplement the project water supply. Other districts are encouraging their irrigators to drill wells for supplemental water supplies.


The industrial, municipal, and fish hatchery water supply requirements will be met in full.

During 1976, under all inflow forecast conditions, storage water will be in excess of project needs in Bonny Reservoir and Waconda Lake and will be available for sale to private irrigators or for other non-project uses. Under normal forecast conditions, excess storage will also be available for sale from Harry Strunk, Hugh Butler, Swanson, and Harlan County Lakes during July only.

With dry-year forecasted inflows, the conservation pools of Merritt, Sherman, Bonny and Lovewell Reservoirs and Harry Strunk and Waconda Lakes will fill during 1976. Most probable forecasted inflows would also fill Swanson, Hugh Butler and Harlan County Lakes.

Even with low pool levels in the reservoirs and inadequate water supplies for irrigation of some project lands, the recommendations of various State agencies will be considered. As in the past, irrigation and reclamation districts will advise State agencies regarding aquatic weed control and canal operations. The Bureau of Reclamation will continue to operate the reservoirs and other facilities under its jurisdiction in the best interests of all project functions and for the greatest public benefit whenever possible.

HEADLINES 75



Irrigation well registration in Nebraska. Top figure shows number of wells registered in 1974. Bottom figure shows number registered in 1975.

Rush to Pump Irrigation Reached Floodtide in 1975

By Don Ringler
Nebraska irrigators put a recent rush to pump water into their systems during 1975.


Oberlin's 2.06 Inches
Tops Moisture Totals

TOTAL \$2,501,729

Construction Contracts For Rural
Water District No. 3 Are Approved

Sunday World-Herald
OMAHA, NEB., MAY 18, SECTION 8 - 32 PAGES

Pumps Cloud Future Of Enders Irrigation



Lake Supply,
Water Table
Dropping Off

Drought Spur to Irrigation

Water Near Adequate
For Area Irrigators

The High Plains of Texas has
several ground-water
basins, and according to some
reports, it's a water saving
device. Irrigators may be
pumped virtually dry in some
in 20 years.

Level Runs Low in High Plains

Ideas Shared with Irrigators
Water Solution Could Be Costly

By Don Ringler
COLLIERSON - Shortage of water and what to do about it
was the main theme of the annual meeting of the NEBWA
Irrigation Districts Thursday night in the 1975 Hall in Council
Bluffs.

MUSKOGEE, NEBRASKA 68801, FRIDAY, MAY 16, 1975

Flow Meters Will Be Put on Wells

Water Allocations Likely in SW Nebraska

Pumps Cloud Future
Of Enders Irrigation

Moisture Boost for Crops
Enders Area Soaked by Showers

To Save Water: Impound

State Is Challenged
To Fund Water Plans

FOR LAST YEAR
Harvest 57 Tons Of
Fish In G. E. Reservoir

Creeks Swollen, Crops Down After Torrential Rainstorm

Real Heavy Rain
Supper Creek Overflows
High Water Warning

Cloud Funnels Form
In Turbulent Skies

\$3.5 Million Piped Into
Local Rural Water Dist.

BELOIT, KANSAS, TUESDAY, APRIL 8, 1975

Pump Irrigators Looking
For Self-Governing Plan

Rain-making study underway

Raindrops Keep Falling...
June Moisture Close
To Modern-Day Record

Postwick Irrigation district key
ingredient in Courtland economy

Kansans sue rainmaker

Y CALL

ICIAL COUNTY AND CITY NEWSPAPER

40 PERCENT COMPLETE
Report Progress On
Water District Two

CHAPTER I - INTRODUCTION

PURPOSE OF THIS REPORT

In addition to describing the operational responsibilities of the Bureau of Reclamation, Corps of Engineers, and irrigation or reclamation districts in the three basins, this Annual Operating Plan advises water users, cooperating agencies, and other interested groups or persons of the actual operations during 1975 and serves as guidelines for the 1976 operations.

OPERATIONAL RESPONSIBILITIES

The Bureau of Reclamation is responsible for irrigation operations at all Federal reservoirs in the Kansas River Projects area. At those reservoirs which were constructed by the Bureau of Reclamation, the Bureau is also responsible for the operation and maintenance, safety of the structure, and reservoir operations not specifically associated with regulation of the flood control storage. In addition to irrigation, these reservoirs provide benefits for functions such as recreation, fish and wildlife, municipal and industrial, etc.

The Corps of Engineers is responsible for regulation of the flood control storage at all Federal reservoirs in the Kansas River Basin, and for conservation functions other than irrigation at the dams where it is the construction agency.

By contractual arrangements with the Bureau of Reclamation, 12 irrigation or reclamation districts are responsible for the operation of irrigation facilities constructed or rehabilitated by the Bureau of Reclamation in the Niobrara, Lower Platte, and Kansas River Basins with the exception of the reservoirs in the Kansas River Basin.

The States of Nebraska, Colorado, and Kansas are responsible for administration and enforcement of the laws of their respective States pertaining to the water rights and priorities of all parties concerned with the use of water.

The Republican River Compact was authorized on August 4, 1942, by Public Law No. 696, which was enacted by the 77th Congress. The Compact was ratified by the States of Colorado, Kansas, and Nebraska. This Annual Operating Plan is in accordance with the objectives of the Compact, which are: "...to provide for the most efficient use of the waters of the Republican River Basin for multiple purposes; to provide for an equitable division of such waters; to remove all causes, present and future, which might lead to controversies; to promote interstate comity; to recognize that the most efficient utilization of the waters within the Basin is for beneficial consumptive use, and to promote joint action by the States and the United States in the efficient use of water and the control of destructive floods."

TABLES AND EXHIBITS

Principal records for the facilities reported herein are attached as tables and exhibits.

WATER SUPPLY

For forecasting purposes, values of annual inflows that will be statistically equalled or exceeded 10, 50 and 90 percent of the time were selected from the probability curve to be "reasonable maximum" (wet year), "most probable" (normal year), and "reasonable minimum" (dry year) inflow conditions, respectively.

RESERVOIR OPERATIONS

All operations are scheduled for optimum benefits to project functions. At the end of the irrigation season and at the end of each month during the non-irrigation period, the carryover storage in each reservoir and the reasonable minimum inflow are evaluated to determine if water in excess of that required to fill the conservation pool may be anticipated. If excess inflow is apparent, controlled releases will be made to accomplish maximum downstream benefits.

MAJOR FEATURES

The Mirage Flats Project was constructed under the Water Conservation and Utilization Act and includes an irrigation storage reservoir, diversion dam, and canal system. The other features in the scope of this report are a part of the Pick-Sloan Missouri Basin Program and include multipurpose reservoirs, diversion dams, pump stations, and canal systems. Fifteen storage facilities are now in operation as follows:

Constructed by the Bureau of Reclamation:

- (a) Operated by Irrigation or reclamation districts--Box Butte and Merritt Dams in the Niobrara River Basin and Sherman Dam in the Lower Platte River Basin.
- (b) Operated by the Bureau of Reclamation--Bonny, Trenton, Enders, Red Willow, Medicine Creek, Norton, Lovewell, Kirwin, Webster, Glen Elder, and Cedar Bluff Dams in the Kansas River Basin.

Constructed and operated by the Corps of Engineers:

- (a) Harlan County Dam in the Kansas River Basin.

IRRIGATION DISTRICTS

Thirteen irrigation districts in the Niobrara, Lower Platte, and Kansas River Basins have contracted with the Bureau of Reclamation for water supply and irrigation facilities. Sargent and Farwell Irrigation Districts have contracted their operation and maintenance to the Loup Basin Reclamation District.

The normal irrigation season for Mirage Flats Irrigation District is April through September. The contracted irrigation season for Frenchman Valley, H & RW, Frenchman-Cambridge, and Cedar Bluff Irrigation Districts is from May 1 to October 15, and for all other districts, May 1 to September 30th.

MUNICIPAL AND INDUSTRIAL WATER

Three municipalities and two oil companies have executed water service contracts for full or supplemental water supplies.

FISH HATCHERY

A United States Fish and Wildlife Service warm-water fish hatchery is in operation below Cedar Bluff Reservoir.

ENVIRONMENTAL CONSIDERATIONS

A "Statement of Operational Objectives" for Harlan County Reservoir sets forth the general operational objectives and the specific reservoir uses considered desirable, such as that fish and wildlife interests will be best served by high pool levels with minimum fluctuations and regulation of outflow in excess of minimum requirements insofar as feasible. The statement recognizes that to assure realization of the greatest public benefits, operation plans should be sufficiently comprehensive to permit the maximum integration of the secondary uses consistent with the primary purposes of flood control and irrigation.

Insofar as practicable, the above-mentioned objectives are also considered in the operation of all reservoirs in the Kansas River Basin, Merritt and Box Butte Reservoirs in the Niobrara River Basin, and Sherman Reservoir in the Lower Platte River Basin. The regulated outflow will also be of advantage to farmers, ranchers, industries, cities, and other interests below all reservoirs.

CHAPTER II - NIOBRARA AND LOWER PLATTE RIVER BASINS

MIRAGE FLATS PROJECT IN NEBRASKA

GENERAL

Niobrara River flows and Box Butte Reservoir storage provide a water supply which is normally insufficient to achieve maximum yields from the 11,662-acre Mirage Flats Irrigation District. The project water supply will yield an average diversion of one and a half acre-feet per acre which is about one-half acre-foot per acre short of the long-term average for a full water supply. Several of the landowners in the district have drilled irrigation wells as a source of a supplemental supply. The farmers that own wells share the well water with their neighbors but the wells are too few in number to fully supplement the project water supply.

During the 1975 irrigation season, personnel from the Kansas River Projects Office aided irrigation district personnel in conducting a study to determine both losses and waste from the irrigation system. Four recorders were operated on wasteways and flow measurements were taken throughout the summer. Results were as follows:

<u>Lateral Wasteway</u>	<u>Discharge (Acre-Feet)</u>			
	<u>July</u>	<u>August</u>	<u>September</u>	<u>Total</u>
Fairfield	29.6	27.4	0.0	57.0
Mirage Flats	108.0	72.0	8.0	188.0
Sturgeon	16.7	21.3	2.9	40.9
Peters	31.6	33.0	0.0	64.6

The Mirage Flats Irrigation District cooperates with the Nebraska Game and Parks Commission by operating the Box Butte Dam outlet works gates and the Dunlap Diversion Dam gates in a manner that avoids large sudden changes in the flows of the Niobrara River.

1975 SUMMARY

The Niobrara River flows and the carryover storage in Box Butte Reservoir were insufficient for a full water supply for the Mirage Flats Irrigation District lands and the active storage was evacuated by August 24th. This is the sixth consecutive year that all of the available active storage was used. The total precipitation in the Mirage Flats area was 12.43 inches, which is 81 percent of normal.

There were 10,950 acres irrigated, which is 94 percent of the acres with service available. The farm deliveries from the project water supply were 0.73 acre-foot per acre. An additional 0.5 acre-foot per acre of water was

provided by privately owned irrigation wells. The gross crop value was \$2,609,130, which is 93 percent of the 1974 value.

1976 OUTLOOK

The water level in the reservoir on January 1, 1976, was over two feet lower than it was on that day one year previously. The Mirage Flats Irrigation District will announce to their water users in the spring the amount of water that will be available from Box Butte storage. The project water supply is expected to be inadequate in 1976 as it has been in past years. The district plans, however, for the irrigators to continue the use of water from privately owned irrigation wells as a supplemental supply. There are 11,000 acres expected to be irrigated in 1976.

AINSWORTH UNIT, SANDHILLS DIVISION IN NEBRASKA

GENERAL

The water supply for 33,960 acres with service available in the Ainsworth Irrigation District is provided by Merritt Reservoir storage and Snake River flows. To avoid ice damage to the soil cement on the upstream face of Merritt Dam during the winter months, releases from Merritt Reservoir are regulated to maintain a water level about 5 feet below the top of the conservation capacity. When the reservoir surface clears of ice each spring, the conservation capacity is slowly filled. This operation greatly enhances the spring spawning of fish.

The Ainsworth Irrigation District cooperates with the Nebraska Game and Parks Commission by avoiding sudden large changes in reservoir releases. Small releases of 15 cubic feet per second, although not required, are made into the Snake River below Merritt Dam for fish, wildlife and recreation purposes.

1975 SUMMARY

The total precipitation of 11.31 inches for the year in the Merritt Dam vicinity was 65 percent of normal. The water supply was more than adequate to meet the irrigation requirements of 84,439 acre-feet to serve 33,694 acres of land irrigated in 1975. The gross crop value was \$10,277,182, which is over 350,000 dollars greater than the previous year.

1976 OUTLOOK

Releases from Merritt Reservoir will be regulated to slowly fill the conservation capacity by mid-May. The water supply is expected to be adequate for the irrigation of an estimated 33,700 acres.

SARGENT UNIT, MIDDLE LOUP DIVISION IN NEBRASKA

GENERAL

The Sargent Irrigation District has contracted with the Loup Basin Reclamation District for the operation and maintenance of the Milburn Diversion Dam and Sargent Canal system serving 13,650 acres in this unit. The water supply is diverted from the Middle Loup River into the Sargent Canal under an appropriated natural flow right from the State of Nebraska. These diversions may exceed the natural flow appropriation of 198 cubic feet per second by an exchange of storage from Sherman Reservoir, provided that water is available after all senior appropriations are satisfied and the excess is not greater than the storage releases from Sherman Reservoir.

1975 SUMMARY

The annual precipitation over the Sargent Unit was about 70 percent of normal. The diversions into Sargent Canal of 28,034 acre-feet were slightly below normal year forecasts. The diversions exceeded the appropriated right for 32 days during 1975. There were 13,042 acres irrigated with a gross crop value of \$3,842,744, which is about \$600,000 less than in 1974.

1976 OUTLOOK

The Loup Basin Reclamation District estimates that 13,000 acres in the Sargent Unit will be irrigated in 1976. The water supply is expected to be adequate.

FARWELL UNIT, MIDDLE LOUP DIVISION IN NEBRASKA

GENERAL


The Loup Basin Reclamation District operates and maintains the Arcadia Diversion Dam, Sherman Feeder Canal, Sherman Dam and Reservoir, and the Farwell Canal system serving 48,250 acres of Farwell Irrigation District land. Diversions are also made through the Arcadia Diversion Dam to 13,500 acres of non-project lands in the Middle Loup Public Power and Irrigation District under appropriated natural-flow water rights.

During the winter months, the pool level of Sherman Reservoir is normally regulated to 5 feet below the top of the conservation capacity to avoid ice damage to the upstream face of Sherman Dam. This low pool level also minimizes seepage from the reservoir into the ground water table. Each spring, diversions into Sherman Feeder Canal from the Middle Loup River are regulated to fill the conservation capacity of Sherman Reservoir by mid-June. The gradual rising water surface in the spring is ideal for fish spawning.

Whenever the flows in the Middle Loup River at Arcadia, Nebraska, exceed 6,000 cubic feet per second, and safe capacity flows are diverted into Sherman Feeder Canal to Sherman Reservoir, flood control benefits can be accrued by such operations.



Special studies are being made on the Farwell Canal system operation to evaluate the efficiency. This water stage recorder was installed on an operational wasteway near Dannebrog, Nebraska.



During the peak irrigation periods in the mid-summer months, all of the flows in the Middle Loup River are diverted at Arcadia Diversion Dam. In 1975 more than 160 thousand acre-feet were delivered to Middle Loup Public Power and Irrigation District canals and Sherman Reservoir.

1975 SUMMARY

The diversions from the Middle Loup River at Arcadia Diversion Dam were 32,045 acre-feet to Middle Loup Public Power and Irrigation District and 128,840 acre-feet into Sherman Feeder Canal.

Sherman Feeder Canal diversions into Sherman Reservoir were started on April 29, and the conservation capacity was filled on June 8, 1975. The precipitation at Sherman Dam was 15.01 inches, which is 72 percent of normal. Releases into the Farwell Canals totaled 108,733 acre-feet. Due to dry weather conditions causing low flows in the Middle Loup River and large irrigation demands, all active storage in Sherman Reservoir was evacuated by August 2nd. The Loup Basin Reclamation District reports that 43,702 acres of Farwell Irrigation District lands were irrigated in 1975. The gross crop value of \$10,488,828 was approximately 2,300,000 less than in 1974.

The Irrigation Management Services program was continued during 1975. A total of 53 farms, covering 6,053 acres were served by the program.

1976 OUTLOOK

Diversions from the Middle Loup River into Sherman Feeder Canal for the normal spring filling of the conservation capacity of Sherman Reservoir are expected to start in April.

Under most probable inflow conditions, a small shortage is expected for the 44,000 acres that are planned to be irrigated in 1976. This shortage is attributable to high system losses and the distribution of approximately 90% of the total season irrigation requirement during the months of July and August.

ARMEL UNIT, UPPER REPUBLICAN DIVISION IN COLORADO

GENERAL

Bonny Reservoir storage is transferred to Swanson Lake as required where releases into the Republican River are regulated to meet the industrial needs of the Amoco Production Company and Ladd Petroleum Corporation for their water flood operations in the Sleepy Hollow Oil Field, south of Bartley, Nebraska.

Bonny Reservoir inflows from the South Fork of the Republican River and Landsman Creek are released into Hale Ditch, as requested by the State Engineer of Colorado. Bonny storage water is available to Hale Ditch and other natural flow appropriators under temporary contracts. Much of the 700 acres served by Hale Ditch is now owned and operated by the Colorado Department of Natural Resources, Division of Wildlife, for wildlife purposes.

The normal operation pattern of Bonny Reservoir, with a slowly rising or stable pool, enhances fish spawning in the spring and affords excellent hunting conditions each fall.

1975 SUMMARY

The precipitation was 123 percent of normal while the inflow to Bonny Reservoir was equal to the most probable year forecast. The water supply was adequate to furnish 278 acre-feet to Amoco Production Company and 41 acre-feet to Ladd Petroleum Corporation.

There were 244 acre-feet of storage water delivered to the State of Colorado Department of Natural Resources under temporary contract sales for industrial or irrigation purposes during 1975. As directed by the Colorado Water Commissioner, 2,097 acre-feet of reservoir inflows from the South Fork of the Republican River and Landsman Creek were passed through Bonny Reservoir into Hale Ditch.

1976 OUTLOOK

Amoco Production Company and Ladd Petroleum Corporation will have an adequate water supply in 1976. Bonny storage will also be available for sale to Hale Ditch and other private irrigators under temporary contracts.

The prospects are excellent for hunting, fishing, and recreation uses.

GENERAL

The transportation of water from Enders Reservoir through 52 miles of Frenchman Creek channel to the Culbertson Diversion Dam created an erosion problem that made it necessary to initiate a control and stabilization program in 1964, which is expected to continue until 1978. The program has restored private access, protected private and public improvements, stabilized various reaches of channel banks, and reduced sediment from the flow in the Culbertson Canal and the stream at the Culbertson Diversion Dam.

The Culbertson Canal and the Culbertson Extension Canal systems serve 9,600 acres in the Frenchman Valley Irrigation District and 11,500 acres in the H & RW Irrigation District. The water supply for these lands is furnished by flows from Frenchman Creek and Stinking Water Creek and off-season storage in Enders Reservoir.

The normal operation of Enders Reservoir, with the gradual rise in water surface during the spring months, provides desirable fish spawning conditions. Large irrigation releases substantially lower the pool level by late summer, thereby limiting the fishing and recreational usage.

1975 SUMMARY

The annual precipitation at Enders Dam was 98 percent of normal, while the annual inflow into Enders Reservoir was between the normal and dry-year forecasts. The 1975 inflow of about 38,300 acre-feet is significantly below the average pre-construction historical runoff at Enders damsite (60,700 acre-feet, 1929-1947). This is the eighth consecutive year with below-normal inflows. The conservation pool was not filled during 1975. A total of 3,243 acre-feet was conserved by pumpback of seepage into the reservoir between the 1974 and 1975 irrigation seasons. Irrigation releases were stopped the 28th of August with 1,800 acre-feet of active storage remaining.

The farm delivery averaged about 14.6 inches per acre for the two districts. A few farmers were able to supplement their project water supply from private irrigation wells. The Frenchman Valley Irrigation District reports that 9,060 acres received water in 1975, and H & RW reports 11,124 acres, which are 94 and 97 percent, respectively, of the lands with service available. The gross crop values for Frenchman Valley Irrigation District was \$2,414,596, and for H & RW, \$2,723,421, which are a 21- and 32-percent decrease, respectively, from the previous year.

1976 OUTLOOK

The fall and early winter inflows into Enders Reservoir were about midway between normal and dry-year forecasts. If dry-year conditions prevail, the project water supply is expected to be inadequate to irrigate 9,000 acres in

Frenchman Valley Irrigation District and 11,000 acres in H & RW Irrigation District. As much as 3,400 acre-feet are expected to be conserved by pumping seepage into the Enders Reservoir.

The control and stabilization program of the Frenchman River channel will be continued in 1976.

MEEKER-DRIFTWOOD, RED WILLOW, AND CAMBRIDGE UNITS, FRENCHMAN-CAMBRIDGE
DIVISION IN NEBRASKA

GENERAL

The normal operation of Trenton Dam and Swanson Lake, Red Willow Dam and Hugh Butler Lake, and Medicine Creek Dam and Harry Strunk Lake during the spring months, with a slowly rising or stable pool level, enhances optimum spawning of northern and walleye pike. These lakes provide excellent opportunities for fishing, water sports, and recreation. The seepage below Red Willow and Medicine Creek Dams provides excellent fishing.


Service is provided for Frenchman-Cambridge Irrigation District by Meeker-Driftwood Canal to 16,476 acres; Red Willow Canal to 4,932 acres; Bartley Canal to 6,539 acres; and Cambridge Canal to 17,053 acres. The water supply for these lands is provided by storage in Swanson, Hugh Butler, and Harry Strunk Lakes, and flows of the Republican River and Red Willow and Medicine Creeks.

1975 SUMMARY

The precipitation at Trenton Dam was 103 percent of normal and the outflow to Swanson Lake was between the dry and normal-year forecasts. The content was 1,800 acre-feet below the top of conservation capacity at the beginning of the irrigation season in 1975. This storage and the 1975 inflows furnished full water supplies to project lands served by the Meeker-Driftwood and Bartley Canal systems. The Frenchman-Cambridge Irrigation District diverted 41,634 acre-feet into Meeker-Driftwood Canal to irrigate 16,156 acres, and 11,551 acre-feet into Bartley Canal for 6,289 acres.

The precipitation at Red Willow Dam was 98 percent of normal while the inflow into Hugh Butler Lake was above the normal-year forecasts. The water supply was more than adequate for Red Willow Canal diversions. The district diverted 10,011 acre-feet for the irrigation of 4,782 acres served by Red Willow Canal. There were an estimated 600 acre-feet of Red Willow Creek flows used downstream from Red Willow Dam for irrigation of non-project lands under senior water rights.

During late August, in order to conserve water in Swanson Lake, part of the demand for the Bartley Canal was satisfied by utilizing storage water from Hugh Butler Lake.



The Youth Conservation Corps constructed this shelter in 1975 near the south boat ramp of Hugh Butler Lake. This program has enhanced the visitation to the area lakes by the construction of these and other facilities.



View of the downstream face of Medicine Creek Dam. Note the trees and grass over the general area. It takes as long as twenty years from the time of construction for grasses and trees to cover the scars of construction. The dam was placed in operation in 1949.

The annual precipitation was 123 percent of normal at Medicine Creek Dam while the inflow was between the normal- and dry-year forecasts. The water supply was adequate for the diversion of 33,205 acre-feet for 16,633 acres served by the Cambridge Canal.

The 1975 gross crop value from the lands served by Meeker-Driftwood, Bartley, Red Willow, and Cambridge Canals was \$12,712,180, as compared to \$17,012,178 in 1974.

There were 56 acre-feet of storage water from Hugh Butler Lake sold under temporary contracts to private irrigators in Red Willow valley. Also, 270 acre-feet of storage water from Harry Strunk Lake were sold to private irrigators in Medicine Creek valley.

1976 OUTLOOK

The carryover storage and 1976 flows are forecasted to furnish an adequate water supply to irrigate 43,900 acres in the Frenchman-Cambridge Irrigation District. It is estimated that 16,200 acres will be served from the Meeker-Driftwood Canal, 16,600 acres from the Cambridge Canal, 4,800 acres from Red Willow Canal, and 6,300 acres from Bartley Canal.

ALMENA UNIT, KANSASKA DIVISION IN KANSAS

GENERAL

There are 5,350 acres with service available in the Almena Irrigation District. The project water supply is provided by Prairie Dog Creek flows and Norton Reservoir storage.

The water service contract for the City of Norton, Kansas, provides for a maximum annual use of 1,600 acre-feet from Norton Reservoir.

1975 SUMMARY

The annual precipitation at Norton Dam was 128 percent of normal. The total 1975 inflow was slightly above the normal-year forecast.

Of the 1.64 acre-feet per acre of farm delivery to 5,280 acres of Almena Irrigation District land, 0.80 acre-feet per acre was available from project water supply and the balance from private irrigation wells.

Heavy rains during June 1975 above Norton Reservoir resulted in an inflow more than double the normal June inflow. The reservoir elevation rose nearly 12 feet during the month. Until this time, no active storage was available for irrigation releases.

For the fifth consecutive year, the district used water from privately owned irrigation wells to supplement the project water supply.

There were 9,018 acre-feet released from Norton Reservoir, of which the Almaena Irrigation District diverted 6,697 acre-feet from Prairie Dog Creek. The water users pumped 4,440 acre-feet from irrigation wells as a supplemental supply to project lands. This well water combined with available project water provided a full irrigation supply. The average crop yields were the highest of the 13 districts discussed in this report and the highest ever for the District. The 5,280 acres that were irrigated in 1975 produced a gross crop value of \$1,837,493 (\$348.01 per acre). This is 88% of the crop value for 1974.

The City of Norton used 883 acre-feet to municipal water during 1975.

1976 OUTLOOK

The Almaena Irrigation District expects to deliver water to 5,300 acres if an adequate water supply is available. If 1976 is a dry year without significant run-off producing storms above Norton Reservoir, a requirement shortage of approximately 11,000 acre-feet may be experienced. If normal inflow into the reservoir and normal rainfall over the irrigated area occur in 1976, a full water supply can be furnished the irrigation district lands from Norton storage and Prairie Dog Creek flows.

The City of Norton requirements are expected to be met in full in 1976.

FRANKLIN, SUPERIOR-COURTLAND, AND COURTLAND UNITS, BOSTWICK DIVISION IN NEBRASKA AND KANSAS

GENERAL

Harlan County Lake storage and Republican River Basin flows provide a project water supply for 22,787 acres in the Bostwick Irrigation District in Nebraska, and 12,771 acres in the Kansas-Bostwick Irrigation District above Lovewell Reservoir and, together with White Rock Creek flows and Lovewell Reservoir Storage, furnish a water supply for 27,329 acres below Lovewell Reservoir in the Kansas-Bostwick Irrigation District.

The lands in the Franklin and Superior-Courtland Units are in the Bostwick Irrigation District in Nebraska. The lands in the Courtland Unit are in the Kansas-Bostwick Irrigation District.

As recommended by the Kansas State Board of Health, the Nebraska State Department of Health, and the U. S. Public Health Service, it is desirable, for the sanitary quality of the stream, to maintain daily flows of 40 cubic feet per second in the Republican River below Superior, Nebraska, from

June through September. During normal years when the Superior Canal and Courtland Canal (in Nebraska) are in operation, the return flows of seepage and surface irrigation runoff plus the natural flow pickup in the Republican River below the Superior-Courtland Diversion Dam will meet this recommended flow. If it is possible through normal reservoir operations to comply with the above recommendations, the Bureau, as it has done in the past, will do so; however, during dry years when the forecasted reasonable minimum inflows will not fill Harlan County Lake before the start of the next irrigation season, the available flows in the Republican River below Harlan County Dam plus a minimum release of 10 cubic feet per second from Harlan County Lake are diverted into the Courtland Canal to be stored in Lovewell Reservoir. When this condition exists, the flow in the Republican River below Superior, Nebraska, will be less than the 40 cubic feet per second that was recommended.

At the request of the Kansas-Forestry, Fish and Game Commission, the Kansas-Bostwick Irrigation District and the Bureau of Reclamation maintain, when it is possible, a flow of 20 cubic feet per second into Lovewell Reservoir when the Courtland Canal is in operation and the conservation pool is below capacity. This recommended inflow provides excellent fishing around the canal inlet to the reservoir. The seepage below Lovewell Dam into White Rock Creek maintains a small live stream throughout the year.

1975 SUMMARY - BOSTWICK DIVISION HARLAN COUNTY OPERATIONS

The precipitation at Harlan County Dam was 123 percent of normal, while the annual inflow was between the dry- and normal-year forecasts. The conservation capacity of Harlan County Lake was full at the beginning of the 1975 irrigation season. The 32,987 irrigated acres in the Bostwick Division in Nebraska and Kansas above Lovewell Dam were furnished a full water supply. Also 43,740 acre-feet were delivered to Lovewell Reservoir through Courtland Canal.

During the irrigation season, the mean daily flows in the Republican River below Superior, Nebraska, were greater than the 40 cubic feet per second recommended by various State and Federal health agencies.

1975 SUMMARY - BOSTWICK DIVISION - NEBRASKA

The Bostwick Irrigation District in Nebraska diverted 52,810 acre-feet for the irrigation of 20,797 acres. The gross crop value was \$5,524,766, which is about \$964,000 less than in 1974.

1975 SUMMARY - BOSTWICK DIVISION- KANSAS

The Kansas-Bostwick Irrigation District diverted a total of 79,574 acre-feet to serve 12,190 acres above Lovewell Dam and 19,587 acres below

Lovewell. The gross crop value was \$8,273,460, which is \$1,000,000 less than in the previous year.

1976 OUTLOOK - BOSTWICK DIVISION

The Bostwick Irrigation District in Nebraska and the Kansas-Bostwick Irrigation District expect to deliver water to 21,000 and 32,000 acres, respectively. The storage in Harlan County Lake and Lovewell Reservoir and the flows of the Republican River and White Rock Creek are forecasted to furnish an adequate water supply for the Bostwick lands.

CHAPTER IV - SMOKY HILL RIVER BASIN

KIRWIN UNIT, SOLOMON DIVISION IN KANSAS

GENERAL

The water supply for the 11,435 acres of land in the Kirwin Irrigation District is furnished by storage from Kirwin Reservoir and inflows from the North Fork of the Solomon River.

The operation of Kirwin Dam and Reservoir affords many opportunities for recreation, fishing, hunting, water sports, spawning of fish, and for preservation of waterfowl species.

1975 SUMMARY

The precipitation was 116 percent of normal. The inflow was between the normal- and wet-year forecasts. The water supply was adequate to fully meet the irrigation requirements.

The Kirwin Irrigation District diverted 21,399 acre-feet for irrigation of 9,410 acres. The gross crop value from these acres was \$2,365,720, which is about \$216,000 less than in 1974.

1976 OUTLOOK

The Kirwin Irrigation District estimates that 9,400 acres will be irrigated in 1976. The carryover storage in Kirwin Reservoir and the forecasted inflows from the North Fork of the Solomon River are expected to be adequate to irrigate these lands.


A pilot Irrigation Management Services program is expected to begin on the Kirwin and Webster Irrigation Districts during the 1976 irrigation season. This program will cover approximately 2,500 acres within the two districts.

WEBSTER UNIT, SOLOMON DIVISION IN KANSAS


GENERAL


The Webster Irrigation District has service available to 8,500 acres. The project water supply is provided by Webster Reservoir storage and flows of the South Fork of the Solomon River.

The Kansas Forestry, Fish and Game Commission operates a seasonal fish hatchery at the Webster Dam spillway stilling basin during the spring




June floods on central Kansas streams greatly increased the storage in Norton, Kirwin, Webster, Glen Elder, Lovewell and Cedar Bluff Reservoirs. The above view illustrates the magnitude of the floods with over-bank flows in Bow Creek above Kirwin Reservoir on June 20, 1975. The view below shows the north fork of the Solomon River at Lenora, Kansas, on June 19, 1975.





An FM repeater two-way radio system was completed in 1975 providing communications between the Kansas River Projects Office and the twelve dams included in this report.



Releases near bank full capacity were made from Waconda Lake during late June 1975. These releases were made to test the operation of the Glen Elder Dam outlet works at flows above 3,000 cubic feet per second.

months. Unless absolutely necessary for flood control releases, the spillway gates are not opened while the hatchery is in operation.

1975 SUMMARY

In 1975, the precipitation at Webster Dam was normal. The inflow of 52,530 acre-feet was between normal- and wet-year forecasts.

During 1975, 14,960 acre-feet were diverted to Osborne Canal providing a full water supply for irrigation of 6,362 acres. The Webster Irrigation District reports a gross 1975 crop value of \$1,690,797.

1976 OUTLOOK

The carryover storage and the flows in the South Fork of the Solomon River are expected to be adequate to irrigate 6,350 acres in the Webster Irrigation District in 1976.

A pilot Irrigation Management Services program is expected to begin on the Kirwin and Webster Irrigation Districts during the 1976 irrigation season. This program will cover approximately 2,500 acres within the two districts.

GLEN ELDER UNIT, SOLOMON DIVISION IN KANSAS

GENERAL

Releases from Waconda Lake will be regulated as required for the City of Beloit, Kansas, and water right administration.

The water service contract with Beloit provides for a normal annual use of up to 2,000 acre-feet of Waconda Lake storage as measured at the Glen Elder Dam river outlet works. In any water year that the City's water supply is insufficient and there is surplus water in Waconda Lake, such additional water may be delivered to the City at a rate of \$15.00 per acre-foot.

The water service contract with the Mitchell County Rural Water District No. 2 provides for use of storage water as available from Waconda Lake, not to exceed 1,009 acre-feet per calendar year.

The available facilities along the shores of Waconda Lake and the large water surface area afford opportunities to many thousands of people for picnics, sightseeing, recreation, water sports, hunting, and fishing.

When compatible with flood control operations, the operating criteria

for Waconda Lake provide for a stable or rising pool level during the fish spawning period each spring.

1975 SUMMARY

The precipitation at Glen Elder Dam was 96 percent of normal and the inflow slightly above that expected in normal-year forecasts.

A total of 107 acre-feet was released for use by the City of Beloit, Kansas.

Modification of the outlet works at Glen Elder Dam was completed during 1975. This modification will enable releases to the WCH&T Rural Water District No. 2, Mitchell County, Kansas.

At the request of the State of Kansas, releases from Waconda Lake were increased from 150 to 250 cfs for a three-day period beginning April 15th. This increase was made to enhance upstream movement of fish below Glen Elder Dam.

1976 OUTLOOK

The municipal requirements of Beloit will be met in full with releases as required from Waconda Lake. It is expected that the Water Commissioner of the State of Kansas will request that inflows be passed through the lake for water right administration.

To facilitate the investigation of the condition of the soil cement on the upstream face of Glen Elder Dam, releases will be regulated beginning early July to lower the water level to 1453.0 by mid-August. This is 2.6 feet below the top of the conservation pool. This operation of lowering the pool elevation was not a requirement at the time Exhibit 14 was plotted. Therefore, Exhibit 14 represents normal operation without any additional drawdown.

Releases (up to 1,009 acre-feet per year) to the WCH&T Rural Water District No. 2 are expected to begin during early 1976.

CEDAR BLUFF UNIT, SMOKY HILL DIVISION IN KANSAS

GENERAL

Cedar Bluff Reservoir storage and Smoky Hill River flows provide a full water supply for the 6,800 acres in the Cedar Bluff Irrigation District, and up to 4,000 acre-feet for the Cedar Bluff National Fish Hatchery. Cedar Bluff storage also furnishes a maximum of 2,000 acre-feet per annum if required for the City of Russell, Kansas.

The return flows from the Cedar Bluff National Fish Hatchery and seepage from Cedar Bluff Reservoir maintain fisheries and enhance fishing in the Smoky Hill River below Cedar Bluff Dam.

1975 SUMMARY

The precipitation was 88 percent of normal. The inflow was just below the normal-year forecast. The water supplies for the Cedar Bluff Irrigation District and the Cedar Bluff National Fish Hatchery were furnished in full. No releases were required for the City of Russell.

The Cedar Bluff Irrigation District diverted 14,997 acre-feet to irrigate 6,755 acres of project lands. The gross crop value of \$1,515,177 was a decrease of nearly \$263,000 from the previous year.

The Cedar Bluff National Fish Hatchery diverted 1,721 acre-feet. Of this, 868 acre-feet were passed through the hatchery facilities and returned to the Smoky Hill River below Cedar Bluff Dam.

1976 OUTLOOK

The carryover storage in Cedar Bluff Reservoir and the inflows from the Smoky Hill River are expected to fully meet the requirements of the Cedar Bluff National Fish Hatchery, the City of Russell, and the irrigation of 6,750 acres of project lands.

TABLES
AND
EXHIBITS

TABLE 1
RESERVOIR DATA - NIOBRARA, LOWER PLATTE AND KANSAS RIVER BASINS

		CAPACITY ALLOCATIONS 1/			
RESERVOIR		DEAD	LIVE CONSERVATION		FLOOD CONTROL
			Inactive	Active	
Box Butte	- Elevation Ft.	3969.0	3976.5	4007.0	---
	Total Acre-feet	640	2,275	31,060	---
	Net Acre-feet	640	1,635	28,785	---
Merritt	- Elevation Ft.	2875.0	2896.0	2946.0	---
	Total Acre-feet	1,614	6,800	74,486	---
	Net Acre-feet	1,614	5,186	67,686	---
Sherman	- Elevation Ft.	2118.5	2129.0	2162.3	---
	Total Acre-feet	3,839	10,496	69,076	---
	Net Acre-feet	3,839	6,657	58,580	---
Bonny	- Elevation Ft.	3635.5	3638.0	3672.0	3710.0
	Total Acre-feet	1,418	2,134	41,340	170,160
	Net Acre-feet	1,418	716	39,206	128,820
Swanson Lake	- Elevation Ft.	2710.0	2720.0	2752.0	2773.0
	Total Acre-feet	4,101	15,510	120,160	253,950
	Net Acre-feet	4,101	11,409	104,650	133,790
Enders	- Elevation Ft.	3080.0	3082.4	3112.3	3127.0
	Total Acre-feet	8,467	9,968	44,480	74,520
	Net Acre-feet	8,467	1,501	34,512	30,040
Hugh Butler Lake	- Elevation Ft.	2552.0	2558.0	2581.8	2604.9
	Total Acre-feet	6,313	10,450	37,776	86,630
	Net Acre-feet	6,313	4,137	27,326	48,854
Harry Strunk Lake	- Elevation Ft.	2335.0	2343.0	2366.1	2386.2
	Total Acre-feet	4,911	9,548	37,141	89,313
	Net Acre-feet	4,911	4,637	27,593	52,172
Norton	- Elevation Ft.	2275.0	2280.4	2304.3	2331.4
	Total Acre-feet	2,718	5,284	35,935	134,740
	Net Acre-feet	2,718	2,566	30,651	98,805
Harlan County Lake	- Elevation Ft.	1885.0	1927.0	1946.0	1973.5
	Total Acre-feet	0	126,727	319,787	828,776
	Net Acre-feet	0	126,727	193,060	508,989
Lovewell	- Elevation Ft.	1562.0	1571.7	1582.6	1595.3
	Total Acre-feet	5,054	16,760	41,690	92,150
	Net Acre-feet	5,054	11,706	24,930	50,460
Kirwin	- Elevation Ft.	1693.0	1697.0	1729.25	1757.3
	Total Acre-feet	6,385	9,785	99,435	314,550
	Net Acre-feet	6,385	3,400	89,650	215,115
Webster	- Elevation Ft.	1855.5	1860.0	1892.45	1923.7
	Total Acre-feet	2,184	5,300	77,370	260,740
	Net Acre-feet	2,184	3,116	72,070	183,370
Waconda Lake	- Elevation Ft.	1407.8	1428.0	1455.6	1488.3
	Total Acre-feet	1,236	36,671	241,460	963,775
	Net Acre-feet	1,236	35,435	204,789	722,315
Cedar Bluff	- Elevation Ft.	2090.0	2107.8	2144.0	2166.0
	Total Acre-feet	8,261	35,320	185,090	376,950
	Net Acre-feet	8,261	27,059	149,770	191,860
Total Storage (A.F.)		57,141	303,028	1,456,286	3,646,254
Total Net Acre-feet		57,141	245,887	1,153,258	2,364,590

1/ Includes space for sediment storage.

TABLE 2
SUMMARY OF 1975 OPERATIONS

MIRAGE FLATS PROJECT
BOX BUTTE RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	MIRAGE FLATS CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	1,459	46	61	0.10	8,806	0	0
Feb.	1,934	42	73	0.24	10,625	0	0
Mar.	2,609	49	147	1.10	13,038	0	0
Apr.	2,999	60	323	1.59	15,654	0	0
May	1,527	61	405	2.52	16,715	0	0
June	535	60	509	2.47	16,681	0	0
July	0	8,637	576	2.35	7,468	7,633	3,621
Aug.	838	7,222	212	1.09	872	7,071	4,323
Sep.	1,438	192	94	0.34	2,024	151	90
Oct.	931	43	79	0.26	2,833	0	0
Nov.	1,577	42	97	0.18	4,271	0	0
Dec.	1,881	43	57	0.17	6,052	0	0
TOTAL	17,728	16,497	2,633	12.43	---	14,855	8,034

NOTE.--Mirage Flats Canal:
Acres irrigated 1975 -- 10,950

SANDHILLS DIVISION
AINSWORTH UNIT
MERRITT RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	AINSWORTH CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	12,937	12,311	276	0.32	61,166	0	0
Feb.	12,236	11,697	283	0.14	61,422	0	0
Mar.	14,472	10,959	403	1.00	64,532	0	0
Apr.	15,118	7,340	824	1.03	74,486	0	0
May	15,062	13,914	1,148	1.32	74,486	3,819	480
June	13,867	11,937	1,341	3.08	75,075	3,967	1,067
July	14,045	34,935	1,623	1.61	52,558	33,926	27,254
Aug.	15,622	34,046	949	1.32	37,385	33,967	27,906
Sep.	15,275	9,800	533	0.32	37,327	8,710	4,983
Oct.	15,742	1,073	559	0.37	51,437	50	70
Nov.	13,554	4,183	397	0.53	60,411	0	0
Dec.	13,357	12,079	297	0.27	61,422	0	0
TOTAL	173,917	165,078	8,583	11.31	---	84,439	61,760

NOTE.--Ainsworth Canal:
Acres irrigated 1975 -- 33,694

MIDDLE LOUP DIVISION

MIDDLE LOUP UNIT 1/
MIDDLE LOUP PUBLIC

FARWELL UNIT

SARGENT UNIT SARGENT CANAL		MIDDLE LOUP PUBLIC POWER CANALS		SHERMAN RESERVOIR		FARWELL CANALS	
Divisions To Canal (AF)	Delivered To Farms (AF)	Divisions To Canals (AF)	Diversion To Sherman Feeder Canal (AF)	Inflow (AF)	Outflow (AF)	Release To Canals (AF)	Delivered To Farms (AF)
Jan.	0	0	0	0	1,390	0	0
Feb.	0	0	0	0	1,579	0	0
Mar.	0	0	0	0	473	0	0
Apr.	0	0	0	0	1,679	0	0
May	676	11	2,259	440	5,232	3,184	14
June	2,364	99	3,333	26,860	19,541	14,971	149
July	10,612	7,126	10,435	19,680	44,372	42,633	23,431
Aug.	11,954	9,218	12,426	16,180	44,265	42,881	26,823
Sep.	2,428	1,518	3,592	12,750	5,892	5,064	2,843
Oct.	0	0	0	27,280	437	0	0
Nov.	0	0	0	25,650	1,384	0	0
Dec.	0	0	0	0	1,073	0	0
TOTAL	28,034	17,972	32,045	0	1,516	108,733	53,260

1/ Non-Project.

NOTE.--Sargent Canal: Middle Loup P. P. Canals: Farwell Canals:
Acres irrigated 1975 -- 13,042 Acres irrigated 1975 -- 13,694 Acres irrigated 1975 -- 43,702

UPPER REPUBLICAN DIVISION
ARMEL UNIT
BOHNY RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	Outflow To Hale Ditch (AF)	Industrial Uses (AF)
Jan.	1,800	310	0	0.34	39,530	0	26
Feb.	1,510	310	0	0.13	40,730	0	24
Mar.	1,324	344	60	0.56	41,650	0	29
Apr.	1,970	1,808	592	1.17	41,220	374	29
May	4,570	954	1,006	6.46	43,830	382	25
June	6,380	4,600	1,030	4.55	44,580	272	27
July	1,970	4,424	1,376	2.92	40,750	493	27
Aug.	530	694	1,196	1.40	39,390	318	23
Sep.	140	628	782	0.53	38,120	258	26
Oct.	890	346	894	0.06	37,770	0	30
Nov.	1,460	350	140	1.80	38,740	0	26
Dec.	1,872	372	0	0.16	40,240	0	27
TOTAL	24,416	15,140	7,076	20.08	---	2,097 2/	319

2/ includes 244 A.F. under temporary contracts.

TABLE 2
SUMMARY OF 1975 OPERATIONS

FRENCHMAN-CAMBRIDGE DIVISION
FRENCHMAN UNIT

ENDERS RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	CULBERTSON CANAL Diversions To Canal 1/ (AF)	CULBERTSON EXT. CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	3,190	20	0	0.08	27,570	0	0	0
Feb.	2,756	56	0	0.48	30,270	0	0	0
Mar.	2,260	60	0	0.76	32,470	0	0	0
Apr.	2,810	60	480	2.05	34,740	3,567	0	0
May	3,200	62	708	4.25	37,170	658	3,000	78
June	3,620	116	784	4.82	39,890	448	3,824	300
July	4,540	18,834	986	2.85	24,610	6,941	9,585	6,189
Aug.	2,860	14,846	574	0.44	12,050	7,843	8,614	5,558
Sep.	3,290	0	330	0.81	15,010	0	0	0
Oct.	3,160	0	340	0.09	17,830	0	0	0
Nov.	3,090	0	60	1.50	20,860	0	0	0
Dec.	3,560	0	0	0.18	24,420	0	0	0
TOTAL	38,336	34,054	4,262	18.31	---	19,457	25,023	12,125

1/ A.F. delivery to farms unavailable
due to lack of measuring devices.

NOTE.--Culbertson Canal:

Acres irrigated 1975 -- 9,060

Culbertson Extension Canal:

Acres irrigated 1975 -- 11,124

FRENCHMAN-CAMBRIDGE DIVISION (Continued)
MEEKER-DRIFTWOOD UNIT

SWANSON LAKE

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	MEEKER-DRIFTWOOD Diversions To Canal (AF)	Delivered To Farms (AF)	BARTLEY CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	5,280	60	0	0.12	74,210	0	0	0	0
Feb.	6,636	56	0	0.55	80,970	0	0	0	0
Mar.	7,400	62	28	0.60	88,100	0	0	0	0
Apr.	9,580	60	1,360	1.81	96,260	0	0	0	0
May	8,350	2,260	2,030	3.85	100,320	1,534	8	910	28
June	22,189	1,783	2,396	6.84	118,330	1,765	0	486	0
July	4,520	27,842	3,098	1.32	91,910	18,645	14,715	5,261	4,308
Aug.	480	20,980	3,380	0.62	68,030	16,174	12,441	3,890	3,016
Sep.	114	3,922	1,732	1.15	62,490	3,516	2,308	1,004	844
Oct.	184	62	1,452	0.06	61,160	0	0	0	0
Nov.	1,130	60	240	2.84	61,990	0	0	0	0
Dec.	5,382	62	0	0.13	67,310	0	0	0	0
TOTAL	71,245	57,209	15,716	19.89	---	41,634	29,482	11,551	8,196

NOTE.--Meeker-Driftwood Canal:

Acres irrigated 1975 -- 16,156

Bartley Canal:

Acres irrigated 1975 -- 6,289

FRENCHMAN-CAMBRIDGE DIVISION (Continued)
RED WILLOW UNIT

HUGH BUTLER LAKE

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	RED WILLOW CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	1,520	310	0	0.23	30,970	0	0
Feb.	1,436	306	0	0.65	32,100	0	0
Mar.	2,020	380	0	0.68	33,740	0	0
Apr.	2,480	320	570	1.94	35,330	0	0
May	1,910	1,022	838	1.88	35,380	537	28
June	5,220	1,308	842	6.95	38,450	692	16
July	1,680	6,372	1,148	1.52	32,610	4,903	3,843
Aug.	2,200	4,928	922	1.34	28,960	2,973	2,233
Sep.	1,100	1,916	544	0.85	27,600	906	601
Oct.	1,270	320	500	0.04	28,050	0	0
Nov.	1,490	312	88	3.19	29,140	0	0
Dec.	1,950	310	0	0.05	30,780	0	0
TOTAL	24,276	17,804 2/	5,452	19.32	---	10,011	6,721

2/ Includes 56 A.F. under temporary contracts.

NOTE.--Red Willow Canal:

Acres irrigated 1975 -- 4,782

FRENCHMAN-CAMBRIDGE DIVISION (Continued)
CAMBRIDGE UNIT

HARRY STRUNK LAKE

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	CAMBRIDGE CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	3,150	60	0	0.10	26,290	0	0
Feb.	2,686	56	0	0.63	28,920	0	0
Mar.	3,612	62	0	1.21	32,470	0	0
Apr.	3,920	60	550	1.16	35,780	0	0
May	2,870	640	940	1.23	37,070	346	0
June	12,400	8,686	964	9.83	39,820	2,781	0
July	3,760	14,476	1,104	3.97	28,000	15,810	12,698
Aug.	2,970	10,330	750	1.80	19,890	12,361	9,768
Sep.	2,040	1,526	454	0.99	19,950	1,907	1,119
Oct.	2,490	124	466	0.09	21,850	0	0
Nov.	2,940	120	100	2.44	24,570	0	0
Dec.	3,364	124	0	0.09	27,810	0	0
TOTAL	46,202	36,264 3/	5,328	23.54	---	33,205	23,585

3/ Includes 269.5 A.F. under temporary contracts.

NOTE.--Cambridge Canal:

Acres irrigated 1975 -- 16,633

TABLE 2
SUMMARY OF 1975 OPERATIONS

KANASKA DIVISION
ALMENA UNIT

NORTON RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	Release To City Of Norton (AF)	ALMENA CANAL Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	172	62	0	0.06	3,860	49	0	0
Feb.	190	70	0	0.58	3,980	68	0	0
Mar.	342	92	0	0.83	4,230	47	0	0
Apr.	480	120	180	1.93	4,410	52	0	0
May	512	160	272	3.21	4,490	97	73	0
June	10,180	182	388	7.41	14,100	68	440	0
July	226	5,258	688	2.44	8,380	163	4,162	2,854
Aug.	5,140	2,648	582	4.66	10,290	114	2,018	1,368
Sep.	140	140	380	1.43	9,910	85	4	0
Oct.	98	122	366	0.20	9,520	54	0	0
Nov.	290	116	84	3.31	9,610	49	0	0
Dec.	232	62	0	0.05	9,780	37	0	0
TOTAL	18,002	9,032	2,940	26.11	---	883	6,697	4,222

NOTE--Almena Canal:

Acres irrigated 1975 -- 5,280

BOSTWICK DIVISION
FRANKLIN UNIT

HARLAN COUNTY LAKE

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	Release To Canal (AF)	Delivered To Farms (AF)	Release To Canal (AF)	Delivered To Farms (AF)
Jan.	9,300	620	0	0.04	247,130	0	0	0	0
Feb.	9,640	560	0	0.74	256,210	0	0	0	0
Mar.	15,760	620	0	0.70	271,350	0	0	0	0
Apr.	16,230	600	3,500	2.36	283,480	0	0	0	0
May	15,840	1,990	6,360	5.64	290,970	0	0	0	0
June	72,200	10,738	6,312	4.72	346,120	2,918	8	8	0
July	21,270	69,840	9,000	3.82	288,550	13,461	6,926	1,911	1,326
Aug.	22,120	44,376	6,514	3.83	259,780	12,211	5,814	1,468	916
Sep.	2,600	6,196	4,664	0.89	251,520	1,023	210	0	0
Oct.	4,460	620	4,530	0.10	250,830	0	0	0	0
Nov.	6,880	600	780	2.73	256,330	0	0	0	0
Dec.	9,750	620	0	0.09	265,460	0	0	0	0
TOTAL	205,050	137,380	41,660	25.66	---	29,613	12,958	3,387	2,242

NOTE--Franklin Canal:

Acres irrigated 1975 -- 10,249

Naponee Canal:

Acres irrigated 1975 -- 1,405

BOSTWICK DIVISION (Continued)
SUPERIOR-COURTLAND UNIT

MONTH	FRANKLIN PUMP CANAL		SUPERIOR CANAL		Total Diversion (AF)	NEBRASKA USE		KANSAS USE	
	Diversions To Canal (AF)	Delivered To Farms (AF)	Diversions To Canal (AF)	Delivered To Farms (AF)		Total (AF)	Delivered To Farms (AF)	Diversions To Canal (AF)	Delivered To Farms (AF)
Jan.	0	0	0	0	0	0	0	0	0
Feb.	0	0	0	0	0	0	0	0	0
Mar.	0	0	0	0	0	0	0	0	0
Apr.	0	0	0	0	900	0	0	0	0
May	0	0	1,334	0	4,905	7	6	248	33
June	0	0	57	0	3,542	0	0	708	0
July	2,043	882	7,811	4,858	36,293	1,226	1,096	16,493	10,557
Aug.	1,406	764	4,983	2,643	28,017	526	438	9,791	6,278
Sep.	0	0	392	77	7,442	25	16	679	252
Oct.	0	0	0	0	0	0	0	0	0
Nov.	0	0	0	0	0	0	0	0	0
Dec.	0	0	0	0	0	0	0	0	0
TOTAL	3,449	1,646	14,577	7,578	81,099	1,784	1,556	27,919	17,120

NOTE--Franklin Pump Canal:

Acres irrigated 1975 -- 2,041

Superior Canal:

Acres irrigated 1975 -- 5,340

NOTE--Courtland Canal--Nebraska Use:

Acres irrigated 1975 -- 1,762

Courtland Canal--Kansas Use:

Acres irrigated 1975 -- 12,190

BOSTWICK DIVISION (Continued)
COURTLAND UNIT

LOVEWELL RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	COURTLAND (Below) Release To Canal (AF)	Delivered To Farms (AF)
Jan.	790	60	0	0.75	32,220	0	0
Feb.	1,476	56	0	1.29	33,640	0	0
Mar.	6,400	60	0	1.44	39,980	0	0
Apr.	2,424	190	824	2.64	41,390	134	0
May	3,801	2,054	1,387	3.25	41,750	1,978	14
June	21,274	10,526	1,288	6.29	51,210	2,227	0
July	20,580	33,728	1,882	0.84	36,180	28,948	20,860
Aug.	15,872	17,557	1,575	2.68	32,920	17,433	10,911
Sep.	5,551	905	976	0.99	36,590	885	214
Oct.	330	62	1,318	0.03	35,540	0	0
Nov.	850	60	260	3.00	36,070	0	0
Dec.	312	62	0	0.18	36,320	0	0
TOTAL	79,660	65,320	9,510	23.38	---	51,655	31,999

NOTE--Courtland Canal below Lovewell:

Acres irrigated 1975 -- 19,587

TABLE 2
SUMMARY OF 1975 OPERATIONS

SOLOMON DIVISION
KIRWIN UNIT

KIRWIN RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	KIRWIN CANAL Release To Canal (AF)	Delivered To Farms (AF)
Jan.	950	0	250	0.06	31,210	0	0
Feb.	1,070	0	150	0.56	32,130	0	0
Mar.	1,750	0	300	0.95	33,580	0	0
Apr.	1,952	0	702	1.83	34,830	0	0
May	2,332	0	1,212	6.52	35,950	0	0
June	34,858	1,144	1,554	6.70	68,110	1,142	0
July	3,468	10,890	2,428	0.34	58,260	10,707	6,402
Aug.	7,220	9,318	1,942	3.87	54,220	9,072	5,940
Sep.	214	564	1,310	2.40	52,560	478	117
Oct.	24	0	1,294	0.05	51,250	0	0
Nov.	1,650	0	1,030	2.65	51,910	0	0
Dec.	1,740	0	770	0.00	52,880	0	0
TOTAL	57,228	21,916	12,942	25.93	---	21,399	12,459

NOTE.--Kirwin Canal:

Acres irrigated 1975 -- 9,410

SOLOMON DIVISION (Continued)
WEBSTER UNIT

WEBSTER RESERVOIR

MONTH	Inflow (AF)	Outflow (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	OSBORNE CANAL Diversion To Canal (AF)	Delivered To Farms (AF)
Jan.	400	0	210	0.16	16,040	0	0
Feb.	530	0	100	0.67	16,470	0	0
Mar.	1,050	0	200	1.08	17,320	0	0
Apr.	1,502	0	502	1.94	18,320	0	0
May	2,228	0	858	5.85	19,690	0	0
June	38,034	250	1,224	6.36	56,250	609	0
July	2,698	9,352	2,136	0.33	47,460	7,819	3,917
Aug.	3,200	7,866	1,694	3.19	41,100	6,204	3,958
Sep.	38	86	1,582	1.11	39,470	58	52
Oct.	20	0	1,260	0.02	38,230	0	0
Nov.	1,180	0	1,010	3.17	38,400	0	0
Dec.	1,650	0	760	0.00	39,290	0	0
TOTAL	52,530	17,554	11,536	23.88	---	14,690	7,927

NOTE.--Osborne Canal:

Acres irrigated 1975 -- 6,362

SOLOMON DIVISION (Continued)
GLEN ELDER UNIT

WACONDA LAKE

MONTH	Inflow (AF)	Outflow 1/ (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	City of Beloit (AF)	Controlled Releases 2/ (AF)
Jan.	7,390	732	1,548	1.00	237,940	107	625
Feb.	6,676	3,486	800	1.15	240,330	0	3,486
Mar.	11,352	9,672	1,550	1.86	240,460	0	9,672
Apr.	13,982	9,924	3,688	3.13	240,830	0	9,924
May	14,246	4,426	5,920	3.71	244,730	0	4,426
June	80,318	29,768	6,530	5.45	288,750	0	29,768
July	6,918	50,266	8,712	0.87	236,690	0	50,266
Aug.	10,586	2,270	7,946	2.97	237,060	0	2,270
Sep.	3,048	1,152	4,906	1.59	234,050	0	1,152
Oct.	2,360	1,540	4,710	0.02	230,160	0	1,540
Nov.	8,000	590	3,770	2.46	233,800	0	590
Dec.	7,033	433	2,830	0.20	237,570	0	433
TOTAL	171,909	114,259	52,910	24.41	---	107	114,152

1/ No releases required for City of Beloit, Kansas.

2/ Flood control and water right administration.

SMOKY HILL DIVISION
ELLIS UNIT

CEDAR BLUFF RESERVOIR

MONTH	Inflow (AF)	Outflow 3/ (AF)	Evap. (AF)	Precip. (Inches)	End Of Month Content (AF)	CEDAR BLUFF CANAL Release To Canal (AF)	Delivered To Farms (AF)	Release To Fish Hatchery (AF)
Jan.	318	138	550	0.07	108,960	0	0	65
Feb.	502	112	300	0.86	109,050	0	0	59
Mar.	800	110	600	0.67	109,140	0	0	64
Apr.	1,834	120	1,524	1.75	109,330	0	0	89
May	3,371	1,201	2,630	4.92	108,870	932	0	229
June	21,599	808	2,751	5.63	126,310	475	0	271
July	703	7,388	3,675	0.38	116,550	7,066	5,219	243
Aug.	6,050	5,192	3,468	1.98	113,940	4,937	3,483	227
Sep.	24	1,854	2,830	0.75	109,280	1,587	1,026	183
Oct.	0	130	2,300	0.00	106,850	0	0	124
Nov.	850	88	762	2.43	106,850	0	0	87
Dec.	1,439	89	1,300	0.00	106,900	0	0	80
TOTAL	37,490	17,230	22,690	19.44	---	14,997	9,728	1,721

3/ No releases required for City of Russell, Kansas.

NOTE.--Cedar Bluff Canal:

Acres irrigated 1975 -- 6,755

TABLE 3
ACRES IRRIGATED IN 1975 AND ESTIMATES FOR 1976

<u>Irrigation District and Canal</u>	<u>Acres With Service Available</u>	<u>Acres Irrigated in 1975</u>	<u>Estimated Acres to be Irrigated in 1976</u>
Mirage Flats Irrigation District			
Mirage Flats Canal	11,662	10,950	11,000
Ainsworth Irrigation District			
Ainsworth Canal	33,960	33,694	33,700
Sargent Irrigation District			
Sargent Canal	13,650	13,042	13,000
Farwell Irrigation District			
Farwell Canal	48,250	43,702	44,000
Frenchman Valley Irrigation District			
Culbertson Canal	9,600	9,060	8,500
H & RW Irrigation District			
Culbertson Extension Canal	11,500	11,124	10,800
Frenchman-Cambridge Irrigation District			
Meeker-Driftwood Canal	16,476	16,156	16,200
Bartley Canal	6,539	6,289	6,300
Red Willow Canal	4,932	4,782	4,800
Cambridge Canal	<u>17,053</u>	<u>16,633</u>	<u>16,600</u>
Total Frenchman-Cambridge Irr. Dist.	45,000	43,860	43,900
Almena Irrigation District			
Almena Canal	5,350	5,280	5,300
Bostwick Irrigation District in Nebraska			
Franklin Canal	11,116	10,249	10,400
Naponee	1,737	1,405	1,500
Franklin Pump Canal	2,091	2,041	2,100
Superior Canal	5,863	5,340	5,300
Courtland Canal (Nebr.)	<u>1,980</u>	<u>1,762</u>	<u>1,700</u>
Total Bostwick Irr. Dist. in Nebraska	22,787	20,797	21,000
Kansas-Bostwick Irrigation District			
Courtland Canal above Lovewell	12,771	12,190	9,800
Courtland Canal below Lovewell	<u>27,329</u>	<u>19,587</u>	<u>22,200</u>
Total Kansas-Bostwick Irr. Dist.	40,100	31,777	32,000
Kirwin Irrigation District			
Kirwin Canal	11,435	9,410	9,400
Webster Irrigation District			
Osborne Canal	8,500	6,362	6,350
Cedar Bluff Irrigation District			
Cedar Bluff Canal	6,800	6,755	6,750
Non-Project Uses			
Middle Loup P. P. Canals	13,500	13,694	13,700
Hale Ditch	700	700	700

TABLE 4
SHEET 1 OF 15

BOX BUTTE RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	INCHES	1000 AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	33.	2.0	1.09	.1	2.	.1	0.0	0.0	3987.1	7.9	1.8
FEB	38.	2.1	1.15	.1	2.	.1	0.0	0.0	3989.4	9.8	1.9
MAR	52.	3.2	2.07	.2	2.	.1	0.0	0.0	3992.6	12.7	2.9
APR	44.	2.6	3.76	.3	29.	1.7	0.0	0.0	3993.2	13.3	.6
MAY	23.	1.4	6.32	.5	55.	3.4	0.0	0.0	3990.6	10.8	-2.5
JUN	13.	.8	7.22	.5	57.	3.4	0.0	0.0	3986.8	7.7	-3.1
JUL	8.	.5	8.60	.4	166.	10.2	0.0	4.7	3976.5	2.3	-5.4
AUG	8.	.5	7.98	.2	166.	10.2	0.0	9.9	3976.5	2.3	0.0
SEP	8.	.5	5.81	.2	86.	5.1	0.0	4.8	3976.5	2.3	0.0
OCT	11.	.7	4.64	.1	2.	.1	0.0	0.0	3977.9	2.8	.5
NOV	25.	1.5	2.97	.1	2.	.1	0.0	0.0	3980.8	4.1	1.3
DEC	36.	2.2	1.39	.1	2.	.1	0.0	0.0	3984.3	6.1	2.0
TOTAL		18.0	53.00	2.8		34.6	0.0	19.4			-1.0
MOST PROBABLE INFLOW CONDITIONS											
JAN	37.	2.3	.99	.1	2.	.1	0.0	0.0	3987.4	8.2	2.1
FEB	43.	2.4	1.04	.1	2.	.1	0.0	0.0	3990.1	10.4	2.2
MAR	55.	3.4	1.89	.1	2.	.1	0.0	0.0	3993.5	13.6	3.2
APR	49.	2.9	3.41	.3	20.	1.2	0.0	0.0	3994.9	15.0	1.4
MAY	24.	1.5	5.71	.5	18.	1.1	0.0	0.0	3994.8	14.9	-.1
JUN	24.	1.4	6.54	.6	42.	2.5	0.0	0.0	3993.1	13.2	-1.7
JUL	18.	1.1	7.80	.5	141.	8.7	0.0	0.0	3982.6	5.1	-8.1
AUG	16.	1.0	7.23	.3	143.	8.8	0.0	5.3	3976.5	2.3	-2.8
SEP	12.	.7	5.24	.1	40.	2.4	0.0	1.8	3976.5	2.3	0.0
OCT	16.	1.0	4.19	.1	2.	.1	0.0	0.0	3978.6	3.1	.8
NOV	32.	1.9	2.70	.1	2.	.1	0.0	0.0	3982.1	4.8	1.7
DEC	41.	2.5	1.26	.1	2.	.1	0.0	0.0	3985.9	7.1	2.3
TOTAL		22.1	48.00	2.9		25.3	0.0	7.1			1.0
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	42.	2.6	.91	.1	2.	.1	0.0	0.0	3987.8	8.5	2.4
FEB	49.	2.7	.95	.1	2.	.1	0.0	0.0	3990.8	11.0	2.5
MAR	76.	4.7	1.72	.1	2.	.1	0.0	0.0	3995.3	15.5	4.5
APR	62.	3.7	3.12	.3	10.	.6	0.0	0.0	3997.8	18.3	2.8
MAY	39.	2.4	5.25	.5	13.	.8	0.0	0.0	3998.7	19.4	1.1
JUN	54.	3.2	6.00	.6	27.	1.6	0.0	0.0	3999.5	20.4	1.0
JUL	34.	2.1	7.14	.7	107.	6.6	0.0	0.0	3995.1	15.2	-5.2
AUG	26.	1.6	6.63	.5	106.	6.5	0.0	0.0	3989.4	9.6	-5.4
SEP	22.	1.3	4.82	.3	29.	1.7	0.0	0.0	3988.6	9.1	-.7
OCT	29.	1.8	3.85	.3	2.	.1	0.0	0.0	3990.2	10.5	1.4
NOV	42.	2.5	2.46	.2	2.	.1	0.0	0.0	3992.6	12.7	2.2
DEC	47.	2.9	1.15	.1	2.	.1	0.0	0.0	3995.3	15.4	2.7
TOTAL		31.5	44.00	3.8		18.4	0.0	0.0			9.3

TABLE 4
SHEET 2 OF 15

MERRITT RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	INCHES	1000 AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	236.	14.5	1.13	.2	16.	1.0	13.8	0.0	2941.0	60.9	-.5
FEB	254.	14.1	1.43	.3	18.	1.0	12.8	0.0	2941.0	60.9	0.0
MAR	270.	16.6	1.99	.5	16.	1.0	1.5	0.0	2946.0	74.5	13.6
APR	257.	15.3	3.31	.8	17.	1.0	13.5	0.0	2946.0	74.5	0.0
MAY	257.	15.8	4.79	1.2	104.	6.4	8.2	0.0	2946.0	74.5	0.0
JUN	235.	14.0	6.20	1.5	165.	9.8	2.7	0.0	2946.0	74.5	0.0
JUL	216.	13.3	8.03	1.6	712.	43.8	0.0	0.0	2932.5	42.4	-32.1
AUG	218.	13.4	7.33	.8	712.	43.8	0.0	0.0	2904.7	11.2	-31.2
SEP	224.	13.3	5.39	.3	141.	8.4	0.0	0.0	2911.3	15.8	4.6
OCT	241.	14.8	3.76	.3	16.	1.0	0.0	0.0	2924.2	29.3	13.5
NOV	245.	14.6	2.15	.3	17.	1.0	0.0	0.0	2932.6	42.6	13.3
DEC	246.	15.1	1.49	.3	16.	1.0	0.0	0.0	2939.1	56.4	13.8
TOTAL		174.8	47.00	8.1		119.2	52.5	0.0			-5.0
MOST PROBABLE INFLOW CONDITIONS											
JAN	263.	16.2	1.07	.2	16.	1.0	15.5	0.0	2941.0	60.9	-.5
FEB	274.	15.2	1.34	.3	18.	1.0	13.9	0.0	2941.0	60.9	0.0
MAR	283.	17.4	1.87	.4	16.	1.0	2.4	0.0	2946.0	74.5	13.6
APR	284.	16.9	3.10	.8	17.	1.0	15.1	0.0	2946.0	74.5	0.0
MAY	280.	17.2	4.48	1.1	81.	5.0	11.1	0.0	2946.0	74.5	0.0
JUN	260.	15.5	5.80	1.4	129.	7.7	6.4	0.0	2946.0	74.5	0.0
JUL	241.	14.8	7.50	1.7	527.	32.4	0.0	0.0	2938.6	55.2	-19.3
AUG	241.	14.8	6.85	1.1	527.	32.4	0.0	0.0	2929.1	36.5	-18.7
SEP	249.	14.8	5.04	.7	108.	6.4	0.0	0.0	2933.5	44.2	7.7
OCT	259.	15.9	3.52	.6	16.	1.0	0.0	0.0	2940.0	58.5	14.3
NOV	266.	15.8	2.02	.4	17.	1.0	12.0	0.0	2941.0	60.9	2.4
DEC	262.	16.1	1.41	.3	16.	1.0	14.8	0.0	2941.0	60.9	0.0
TOTAL		190.6	44.00	9.0		90.9	91.2	0.0			-.5
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	281.	17.3	.94	.2	16.	1.0	16.6	0.0	2941.0	60.9	-.5
FEB	293.	16.3	1.19	.3	18.	1.0	15.0	0.0	2941.0	60.9	0.0
MAR	304.	18.7	1.65	.4	16.	1.0	3.7	0.0	2946.0	74.5	13.6
APR	316.	18.8	2.75	.7	17.	1.0	17.1	0.0	2946.0	74.5	0.0
MAY	299.	18.4	3.97	1.0	55.	3.4	14.0	0.0	2946.0	74.5	0.0
JUN	279.	16.6	5.15	1.2	84.	5.0	10.4	0.0	2946.0	74.5	0.0
JUL	265.	16.3	6.66	1.6	345.	21.2	0.0	0.0	2943.7	68.0	-6.5
AUG	257.	15.8	6.08	1.3	345.	21.2	0.0	0.0	2941.1	61.3	-6.7
SEP	266.	15.8	4.47	1.0	74.	4.4	0.0	0.0	2945.0	71.7	10.4
OCT	275.	16.9	3.12	.7	16.	1.0	26.0	0.0	2941.0	60.9	-10.8
NOV	279.	16.6	1.78	.4	17.	1.0	15.2	0.0	2941.0	60.9	0.0
DEC	285.	17.5	1.24	.3	16.	1.0	16.2	0.0	2941.0	60.9	0.0
TOTAL		205.0	39.00	9.1		62.2	134.2	0.0			-.5

TABLE 4
SHEET 3 OF 15

SHERMAN RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	1000 INCHES	AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	0.	0.0	.65	.1	28.	1.7	0.0	0.0	2153.8	47.4	-1.8
FEB	0.	0.0	.71	.1	31.	1.7	0.0	0.0	2153.0	45.6	-1.8
MAR	0.	0.0	1.59	.3	28.	1.7	0.0	0.0	2152.1	43.6	-2.0
APR	348.	20.7	3.85	.8	29.	1.7	0.0	0.0	2159.7	61.8	18.2
MAY	166.	10.2	3.74	.9	33.	2.0	0.0	0.0	2162.3	69.1	7.3
JUN	188.	11.2	4.67	1.1	170.	10.1	0.0	0.0	2162.3	69.1	0.0
JUL	179.	11.0	7.91	1.3	1168.	71.8	0.0	3.5	2129.0	10.5	-58.6
AUG	120.	7.4	7.12	.5	1140.	70.1	0.0	63.2	2129.0	10.5	0.0
SEP	424.	25.2	4.27	.4	171.	10.2	0.0	0.0	2141.8	25.1	14.6
OCT	532.	32.7	4.16	.7	23.	1.4	0.0	0.0	2157.3	55.7	30.6
NOV	0.	0.0	2.26	.5	29.	1.7	0.0	0.0	2156.4	53.5	-2.2
DEC	0.	0.0	.79	.2	28.	1.7	0.0	0.0	2155.6	51.6	-1.9
TOTAL		118.4	41.72	6.9		175.8	0.0	66.7			2.4
MOST PROBABLE INFLOW CONDITIONS											
JAN	0.	0.0	.43	.1	28.	1.7	0.0	0.0	2153.8	47.4	-1.8
FEB	0.	0.0	.60	.1	31.	1.7	0.0	0.0	2153.0	45.6	-1.8
MAR	0.	0.0	1.19	.2	28.	1.7	0.0	0.0	2152.1	43.7	-1.2
APR	262.	15.6	2.08	.4	29.	1.7	0.0	0.0	2157.9	57.2	13.5
MAY	234.	14.4	2.22	.5	33.	2.0	0.0	0.0	2162.3	69.1	11.9
JUN	139.	8.3	3.32	.8	126.	7.5	0.0	0.0	2162.3	69.1	0.0
JUL	296.	18.2	5.59	1.1	802.	49.3	0.0	0.0	2148.7	36.9	-32.2
AUG	207.	12.7	5.12	.6	781.	48.0	0.0	9.5	2129.0	10.5	-26.4
SEP	541.	32.2	3.23	.4	121.	7.2	0.0	0.0	2147.8	35.1	24.6
OCT	369.	22.7	3.81	.7	23.	1.4	0.0	0.0	2157.3	55.7	20.6
NOV	0.	0.0	1.76	.4	29.	1.7	0.0	0.0	2156.5	53.6	-2.1
DEC	0.	0.0	.58	.1	28.	1.7	0.0	0.0	2155.7	51.8	-1.8
TOTAL		124.1	29.93	5.4		125.6	0.0	9.5			2.6
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	0.	0.0	.21	0.0	28.	1.7	0.0	0.0	2153.9	47.5	-1.7
FEB	0.	0.0	.32	.1	31.	1.7	0.0	0.0	2153.0	45.7	-1.8
MAR	0.	0.0	.42	.1	28.	1.7	0.0	0.0	2152.2	43.9	-1.8
APR	292.	17.4	.59	.1	29.	1.7	0.0	0.0	2158.8	59.5	15.6
MAY	190.	11.7	.39	.1	33.	2.0	0.0	0.0	2162.3	69.1	9.6
JUN	99.	5.9	.91	.2	96.	5.7	0.0	0.0	2162.3	69.1	0.0
JUL	384.	23.6	4.82	1.1	551.	33.9	0.0	0.0	2158.1	57.7	-11.4
AUG	268.	16.5	4.02	.8	532.	32.7	0.0	0.0	2150.7	40.7	-17.0
SEP	350.	20.8	2.14	.4	91.	5.4	0.0	0.0	2157.3	55.7	15.0
OCT	0.	0.0	3.37	.7	23.	1.4	0.0	0.0	2156.5	53.6	-2.1
NOV	0.	0.0	.40	.1	29.	1.7	0.0	0.0	2155.7	51.8	-1.8
DEC	0.	0.0	.24	0.0	28.	1.7	0.0	0.0	2155.0	50.1	-1.7
TOTAL		25.9	17.83	3.7		91.3	0.0	0.0			.9

BONNY RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT				RES SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	1000 INCHES	1000 AF	1000 AF	1000 AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS													
JAN	23.	1.4	1.45	.2	0.0	.3	5.	.3	0.0	0.0	3671.9	41.1	.9
FEB	25.	1.4	1.55	.3	0.0	.3	5.	.3	.6	0.0	3672.0	41.3	.2
MAR	28.	1.7	2.45	.4	0.0	.3	5.	.3	1.0	0.0	3672.0	41.3	0.0
APR	27.	1.6	4.30	.7	.3	.3	10.	.6	.3	0.0	3672.0	41.3	0.0
MAY	55.	3.4	5.35	.9	.9	.3	20.	1.2	1.3	0.0	3672.0	41.3	0.0
JUN	45.	2.7	6.95	1.2	.9	.3	20.	1.2	.3	0.0	3672.0	41.3	0.0
JUL	26.	1.6	8.30	1.4	.9	.3	20.	1.2	0.0	0.0	3671.5	40.3	-1.0
AUG	23.	1.4	7.00	1.2	.8	.3	18.	1.1	0.0	0.0	3671.0	39.4	-.9
SEP	17.	1.0	5.20	.9	.6	.3	15.	.9	0.0	0.0	3670.6	38.6	-.8
OCT	18.	1.1	5.05	.8	.5	.3	13.	.8	0.0	0.0	3670.4	38.1	-.5
NOV	22.	1.3	3.05	.5	.3	.3	10.	.6	0.0	0.0	3670.5	38.3	.2
DEC	21.	1.3	1.85	.3	0.0	.3	5.	.3	0.0	0.0	3670.8	39.0	.7
TOTAL		19.9	52.50	8.8	5.2	3.6	8.8	3.5	0.0	0.0			-1.2
MOST PROBABLE INFLOW CONDITIONS													
JAN	28.	1.7	1.20	.2	0.0	.3	5.	.3	.1	0.0	3672.0	41.3	1.1
FEB	31.	1.7	1.40	.2	0.0	.3	5.	.3	1.2	0.0	3672.0	41.3	0.0
MAR	36.	2.2	1.85	.3	0.0	.3	5.	.3	1.6	0.0	3672.0	41.3	0.0
APR	34.	2.0	2.80	.5	.4	.3	12.	.7	.8	0.0	3672.0	41.3	0.0
MAY	67.	4.1	3.00	.5	.6	.3	15.	.9	2.7	0.0	3672.0	41.3	0.0
JUN	55.	3.3	4.60	.8	.6	.3	15.	.9	1.6	0.0	3672.0	41.3	0.0
JUL	33.	2.0	6.25	1.1	.4	.3	11.	.7	.2	0.0	3672.0	41.3	0.0
AUG	28.	1.7	6.10	1.0	.4	.3	11.	.7	0.0	0.0	3672.0	41.3	0.0
SEP	20.	1.2	4.30	.7	.6	.3	15.	.9	0.0	0.0	3671.8	40.9	-.4
OCT	21.	1.3	4.55	.8	.6	.3	15.	.9	0.0	0.0	3671.6	40.5	-.4
NOV	27.	1.6	2.80	.5	.2	.3	8.	.5	0.0	0.0	3671.9	41.1	.6
DEC	26.	1.6	1.55	.3	0.0	.3	5.	.3	.8	0.0	3672.0	41.3	.2
TOTAL		24.4	40.40	6.9	3.8	3.6	7.4	9.0	0.0	0.0			1.1
REASONABLE MAXIMUM INFLOW CONDITIONS													
JAN	52.	3.2	.90	.2	0.0	.3	5.	.3	1.6	0.0	3672.0	41.3	1.1
FEB	58.	3.2	1.25	.2	0.0	.3	5.	.3	2.7	0.0	3672.0	41.3	0.0
MAR	65.	4.0	1.35	.2	0.0	.3	5.	.3	3.5	0.0	3672.0	41.3	0.0
APR	62.	3.7	2.40	.4	.3	.3	10.	.6	2.7	0.0	3672.0	41.3	0.0
MAY	124.	7.6	2.05	.3	.5	.3	13.	.8	6.5	0.0	3672.0	41.3	0.0
JUN	104.	6.2	2.50	.4	.2	.3	8.	.5	5.3	0.0	3672.0	41.3	0.0
JUL	60.	3.7	5.05	.9	.2	.3	8.	.5	2.3	0.0	3672.0	41.3	0.0
AUG	50.	3.1	4.00	.7	.4	.3	11.	.7	1.7	0.0	3672.0	41.3	0.0
SEP	37.	2.2	3.20	.5	.4	.3	12.	.7	1.0	0.0	3672.0	41.3	0.0
OCT	41.	2.5	3.40	.6	.3	.3	10.	.6	1.3	0.0	3672.0	41.3	0.0
NOV	49.	2.9	2.60	.4	.3	.3	10.	.6	1.9	0.0	3672.0	41.3	0.0
DEC	49.	3.0	1.30	.2	0.0	.3	5.	.3	2.5	0.0	3672.0	41.3	0.0
TOTAL		45.3	30.00	5.0	2.6	3.6	6.2	33.0	0.0	0.0			1.1

TABLE 4
SHEET 5 OF 15

SWANSON LAKE OPERATION ESTIMATES - 1976

MONTH	UNDEPLETED INFLOW 1000 AF	UPSTREAM DEPLETIONS 1000 AF	DEPLETED INFLOW MEAN 1000 CFS AF	NET EVAPORATION 1000 INCHES AF	RELEASE REQUIREMENT MEAN 1000 CFS AF	RES SPILL 1000 AF	REQ SHORT 1000 AF	END OF MONTH ELEV FT	MONTH CONT 1000 AF	RES CHANGE 1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS										
JAN	7.5	-1.1	104. 6.4	1.05 .3	2. .1	0.0	0.0	2741.4	73.3	6.0
FEB	9.5	-.5	162. 9.0	1.20 .4	2. .1	0.0	0.0	2743.5	81.8	8.5
MAR	11.1	-.4	174. 10.7	1.95 .7	2. .1	0.0	0.0	2745.9	91.7	9.9
APR	8.5	-.7	131. 7.8	3.85 1.4	2. .1	0.0	0.0	2747.3	98.0	6.3
MAY	7.7	-.9	111. 6.8	4.10 1.5	99. 6.1	0.0	0.0	2747.1	97.2	-.8
JUN	6.9	-1.2	96. 5.7	5.20 1.9	123. 7.3	0.0	0.0	2746.3	93.7	-3.5
JUL	2.4	-.5	31. 1.9	7.70 2.7	348. 21.4	0.0	0.0	2741.0	71.5	-22.2
AUG	1.9	-.4	24. 1.5	6.90 2.0	343. 21.1	0.0	0.0	2734.9	49.9	-21.6
SEP	.5	-.1	7. .4	5.25 1.3	198. 11.8	0.0	0.0	2730.4	37.2	-12.7
OCT	2.6	-.3	37. 2.3	4.60 1.0	63. 3.9	0.0	0.0	2729.4	34.6	-2.6
NOV	5.7	-.7	84. 5.0	2.70 .6	2. .1	0.0	0.0	2731.1	38.9	4.3
DEC	6.7	-1.0	93. 5.7	1.30 .3	2. .1	0.0	0.0	2733.0	44.2	5.3
TOTAL	71.0	-7.8	63.2	45.80 14.1	72.2	0.0	0.0			-23.1
MOST PROBABLE INFLOW CONDITIONS										
JAN	9.6	-1.3	135. 8.3	.75 .2	2. .1	0.0	0.0	2741.9	75.3	8.0
FEB	12.0	-.2	212. 11.8	1.00 .3	2. .1	0.0	0.0	2744.7	86.7	11.4
MAR	14.3	-.3	228. 14.0	1.40 .5	2. .1	0.0	0.0	2747.8	100.1	13.4
APR	12.0	-.5	193. 11.5	2.40 .9	2. .1	0.0	0.0	2750.0	110.6	10.5
MAY	13.5	-.5	211. 13.0	2.10 .8	24. 1.5	1.1	0.0	2752.0	120.2	9.6
JUN	15.7	-.8	250. 14.9	3.70 1.5	27. 1.6	11.8	0.0	2752.0	120.2	0.0
JUL	5.7	-1.2	73. 4.5	6.10 2.4	265. 16.3	0.0	0.0	2749.0	106.0	-14.2
AUG	6.0	-1.1	80. 4.9	5.70 2.1	299. 18.4	0.0	0.0	2745.6	90.4	-15.6
SEP	5.0	-.3	79. 4.7	3.40 1.2	91. 5.4	0.0	0.0	2745.1	98.5	-1.9
OCT	4.6	-.4	68. 4.2	4.30 1.5	26. 1.6	0.0	0.0	2745.4	89.6	1.1
NOV	8.1	-1.1	118. 7.0	2.10 .8	2. .1	0.0	0.0	2746.8	95.7	6.1
DEC	8.5	-.5	130. 8.0	1.10 .4	2. .1	0.0	0.0	2748.4	103.2	7.5
TOTAL	115.0	-8.2	106.8	34.05 12.6	45.4	12.9	0.0			35.9
REASONABLE MAXIMUM INFLOW CONDITIONS										
JAN	11.8	-1.3	171. 10.5	.55 .2	2. .1	0.0	0.0	2742.5	77.5	10.2
FEB	14.5	-.2	257. 14.3	.60 .2	2. .1	0.0	0.0	2745.8	91.5	14.0
MAR	19.3	-.2	311. 19.1	.60 .2	2. .1	0.0	0.0	2750.0	110.3	18.8
APR	16.3	-.4	267. 15.9	.60 .2	2. .1	5.7	0.0	2752.0	120.2	9.9
MAY	23.1	-.3	371. 22.8	.80 .3	13. .8	21.7	0.0	2752.0	120.2	0.0
JUN	27.4	-.4	454. 27.0	1.90 .8	17. 1.0	25.2	0.0	2752.0	120.2	0.0
JUL	29.3	-1.0	460. 28.3	4.00 1.7	145. 8.9	17.7	0.0	2752.0	120.2	0.0
AUG	18.3	-.8	285. 17.5	5.00 2.1	166. 10.2	5.2	0.0	2752.0	120.2	0.0
SEP	10.5	-.5	168. 10.0	2.40 1.0	30. 1.8	7.2	0.0	2752.0	120.2	0.0
OCT	8.7	-.6	132. 8.1	3.80 1.6	16. 1.0	5.5	0.0	2752.0	120.2	0.0
NOV	10.1	-.4	163. 9.7	1.60 .7	2. .1	8.9	0.0	2752.0	120.2	0.0
DEC	10.7	-.2	171. 10.5	.65 .3	2. .1	10.1	0.0	2752.0	120.2	0.0
TOTAL	200.0	-6.3	193.7	22.50 9.3	24.3	107.2	0.0			52.9

TABLE 4
SHEET 6 OF 15

ENDERS RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	INCHES	1000 AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
	REASONABLE MINIMUM INFLOW CONDITIONS										
JAN	50.	3.1	1.05	.1	0.	0.0	0.0	0.0	3100.7	27.4	3.0
FEB	52.	2.9	1.20	.1	0.	0.0	0.0	0.0	3102.8	30.2	2.8
MAR	50.	3.1	1.95	.2	3.	.2	0.0	0.0	3104.8	32.9	2.7
APR	45.	2.7	4.10	.5	3.	.2	0.0	0.0	3106.2	34.9	2.0
MAY	49.	3.0	4.65	.6	52.	3.2	0.0	0.0	3105.7	34.1	-8
JUN	54.	3.2	5.25	.6	61.	3.6	0.0	0.0	3105.0	33.1	-1.0
JUL	47.	2.9	8.60	.8	329.	20.2	0.0	0.0	3089.0	15.0	-18.1
AUG	44.	2.7	6.85	.4	309.	19.0	0.0	11.7	3082.4	10.0	-5.0
SEP	49.	2.9	5.50	.3	121.	7.2	0.0	4.6	3082.4	10.0	0.0
OCT	44.	2.7	4.60	.3	3.	.2	0.0	0.0	3085.6	12.2	2.2
NOV	49.	2.9	2.65	.2	0.	0.0	0.0	0.0	3088.9	14.9	2.7
DEC	49.	3.0	1.20	.1	0.	0.0	0.0	0.0	3092.1	17.8	2.9
TOTAL		35.1	47.60	4.2		53.8	0.0	16.3			-6.6
MOST PROBABLE INFLOW CONDITIONS											
JAN	60.	3.7	.75	.1	0.	0.0	0.0	0.0	3101.1	28.0	3.6
FEB	61.	3.4	.95	.1	0.	0.0	0.0	0.0	3103.7	31.3	3.3
MAR	62.	3.8	1.35	.2	3.	.2	0.0	0.0	3106.1	34.7	3.4
APR	55.	3.3	2.60	.3	3.	.2	0.0	0.0	3108.0	37.5	2.8
MAY	59.	3.6	3.00	.4	11.	.7	0.0	0.0	3109.6	40.0	2.5
JUN	66.	3.9	3.55	.5	15.	.9	0.0	0.0	3111.1	42.5	2.5
JUL	59.	3.6	5.90	.7	236.	14.5	0.0	0.0	3103.4	30.9	-11.6
AUG	54.	3.3	6.50	.6	247.	15.2	0.0	0.0	3092.7	18.4	-12.5
SEP	57.	3.4	3.45	.3	50.	3.0	0.0	0.0	3092.8	18.5	.1
OCT	55.	3.4	4.30	.4	0.	0.0	0.0	0.0	3095.7	21.5	3.0
NOV	59.	3.5	2.30	.2	0.	0.0	0.0	0.0	3098.6	24.8	3.3
DEC	59.	3.6	.90	.1	0.	0.0	0.0	0.0	3101.4	28.3	3.5
TOTAL		42.5	35.55	3.9		34.7	0.0	0.0			3.9
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	72.	4.4	.55	.1	0.	0.0	0.0	0.0	3101.7	28.7	4.3
FEB	72.	4.0	.30	0.0	0.	0.0	0.0	0.0	3104.7	32.7	4.0
MAR	72.	4.4	.95	.1	3.	.2	0.0	0.0	3107.5	36.8	4.1
APR	66.	3.9	.80	.1	3.	.2	0.0	0.0	3109.8	40.4	3.6
MAY	68.	4.2	1.25	.2	3.	.2	0.0	0.0	3112.1	44.2	3.8
JUN	76.	4.5	2.40	.3	3.	.2	3.7	0.0	3112.3	44.5	.3
JUL	67.	4.1	4.35	.6	135.	8.3	0.0	0.0	3109.4	39.7	-4.8
AUG	62.	3.8	4.50	.6	148.	9.1	0.0	0.0	3105.5	33.8	-5.9
SEP	66.	3.9	2.30	.3	22.	1.3	0.0	0.0	3107.0	36.1	2.3
OCT	63.	3.9	3.35	.4	0.	0.0	0.0	0.0	3109.3	39.6	3.5
NOV	69.	4.1	1.90	.3	0.	0.0	0.0	0.0	3111.7	43.4	3.8
DEC	68.	4.2	.65	.1	0.	0.0	3.0	0.0	3112.3	44.5	1.1
TOTAL		49.4	23.30	3.1		19.5	6.7	0.0			20.1

TABLE 4
SHEET 7 OF 15

HUGH BUTLER LAKE OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	1000 INCHES	AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	16.	1.0	.92	.1	5.	.3	0.0	0.0	2577.6	31.4	.6
FEB	20.	1.1	1.11	.1	5.	.3	0.0	0.0	2578.1	32.1	.7
MAR	24.	1.5	2.01	.2	5.	.3	0.0	0.0	2578.8	33.1	1.0
APR	22.	1.3	4.39	.5	5.	.3	0.0	0.0	2579.1	33.6	.5
MAY	26.	1.6	4.45	.6	29.	1.8	0.0	0.0	2578.6	32.8	-.8
JUN	39.	2.3	7.01	.9	30.	1.8	0.0	0.0	2578.3	32.4	-.4
JUL	23.	1.4	8.45	1.0	80.	4.9	0.0	0.0	2575.1	27.9	-4.5
AUG	15.	.9	6.73	.7	76.	4.7	0.0	0.0	2571.4	23.4	-4.5
SEP	17.	1.0	6.08	.6	39.	2.3	0.0	0.0	2569.7	21.5	-1.9
OCT	15.	.9	4.72	.4	15.	.9	0.0	0.0	2569.4	21.1	-.4
NOV	15.	.9	2.63	.2	5.	.3	0.0	0.0	2569.7	21.5	.4
DEC	16.	1.0	1.20	.1	5.	.3	0.0	0.0	2570.3	22.1	.6
TOTAL		14.9	49.70	5.4		18.2	0.0	0.0			-8.7
MOST PROBABLE INFLOW CONDITIONS											
JAN	21.	1.3	.70	.1	5.	.3	0.0	0.0	2577.9	31.7	.9
FEB	27.	1.5	.75	.1	5.	.3	0.0	0.0	2578.6	32.8	1.1
MAR	34.	2.1	1.35	.2	5.	.3	0.0	0.0	2579.7	34.4	1.6
APR	32.	1.9	2.70	.4	5.	.3	0.0	0.0	2580.4	35.6	1.2
MAY	37.	2.3	2.80	.4	16.	1.0	0.0	0.0	2581.0	36.5	.9
JUN	54.	3.2	2.99	.4	15.	.9	.6	0.0	2581.8	37.8	1.3
JUL	33.	2.0	6.09	.8	68.	4.2	0.0	0.0	2579.9	34.8	-3.0
AUG	21.	1.3	5.52	.7	73.	4.5	0.0	0.0	2577.3	30.9	-3.9
SEP	25.	1.5	3.81	.4	22.	1.3	0.0	0.0	2577.1	30.7	-.2
OCT	20.	1.2	3.88	.5	11.	.7	0.0	0.0	2577.1	30.7	0.0
NOV	22.	1.3	1.84	.2	5.	.3	0.0	0.0	2577.7	31.5	.8
DEC	21.	1.3	.87	.1	5.	.3	0.0	0.0	2578.3	32.4	.9
TOTAL		20.9	33.30	4.3		14.4	.6	0.0			1.6
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	31.	1.9	.40	0.0	5.	.3	0.0	0.0	2578.3	32.4	1.6
FEB	38.	2.1	.47	.1	5.	.3	0.0	0.0	2579.5	34.1	1.7
MAR	47.	2.9	.85	.1	5.	.3	0.0	0.0	2581.1	36.6	2.5
APR	44.	2.6	1.52	.2	5.	.3	.9	0.0	2581.8	37.8	1.2
MAY	52.	3.2	1.78	.2	13.	.8	2.2	0.0	2581.8	37.8	0.0
JUN	74.	4.4	1.82	.2	12.	.7	3.5	0.0	2581.8	37.8	0.0
JUL	46.	2.8	3.42	.5	47.	2.9	0.0	0.0	2581.4	37.2	-.6
AUG	29.	1.8	4.12	.5	47.	2.9	0.0	0.0	2580.4	35.6	-1.6
SEP	34.	2.0	3.09	.4	17.	1.0	0.0	0.0	2580.8	36.2	.6
OCT	26.	1.6	3.21	.4	8.	.5	0.0	0.0	2581.3	36.9	.7
NOV	30.	1.8	1.15	.2	5.	.3	.4	0.0	2581.8	37.8	.9
DEC	29.	1.8	.77	.1	5.	.3	1.4	0.0	2581.8	37.8	0.0
TOTAL		28.9	22.60	2.9		10.6	8.4	0.0			7.0

TABLE 4
SHEET 8 OF 15

HARRY STRUNK LAKE OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL 1000 AF	REQUIREMENT SHORTAGE 1000 AF	END OF MONTH ELEV FT	MONTH CONT 1000 AF	RESERVOIR CHANGE 1000 AF
	MEAN CFS	1000 AF	INCHES	1000 AF	MEAN CFS	1000 AF					
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	36.	2.2	.76	.1	3.	.2	0.0	0.0	2361.7	29.7	1.9
FEB	45.	2.5	.89	.1	4.	.2	0.0	0.0	2363.1	31.9	2.2
MAR	52.	3.2	1.87	.3	3.	.2	0.0	0.0	2364.7	34.6	2.7
APR	54.	3.2	4.23	.6	3.	.2	0.0	0.0	2366.0	37.0	2.4
MAY	63.	3.9	4.07	.6	59.	3.6	0.0	0.0	2365.9	36.7	-.3
JUN	106.	6.3	5.02	.8	64.	3.8	1.3	0.0	2366.1	37.1	.4
JUL	62.	3.8	8.41	1.1	228.	14.0	0.0	0.0	2359.1	25.8	-11.3
AUG	41.	2.5	7.42	.7	224.	13.8	0.0	0.0	2348.4	13.8	-12.0
SEP	37.	2.2	4.64	.3	106.	6.3	0.0	.1	2343.0	9.5	-4.3
OCT	36.	2.2	4.52	.3	21.	1.3	0.0	0.0	2343.8	10.1	.6
NOV	35.	2.1	2.57	.2	3.	.2	0.0	0.0	2346.0	11.8	1.7
DEC	34.	2.1	1.10	.1	3.	.2	0.0	0.0	2348.2	13.6	1.8
TOTAL		36.2	45.50	5.2		44.0	1.3	.1			-14.2
MOST PROBABLE INFLOW CONDITIONS											
JAN	52.	3.2	.50	.1	3.	.2	0.0	0.0	2362.3	30.7	2.9
FEB	65.	3.6	.75	.1	4.	.2	0.0	0.0	2364.3	34.0	3.3
MAR	75.	4.6	1.40	.2	3.	.2	1.1	0.0	2366.1	37.1	3.1
APR	77.	4.6	2.29	.4	3.	.2	4.0	0.0	2366.1	37.1	0.0
MAY	93.	5.7	2.41	.4	5.	.3	5.0	0.0	2366.1	37.1	0.0
JUN	151.	9.0	3.57	.6	8.	.5	7.9	0.0	2366.1	37.1	0.0
JUL	89.	5.5	5.95	.9	177.	10.9	0.0	0.0	2362.4	30.8	-6.3
AUG	57.	3.5	5.33	.6	202.	12.4	0.0	0.0	2355.6	21.3	-9.5
SEP	54.	3.2	3.51	.4	35.	2.1	0.0	0.0	2356.2	22.0	.7
OCT	50.	3.1	4.14	.4	5.	.3	0.0	0.0	2358.0	24.4	2.4
NOV	49.	2.9	2.00	.2	3.	.2	0.0	0.0	2359.8	26.9	2.5
DEC	49.	3.0	.81	.1	3.	.2	0.0	0.0	2361.6	29.6	2.7
TOTAL		51.9	32.66	4.4		27.7	18.0	0.0			1.8
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	80.	4.9	.25	0.0	3.	.2	0.0	0.0	2363.5	32.5	4.7
FEB	101.	5.6	.40	.1	4.	.2	.7	0.0	2366.1	37.1	4.6
MAR	115.	7.1	.49	.1	3.	.2	6.8	0.0	2366.1	37.1	0.0
APR	121.	7.2	.65	.1	3.	.2	6.9	0.0	2366.1	37.1	0.0
MAY	141.	8.7	.42	.1	3.	.2	8.4	0.0	2366.1	37.1	0.0
JUN	235.	14.0	.98	.2	3.	.2	13.6	0.0	2366.1	37.1	0.0
JUL	138.	8.5	5.13	.8	88.	5.4	2.3	0.0	2366.1	37.1	0.0
AUG	89.	5.5	4.19	.6	106.	6.5	0.0	0.0	2365.2	35.5	-1.6
SEP	82.	4.9	2.33	.4	8.	.5	2.4	0.0	2366.1	37.1	1.6
OCT	78.	4.8	3.66	.6	3.	.2	4.0	0.0	2366.1	37.1	0.0
NOV	76.	4.5	.46	.1	3.	.2	4.2	0.0	2366.1	37.1	0.0
DEC	76.	4.7	.34	.1	3.	.2	4.4	0.0	2366.1	37.1	0.0
TOTAL		80.4	19.30	3.2		14.2	53.7	0.0			9.3

TABLE 4
SHEET 9 OF 15

NORTON RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	INCHES	AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	2.	.1	.95	.1	2.	.1	0.0	0.0	2286.4	9.7	-.1
FEB	4.	.2	1.00	.1	2.	.1	0.0	0.0	2286.4	9.7	0.0
MAR	7.	.4	1.98	.1	2.	.1	0.0	0.0	2286.6	9.9	.2
APR	5.	.3	4.34	.3	2.	.1	0.0	0.0	2286.5	9.8	-.1
MAY	16.	1.0	4.10	.3	7.	.4	0.0	0.0	2286.9	10.1	.3
JUN	32.	1.9	7.86	.6	10.	.6	0.0	0.0	2287.6	10.8	.7
JUL	23.	1.4	8.77	.5	130.	8.0	0.0	0.0	2277.3	3.7	-7.1
AUG	11.	.7	7.38	.3	127.	7.8	0.0	7.3	2277.1	3.6	-.1
SEP	10.	.6	6.12	.2	54.	3.2	0.0	2.8	2277.1	3.6	0.0
OCT	7.	.4	4.66	.2	23.	1.4	0.0	1.2	2277.1	3.6	0.0
NOV	2.	.1	2.62	.1	2.	.1	0.0	.1	2277.1	3.6	0.0
DEC	2.	.1	1.22	0.0	2.	.1	0.0	0.0	2277.1	3.6	0.0
TOTAL		7.2	51.00	2.8		22.0	0.0	11.4			-6.2
MOST PROBABLE INFLOW CONDITIONS											
JAN	5.	.3	.80	.1	2.	.1	0.0	0.0	2286.6	9.9	.1
FEB	11.	.6	.85	.1	2.	.1	0.0	0.0	2287.1	10.3	.4
MAR	13.	.8	1.24	.1	2.	.1	0.0	0.0	2287.8	10.9	.6
APR	10.	.6	2.78	.2	2.	.1	0.0	0.0	2288.1	11.2	.3
MAY	37.	2.3	2.55	.2	2.	.1	0.0	0.0	2290.0	13.2	2.0
JUN	74.	4.4	3.85	.4	2.	.1	0.0	0.0	2293.3	17.1	3.9
JUL	55.	3.4	5.97	.6	75.	4.6	0.0	0.0	2291.9	15.3	-1.8
AUG	26.	1.6	5.89	.5	85.	5.2	0.0	0.0	2289.1	11.2	-4.1
SEP	24.	1.4	4.38	.4	20.	1.2	0.0	0.0	2287.9	11.0	-.2
OCT	16.	1.0	4.14	.3	7.	.4	0.0	0.0	2288.2	11.3	.3
NOV	5.	.3	2.12	.2	2.	.1	0.0	0.0	2288.2	11.3	0.0
DEC	5.	.3	1.03	.1	2.	.1	0.0	0.0	2288.3	11.4	.1
TOTAL		17.0	35.60	3.2		12.2	0.0	0.0			1.6
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	11.	.7	.50	0.0	2.	.1	0.0	0.0	2287.2	10.4	.6
FEB	27.	1.5	.52	0.0	2.	.1	0.0	0.0	2288.7	11.8	1.4
MAR	33.	2.0	.54	0.0	2.	.1	0.0	0.0	2290.4	13.7	1.9
APR	27.	1.6	1.43	.1	2.	.1	0.0	0.0	2291.7	15.1	1.4
MAY	94.	5.8	1.16	.1	2.	.1	0.0	0.0	2295.9	20.7	5.6
JUN	185.	11.0	2.52	.4	2.	.1	0.0	0.0	2302.0	31.2	10.5
JUL	137.	8.4	4.42	.8	15.	.9	2.0	0.0	2304.3	35.9	4.7
AUG	63.	3.9	5.23	1.0	31.	1.9	1.0	0.0	2304.3	35.9	0.0
SEP	61.	3.6	3.07	.6	2.	.1	2.9	0.0	2304.3	35.9	0.0
OCT	41.	2.5	2.72	.5	2.	.1	1.9	0.0	2304.3	35.9	0.0
NOV	12.	.7	1.25	.2	2.	.1	.4	0.0	2304.3	35.9	0.0
DEC	11.	.7	.64	.1	2.	.1	.5	0.0	2304.3	35.9	0.0
TOTAL		42.4	24.00	3.8		3.8	8.7	0.0			26.1

HARLAN COUNTY RESERVOIR OPERATION ESTIMATES - 1976

MONTH	UNDEPLETED INFLOW 1000 AF	UPSTREAM DEPLETIONS 1000 AF	DEPLETED INFLOW MEAN 1000 CFS AF	NET EVAPORATION 1000 INCHES AF	RELEASE REQUIREMENT MEAN 1000 CFS AF	RES SPILL 1000 AF	REQ SHORT 1000 AF	END OF ELEV FT	MONTH CONT 1000 AF	RES CHANGE 1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS										
JAN	19.2	-11.9	119. 7.3	.90 .9	10. .6	0.0	0.0	1942.2	271.3	5.8
FEB	24.3	-14.4	178. 9.9	.78 .8	11. .6	0.0	0.0	1942.9	279.8	8.5
MAR	32.1	-17.3	241. 14.8	1.74 1.8	10. .6	0.0	0.0	1943.9	292.2	12.4
APR	28.0	-14.0	235. 14.0	4.70 5.0	10. .6	0.0	0.0	1944.5	300.6	8.4
MAY	36.5	-14.8	353. 21.7	4.38 4.7	215. 13.2	0.0	0.0	1944.8	304.4	3.8
JUN	42.0	-16.4	430. 25.6	6.60 7.1	311. 18.5	0.0	0.0	1944.8	304.4	0.0
JUL	15.4	8.4	387. 23.8	9.71 10.2	670. 41.2	0.0	0.0	1942.7	276.8	-27.6
AUG	13.6	10.1	385. 23.7	8.41 8.3	751. 46.2	0.0	0.0	1940.1	246.0	-30.8
SEP	6.2	2.1	139. 8.3	5.56 5.0	397. 23.6	0.0	0.0	1938.3	225.7	-20.3
OCT	5.6	-5.6	0. 0.0	4.52 3.9	10. .6	0.0	0.0	1937.8	221.2	-4.5
NOV	13.2	-8.9	72. 4.3	2.58 2.2	10. .6	0.0	0.0	1938.0	222.7	1.5
DEC	16.9	-10.4	106. 6.5	1.12 1.0	10. .6	0.0	0.0	1938.4	227.6	4.9
TOTAL	253.0	-93.1	159.9	51.00 50.9	146.9	0.0	0.0			-37.9
MOST PROBABLE INFLOW CONDITIONS										
JAN	22.4	-16.1	102. 6.3	.65 .7	10. .6	0.0	0.0	1942.2	270.5	5.0
FEB	31.2	-19.3	214. 11.9	.61 .6	11. .6	0.0	0.0	1943.0	281.2	10.7
MAR	38.0	-22.5	252. 15.5	1.13 1.2	10. .6	0.0	0.0	1944.1	294.9	13.7
APR	38.8	-16.4	376. 22.4	1.31 1.4	10. .6	0.0	0.0	1945.7	315.3	20.4
MAY	59.9	-21.0	633. 38.9	3.27 3.6	24. 1.5	29.3	0.0	1946.0	319.8	4.5
JUN	106.6	-15.9	1524. 90.7	5.46 6.1	27. 1.6	83.0	0.0	1946.0	319.8	0.0
JUL	42.1	-7.0	571. 35.1	7.70 8.6	446. 27.4	0.0	0.0	1945.9	318.9	-9.9
AUG	26.6	-2.4	394. 24.2	6.01 6.6	468. 28.8	0.0	0.0	1945.1	307.7	-11.2
SEP	19.7	-9.7	168. 10.0	4.47 4.8	116. 6.9	0.0	0.0	1944.9	306.0	-1.7
OCT	16.4	-13.2	52. 3.2	3.43 3.7	10. .6	0.0	0.0	1944.9	304.9	-1.1
NOV	20.8	-13.3	126. 7.5	1.55 1.7	10. .6	0.0	0.0	1945.3	310.1	5.2
DEC	23.5	-14.2	151. 9.3	.71 .8	10. .6	0.0	0.0	1945.9	318.0	7.9
TOTAL	446.0	-171.0	275.0	36.30 39.8	70.4	112.3	0.0			52.5
REASONABLE MAXIMUM INFLOW CONDITIONS										
JAN	29.1	-21.7	104. 6.4	0.00 0.0	10. .6	0.0	0.0	1942.2	271.3	5.8
FEB	42.6	-25.2	313. 17.4	.28 .3	11. .6	0.0	0.0	1943.5	287.8	16.5
MAR	57.1	-26.9	491. 30.2	.70 .8	10. .6	0.0	0.0	1945.8	316.6	28.8
APR	55.8	-16.1	667. 39.7	.21 .2	10. .6	35.7	0.0	1946.0	319.8	3.2
MAY	105.5	-11.7	1526. 93.8	1.78 2.0	13. .8	91.0	0.0	1946.0	319.8	0.0
JUN	166.5	-14.3	2558. 152.2	1.58 1.8	13. .8	149.6	0.0	1946.0	319.8	0.0
JUL	105.4	-26.0	1291. 79.4	6.53 7.3	104. 6.4	65.7	0.0	1946.0	319.8	0.0
AUG	63.8	-20.5	704. 43.3	3.43 3.8	104. 6.4	33.1	0.0	1946.0	319.8	0.0
SEP	75.0	-11.7	1064. 63.3	3.84 4.3	25. 1.5	57.5	0.0	1946.0	319.8	0.0
OCT	34.4	-8.9	415. 25.5	2.28 2.5	10. .6	22.4	0.0	1946.0	319.8	0.0
NOV	31.4	-4.5	452. 26.9	1.03 1.1	10. .6	25.2	0.0	1946.0	319.8	0.0
DEC	30.4	-2.2	491. 30.2	.40 .4	10. .6	29.2	0.0	1946.0	319.8	0.0
TOTAL	796.0	-187.7	608.3	22.06 24.5	20.1	509.4	0.0			54.3

TABLE 4
SHEET 11 OF 15

LOVEWELL RESERVOIR OPERATION ESTIMATES - 1976

MONTH	WHITE ROCK CREEK INFLOW 1000 AF	COURTLAND CANAL INFLOW 1000 AF	TOTAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RES SPILL	REQ SHORT	END OF ELEV	MONTH CONT	RES CHANGE
			MEAN 1000 CFS	AF	1000 INCHES	AF	MEAN 1000 CFS	AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS													
JAN	.1	0.0	2.	.1	.77	.2	0.	0.0	0.0	0.0	1580.7	36.2	-.1
FEB	.2	0.0	4.	.2	.75	.2	0.	0.0	0.0	0.0	1580.7	36.2	0.0
MAR	.2	0.0	3.	.2	1.69	.4	0.	0.0	0.0	0.0	1580.6	36.0	-.2
APR	.2	0.0	3.	.2	3.79	.8	0.	0.0	0.0	0.0	1580.4	35.4	-.6
MAY	.6	6.2	111.	6.8	3.55	.8	94.	5.8	0.0	0.0	1580.4	35.6	.2
JUN	1.3	12.0	224.	13.3	5.84	1.4	97.	5.8	0.0	0.0	1582.6	41.7	6.1
JUL	.8	13.7	236.	14.5	7.75	1.9	278.	17.1	0.0	0.0	1581.0	37.2	-4.5
AUG	.5	13.7	231.	14.2	6.09	1.3	325.	20.0	0.0	0.0	1578.3	30.1	-7.1
SEP	.4	10.0	175.	10.4	5.15	1.0	145.	8.6	0.0	0.0	1578.6	30.9	.8
OCT	.3	0.0	5.	.3	3.45	.7	0.	0.0	0.0	0.0	1578.4	30.5	-.4
NOV	.1	0.0	2.	.1	2.37	.5	0.	0.0	0.0	0.0	1578.3	30.1	-.4
DEC	.1	0.0	2.	.1	.96	.2	0.	0.0	0.0	0.0	1578.2	30.0	-.1
TOTAL	4.8	55.6		60.4	42.16	9.4		57.3	0.0	0.0			-6.3
MOST PROBABLE INFLOW CONDITIONS													
JAN	.3	0.0	5.	.3	.50	.1	0.	0.0	0.0	0.0	1580.8	36.5	.2
FEB	.9	0.0	16.	.9	.40	.1	0.	0.0	0.0	0.0	1581.1	37.3	.8
MAR	1.0	0.0	16.	1.0	.92	.2	0.	0.0	0.0	0.0	1581.4	38.1	.8
APR	1.1	0.0	18.	1.1	1.97	.5	0.	0.0	0.0	0.0	1581.6	38.7	.6
MAY	3.0	1.2	68.	4.2	1.58	.4	33.	2.0	0.0	0.0	1582.2	40.5	1.8
JUN	5.9	1.2	119.	7.1	1.75	.4	34.	2.0	3.5	0.0	1582.6	41.7	1.2
JUL	3.9	9.0	210.	12.9	5.22	1.2	267.	16.4	0.0	0.0	1581.0	37.0	-4.7
AUG	2.2	7.6	159.	9.8	4.22	.9	272.	16.7	0.0	0.0	1577.9	29.2	-7.8
SEP	2.0	2.6	77.	4.6	3.36	.7	71.	4.2	0.0	0.0	1577.7	28.9	-.3
OCT	1.2	0.0	20.	1.2	2.09	.4	0.	0.0	0.0	0.0	1578.1	29.7	.8
NOV	.4	0.0	7.	.4	1.41	.3	0.	0.0	0.0	0.0	1578.1	29.8	.1
DEC	.3	0.0	5.	.3	.43	.1	0.	0.0	0.0	0.0	1578.2	30.0	.2
TOTAL	22.2	21.6		43.8	23.85	5.3		41.3	3.5	0.0			-6.3
REASONABLE MAXIMUM INFLOW CONDITIONS													
JAN	.8	0.0	13.	.8	.16	0.0	0.	0.0	0.0	0.0	1581.0	37.1	.8
FEB	2.5	0.0	45.	2.5	.26	.1	0.	0.0	0.0	0.0	1581.9	39.5	2.4
MAR	2.9	0.0	47.	2.9	.35	.1	0.	0.0	.6	0.0	1582.6	41.7	2.2
APR	3.1	0.0	52.	3.1	.44	.1	0.	0.0	3.0	0.0	1582.6	41.7	0.0
MAY	8.5	1.2	158.	9.7	.54	.1	15.	.9	8.7	0.0	1582.6	41.7	0.0
JUN	16.8	1.2	303.	18.0	-1.08	-.3	18.	1.1	17.2	0.0	1582.6	41.7	0.0
JUL	11.1	1.2	200.	12.3	4.30	1.1	130.	8.0	3.2	0.0	1582.6	41.7	0.0
AUG	6.1	1.2	119.	7.3	3.06	.8	130.	8.0	0.0	0.0	1582.1	40.2	-1.5
SEP	5.7	1.2	116.	6.9	1.78	.4	34.	2.0	3.0	0.0	1582.6	41.7	1.5
OCT	3.4	0.0	55.	3.4	1.49	.4	0.	0.0	3.0	0.0	1582.6	41.7	0.0
NOV	1.1	0.0	18.	1.1	1.00	.2	0.	0.0	.9	0.0	1582.6	41.7	0.0
DEC	.8	0.0	13.	.8	-.15	0.0	0.	0.0	.8	0.0	1582.6	41.7	0.0
TOTAL	62.8	6.0		68.8	12.15	3.0		20.0	40.4	0.0			5.4

TABLE 4
SHEET 12 OF 15

KIRWIN RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	1000 INCHES	AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	5.	.3	.91	.3	0.	0.0	0.0	0.0	1718.3	52.9	0.0
FEB	9.	.5	1.04	.3	0.	0.0	0.0	0.0	1718.4	53.1	.2
MAR	13.	.8	1.79	.5	0.	0.0	0.0	0.0	1718.5	53.4	.3
APR	17.	1.0	4.60	1.3	0.	0.0	0.0	0.0	1718.4	53.1	-.3
MAY	31.	1.9	4.77	1.4	41.	2.5	0.0	0.0	1717.8	51.1	-2.0
JUN	72.	4.3	6.32	1.8	44.	2.6	0.0	0.0	1717.8	51.0	-.1
JUL	46.	2.8	8.80	2.4	122.	7.5	0.0	0.0	1715.6	43.9	-7.1
AUG	33.	2.0	7.74	1.8	141.	8.7	0.0	0.0	1712.5	35.4	-8.5
SEP	22.	1.3	5.66	1.1	64.	3.8	0.0	0.0	1711.1	31.8	-3.6
OCT	13.	.8	4.61	.9	0.	0.0	0.0	0.0	1711.0	31.7	-.1
NOV	7.	.4	2.54	.5	0.	0.0	0.0	0.0	1711.0	31.6	-.1
DEC	5.	.3	1.22	.2	0.	0.0	0.0	0.0	1711.0	31.7	.1
TOTAL		16.4	50.00	12.5		25.1	0.0	0.0			-21.2
MOST PROBABLE INFLOW CONDITIONS											
JAN	10.	.6	.73	.2	0.	0.0	0.0	0.0	1718.4	53.3	.4
FEB	23.	1.3	.77	.2	0.	0.0	0.0	0.0	1718.8	54.4	1.1
MAR	29.	1.8	1.04	.3	0.	0.0	0.0	0.0	1719.2	55.9	1.5
APR	39.	2.3	1.89	.6	0.	0.0	0.0	0.0	1719.6	57.6	1.7
MAY	73.	4.5	3.60	1.1	13.	.8	0.0	0.0	1720.3	60.2	2.6
JUN	168.	10.0	4.65	1.5	13.	.8	0.0	0.0	1722.3	67.9	7.7
JUL	107.	6.6	6.33	2.1	111.	6.8	0.0	0.0	1721.7	65.6	-2.3
AUG	76.	4.7	5.56	1.8	111.	6.8	0.0	0.0	1720.7	61.7	-3.9
SEP	50.	3.0	4.25	1.4	29.	1.7	0.0	0.0	1720.7	61.6	-.1
OCT	33.	2.0	3.59	1.2	0.	0.0	0.0	0.0	1720.9	62.4	.8
NOV	15.	.9	1.85	.6	0.	0.0	0.0	0.0	1721.0	62.7	.3
DEC	11.	.7	.74	.2	0.	0.0	0.0	0.0	1721.1	63.2	.5
TOTAL		38.4	35.00	11.2		16.9	0.0	0.0			10.3
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	24.	1.5	.45	.1	0.	0.0	0.0	0.0	1718.7	54.3	1.4
FEB	54.	3.0	.50	.2	0.	0.0	0.0	0.0	1719.5	57.1	2.8
MAR	65.	4.0	.56	.2	0.	0.0	0.0	0.0	1720.5	60.9	3.8
APR	87.	5.2	.53	.2	0.	0.0	0.0	0.0	1721.8	65.9	5.0
MAY	169.	10.4	1.68	.6	8.	.5	0.0	0.0	1724.0	75.2	9.3
JUN	383.	22.8	1.66	.6	10.	.6	0.0	0.0	1728.7	96.8	21.6
JUL	247.	15.2	5.47	2.3	68.	4.2	6.1	0.0	1729.2	99.4	2.6
AUG	174.	10.7	4.67	2.0	68.	4.2	4.5	0.0	1729.2	99.4	0.0
SEP	118.	7.0	2.75	1.2	17.	1.0	4.8	0.0	1729.2	99.4	0.0
OCT	73.	4.5	2.27	1.0	0.	0.0	3.5	0.0	1729.2	99.4	0.0
NOV	37.	2.2	1.02	.4	0.	0.0	1.8	0.0	1729.2	99.4	0.0
DEC	26.	1.6	.54	.2	0.	0.0	1.4	0.0	1729.2	99.4	0.0
TOTAL		88.1	22.10	9.0		10.5	22.1	0.0			46.5

TABLE 4
SHEET 13 OF 15

WEBSTER RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH ELEV	MONTH CONT	RESERVOIR CHANGE
	MEAN CFS	1000 AF	1000 INCHES	1000 AF	MEAN CFS	1000 AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	3.	.2	.96	.2	0.	0.0	0.0	0.0	1880.2	39.3	0.0
FEB	7.	.4	1.11	.2	0.	0.0	0.0	0.0	1880.3	39.5	.2
MAR	10.	.6	2.08	.4	0.	0.0	0.0	0.0	1880.3	39.7	.2
APR	12.	.7	4.92	1.0	0.	0.0	0.0	0.0	1880.2	39.4	-.3
MAY	24.	1.5	4.75	1.0	46.	2.8	0.0	0.0	1879.3	37.1	-2.3
JUN	47.	2.8	7.50	1.5	62.	3.7	0.0	0.0	1878.3	34.7	-2.4
JUL	36.	2.2	9.04	1.7	125.	7.7	0.0	0.0	1875.0	27.5	-7.2
AUG	20.	1.2	8.08	1.3	140.	8.6	0.0	0.0	1870.4	18.8	-8.7
SEP	15.	.9	6.70	.9	79.	4.7	0.0	0.0	1867.4	14.1	-4.7
OCT	11.	.7	4.71	.6	0.	0.0	0.0	0.0	1867.5	14.2	.1
NOV	5.	.3	2.45	.3	0.	0.0	0.0	0.0	1867.5	14.2	0.0
DEC	3.	.2	1.20	.1	0.	0.0	0.0	0.0	1867.6	14.3	.1
TOTAL		11.7	53.50	9.2		27.5	0.0	0.0			-25.0
MOST PROBABLE INFLOW CONDITIONS											
JAN	10.	.6	.67	.1	0.	0.0	0.0	0.0	1880.4	39.8	.5
FEB	22.	1.2	.81	.2	0.	0.0	0.0	0.0	1880.8	40.8	1.0
MAR	26.	1.6	1.48	.3	0.	0.0	0.0	0.0	1881.3	42.1	1.3
APR	32.	1.9	2.72	.6	0.	0.0	0.0	0.0	1881.8	43.4	1.3
MAY	65.	4.0	3.13	.7	13.	.8	0.0	0.0	1882.7	45.9	2.5
JUN	131.	7.8	4.40	1.0	15.	.9	0.0	0.0	1884.8	51.8	5.9
JUL	99.	6.1	7.02	1.7	112.	6.9	0.0	0.0	1883.9	49.3	-2.5
AUG	55.	3.4	5.72	1.3	112.	6.9	0.0	0.0	1882.2	44.5	-4.8
SEP	39.	2.3	4.69	1.0	34.	2.0	0.0	0.0	1881.9	43.8	-.7
OCT	29.	1.8	3.37	.8	0.	0.0	0.0	0.0	1882.3	44.8	1.0
NOV	13.	.8	1.61	.4	0.	0.0	0.0	0.0	1882.5	45.2	.4
DEC	10.	.6	.78	.2	0.	0.0	0.0	0.0	1882.6	45.6	.4
TOTAL		32.1	36.40	8.3		17.5	0.0	0.0			6.3
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	29.	1.8	.53	.1	0.	0.0	0.0	0.0	1880.9	41.0	1.7
FEB	59.	3.3	.48	.1	0.	0.0	0.0	0.0	1882.1	44.2	3.2
MAR	72.	4.4	.70	.2	0.	0.0	0.0	0.0	1883.6	48.4	4.2
APR	92.	5.5	1.00	.2	0.	0.0	0.0	0.0	1885.4	53.7	5.3
MAY	181.	11.1	1.74	.5	0.	0.0	0.0	0.0	1888.8	64.3	10.6
JUN	366.	21.8	.72	.2	0.	0.0	8.5	0.0	1892.4	77.4	13.1
JUL	278.	17.1	5.63	1.8	57.	3.5	11.8	0.0	1892.4	77.4	0.0
AUG	155.	9.5	4.03	1.3	59.	3.6	4.6	0.0	1892.4	77.4	0.0
SEP	109.	6.5	3.75	1.2	3.	.2	5.1	0.0	1892.4	77.4	0.0
OCT	85.	5.2	2.83	.9	0.	0.0	4.3	0.0	1892.4	77.4	0.0
NOV	37.	2.2	.99	.3	0.	0.0	1.9	0.0	1892.4	77.4	0.0
DEC	29.	1.8	.60	.2	0.	0.0	1.6	0.0	1892.4	77.4	0.0
TOTAL		90.2	23.00	7.0		7.3	37.8	0.0			38.1

TABLE 4
SHEET 14 OF 15

WACONDA LAKE OPERATION ESTIMATES - 1976

MONTH	UNDEPLETED INFLOW 1000	UPSTREAM DEPLETIONS 1000	DEPLETED INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RES SPILL	REQ SHORT	END OF ELEV	MONTH CONT	RES CHANGE
	AF	AF	MEAN 1000 CFS	AF	1000 INCHES	AF	MEAN 1000 CFS	AF	1000 AF	1000 AF	FT	1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS													
JAN	1.8	0.0	29.	1.8	.89	.9	3.	.2	0.0	0.0	1455.3	238.3	.7
FEB	3.2	-.5	49.	2.7	1.00	1.0	4.	.2	0.0	0.0	1455.5	239.8	1.5
MAR	4.4	-.9	57.	3.5	1.83	1.9	3.	.2	0.0	0.0	1455.6	241.2	1.4
APR	5.3	-1.1	71.	4.2	4.55	4.8	0.	0.0	0.0	0.0	1455.5	240.6	-.6
MAY	8.0	-1.9	99.	6.1	4.48	4.7	0.	0.0	.5	0.0	1455.6	241.5	.9
JUN	15.1	-4.6	176.	10.5	6.57	6.9	0.	0.0	3.6	0.0	1455.6	241.5	0.0
JUL	11.1	-2.3	143.	8.8	8.05	8.2	332.	20.4	0.0	0.0	1454.0	221.7	-19.8
AUG	6.0	-.3	93.	5.7	8.50	8.3	146.	9.0	0.0	0.0	1453.0	210.1	-11.6
SEP	4.5	.5	84.	5.0	6.19	5.9	0.	0.0	0.0	0.0	1452.9	209.2	-.9
OCT	2.0	-.8	20.	1.2	4.42	4.2	0.	0.0	0.0	0.0	1452.6	206.2	-3.0
NOV	1.9	-.3	27.	1.6	2.46	2.3	0.	0.0	0.0	0.0	1452.6	205.5	-.7
DEC	2.2	.1	37.	2.3	1.16	1.1	3.	.2	0.0	0.0	1452.7	206.5	1.0
TOTAL	65.5	-12.1	53.4		50.10	50.2		30.2	4.1	0.0			-31.1
MOST PROBABLE INFLOW CONDITIONS													
JAN	4.4	-.7	60.	3.7	.53	.6	3.	.2	0.0	0.0	1455.5	240.5	2.9
FEB	6.3	-2.1	76.	4.2	.63	.7	4.	.2	2.3	0.0	1455.6	241.5	1.0
MAR	7.5	-2.9	75.	4.6	.84	.9	3.	.2	3.5	0.0	1455.6	241.5	0.0
APR	11.6	-3.6	134.	8.0	2.90	3.0	0.	0.0	5.0	0.0	1455.6	241.5	0.0
MAY	27.5	-7.7	322.	19.8	2.96	3.1	0.	0.0	16.7	0.0	1455.6	241.5	0.0
JUN	49.0	-16.8	541.	32.2	3.32	3.5	0.	0.0	28.7	0.0	1455.6	241.5	0.0
JUL	24.1	-10.3	224.	13.8	6.05	6.2	459.	28.2	0.0	0.0	1453.9	220.9	-20.6
AUG	13.0	-5.5	122.	7.5	4.46	4.3	228.	14.0	0.0	0.0	1453.0	210.1	-10.8
SEP	13.8	-3.6	171.	10.2	3.96	3.8	0.	0.0	0.0	0.0	1453.5	216.5	6.4
OCT	6.0	-3.1	47.	2.9	3.24	3.2	0.	0.0	0.0	0.0	1453.5	216.2	-.3
NOV	4.8	-1.3	59.	3.5	1.85	1.8	0.	0.0	0.0	0.0	1453.7	217.9	1.7
DEC	5.0	-.7	70.	4.3	.76	.7	3.	.2	0.0	0.0	1453.9	221.3	3.4
TOTAL	173.0	-58.3	114.7		31.50	31.8		43.0	56.2	0.0			-16.3
REASONABLE MAXIMUM INFLOW CONDITIONS													
JAN	9.5	-2.8	109.	6.7	.36	.4	0.	0.0	2.4	0.0	1455.6	241.5	3.9
FEB	15.5	-5.9	173.	9.6	.21	.2	0.	0.0	9.4	0.0	1455.6	241.5	0.0
MAR	19.0	-7.9	181.	11.1	.34	.4	0.	0.0	10.7	0.0	1455.6	241.5	0.0
APR	36.4	-10.1	442.	26.3	1.39	1.5	0.	0.0	24.8	0.0	1455.6	241.5	0.0
MAY	56.6	-21.2	576.	35.4	.87	.9	0.	0.0	34.5	0.0	1455.6	241.5	0.0
JUN	165.9	-35.7	2188.	130.2	-.20	-.2	0.	0.0	130.4	0.0	1455.6	241.5	0.0
JUL	69.8	-13.4	917.	56.4	4.46	4.6	1161.	71.4	0.0	0.0	1454.0	221.9	-19.6
AUG	41.8	-9.8	520.	32.0	3.27	3.2	660.	40.6	0.0	0.0	1453.0	210.1	-11.8
SEP	53.5	-3.2	845.	50.3	2.29	2.3	0.	0.0	16.6	0.0	1455.6	241.5	31.4
OCT	28.5	-1.2	444.	27.3	2.41	2.5	0.	0.0	24.8	0.0	1455.6	241.5	0.0
NOV	14.9	-.3	245.	14.6	.92	1.0	0.	0.0	13.6	0.0	1455.6	241.5	0.0
DEC	9.6	.2	159.	9.8	.38	.4	0.	0.0	9.4	0.0	1455.6	241.5	0.0
TOTAL	521.0	-111.3	409.7		16.70	17.2		112.0	276.6	0.0			3.9

TABLE 4
SHEET 15 OF 15

CEDAR BLUFF RESERVOIR OPERATION ESTIMATES - 1976

MONTH	HISTORICAL INFLOW		NET EVAPORATION		RELEASE REQUIREMENT		RESERVOIR SPILL	REQUIREMENT SHORTAGE	END OF MONTH		RESERVOIR CHANGE
	MEAN CFS	1000 AF	1000 INCHES	AF	MEAN CFS	1000 AF	1000 AF	1000 AF	ELEV FT	CONT 1000 AF	1000 AF
REASONABLE MINIMUM INFLOW CONDITIONS											
JAN	3.	.2	1.23	.5	8.	.5	0.0	0.0	2130.1	106.1	-.8
FEB	5.	.3	1.39	.5	7.	.4	0.0	0.0	2130.0	105.5	-.6
MAR	8.	.5	2.48	.9	10.	.6	0.0	0.0	2129.8	104.5	-1.0
APR	15.	.9	5.30	2.0	7.	.4	0.0	0.0	2129.5	103.0	-1.5
MAY	34.	2.1	5.10	1.9	44.	2.7	0.0	0.0	2128.9	100.5	-2.5
JUN	79.	4.7	7.76	2.8	44.	2.6	0.0	0.0	2128.7	99.8	-.7
JUL	39.	2.4	9.16	3.2	111.	6.8	0.0	0.0	2126.9	92.2	-7.6
AUG	36.	2.2	8.88	2.9	111.	6.8	0.0	0.0	2125.0	84.7	-7.5
SEP	20.	1.2	6.41	2.0	61.	3.6	0.0	0.0	2123.8	80.3	-4.4
OCT	15.	.9	4.93	1.5	24.	1.5	0.0	0.0	2123.3	78.2	-2.1
NOV	5.	.3	2.90	.9	7.	.4	0.0	0.0	2123.0	77.2	-1.0
DEC	3.	.2	1.46	.4	7.	.4	0.0	0.0	2122.8	76.6	-.6
TOTAL	15.9		57.00	19.5	26.7		0.0	0.0			-30.3
MOST PROBABLE INFLOW CONDITIONS											
JAN	8.	.5	1.08	.4	8.	.5	0.0	0.0	2130.2	106.5	-.4
FEB	16.	.9	1.13	.4	7.	.4	0.0	0.0	2130.3	106.6	.1
MAR	21.	1.3	1.72	.7	10.	.6	0.0	0.0	2130.3	106.6	0.0
APR	37.	2.2	3.77	1.4	7.	.4	0.0	0.0	2130.3	107.0	.4
MAY	86.	5.3	3.22	1.2	21.	1.3	0.0	0.0	2131.0	109.8	2.8
JUN	200.	11.9	4.29	1.7	20.	1.2	0.0	0.0	2132.8	118.8	9.0
JUL	101.	6.2	7.39	3.0	93.	5.7	0.0	0.0	2132.3	116.3	-2.5
AUG	93.	5.7	6.04	2.4	106.	6.5	0.0	0.0	2131.7	113.1	-3.2
SEP	49.	2.9	4.48	1.8	34.	2.0	0.0	0.0	2131.5	112.2	-.9
OCT	37.	2.3	3.73	1.5	21.	1.3	0.0	0.0	2131.4	111.7	-.5
NOV	13.	.8	2.46	1.0	7.	.4	0.0	0.0	2131.2	111.1	-.6
DEC	10.	.6	1.20	.5	7.	.4	0.0	0.0	2131.2	110.8	-.3
TOTAL	40.6		40.51	16.0	20.7		0.0	0.0			3.9
REASONABLE MAXIMUM INFLOW CONDITIONS											
JAN	23.	1.4	.92	.3	8.	.5	0.0	0.0	2130.5	107.5	.6
FEB	45.	2.5	.87	.3	7.	.4	0.0	0.0	2130.9	109.3	1.8
MAR	60.	3.7	1.20	.5	10.	.6	0.0	0.0	2131.4	111.9	2.6
APR	104.	6.2	2.32	.9	7.	.4	0.0	0.0	2132.4	116.8	4.9
MAY	239.	14.7	2.02	.9	18.	1.1	0.0	0.0	2134.9	129.5	12.7
JUN	553.	32.9	1.25	.6	17.	1.0	0.0	0.0	2140.3	160.8	31.3
JUL	276.	17.0	5.22	2.8	62.	3.8	0.0	0.0	2141.9	171.2	10.4
AUG	257.	15.8	4.25	2.4	70.	4.3	0.0	0.0	2143.3	180.3	9.1
SEP	136.	8.1	3.86	2.2	24.	1.4	0.0	0.0	2144.0	184.8	4.5
OCT	106.	6.5	2.56	1.5	16.	1.0	3.7	0.0	2144.0	185.1	.3
NOV	37.	2.2	1.62	.9	7.	.4	.9	0.0	2144.0	185.1	0.0
DEC	24.	1.5	.92	.5	7.	.4	.6	0.0	2144.0	185.1	0.0
TOTAL	112.5		27.01	13.8	15.3		5.2	0.0			78.2

TABLE 5
FLOOD DAMAGES PREVENTED BY KANSAS RIVER PROJECT'S RESERVOIRS

BONNY			SWANSON			ENDERS			HUGH BUTLER			HARRY STRUNK		
Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total
1951	\$ 293,000	\$ 293,000	1957	\$ 233,000	\$ 233,000	1951	\$ 220,000	\$ 220,000	1962	\$ 2,000	\$ 2,000	1951	\$ 14,000	\$ 14,000
1953	135,000	428,000	1960	900,000	1,133,000	1956	104,000	324,000	1965	137,000	139,000	1957	5,000	19,000
1957	1,050,000	1,478,000	1962	126,000	1,259,000	1960	412,000	736,000	1967	42,000	181,000	1960	198,000	217,000
1960	169,000	1,647,000	1964	50,000	1,309,000	1962	37,000	773,000				1962	29,000	246,000
1965	273,000	1,920,000	1965	477,000	1,786,000	1965	137,000	910,000				1967	129,000	375,000
1967	42,000	1,962,000	1967	182,000	1,968,000	1967	42,000	952,000				1969	6,000	381,000
1969	200,000	2,162,000	1969	1,000	1,969,000	1969	1,000	953,000						

NORTON			HARLAN COUNTY			LOVEWELL			KIRWIN			WEBSTER		
Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total
1966	\$ 132,000	\$ 132,000	1957	\$1,045,000	\$ 1,045,000	1957	\$ 349,000	\$ 349,000	1957	\$ 522,000	\$ 522,000	1957	\$ 326,000	\$ 326,000
1967	885,000	1,017,000	1960	4,853,000	5,898,000	1960	178,000	527,000	1958	10,000	532,000	1958	114,000	440,000
1972	498,000	1,515,000	1961	255,000	6,153,000	1961	165,000	692,000	1960	499,000	1,031,000	1960	1,018,000	1,458,000
			1962	45,000	6,198,000	1962	5,000	697,000	1961	1,000	1,032,000	1961	1,000	1,459,000
			1964	182,000	6,380,000	1971	9,000	706,000	1962	1,000	1,033,000	1962	1,000	1,460,000
			1965	60,000	6,440,000	1973	1,728,000	2,434,000	1964	34,000	1,067,000	1964	17,000	1,477,000
			1966	1,658,000	8,098,000	1975	98,000	2,532,000	1965	325,000	1,392,000	1965	325,000	1,802,000
			1967	3,539,000	11,637,000				1967	191,000	1,583,000	1967	85,000	1,887,000
			1969	14,000	11,651,000				1968	44,000	1,627,000	1968	2,000	1,889,000
			1971	64,000	11,715,000				1969	2,000	1,629,000	1969	1,000	1,890,000
			1973	1,310,000	13,025,000				1971	3,000	1,632,000	1971	3,000	1,893,000
			1974	1,000	13,026,000				1973	40,000	1,672,000	1973	54,000	1,947,000
			1975	200,000	13,226,000				1975	618,000	2,290,000	1975	885,000	2,832,000

WACONDA			CEDAR BLUFF			PROJECT TOTALS		
Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total	Year	Damages Prevented	Cumulative Total
1968	\$ 280,000	\$ 280,000	1951	\$ 597,000	\$ 597,000	1951	\$1,124,000	\$ 1,124,000
1969	606,000	886,000	1955	357,000	954,000	1953	135,000	1,259,000
1971	9,000	895,000	1956	19,000	973,000	1955	357,000	1,616,000
1973	3,797,000	4,692,000	1957	4,812,000	5,785,000	1956	123,000	1,739,000
1974	1,000	4,693,000	1958	829,000	6,614,000	1957	8,342,000	10,081,000
1975	967,000	5,660,000	1960	1,573,000	8,187,000	1958	953,000	11,034,000
			1961	101,000	8,288,000	1960	9,800,000	20,834,000
			1962	1,000	8,289,000	1961	523,000	21,357,000
			1964	17,000	8,306,000	1962	247,000	21,604,000
			1965	38,000	8,344,000	1964	300,000	21,904,000
			1967	42,000	8,386,000	1965	1,772,000	23,676,000
			1969	1,000	8,387,000	1966	1,790,000	25,466,000
			1971	8,000	8,395,000	1967	5,179,000	30,645,000
			1973	536,000	8,931,000	1968	326,000	30,971,000
			1975	11,000	8,942,000	1969	832,000	31,803,000
						1971	96,000	31,899,000
						1972	498,000	32,397,000
						1973	7,465,000	39,862,000
						1974	2,000	39,864,000
						1975	2,779,000	42,643,000

NOTE.--Construction cost of storage dams --
\$208,954,130.

TABLE 6
OTHER USES AT FEDERALLY CONSTRUCTED STORAGE AND DIVERSION DAMS
NIOBRARA, LOWER PLATTE AND KANSAS RIVER BASINS
DURING 1975
Annual Totals




Features	Visitors	Cars in Area	Water Craft	Sport Fish Caught	Season Take Ducks	Season Take Geese
Colorado						
Bonny Reservoir	335,372	95,820	5,290	13,352	1,340	70
Kansas						
Norton Reservoir	127,913	36,547	3,302	40,000	300	30
Almena Diversion Dam	1,595	500	0	130	0	0
Lovewell Reservoir	184,110	48,450	4,750	2,734	250	65
Kirwin Reservoir	75,056	37,368	175	21,415	120	188
Webster Reservoir	140,371	37,938	375	57,000	750	100
Woodston Diversion Dam	2,010	670	0	900	0	0
Waconda Lake	307,334	83,065	5,446	174,790	1,000	200
Cedar Bluff Reservoir	200,200	57,200	6,477	40,000	300	30
Nebraska						
Box Butte Reservoir	51,218	15,304	4,822	16,500	130	12
Merritt Reservoir	54,846	18,902	4,375	78,382	1,750	0
Arcadia Diversion Dam	15,150	3,990	0	9,500	300	25
Sherman Reservoir	88,000	32,592	17,000	75,000	1,600	500
Swanson Lake	136,471	57,179	5,328	7,500	400	20
Enders Reservoir	25,837	6,130	1,066	3,000	500	25
Hugh Butler Lake	112,815	42,903	5,514	13,000	500	15
Harry Strunk Lake	56,161	13,874	1,711	8,000	500	20
Harlan County Reservoir	954,666	275,605	93,000	100,000 <u>1/</u>	380	275
TOTAL REPORTED	2,869,125	864,037	158,631	561,203	10,120	1,575

Visitors = Total visitor-days which includes fishing, hunting, boating, skiing, camping, picnicking and sightseeing.



Water Craft = Boating days which includes rentals, inboards, outboards, rowboats and sailboats.

1/ lbs. -- excluded from total.


BOX BUTTE RESERVOIR HISTORICAL OPERATION




BOX BUTTE RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 75,075 A.F.
ANNUAL MINIMUM 32,385 A.F.





MOST PROBABLE
REASONABLE MAXIMUM
REASONABLE MINIMUM
ACTUAL




MERRITT RESERVOIR HISTORICAL OPERATION



MERRITT RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 16,761 A.F.
ANNUAL MINIMUM 872 A.F.





MOST PROBABLE ———
REASONABLE MAXIMUM - - - - -
REASONABLE MINIMUM
ACTUAL [Hatched Area]


SHERMAN RESERVOIR HISTORICAL OPERATION



SHERMAN RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 70,230 A.F.
 ANNUAL MINIMUM 8,041 A.F.





MOST PROBABLE
 REASONABLE MAXIMUM
 REASONABLE MINIMUM
 ACTUAL


BONNY RESERVOIR HISTORICAL OPERATION



BONNY RESERVOIR OPERATING PLANS




ANNUAL MAXIMUM 45,467 A.F.
ANNUAL MINIMUM 38,056 A.F.





MOST PROBABLE —————
REASONABLE MAXIMUM - - - - -
REASONABLE MINIMUM
ACTUAL 


SWANSON LAKE HISTORICAL OPERATION




SWANSON LAKE OPERATING PLANS






ANNUAL MAXIMUM 118,380 A.F.
ANNUAL MINIMUM 61,050 A.F.





MOST PROBABLE
REASONABLE MAXIMUM
REASONABLE MINIMUM
ACTUAL




ENDERS RESERVOIR HISTORICAL OPERATION



ENDERS RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 39,934 A.F.
ANNUAL MINIMUM 11,802 A.F.





MOST PROBABLE —————
REASONABLE MAXIMUM - - - - -
REASONABLE MINIMUM
ACTUAL


HUGH BUTLER LAKE HISTORICAL OPERATION



HUGH BUTLER LAKE OPERATING PLANS






ANNUAL MAXIMUM 39,562 A.F.
 ANNUAL MINIMUM 27,371 A.F.





MOST PROBABLE
 REASONABLE MAXIMUM
 REASONABLE MINIMUM
 ACTUAL


HARRY STRUNK LAKE HISTORICAL OPERATION




HARRY STRUNK LAKE OPERATING PLANS




ANNUAL MAXIMUM 41,890 Δ F
ANNUAL MINIMUM 18,732 Δ F





MOST PROBABLE
REASONABLE MAXIMUM
REASONABLE MINIMUM
ACTUAL




NORTON RESERVOIR HISTORICAL OPERATION



NORTON RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 9,288 A.F.
 ANNUAL MINIMUM 4,417 A.F.





MOST PROBABLE
 REASONABLE MAXIMUM
 REASONABLE MINIMUM
 ACTUAL


HARLAN COUNTY RESERVOIR HISTORICAL OPERATION




HARLAN COUNTY RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 348,356 A.F.
ANNUAL MINIMUM 238,562 A.F.





MOST PROBABLE —————
REASONABLE MAXIMUM - - - - -
REASONABLE MINIMUM
ACTUAL 


LOVEWELL RESERVOIR HISTORICAL OPERATION




LOVEWELL RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 71,882 A.F.
ANNUAL MINIMUM 28,150 A.F.





MOST PROBABLE
REASONABLE MAXIMUM
REASONABLE MINIMUM
ACTUAL




KIRWIN RESERVOIR HISTORICAL OPERATION




KIRWIN RESERVOIR OPERATING PLANS




ANNUAL MAXIMUM 68,270 A.F.
ANNUAL MINIMUM 30,508 A.F.





MOST PROBABLE ———
REASONABLE MAXIMUM - - - - -
REASONABLE MINIMUM
ACTUAL 


WEBSTER RESERVOIR HISTORICAL OPERATION



WEBSTER RESERVOIR OPERATING PLANS






ANNUAL MAXIMUM 56,344 A.F.
ANNUAL MINIMUM 15,846 A.F.







MOST PROBABLE
REASONABLE MAXIMUM
REASONABLE MINIMUM
ACTUAL

WACONDA LAKE HISTORICAL OPERATION






WACONDA LAKE OPERATING PLANS





MOST PROBABLE ———
 REASONABLE MAXIMUM - - - - -
 REASONABLE MINIMUM
 ACTUAL 


CEDAR BLUFF RESERVOIR HISTORICAL OPERATION



CEDAR BLUFF RESERVOIR OPERATING PLANS




ANNUAL MAXIMUM 126,910 A.F.
ANNUAL MINIMUM 106,440 A.F.




MOST PROBABLE ———
REASONABLE MAXIMUM - - - - -
REASONABLE MINIMUM
ACTUAL 

CANAL DIVERSIONS AND ACRES IRRIGATED

All Districts in Niobrara, Lower Platte and Kansas River Basins




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED Mirage Flats Irrigation District




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

Ainsworth Irrigation District

Acres Feet Diverted and Acres Irrigated
-Thousands-



CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED Sargent Irrigation District




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED


Farwell Irrigation District

FARWELL CANAL

Acre Feet Diverted and Acres Irrigated
—Thousands—




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED Frenchman Valley Irrigation District



CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

H. and R.W. Irrigation District


Acres Feet Diverted and Acres Irrigated
— Thousands —



CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED


Frenchman - Cambridge Irrigation District

Acre Feet Diverted and Acres Irrigated
—Thousands—




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

Almena Irrigation District




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

Bostwick Irrigation District in Nebraska




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

Kansas - Bostwick Irrigation District




CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

Kirwin Irrigation District



CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED

Webster Irrigation District



CANAL DIVERSIONS, FARM DELIVERIES AND ACRES IRRIGATED Cedar Bluff Irrigation District

