



Construction Methods
August 1934

U. S. Bureau of Reclamation Photo

STEEL JUMBO FORM aids placing of concrete lining in Nevada penstock header tunnel at Boulder dam. Belt conveyor delivers mix to sides and bottom of lining while concrete for the top arch is placed by pressure gun.