

Valve House Roofs Completely Poured

10-4-35
Concrete slabs to form the roofs of the two valve houses of the Boulder canyon project have been completely poured, a major step in the construction of the two houses which will form the canyon wall outlet works.

The concrete slabs, which were poured over steel rails, will be covered with gravel which, in turn, will be covered with a tar composition.

Three emergency gates are in the process of being installed there, and the crane has been completely installed in the Arizona valve house.