alternativenergy

BPAE WIND-US LIFT PROCEDURE



CRITICAL LIFTS

Issued By:	Hans.Owen@BP.com	11/19/2007	Document No.: AEPA_WND_EDOMH_GN_40_000018_00
Approval By:	Tim Stastny@BP.com	11/19/2007	BPAE- EA

THE PROCEDURES LISTED IN THIS SECTION IS TO BE USED IN CONJUCTION WITH THE BP ALTERNATIVE ENERGY HSSE PLAN AND PROCEDURES.

TABLE OF CONTENTS

1.0 SCOPE	1
2.0 DEFINITIONS	1
3.0 GENERAL	1
4.0 REQUIRED CRITICAL LIFT PLANS	2
5.0 CRITICAL LIFT PLAN COMPONENTS	2
6.0 REVIEW MEETINGS	4
7.0 REVIEW REQUIREMENT	4
8.0 CONTINGENCY PLAN	4
ATTACHMENT 1: PERMIT FOR CRITICAL NONREPETITIVE LIFT	5

1.0 <u>SCOPE</u>

This procedure outlines the specific planning and execution requirements for lifting loads that are considered critical to the facility or project.

2.0 **DEFINITIONS**

"Live Equipment" means equipment that is operating or any non-operating equipment containing liquids and/or gases.

"**Proximity**" means any distance within the radius of the combined length of the crane boom and length of the load fully extended horizontally.

"Critical Lift" - See Section 4.1

3.0 GENERAL

alternativenergy

BPAE WIND-US LIFT PROCEDURE



CRITICAL LIFTS

	•		
Issued By:	Hans.Owen@BP.com	11/19/2007	Document No.: AEPA_WND_EDOMH_GN_40_000018_00
Approval By:	Tim Stastny@BP.com	11/19/2007	BPAE- EA

- **3.1** The Contractor and Operation Personnel shall submit a Critical Lift Plan for review and acceptance by BP Alternative Energy Representative at least fifteen (15) working days prior to performing any lift that is covered by this Project Procedure.
- **3.2** This Critical Lift Plan will be returned to the Contractor accepted, accepted with comments, or not accepted within seven days (7) working days.
- **3.3** The contractor or Operation Personnel hall have critical lifts plans reviewed and approved by a qualified engineer acceptable to state in which the work is being preformed. All lift plans shall be complete with, details, load calculations, crane certification and rigging. Critical Lift Plans shall be stamped by a licensed Professional Engineer.
- **3.4** No lift is allowed if it exceeds 95% of the chart for any given configuration of the crane. Site Manager Approval is required for all Critical Lifts.
- **3.5** Personnel are not allowed in the shadow of the boom's arc while a critical lift is in progress.

4.0 REQUIRED CRITICAL LIFT PLANS

- **4.1** Critical Lift Plans are required for all lifts with a mobile crane, where one or more of the following conditions are present:
 - 4.1.1 The weight of the item to be lifted exceeds 50,000 pounds;
 - 4.1.2 The lift is within an operating facility and the weight of the item to be lifted exceeds 20,000 pounds.
 - 4.1.3 The total load to be lifted exceeds 75% of the chart for the lift configuration of the crane;

OR

- 4.1.4 Any other lift that is deemed as a "critical lift" by BP Alternative Energy that would impact either plant operability, environmental compliance start –up or reputation.
- 4.1.5 All multi pick loads.
- 4.1.6 Any lift that will occur over transmission lines and substation.

5.0 CRITICAL LIFT PLAN COMPONENTS

Page 3 of 7

alternativenergy

BPAE WIND-US LIFT PROCEDURE



CRITICAL LIFTS

Issued By:	Hans.Owen@BP.com	11/19/2007	Document No.: AEPA_WND_EDOMH_GN_40_000018_00
Approval By:	Tim Stastny@BP.com	11/19/2007	BPAE- EA

The Critical Lift Plan shall include, as a minimum, the following:

5.1 A completed Project Critical Lift Permit. See Attachment 1.

5.2 An *Elevation View* showing:

- 5.2.1 Crane manufacturer's document of make and model of the crane with boom, boom length, radius and crane capacity for the configuration used.
- 5.2.2 Rigging accessory information to identify and show capacity of sling, shackles, spreader beams, blocks, etc.
- 5.2.3 Tabulation of weights of all items that constitute load on the crane boom, lifted load, load lines, load blocks, spreaders, slings, shackles, jib, headache ball, etc.
- 5.2.4 Lifted equipment information to include weight, height, and diameter, point of support, center of gravity and degree of dress-out.
- 5.2.5 Calculation of tailing load.
 - A horizontal loading diagram will be drawn to show the initial tailing crane load on the elevation view.
 - The equipment center of gravity is to be obtained from the vendor.
- 5.2.6 Any obstructions or interferences to the lift from existing equipment, structure, etc.
- 5.2.7 Details of the supporting mats or foundation under the lifting crane and tailing crane with notation indication of the bearing capacity of the sub soil and the calculated applied load.
- 5.2.8 Ratio of the lifted load to each crane's chart capacity as configured.
- 5.2.9 Crane boom to load clearances.
- 5.3 The *Plan View* should show, on an overlay of the area plot plan:
 - 5.3.1 The lift and tailing crane location at the beginning of the lift, any travel and the final location.
 - 5.3.2 Initial horizontal position of equipment to be lifted.
 - 5.3.3 Layout and specifics for all required matting.

Note: Crane mats are required whenever the crane outrigger or crawler tracks soil bearing pressure is equal or greater than 2,000 pound/square foot (*lb/ft*²).

5.3.4 The plot layout should show any existing area and any new construction that will be in place when the lift occurs.

alternativenergy

BPAE WIND-US LIFT PROCEDURE



CRITICAL LIFTS

Issued By:	Hans.Owen@BP.com	11/19/2007	Document No.: AEPA_WND_EDOMH_GN_40_000018_00
Approval By:	Tim Stastny@BP.com	11/19/2007	BPAE- EA

- 5.3.5 Special note should be made of any underground lines or if the lift will pass over any operating condition, i.e.: pipe rack, equipment, tank, electrical, building, etc.
- 5.3.6 Special note should be made if any portion of the lifting configuration will, at any time during the lift, pass within ten (10) feet of any exposed live electrical component.
- 5.3.7 The area under the boom's arc that shall be "off-limits" to all personnel not associated with the lift.
- **5.4** Attachments to the rigging study should include any item that will make the review more efficient and complete. Required items are:
 - 5.4.1 Equipment weight information from the Equipment Manufacturer.
 - 5.4.2 Equipment weight verification this can be either scale weight tickets or independently calculated weight.
 - 5.4.3 Cut sheets from the Crane Vendor's capacity chart indicating the appropriate configuration.
 - 5.4.4 Cut sheets from the manufacturer of the rigging attachments showing capacity and weight.
 - 5.4.5 Outrigger or crawler track soil bearing pressure chart or calculations.

6.0 <u>REVIEW MEETINGS</u>

At the option of BP Alternative Energy, a formal rigging review meeting may be scheduled. As a minimum, this meeting shall be attended by the Contractor's site representative and, where appropriate, the rigging engineer and superintendent for the Heavy Lift Subcontractor.

7.0 EMERGENCY ACTION PLAN

The HSSE supervisor shall be notified and emergency action plan shall be reviewed prior to the lift plan.

8.0 <u>REVIEW REQUIREMENT</u>

No critical lift may proceed without a Critical Lift Permit signed and accepted by BPAE Representative.

alternativenergy Provered by BPAE WIND-US LIFT PROCEDURE					
	bp	CRITIC	AL LIFTS		
Issued By:	Hans.Owen@BP.com	11/19/2007	Document No.: AEPA_WND_EDOMH_GN_40_000018_00		
Approval By:	Tim Stastny@BP.com	11/19/2007	BPAE- EA		

.

alternative	nergy BPAE WIN	D-US LIFT	PROCEDURE
	bp ***	CRITIC	AL LIFTS
Issued By:	Hans.Owen@BP.com	11/19/2007	Document No.: AEPA_WND_EDOMH_GN_40_000018_00
Approval By:	Tim Stastny@BP.com	11/19/2007	BPAE- EA

Attachment 1

Г

Attachment 1 is shown on the next page.

CRITICAL LIFT PERMIT For Critical Non-Repetitive Lift

						Issue Da	ate:	/ /	
1. Project Name/Plant		2. Contractor		3	. Lift Date and time	4	. Lift Location		
5. Crane Manufacturer	Crane Manufacturer 6. Model Number		7	7. Serial Number		8. Total Boom/Boom Ext and/or Jib Lgth (ft) @ time of Lift			
9. Max. radius during L (pick, swing	ift , and set)	10. Swing Dir.	& Degrees of swin	ig 1'	1. Lift Elevation (ft)	12	2. Boom Angle		
	. ,				MaxMinPick			Set	
13. Will Jib and/or Boor	n Ext be used	? Yes N	lo	14	. Mfg. rated capacity from ch	nart as outli	ined in Blocks 8	- 13	
lf Yes: Length (f Weight (l	t)	Stowed							
15. Component Weights	s:			16	. Load Description and Weig	ght			
Jib / Boom Extension:		Wt							
Headache Ball	Si	ze:	Wt.	17	17. Who determined weight of Load and Lift?				
Load Block	Si	70.	\\/t		Name:				
Auxiliany Boom Hoods	0		\\/t	-	How:				
Auxiliary Booth Tiead.			VVI	18	. Total Lift Load		19. Load % of	Crane Capacity	
Weight of Cable (Load	Fall):		vvt		(Block 15 + 16)		(Divide Bloc	k 18 by 14)	
Slings, Rigging, Shackle	es, & Etc:		Wt	20	. Rigging Safety factor 5 to 1	1?	21. Rigging acc	cessories size and	
Lifting Beam or Bars:			Wt				condition:		
Allowance for Unaccour	nted Material a	and Equipment	Wt		res No		Slings:		
Other			Wt				Shackles:		
	То	otal Weight					Othory		
							Other:		
22. Tag Line Required Yes No	Sir	3. Parts of Wire R ngle-Line Capacity	ope on Block and of Wire Rope	24	. Soil Conditions? Poor Calculations? Compaction? Crane Mats?	Requi Requi Requi	Good ired ired ired	Not Required Not Required Not Required	
25. HAZARDS:	I					26. Inspe	ction/Testing:		
Electrical?	Yes N	o If Yes,	Explain:			Load Tes	t Date:		
Rain?	Yes N	o If Yes,	Explain:			Periodic I	nsp. Date:		
Overhead?	Yes N	o If Yes,	Explain:		Test Lift:				
Wind Speed	Yes N	o If Yes,	Explain:		Remote Are				
(If wind speed > 35 r	mph (56 kph),	lift is prohibited.)			Lift Location				
Underground?	Yes N	o If Yes,	Explain:				(Block 4)		
Others?	Yes N	o If Yes,	Explain:	1					
27. Pre-lift meeting:	20	28. Attach	11 • • • "	29. Emp	loyee Training verified.	No			
Date:	110	"Elevation	v View"		163				
		"Other Att	achments"						
30. Signatures:									
Representative of company making lift D			Date	BP Alternative Energy Construction Date Manager			Date		
Contractor rigging supervisor			Dato	RD Altornative Energy Droject Manager			Date		
Contractor ngging supervisor Date			Dale	BE Allemanive Energy Froject Manager			Dale		
Contractor Site Manager Da			Date	BP Safety Representative			Date		
31. Immediate Approv	al to Proceed	with Lift.							
Set up is in acc	cordance with	the lift plan witho	ut deviation and th	ie lift may	proceed.				
BP Alternative	BP Alternative Energy Rigging Consultant D			Date	BP Alternative Energy Site Manager			Date	