
Appendix B Draft Engineering Designs



BENCH MARKS

All elevations shown are based on the California Coordinate System, Zone 3, NAD 83, Epoch 1993, as determined by Station HPGN-D-CA-06-RG with an NAVD 88 elevation of 430.00 Feet.

U.S.C. & G.S. MONUMENT

The station is located near the State Highway 41 crossing of the Madera Canal. To reach the station from the junction of State Highways 41 and 145, go south on Highway 41 for 2.3 miles to the bridge over the Madera Canal. Continue south on Highway 41 for 0.1 mile to the station on the left at post mile 6.8. The station is a survey disk encosed in PVC pipe with access cover set in concrete flush with the ground. The station is about 500 FT south of the bridge over the Madera Canal, about 215 FT south of a concrete viduate or flughway 41, 22.5 FT west of the center of the access road on the west side of the canal, 23.5 ET west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal, 23.5 FT west of the center of the access road on the west side of the canal. 2.3 FT west of a carsonite witness post and about 2 FT higher than Highway 41.

TOPOGRAPHY NOTE

Topography shown is photogrametric data provided by Aerial Photomapping Services August 2003, and supplemented by field surveys conducted March 2006.

BOUNDARY NOTE

The boundary/easement information shown on these plans is based upon record information tied to physical monuments, and was prepared under the direction of Craig E. Baum, PLS 7680.

CONSULTING ENGINEERS AND LAND SURVEYORS OF CALIFORNIA. Construction Contractor agrees that in accordance with generally accepted construction practices, construction Contractor will be required to assume sole and complete produces, construction contraction will be required to assume sole and complete responsibility for job site conditions during the course of construction of the project, including safety of all persons and property, that this requirement shall be made to apply continuously and not be limited to normal working hours, and construction Contractor further agrees to defend, indemnify and hold design professional hornless from any and all liability, real and alleged, in connection with the performance of work on this project, excepting liability arising from the sole negligence of design professional. professional

<u>SPECIAL NOTE</u> Where underground and surface structures are shown on the plans, the locations, depth and dimensions of structures are believed to be reasonably correct, but are not guaranteed. Such structures are shown for the information of the Contractor, but information so given is not to be construed as a representation that such structures will, in all cases, be found where shown, or that they represent all of the structures which may be encountered.

Castle and Cooke, Inc.

Madera County, CA

Gateway Village In-Lieu Pipeline




SITE MAP

- 2.
- - 9

SITE SAFETY AND PROTECTION NOTES

- THE DUTY OF THE ENGINEER, OWNER OR ITS AGENTS TO CONDUCT CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE AND THE UNDERTAKING OF INSPECTIONS OR THE GIVING OF INSTRUCTIONS AS AUTHORIZED HEREIN IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF THE ACTUAL CONSTRUCTION NOR MAKE THE ENGINEER, OWNER OR ITS AGENTS RESPONSIBLE FOR PROVIDING A SAFE PLACE FOR THE PERFORMANCE OF WORK BY THE CONTRACTOR, SUBCONTRACTORS, OR SUPPLIERS, OR FOR ACCESS, VISITS, USE, WORK, TRAVEL OR OCCUPANCY BY ANY PERSON.
- THE CONTRACTOR SHALL HAVE AT THE WORK SITE, COPIES OR SUITABLE EXTRACTS OF CONSTRUCTION SAFETY ORDERS, ISSUED BY CAL-OSHA. HE SHALL COMPLY WITH PROVISIONS OF THESE AND ALL OTHER APPLICABLE LAWS, ORDINANCES AND REGULATIONS. THE CONTRACTOR MUST COMPLY WITH PROVISIONS OF THE SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION, PROMULGATED BY THE SECRETARY OF LABOR UNDER SECTION 107 OF THE CONTRACT WORK HOURS AND SAFETY STANDARDS ACT, AS SET FORTH IN TITLE 29 C.F.R.
- TO PROTECT THE LIVES AND HEALTH OF HIS EMPLOYEES UNDER THE CONTRACT, THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT PROVISIONS OF THE "MANUAL OF ACCIDENT PREVENTION IN CONSTRUCTION" ISSUED BY THE ASSOCIATED GENERAL CONTRACTORS OF AMERICA, INC., AND SHALL MAINTAIN AN ACCURATE RECORD OF ALL CASES OF DEATH, OCCUPATIONAL DISEASE, AND INJURY REQUIRING MEDICAL ATTENTION OR CAUSING LOSS OF TIME FROM WORK, ARISING OUT OF AND IN THE COURSE OF EMPLOYMENT OR WORK UNDER THE CONTRACT.
- THE CONTRACTOR ALONE SHALL BE RESPONSIBLE FOR THE SAFETY, EFFICIENCY, AND ADEQUACY OF HIS FACILITIES, APPLIANCES, AND METHODS AND FOR ANY DAMAGE, WHICH MAY RESULT FROM THEIR FAILURE OR THEIR IMPROPER CONSTRUCTION, MAINTENANCE OR OPERATION.
- THE OWNER AND ITS AGENTS' SITE RESPONSIBILITIES ARE LIMITED SOLELY TO THE ACTIVITIES OF THEIR EMPLOYEES ON SITE. THESE RESPONSIBILITIES SHALL NO BE INFERRED BY ANY PARTY TO MEAN THAT THE OWNER OR ITS AGENTS HAVE RESPONSIBILITY FOR SITE SAFETY. SAFETY IN, ON, OR ABOUT THE SITE IS THE SOLE AND EXCLUSIVE RESPONSIBILITY OF THE CONTRACTOR ALONE. THE CONTRACTOR'S METHODS OF WORK PERFORMANCE, SUPERINTENDENCE AND THE CONTRACTOR'S EMPLOYEES, AND SEQUENCING OF CONSTRUCTION ARE ALSO THE SOLE AND EXCLUSIVE RESPONSIBILITIES OF THE CONTRACTOR ALONE. 5.



Know what's below.
Know what's below. Call before you dig.



LEGEND	
EXISTING	PROPOSED

		RIGHT-OF-WAY
E	E	PROPERTY LINE ELECTRIC LINE (UNDERGROUND)
E	E	ELECTRIC LINE (AERIAL)
	T	TELEPHONE LINE (UNDERGROUND) IRRIGATION PIPELINE
	\rightarrow	CHAIN LINK FENCE
		EDGE OF A.C. PAVEMENT
P	(-P)	UTILITY POLE AND ANCHOR
<u>ε</u>	E	ELECTRIC VAULT
0	•	MANHOLE / STANDPIPE
>	→ 	CULVERT (SIZE AS NOTED)
0	•	GUARD POST
Δ	Δ	CONTROL POINT
+	+	BENCHMARK
۵	۲	MONUMENT
I TEL	TEL	TELEPHONE RISER
Ĩ	T,	TELEPHONE VAULT
Ħ	28	FLOW METER
8	θ	WATER VALVE
Φ	•	CANAL GATE
0	٥	WELL
	()	DETAIL NUMBER
	XXX	SHEET NUMBER
<u>EL=</u> DES	=XXX.XXe SC.	SPOT ELEVATION DESCRIPTION
		SECTION LINE
\sim	\sim	APPROX. EDGE OF VEGETATION
		10 FOOT EXISTING GROUND SURFACE CONTROL
		2 FOOT EXISTING GROUND SURFACE CONTROL
		CONSTRUCTION EASEMENT
		O & M EASEMENT
\succ		DIRECTION OF SLOPE

USBR

APN ASSESSOR'S PARCEL NUMBER AMERICAN SOCIETY FOR TESTING AND MATERIALS ASTM вс BEGIN CURVE CALIFORNIA CA CFS CUBIC FEET PER SECOND CAST IN PLACE CIP CL CLASS. CLF CHAIN LINK FENCE CENTER LINE C/L OR Q CONCRETE CONC CONSTRUCTION CONST CY CUBIC YARD DIA OR Ø DIAMETER DIST DISTRIBUTION MADERA IRRIGATION DISTRICT DISTRICT END OF CURVE EC EXISTING GRADE EG ELECTRICAL ELEC ELEV OR EL ELEVATION ELBOW ELL FΡ EDGE OF PAVEMENT ESMT EASEMENT EW EACH WAY EXIST OR (E) EXISTING FURNISH AND INSTALL F&d FG FINISHED GRADE FL OR L FLOW LINE FT FEET FV&C FRESNO VALVE & CASTINGS GALVANIZED GALV GÐ GRADE BREAK HGL HYDRAULIC GRADE LINE HT HEIGHT HIGH WATER LEVEL HWL INSIDE DIAMETER ID INV INVERT IRR IRRIGATION LF LINEAR FEET LT LEFT MAX MAXIMUM MOTOR CONTROL CENTER MCC MADERA IRRIGATION DISTRICT MID MIN MINIMUM NOT IN CONTRACT NIC NTS NOT TO SCALE OPERATION & MAINTENANCE 0&M ON CENTER 0C OD OUTSIDE DIAMETER он OVERHEAD PE PERMANENT EASEMENT PHASE P≻ P/L OR R PROPERTY LINE PROD PRODUCTION PROP OR (P) PROPOSED PSI POUNDS PER SQUARE INCH PVC POLY VINYL CHLORIDE DESIGN FLOW Q RC RADIUS OF CURVE RGRCP RUBBER GASKETED REINFORCED CONCRETE PIPE ROW OR R/W RIGHT OF WAY RT RIGHT S= SLOPE SEC SECTION SOUARE FEET SF SGL STATIC GRADE LINE SP SERVICE POLE STA STATION TCE TEMPORARY CONSTRUCTION EASEMENT TOP OF STRUCTURE TS т₩ TOP OF WALL TRAVELING WATER SCREEN TWS TYPICAL TYP

UNITED STATES BUREAU OF RECLAMATION

ABBREVIATIONS

AP

ANTENNA POLE

GRADING NOTES

- CONTRACTOR SHALL PROVIDE ALL LABOR, MATERIALS, AND EQUIPMENT AND PERFORM ALL GRADING AND EARTHWORK PROCEDURES TO INSTALL STRUCTURES AND PIPELINES AND CONSTRUCT CANAL FMBANKMENTS
- OVEREXCAVATE AND RECOMPACT TO A MINIMUM DEPTH OF 12" UNDER 2. AND WITHIN 5' OF ALL CANAL BANKS, STRUCTURES AND STANDPIPES TO A MINIMUM 90% RELATIVE COMPACTION.
- NATIVE SOIL MATERIALS, EXCLUSIVE OF DEBRIS, LESS THAN 3 INCHES IN MAXIMUM DIMENSION, AT THE PROPER MOISTURE RANCE, AND CONTAINING LESS THAN 0.3% ORGANICS BY WEIGHT MAY BE USED AS ENGINEERED FILL. FINISHED CANAL BANKS SIDES SHALL BE SMOOTH AND FREE OF DEBRIS
- ALL AREAS TO RECEIVE ENGINEERED FILL SHOULD BE SCARIFIED TO A 4 MINIMUM DEPTH OF 12 INCHES, UNIFORMLY MOISTURE CONDITIONED, AND COMPACTED TO AT LEAST 90% RELATIVE COMPACTION.
- ENGINEERED FILL SHOULD BE PLACED IN LOOSE LIFTS NO THICKER THAN 8 INCHES, AND UNIFORMLY MOISTURE CONDITIONED TO AT OR ABOVE OPTIMUM MOISTURE CONTENT AT THE TIME OF COMPACTION, AND RE-COMPACTED TO AT LEAST 90% RELATIVE COMPACTION.
- ENGINEERED FILL SHALL BE CONSTRUCTED USING METHODS THAT MITIGATE STRATIFICATION AND LAMINATION OF THE FILL AND MUST BE COMPACTED LISING KNEADING COMPACTORS (I.E., SHEEPSFOOT) TO UNITE DENDING MERADING COMPACINGS (I.E., SILLE STOUT) TO PROMOTE BLENDING WITHIN AND BETWEEN INDIVIDUAL CONSTRUCTION LIFTS. TRACK ROLLING, PNEUMATIC WHEEL ROLLING, AND SMOOTH DRUM COMPACTORS SHALL NOT BE USED.
- THE MAXIMUM LABORATORY DENSITY AT OPTIMUM MOISTURE CONTENT WILL BE DETERMINED BY TEST METHODS IN CONFORMANCE WITH ASTM D1557. A MINIMUM OF 90% OF THE LABORATORY STANDARD MAXIMUM 7.
- WITHIN 2' OF ANY STRUCTURE, HAND TAMPERS OR OTHER ACCEPTABLE MEANS EXCLUDING HEAVY EQUIPMENT SHALL BE USED TO COMPACT BACKFILL. THE SURFACE AREA AROUND ANY STRUCTURE, SHALL BE GRADED TO CONVEY SURFACE RUNOFF AWAY FROM THE STRUCTURE. THE EARTHWORK SHALL BE CONSTRUCTED IN A CONTINUOUS MANNER CROSS PROPOSED STRUCTURE LOCATION
- MOISTURE CONTENT OF COMPACTED EMBANKMENT MATERIAL AND BACKFILL MATERIAL SHALL NOT BE GREATER THAN 3% ABOVE OPTIMUM MOISTURE CONTENT.
- PROTECT EXCAVATIONS BY SHORING, BRACING, SHEET PILING UNDERPINNING, OR OTHER METHODS REQUIRED TO PREVENT CAVE-IN OR LOOSE SOIL FROM FALLING INTO EXCAVATION. GRADE EXCAVATION TOP PERIMETER TO PREVENT SURFACE WATER RUN-OFF INTO
- 11. COMPACTED EARTHFILL AND SUBGRADES SHALL MEET MINIMUM 90% RELATIVE DENSITY (ASTM D-1557) AND BE ACCOMPLISHED BY MANUALLY OPERATED COMPACTORS AROUND STRUCTURES AND TO A MINIMUM DEPTH OF 12 INCHES OVER TOP OF PIPE.
- 12. ALL TRENCH EXCAVATION SHALL COMPLY WITH THE MOST CURRENT OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION STANDARDS (OSHA).
- 13 THE AREA IMMEDIATELY SURROUNDING THE NEW TURNOUT SHALL BE THE AREA IMMEDIATELY SURROUNDING THE NEW TURNOUT SHALL BE OVER EXCAVATED TWELVE INCHES (12") AND RECOMPACTED TO A RELATIVE DENSITY OF NINETY PERCENT (90%). NATIVE MATERIAL SHALL BE USED FOR THE RECOMPACTED MATERIAL HOWEVER, FILL MATERIAL SHALL BE FREE OF TRASH, ORGANIC MATERIAL HOWEVER, FILL MATERIAL STONES OR COBBLES HAVING A LARGEST DIMENSION GREATER THAN ONE INCH (1") WILL NOT BE USED IN RECOMPACTED MATERIAL. NO OBJECT HAVING A LARGEST DIMENSION GREATER THAN THREE INCHES (3") SHALL BE INCLUDED IN ANY COMPACTED FILL TO BE USED FOR THE NEW TURNOUT.

CONCRETE NOTES

- CONCRETE 28 DAY COMPRESSIVE STRENGTH TO BE MINIMUM 3,500 PSI. CEMENT SHALL BE ASTM TYPE II PORTLAND CEMENT AND BE FREE OF LUMPS AND PARTIALLY SET MASSES, AND PROPORTIONED TO FREE OF LUMPS AND PARTIALLY SET MASSES, AND PROPORTIONED TO INCLUDE NOT LESS THAN 6 SACKS OF CEMENT PER CUBIC YARD OF CONCRETE AND HAVE A MAXIMUM WATER-CEMENT RATIO OF 0.50, AND AIR ENTRAINMENT OF 37-57, WATER SHALL BE FREE FROM ACID, ALKAL, OLIS OR ORGANIC MATTER. AGGREGATE SHALL BE CLEAN, HARD, STRONG AND DURABLE, AND FREE FROM DIRT AND OTHER SUBSTANCES DELETERIOUS TO CONCRETE. THE FINE AND COARSE AGGREGATES SHALL BE A WELL GRADED MIX APPROVED BY THE AND MEED DIE MAXIMUM STZE CE ACCRECATE SHALL NOT EXCEED ENGINEER. THE MAXIMUM SIZE OF AGGREGATE SHALL NOT EXCEED 3/4 INCHES AND CONFORM TO THE REQUIREMENTS OF ASTM C-33.
- CONSISTENCY OF THE CONCRETE SHALL ALLOW IT TO BE WORKED INTO PLACE WITHOUT SEGREGATION. SLUMP SHALL BE MAXIMUM OF 3 INCHES FOR HORIZONTAL SURFACES AND 4 INCHES FOR VERTICAL 2. WALLS. FORMS SHALL BE BRACED AND/OR TIED TOGETHER SO AS TO MAINTAIN POSITION AND SHAPE AND BE SUFFICIENTLY TIGHT TO PREVENT LEAKAGE OF MORTAR.
- NO CONCRETE SHALL BE PLACED UNTIL THE SUBGRADE, FORMS, AND REINFORCING STEEL HAVE BEEN INSPECTED BY THE ENGINEER AND, DEPENDING ON LOCATION, THE DISTRICT ENGINEER. HORIZONTAL CONCRETE SURFACES SHALL BE POURED AGAINST OVERXCAVATED AND RECOMPACTED EARTH. ALL VERTICAL CONCRETE SURFACES SHALL BE POURED AGAINST FORMS IN ALL CASES. CONCRETE SHALL NOT BE DROPPED MORE THAN FIVE FEET VERTICALLY UNLESS SUITABLE EQUIPMENT IS USED TO PREVENT SEGREGATION. CONSOLIDATION OF CONCRETE SHALL BE ACCOMPLISHED BY MEANS OF INTERNAL TYPE MECHANICAL VIBRATORS, OR ENGINEER PRE-APPROVED EQUIVALENT 3. MECHANICAL VIBRATORS, OR ENGINEER PRE-APPROVED EQUIVALENT
- CONSTRUCTION JOINTS SHALL BE PLACED AS SHOWN ON THE PLANS OR AS PRE-APPROVED BY THE ENGINEER ONLY. ENTIRE SURFACE UNDER WALL TO BE ROUGHENED WHILE WET. MINIMUM 1/8" 4. AMPLITUDE DEPTH. JOINTS SHALL BE THOROUGHLY CLEANED AND LAITANCE REMOVED BEFORE A NEW POUR IS MADE. EACH JOINT SHALL BE WETTED IMMEDIATELY BEFORE THE PLACING OF NEW CONCRETE
- ALL CAST-IN-PLACE CONCRETE STRUCTURES SHALL BE FORMED INSIDE AND OUT AND CONCRETE VIBRATED SUFFICIENTLY TO PROVIDE 5. FOR SMOOTH SURFACED WALLS/FLOORS WITHOUT VOIDS AND HONEYCOMBS
- REINFORCING STEEL SHALL BE IN ACCORDANCE WITH STRUCTURAL DETAILS AND NOTES.
- SHOTCRETE OR CONCRETE LINING SHALL EITHER BE REINFORCED WITH 6x6x10x10 WELDED WIRE MESH PLACED IN CENTER, OR BY 2 LBS/CY OF SYNTHETIC FIBER & 50 LBS/CY OF STEEL FIBER REINFORCEMENT.
- REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60 8. REINFORCING SIELE SHALL CUNFORM TO ASIM ADD, GRADE BU STEEL BARS FOR CONCRETE REINFORCEMENT, INTERMEDIATE GRADE, AND SHALL HAVE DEFORMATIONS CONFORMING TO ASTM A615, REINFORCING STEEL SHALL BE CLEANED OF HEAVY FLAKY RUST, LOOSE MILL SCALE, DIRT, GREASE, AND OTHER FOREIGN SUBSTANCES PRIOR TO PLACEMENT. WIRE USED FOR TYNG REINFORCEMENT IN PLACE SHALL BE NO.18 AWG BLACK ANNEALED DE VEAVER OR HEAVIER.

3.

CONSTRUCTION NOTES

CONTRACTOR RESPONSIBLE FOR ALL CLEARING AND GRUBBING.

ALL CONCRETE PRESSURE PIPE WITH STEEL JOINT RING SHALL BE HEAD PRESSURE ASTM C361 CLASS AS SHOWN ON PLANS AND INSTALLED PER CONCRETE PIPE MANUFACTURERS SPECIFICATIONS. ALL OTHER CONCRETE IRRIGATION PIPE SHALL BE RGRCP, CL III AS SHOWN ON PLANS.

THRUST RESTRAINTS SHALL BE PROVIDED AT ALL PIPELINE BENDS WHETHER OR NOT SHOWN ON THE PLANS.

FLOWMETER INSTALLATION NOTES


FLOWMETER SHALL BE A McCROMETER BRAND PROPELLER-TYPE FLOWMETER, MODEL OF12 OR EQUAL. THE NOMINAL SIZE OF THE METER SHALL BE 36 INCHES. CORROSION RESISTANT MATERIALS SHALL BE USED THROUGHOUT THE MECHANICAL ENCLOSURE. EXCEPT FOR THE REGISTER ASSEMBLY, NO ALUMINUM MATERIALS SHALL BE USED AND ALL NON-STAINLESS STEEL SURFACES SHALL BE TREATED WITH A FUSION-BONDED IMPERVIOUS COATING. ALL ROTATING MEMBERS, EXCEPT MEMBERS IN THE REGISTER ASSEMBLY, SHALL BE MOUNTED ON STAINLESS STEEL RADIAL BEARINGS. SLEEVE TYPE OR CORAMIC BEARINGS ARE NOT ACCEPTABLE. FLOWMETER SYSTEM ACCURACY SHALL BE ±2% OF TRUE FLOW RATE WITHIN THE RANGE SPECIFIED.


THE REGISTER SHALL BE ON A COMMON AXIS WITH THE IMPELLER SUPPORT AND SHALL BE RIGIDLY SUPPORTED BY THE HOUSING SUPPORT PLATE OR DROP PIPE. THE REGISTER SHALL CONSIST OF AN INSTANTANEOUS INDICATOR AND TOTALIZER WHICH SHALL BE MOUNTED INSTANTANEOUS INDICATOR AND TOTALIZER WHICH SHALL BE MOUNTED PERPENDICULAR TO THE DIRECTION OF FLOW AND WHICH CAN BE VIEWED THROUGH A TRANSPARENT COVER. THE TOTALIZER SHALL BE SIX-DIGIT, STRAIGHT-READING, DRIVEN BY A POSITIVE DIRECT DRIVE MECHANISM FROM THE IMPELLER COUPLING, AND SHALL REGISTER TOTALIZE VOLUME IN ACRE-FEET (AF). THE FLOW INDICATOR SHALL SHOW FLOWS INSTANTANEOUSLY AND BE DRIVEN BY A MAGNET DRAG MECHANISM FROM A IMPELLER COUPLING. THE FLOW RATE INDICATOR SHALL INDICATE FLOW IN CUBIC FEET PER SECOND (CFS). THE REGISTER SHALL BE FACTORY LUBRICATED AND SEALED WATER-TIGHT FOR INFREQUENT SUBMERSION.


3. FLOWRATE LIMITS OF THE METER SHALL BE AS FOLLOWS: MINIMUM FLOW - 1,500 GPM (3.3 CFS) *LOW-VELOCITY CONSTRUCTION MAXIMUM FLOW - 20.000 GPM (44.6 CFS) INTERMITTENT - 30,000 GPM (66.8 CFS)


INSTALLATION SHALL BE ACCORDING TO MANUFACTURER'S SPECIFICATIONS. SEE McCROMETER PROPELLER FLOWMETERS MANUAL FOR INSTALLATION, OPERATION AND MAINTENANCE.


COPPRIGHT 2011 By PEODOST & PRITCHARD RESERVENCED IN A ALL REST RESERVED. THE ITTER OF IND A ALL REST REST REST of the ITTER of the ALL REST REST REST of the ITTER of the ALL REST REST REST in a supersy transmission of complete the opposite the analysis of the activity of the analysis of the ALL REST REST REST REST in an of the ALL REST REST REST REST of the ALL REST REST REST REST REST REST and the ALL REST REST REST REST REST REST REST REST REST REST REST REST REST REST		
PRELIMINARY FOR REVIEW AND APPROVAL 01/26/2011	No. REVISION BY DATE	
	DATE SIGNED:	
Gateway Village In-Lieu Pipeline Castle and Cooke, Inc. Madera County, CA	GENERAL NOIES	73/2008 B.15 D3 AM G. Milenia/Casile Conter-1434/1434-Galewary1434-Exoon Phs 1/14340405-Galewary Pipeline LD/dwq/SHEET/14340405-GN-NOTES.dwg - aoron
DESIGN ENGINEER:	559/449-2700 FAX 559/449-2715 www.ppeng.com	-1434/1434-Galewav/1434-Expon Phs 1/14340
Randy Hopkins LICENSE NO: 63538 DRAFTED BY: CHECKED DVS SCALE: AS SHOWN DATE: 01/26/2011 JOB NO: 12491101 DWG. NO: SHEET GN2 OF	BY:	2008 8:13:03 AM G: \Clients\Castle_Cooke-

























DT CREEK			ν
		ij	An Employee owned company an Employee owned company an Employee owned company an Employee owned company and the state of the state and t
	SCALE: VERT: AS HORIZ: SHOWN	Village Pipeline Sooke, Inc. unty, CA	PLAN & PROFILE CONSTRUCTION
RT		Gateway Village In-Lieu Pipeline stle and Cooke, Ir Madera County, CA	& PF STRUC
0 © 57.6' RT W MANHOLE	335	Gateway Villa In-Lieu Pipeli Castle and Cooke, Madera County,	CONS
-12-LF 24"¢ CONCRETE LINED -DI-PIPE W/RESTRAINED JOINTS	330	ů	PIPELINE
			IdId
	325	DST&	Company AVENUE 711-6162 7149-2715
"_DL_90" BEND RAINED_JOINTS Ø CONCRETE_LINED		PRITCHARE	A Northe Antwork Company An Employee Owned Company 286 WEST CORUNKEL AVENUE FRESNO, CALFORNIA 93711–6162 559/449–2710 FX 559/449–2715 999-2710 FX 559/449–2715
/RESTRAINED JOINTS	315	PRO	An Employ An Employ 286 WES FRESNO, C. 559/449-27
FIANGE X MJ ADAPTER		DESIGN ENGINE Rondy Hop LICENSE NO:	ER: kins
58 LF 24* Ø CONCRETE LINED DI PIPE W/RESTRAINED JOINTS	310	63538	CHECKED BY:
		DATE: 01/	SHOWN 26/2011
	702	JOB NO: 124 DWG. NO: SHEET	.91101
	300	PP8	OF












#7 EXPANDED METAL GRATING -WELDED TO CHANNEL (SWDx LWD - 48"x 96" SHEETS)


1-INCH DIAMETER ANCHOR BOLTS & SS WASHERS


6"x 6"x 1/4" PLATE --BUTT WELDED TO 3"x 3"x 1/4" ANGLE FRAME

3"x 3"x 1/4" ANGLE FRAME



Now what's below. Call before you dig.	Correlation 2011, by Front, K. Fritten, M. B. Barrell, B. B. Barrell, B. B. Barrell, B. Ba	
	FOR REVIEW AND APPROVAL 01/26/2011 No. REVISION BY DATE	
	A CONTRACT OF CONT	- aaron
	Gateway Village In-Lieu Pipeline Castle and Cooke, Inc. Madera County, CA 24 INCH METERING STRUCTURE	5/29/2008 3:19:53 PM G: \Clients\Castle_Cooke-1434\1434-Gateway\1434-Expan Phs 1\14340405-Gateway PhsEine LD\dwg\SHEET\14340405-ST-TURNOUT DETAILS2.dwg - aaron
	ESTIGNED STORE	4/1434-Gateway/1434-Expan Phs 1/
	DESIGN ENGINEER: Randy Hopkins UCENSE NO: 635538 DRAFTED BY: DVS VSL SCALE: AS SHOWN DATE: 01/26/2011 JOB NO: 12491101 DWG. NO:	19:53 PM G: \Clients\Castle_Cooke-1434
Ø	SHEET ST4 of	5/29/2008 3





1. CASING ENDS SHALL BE PLUGGED WITH UNGROUTED BRICKS, OR ANOTHER APPROVED

2. GROUTING MAY BE REQUIRED BETWEEN THE OUTSIDE OF THE CASING AND THE ROADBED TO FILL VOIDS CAUSED BY THE WORK. GROUT PRESSURE SHALL NOT EXCEED 5 PSI FOR A DURATION SUFFICIENT TO FILL THE VOIDS.

3. IF WING CUTTERS ARE USED, THEY SHALL ONLY ADD A MAXIMUM OF 1 INCH DIAMETER TO THE OUTSIDE DIAMETER OF THE CASING PIPE.


4. A BAND WELDED TO THE LEADING EDGE OF THE CASING SHOULD BE PLACED SQUARE TO THE ALIGNMENT. THE BAND SHOULD NOT BE PLACED ON THE BOTTOM EDGE. FLARING THE LEAD SECTION SHALL NOT BE PERMITTED.


5. CASING LENGTH SHALL EQUAL AUGER LENGTH.


6. FENCING WILL BE REQUIRED AROUND THE JACKING AND RECEIVING PITS.

7. SHORING IF REQUIRED SHALL CONFORM TO OR EXCEED CAL-OSHA MINIMUM REQUIREMENTS.

8. A MINIMUM OF 2 INCHES OF CLEARANCE IS REQUIRED BETWEEN THE INTERIOR OF THE CASING PIPE AND THE EXTERIOR OF THE PIPELINE.







DT4 SCALE: NTS

This Page Left Intentionally Blank

Appendix C – Environmental Protection Measures

- 1. A biologist shall provide training to construction project workers to familiarize them with listed species before project activities are begun at RCWD. The biologist shall provide images of, and describe the identifying characters, life history characteristics, biology and ecology, of SJKF and CTS. Additionally, the protections afforded for listed species and designated critical habitat and penalties for violations under the ESA shall be described, including the definition of "take" as defined under the ESA (U.S.C. 16 Sect. 1531 et. seq.). The U.S. Code states: "Take is defined as harass, harm, pursue, hunt, shoot, wound, kill, trap, capture or collect, or to attempt to engage in any such conduct. Harass is defined by the Service as an intentional or negligent act or omission which creates the likelihood of injury to a listed species by annoying it to such an extent as to significantly disrupt normal behavioral patterns which include, but are not limited to, breeding, feeding, or sheltering. Harm is defined by the Service to include significant habitat modification or degradation that results in death or injury to listed species by impairing behavioral patterns including breeding, feeding, or sheltering."
- 2. The work foreman, or person on site in charge of construction (i.e. Responsible Person), shall be the person designated as responsible for contacting USFWS (Service), DFG and Reclamation biologists, should a listed species be encountered during project activities in RCWD. This person also will be the contact person for any biologist working on the project. The name and contact information of this person shall be provided to Service, DFG and Reclamation biologists prior to beginning any construction.
- 3. If a listed species is observed in the Action Area at RCWD, the Responsible Person shall immediately contact biologists at the Sacramento Fish and Wildlife Office (SFWO), DFG and at Reclamation SCCAO. No further work in RCWD may be taken on the Proposed Action until appropriate consultation with Service and DFG has been completed.
- 4. A standard survey for San Joaquin kit fox (SJKF; Service 2011) shall be conducted between 14 and 30 days before activities on the project begin and a report on the findings filed with Reclamation and the SFWO. Pending the results of that survey, if no evidence of kit fox, their sign, or other evidence of their presence is detected, work may proceed pending completion of environmental compliance and notification of such by Reclamation.
- 5. Standard avoidance measures for SJKF (Service 2011) shall be implemented for the project.

- 6. Rodent burrows shall be avoided and may not be destroyed. At the time when specific locations for facilities are being identified by on the ground personnel, and also prior to beginning earth disturbing work, all burrows that could be affected by construction activities shall be flagged by a biologist (such as with a surveyor flag). Hi-viz barrier fencing at least 3 feet high shall be erected and maintained around burrows or burrow complexes to identify these sensitive areas which shall be avoided during the period of construction.
- 7. From June until the first rain event occurring on or after October 1, if an open hole or trench in the earth 6 inches deep or greater is created during construction, and it must remain open overnight, the opening to the trench or hole must either be covered to preclude entry by animals, or escape ramps suitable for CTS and SJKF must be placed at least every 50 lineal feet. If construction occurs between October 1 and May 31, for any hole or trench greater than 6 inches deep that must be left open overnight, such hole or trench must be completely covered to prevent access by animals, including CTS, if any work is conducted subsequent to a rain event. A rain event is one where measurable precipitation has been recorded at Fresno Yosemite International Airport, or, if the event is not sufficiently widespread to have been measured at this station, but otherwise is "commonly recognized" as to have occurred over the RCWD project area, the latter condition would be defining. No construction is permitted during periods of rain.
- 8. Any open pipe within a trench or hole shall have its opening(s) capped. Each day before work activity occurs in such areas (e.g. for laying pipe), the hole or trench shall be inspected for the presence of listed species. If CTS, SJKF or other listed species is present, Reclamation biologists, the CDFG and SFWO shall be contacted immediately and no further action may be taken until further appropriate consultation with the Service and DFG are completed.
- 9. Any pipe or similar tubular material staged or stored overnight at RCWD in an area which could be accessed by SJKF or CTS, shall be capped or covered to preclude entry. Before it is moved or installed, the openings of these materials and the area surrounding the materials must be examined for the presence of SJKF and CTS or other listed species. If a listed species is present, they must be allowed to leave of their own accord. If the animal does not immediately leave the area or there is risk of take, SFWO, DFG and Reclamation biologists shall be contacted immediately and no further action may be taken until further appropriate consultation with the Service and DFG are completed. Additionally, daily, before equipment is operated, the areas underneath such equipment shall be inspected by the operator for the presence of SJKF or CTS.
- 10. All "take" of migratory birds associated with the Proposed Action is prohibited and must be avoided. In addition to the pre-activity survey for SJKF, a pre-activity survey prior to construction shall be made for burrowing owls. As applicable, measures for avoidance

(DFG 1995) of "take" under MBTA shall be applied (Attention is directed to the Federal Migratory Bird Treaty Act (16 U.S.C. 703-712) 50 CFR Part 10 and California Fish and Game Code Sections 3503, 3513 and 3800, which protect migratory birds, occupied nests and eggs from disturbance and destruction. With regard to "take" under MBTA, 16 U.S.C. § 703 states that "Unless and except as permitted by regulations made as hereinafter provided in this subchapter, it shall be unlawful at any time, by any means or in any manner, to pursue, hunt, take, capture, kill, attempt to take, capture, or kill, possess, offer for sale, sell, offer to barter, barter, offer to purchase, purchase, deliver for shipment, ship, export, import, cause to be shipped, exported, or imported, deliver for transportation, transport or cause to be transported, carry or cause to be carried, or receive for shipment, transportation, carriage, or export, any migratory bird, any part, nest, or eggs of any such bird, or any product, whether or not manufactured, which consists, or is composed in whole or part, of any such bird or any part, nest, or egg thereof, included in the terms of the conventions between the United States and Great Britain for the protection of migratory birds concluded August 16, 1916 (39 Stat. 1702), the United States and the United Mexican States for the protection of migratory birds and game mammals concluded February 7, 1936, the United States and the Government of Japan for the protection of migratory birds and birds in danger of extinction, and their environment concluded March 4, 1972

http://www.fws.gov/permits/mbpermits/regulations/mbta.html - N_1_#N_1_and the convention between the United States and the Union of Soviet Socialist Republics for the conservation of migratory birds and their environments concluded November 19, 1976."

11. Furthermore, should construction be required in February through August, a biologist shall conduct a survey to locate nesting birds in the Action Area at RCWD. Any migratory birds that may be affected by. Those areas in RCWD, where birds or their nests, etc. that may be subjected to "take", as defined under the MBTA as consequence of the Proposed Action, shall be identified and avoidance measures implemented under the guidance of a biologist.

No water conveyed in federal facilities and applied to lands in RCWD would be applied to native lands, or to lands fallowed or left untilled for 3 or more years until such lands are first surveyed for listed species. If such lands are determined to be inhabited by listed species, then no water may be applied on them until effects to listed species are consulted upon. This Page Left Intentionally Blank

Appendix D – ITA and Cultural Resources Determinations

Inthavong, Michael T

From:	Rivera, Patricia L
Sent:	Friday, June 03, 2011 9:12 AM
То:	Inthavong, Michael T
Subject:	RE: ITA Request Form (EA-06-117)

Michael,

I reviewed the proposed action to approve the following requests made by Madera Irrigation District (MID), Root Creek Water District (RCWD), and Shafter-Wasco Irrigation District (SWID):

- Issuance of an MP-620 permit to MID for two turnouts on Lateral 6.2;
- Approval of long-term annual transfers of up to 10,000 acre-feet (AF) of Central Valley Project (CVP) water from MID to RCWD;
- Execution of a temporary contract for Section 215 water with RCWD for Contract Year 2011; and
- Approval of long-term annual exchanges of up to 7,000 AF of CVP water between MID and SWID for ultimate delivery to RCWD via an agreement with Westside.

The MP-620 permit would be issued to MID and would cover both turnouts and easements for the pipelines within Reclamation easement and right-of-way (ROW) for Lateral 6.2. Each turnout would involve excavation and typical concrete structure on Lateral 6.2. MID's new turnout would include a 24-inch diameter pipeline which would then extend towards MID's existing distribution system approximately 0.25 miles south of Lateral 6.2. Excavation to bury the pipeline would be approximately 5 feet (ft) deep and 10 ft wide. RCWD's new turnout would include a 36-inch diameter pipeline, which would transition to a 48-inch diameter pipeline at the meter vault, and then extend towards RCWD's existing distribution system roughly 2.75 miles south of Lateral 6.2. Excavation would be roughly 10 ft wide and up to 11 ft deep depending on elevation to allow at least 3 ft of cover. At Avenue 12 and Root Creek, excavation would involve jack and boring underneath the road and creek.

The long-term annual transfers between MID and RCWD would occur through Contract Year 2035. More specifically, MID would annually transfer up to 25 cubic-feet per second (cfs) from May 1 to August 31 and up to 50 cfs from September 1 to April 30. When available, MID would deliver a portion of its CVP supplies to RCWD via the Madera Canal, Lateral 6.2, and then through the newly built RCWD turnout and pipeline.

The Section 215 contract for RCWD would be for Contract Year 2011, ending on February 29, 2012. As declared available by Reclamation, the Section 215 water would be conveyed through the Madera Canal, Lateral 6.2, and then the newly built RCWD turnout and pipeline by MID.

The annual exchanges between MID and SWID would occur through Contract year 2035. More specifically, Westside would transfer to SWID up to 3,500 AF for years 1-4, up to 5,000 AF for years 5-9, and up to 7,000 AF for years 10+ of non-CVP. SWID would then exchange and make available a like amount of its CVP supplies to MID, which would in turn make a like amount (minus conveyance losses) of its CVP supplies available to RCWD. When available, the CVP water would be conveyed through the Madera Canal, Lateral 6.2, and then the newly built RCWD turnout and pipeline.

The proposed action does not have a potential to affect Indian Trust Assets. The nearest ITA is Table Mountain Rancheria approximately 10 miles NE of the project location.

Patricia

Inthavong, Michael T

From:	Nickels, Adam M
Sent:	Wednesday, June 08, 2011 2:08 PM
То:	Inthavong, Michael T
Cc:	Barnes, Amy J; Bruce, Brandee E; Dunay, Amy L; Fogerty, John A; Goodsell, Joanne E;
	Overly, Stephen A; Perry, Laureen (Laurie) M; Soule, William E; Williams, Scott A
Subject:	RE: Root Creek project (07-SCAO-222)
Attachments:	07-SCAO-222 SHPO Consultation Letter0001.pdf; BUR070809A CONSTRUCT TURNOUT
	NEW PIPE OFF LATERAL 6 2 MADERA CANAL ROOT CK WATER DIST (3).doc

Project No. 07-SCAO-222

Michael,

I have reviewed Draft EA-06-117 and only one small comment changing the CR determination in the environmental consequences in Section 3.4.2 (correction highlighted). Reclamation consulted on this action in 2007 and retained SHPO concurrence (letters attached). The proposed action will have no adverse effect to historic properties resulting in no impacts to cultural resources. After reviewing the EA in comparison to the consultations, I have determined that the existing consultations are sufficient enough for this EA. You have no further obligation for review under Section 106 of the National historic Preservation Act. Please note that in the event that cultural resources are uncovered during project implementation, Reclamation may have further responsibilities under Section 106 as defined by the regulations at 36 CFR Part 800.6 (Post Review Discovery). Thank you for providing the opportunity to comment.

Sincerely,

Adam Nickels

OFFICE OF HISTORIC PRESERVATION DEPARTMENT OF PARKS AND RECREATION P.O. BOX 942896

ACRAMENTO, CA 94296-0001 (916) 653-6624 Fax: (916) 653-9824 calshpo@ohp.parks.ca.gov www.ohp.parks.ca.gov

August 22, 2007

In Reply Refer To: BUR070809A

Susan M. Fry Regional Environmental Officer United States Department of the Interior Bureau of Reclamation Mid-Pacific Regional Office 2800 Cottage Way Sacramento, CA 95825-1898

Re: Approval of a Section 215 Contract for the Root Creek Water District, Madera County, California (Project No. 07-SCAO-222).

Dear Ms. Fry:

Thank you for seeking consultation with me regarding the above noted undertaking. Pursuant to 36 CFR Part 800 (as amended 8-05-04) regulations implementing Section 106 of the National Historic Preservation Act (NHPA), the Bureau of Reclamation (BUR) is the lead Federal agency for this undertaking and is seeking my comments on the effects that the proposed project will have on historic properties. The BUR is proposing to approve a Section 215 contract to deliver water from the BUR's Central Valley Project, for irrigation and direct ground water recharge, to the Root Creek Water District (RCWD). The BUR has determined that their approval of this contract constitutes an undertaking pursuant to the NHPA.

The project will entail the construction, by the RCWD, of a new turnout on the southeast bank of Lateral 6.2, a component of the Madera Canal distribution system operated by the Madera Irrigation District. From the new turnout, a 48-inch diameter buried pipeline will be installed that will extend approximately 2.75 south of Lateral 6.2. The RCWD will additionally construct nine sub-lateral pipelines of 12-15-inch diameters off this main line. The BUR has determined that the location of the proposed turnout on Lateral 6.2, the main 48-inch RCWD pipeline route, and the routes of the nine sub-laterals comprise the project Area of Potential Effects (APE). This linear APE extends for approximately six miles (9.7 kilometers). In addition to your letter of August 7, 2007, you have submitted the following document as evidence of your efforts to identify historic properties in the project APE:

• A Cultural Resources Survey for the Root Creek Water District In-Lieu Groundwater Recharge Facilities Project Avenue 12 at Road 40, Madera County, California (C.K. Roper; Sierra Valley Cultural Planning: February 6, 2007).

BUR070809A 8/22/07

The identification efforts by the BUR have concluded that the only historic property located in the APE is Lateral 6.2. Lateral 6.2 receives water from the Madera Canal, a major water distribution element of the Central Valley Project (CVP), and is thus a component of the CVP itself. The BUR has completed a draft National Register of Historic Places nomination for the CVP that is currently under review at my office. Pending the finalization of the CVP NRHP nomination, and the consensus determination of its contributing elements, the BUR is assuming that Lateral 6.2 is eligible for the NRHP as a component of the CVP, for the purposes of this undertaking only. Accordingly, the BUR has concurred with this analysis of the subject undertaking, in an email (dated 8/22/07) from Patrick Welch of the Mid-Pacific Regional Office, and has agreed that a finding of No Adverse Effect is appropriate for this undertaking.

Based on my review of your letter, supporting documentation, and a phone contact of 8/20/07 and subsequent email contacts between William Soule of my Staff and Patrick Welch of your staff, I have the following comments:

1) I concur that the Area of Potential Effects is appropriate pursuant to 36 CFR Parts 800.4(a)(1) and 800.16(d) and that the efforts made to identify historic properties have been appropriate pursuant to 36 CFR Part 800.4(b).

2) I further concur that a finding of No Adverse Effect is appropriate pursuant to 36 CFR Part 800.5(b).

3) Be advised that under certain circumstances, such as unanticipated discovery or a change in project description, the BUR may have additional future responsibilities for this undertaking under 36 CFR Part 800.

Thank you for seeking my comments and for considering historic properties in planning your project. If you require further information, please contact William Soule, Associate State Archeologist, at phone 916-654-4614 or email <u>wsoule@parks.ca.gov</u>.

Sincerely,

Milford Wayne Donaldson, FAIA State Historic Preservation Officer