

**APPENDIX G – ODFW FISH HABITAT IN THE
CATHERINE CREEK GRANDE RONDE RIVER BASIN
JANUARY 2011**

FISH HABITAT ASSESSMENT IN CATHERINE CREEK,
GRANDE RONDE RIVER BASIN

Peggy Kavanagh
Kim Jones
Staci Stein

January, 2011

Oregon Department of Fish and Wildlife
Aquatic Inventories Project
28655 Highway 34
Corvallis, Oregon 97333

Funded by:
Bureau of Reclamation
Pacific Northwest Regional Office
1150 North Curtis Road, Suite 100
Boise, Idaho 83706

List of Tables	ii
List of Figures	iii
Project Description and Introduction	1
<i>Analysis</i>	3
Results	3
<i>Catherine Creek 2010 habitat survey</i>	3
<i>Comparison of aquatic habitat in Catherine Creek 1991-1995 and 2010</i>	5
<i>Habitat quality relative to life stage requirements</i>	6
References	8
Tables	9
Figures	11
Appendix A	22
Appendix B	187
Appendix C	189
Appendix D	190
Appendix E	192
Appendix F	194

List of Tables

- Table 1. Catherine Creek 1991-95 and Catherine Creek 2010 consolidated into three sections for comparison of reach features.
- Table 2. Catherine Creek 1991-95 and Catherine Creek 2010 consolidated into three sections for comparison of habitat unit-scale features.
- Table 3. Catherine Creek 1991-95 and Catherine Creek 2010 consolidated into three sections for comparison of reach features including bank condition and large woody debris (lwd).
- Table 4. Life history ratings for Chinook salmon and Steelhead trout for Catherine Creek based on 2010 habitat survey data.

List of Figures

- Figure 1. Catherine Creek Watershed within the Grande Ronde River Basin (HU 17060104).
- Figure 2. Catherine Creek reach breaks based on 2010 habitat survey data.
- Figure 3. Catherine Creek 2010 habitat survey split into three sections: lower, middle, upper.
- Figure 4. Catherine Creek divided into three sections (lower, middle, upper) for comparison of 1991-1995 and 2010 habitat survey data.
- Figure 5. Catherine Creek gradient based on the 2010 habitat survey.
- Figure 6. Catherine Creek divided into three sections for comparison of Percent Fine Sediment based on 1991-1995 and 2010 habitat survey data.
- Figure 7. Catherine Creek divided into three sections for comparison Secondary Channel Length based on 1991-1995 and 2010 habitat survey data.
- Figure 8. Catherine Creek 2010 habitat survey data applied to Chinook salmon HabRate life history ratings.
- Figure 9. Catherine Creek 2010 habitat survey data applied to Steelhead trout HabRate life history ratings.

Fish Habitat Assessment in Catherine Creek, Grande Ronde River Basin

Project Description and Introduction

A collaborative project between the Oregon Department of Fish and Wildlife (ODFW), Bureau of Reclamation (BOR), the Grande Ronde Model Watershed (GRMW), Union Soil and Water Conservation District (USWCD), and numerous other partners and landowners was initiated to examine the many factors which contribute to fish, specifically spring Chinook, survival in Catherine Creek. Potential outcomes include the development of operational management plans, stream habitat restoration projects, habitat conservation planning, and watershed analysis. The ODFW Aquatic Inventories Project conducted stream habitat surveys to document the status of stream conditions. These surveys in conjunction with fish distribution form the basis of the analyses. This paper summarizes the condition of stream habitat, the distribution and abundance of salmonid fishes, and the potential for restoration.

Catherine Creek is a tributary to the Grande Ronde River, which originates in the Blue Mountains in northeast Oregon. Catherine Creek flows 89 kilometers from the junction of South Fork and North Fork Catherine Creeks to its (current) confluence with the State Ditch (Figure 1). The creek flows out of the North and South Fork of Catherine Creek which is underlain by Grande Ronde and Imnaha basalt lithology. Most of the surveyed section flows through alluvial deposits that form the valley bottom. The lower reaches are deep, meandering sections of stream with little definition or structure, with remnant, cut-off oxbows. The surrounding landscape consists primarily of agriculture fields. The middle reaches of Catherine Creek have more distinct habitats, flow through an urban area (the town of Union), and has a mix of landscape influences. The upper reaches below North and South Fork Catherine creeks are mostly on state or federal land, have an increased gradient, and have more opportunities for off-channel habitat formation.

Viable anadromous salmonid populations in Catherine Creek and tributaries consist of Spring Chinook salmon (*Oncorhynchus tshawytscha*) and summer steelhead (*O. mykiss*). The salmonids are designated as 'Threatened' under the federal Endangered Species Act. Additionally, bull trout (*Salvelinus confluentus*) and mountain whitefish (*Prosopium williamsoni*) are present. Non-salmonid species are present, but their distributions are either not well-documented or are not the subject of targeted studies. The list of observed fish includes Northern pike minnow (*Ptychocheilus oregonensis*), carp (*Cyprinus carpio*), redbelt shiner (*Richardsonius balteatus*), brown bullhead (*Ameiurus nebulosus*), smallmouth bass (*Micropterus dolomieu*), and catfish (*Ictalurus* species).

Spring Chinook salmon spawn and rear in the upper reaches, higher gradient portions of Catherine Creek. Naturally-produced age-0 fall migrants, account for 78% of the fish (Yanke et. al. 2009), and leave during the fall to overwinter downstream of Davis Dam. In the spring, they migrate out of Catherine Creek and the Grande Ronde watershed to migrate the sea as age-1 juveniles. Another group of juvenile Chinook overwinter in upper Catherine Creek and tributaries, and leave Catherine Creek at age-1 in the spring for the ocean. They return from the ocean to their natal streams two to three years later from June through August as 3 and 4 year old adults. Spawning occurs in the reaches above Davis Dam in August and September.

Summer steelhead trout spawn and rear upstream of the town of Union; they utilize the Creek downstream from Union for migration and rearing. Approximately one third overwinter in downstream areas and are considered early migrants. Steelhead may remain in Catherine Creek for up to 4 years before leaving the basin for their migration downstream to the ocean. The average ocean-going smolt age is 2 (Yanke et al. 2009). Steelhead remain in the ocean 1-2 years before returning to their natal stream to spawn.

Habitat Survey Approach and Methods

ODFW Aquatic habitat surveys were conducted on Catherine Creek in 1991, 1995, and 2010. All surveys described the channel morphology, riparian characteristics, and features and quality of instream habitat during summer flow, following methods described in Moore et al. (2010). Each habitat unit is an area of relatively homogeneous slope, depth, and flow pattern representing different channel forming processes. The units are classified into 22 hierarchically organized types of pools, glides, riffles, rapids, steps, and cascades, including slow water and off-channel pool habitat. Length, width, and depth was estimated or measured for each habitat unit. In addition, water surface slope, woody debris, shade, cover, and bank stability were recorded. Substrate characteristics were visually estimated at every habitat unit. Estimates of percent silt, sand, and gravel in low gradient (1-2%) riffles were used to describe potential spawning gravel quantity and quality. The surveys also provided an inventory of site-specific features such as potential barriers to fish passage (e.g., falls, culverts, and diversions) or oxbows.

Riparian transects described tree type and size, canopy closure, and ground cover associated with the floodplain, terraces, and hillslopes adjacent to the stream. Each transect was 5m wide and extended 30m perpendicular on each side of the stream.

Descriptions of channel and valley morphology followed methods developed at Oregon State University and described in detail in Moore et al. (2010). Valley and channel morphology defined the stream configuration and level of constraint that local landforms such as hillslopes or terraces imposed upon the stream channel (Grant 1988, Gregory et al. 1989, Moore and Gregory 1989). The channel was described as terrace-constrained or unconstrained. Channel dimensions included active (or bankfull) channel width and depth, floodprone width and height, and terrace widths and height. These descriptions of channel morphology have corresponding types within the OWEB and Rosgen channel typing system (Rosgen 1994).

The stream habitat surveys followed a basins, or census, survey design. The basin survey followed methodology proposed by Hankin (1984) and Hankin and Reeves (1988). The sampling design is based on a continuous walking survey from the mouth or confluence of a stream to the headwaters. The stream is stratified into a series of long sections called reaches and into short habitat units within each reach. The methodology provided flexibility of scale, allowing information to be summarized at the level of microhabitat, associations of habitat, portions or reaches of streams, watersheds, and subunits within regions. The continuous-survey approach provides field-based estimates of habitat conditions throughout a stream, described habitat and hydrologic relationships among streams or landscape features, and permitted stream-wide estimates of fish distribution and abundance.

The basin surveys were integrated into coverages on the 1:100,000 scale USGS digitized layer in a Geographical Information System (Jones et al 2001). The surveys were routed and displayed at the channel reach and habitat unit scales.

Analysis

Habitat data were summarized at the reach scale to describe channel morphology, habitat structure, sediment supply and quality, riparian forest connectivity and health, and in-stream habitat complexity. Individual attributes include:

Channel morphology	Channel dimensions Channel constraint features, if any Gradient Percent secondary channels Floodplain connectivity
Pool habitat	Percent pool Percent slow, backwater, and off-channel pools Deep Pools (>1m deep) Complex pools (contain > 3 pieces large wood)
Large Wood	Pieces of large wood (>0.15 diameter and >3m length) Volume of large wood (m ³) Key pieces of wood (>0.6m diameter and >12m length)
Bank structure	Bank erosion Undercut bank
Substrate	Percent fines (silt, sand, organics), gravel, cobble, boulder, bedrock Percent fines and gravel in low gradient riffles Large course substrate – boulder count
Riparian	Shade Density of conifer trees, by size category Density of hardwood trees, by size category

Results

Catherine Creek 2010 habitat survey

The Catherine Creek 2010 habitat survey extended approximately 89 kilometers upstream from its confluence with the State Ditch to its terminus with the North Fork Catherine Creek and South Fork Catherine Creek. Twenty-two reaches were designated based on named tributary junctions, diversion or dam structures, bridge crossings, and geomorphic changes (Figure 2).

The upper reaches are forested below the confluence of North and South Catherine creeks, although the river flows through an agricultural and ranching landscape for most of its length. Catherine Creek flow through the town of Union from 63.7 river kilometer (rkm) to 66.4 rkm. Diversion dams are located at 64.5, 64.8, 65.0, and 66.3 rkm, and the Confederated Tribes of the Umatilla Indian Reservation (CTUIR) operate a weir at 69.2 rkm.

The survey was divided into three sections for this general discussion: a lower section (mouth to Davis Dam), middle section (Davis Dam to Brinkler Creek), and an upper section (Brinkler Creek to North Fork and South Fork Catherine Creeks) (Figure 3). More detail by reach can be found in the Catherine Creek 2010 Habitat Report (Appendix A).

The lower section of Catherine Creek (0 rkm to 56 rkm, Reaches 1 to 9) is a continuous homogenous channel, approximately 20 meters wide, which meanders through agriculture land use. The Creek, opaque with suspended sediment, is deep (average 0.9 meters) with little defined habitat. The gradient of the section is so slight that it averages 0.0 percent. Oxbows, remnant channels, have been cut off from the mainstem with only a control structure connecting the creek with the oxbow. The stream substrate and stream banks are primarily composed of fine sediment (hardpan clay, silt, some sand). Shrubs (hawthorn, willow, dogwood) and grasses line the stream bank providing little in the way of shade or woody (live or dead) structure. Elmer's Dam (20 rkm) is a seasonal dam for irrigation. Boards are placed/removed to control the water height and availability. When all the boards are in place, the water may pool for 21km (personal communication, L. Kuchenbecker). Tributaries entering the lower section of Catherine Creek include Warm Creek, Mill Creek, Old Grande Ronde River, McAlister Slough, and Ladd Creek.

The middle section (56 rkm to 76 rkm, Reaches 10-16) is shallower (average 0.5m) above the Davis Dam pool and characterized by more defined habitat, a mix of land use influences, and an increase in streamside trees. The channel is primarily a single channel, with little off-channel habitat. The stream habitat includes low gradient riffles as well as scour pools and glides. The substrate is a mix of fine sediments, gravel, and cobble. Large willows and other deciduous trees contribute to shading. Little Creek, Pyles Creek, and Brinkler Creek are named tributaries which enter the middle section. Land uses include agriculture, residential, and urban; the creek flows through the town of Union. There are at least five dams/fish ladders/diversions which fish encounter at river kilometer 64.5, 64.8, 65.0, 66.3, and 69.2. Lower Davis Dam marks the downstream margin of this section. Upper Davis Dam, located 1 km upstream from Lower Davis Dam, backs up water approximately 2.6 km. At present, both retain water from June through October through the use of boards.

The upper section of Catherine Creek extends from Brinkler Creek to the confluence of the North and South Fork Catherine Creeks (76 rkm – 89 rkm, Reaches 17-22). The upper section has long stretches of riffles with some rapids and pools; the average depth is 0.37m. The average gradient is 1.3 percent (Figure 5). Catherine Creek State Park and Whitman Nation Forest are within this section. The surrounding area is forested with deciduous and coniferous trees of all size classes. Trees in the riparian areas shade the creek, add stability to stream banks, and are a source of large wood for the channel. Named tributaries include Little Catherine Creek, Milk Creek, and Scout Creek. The stream habitat is complex with secondary channels, backwaters, and alcoves. Secondary channel habitat, nearly a third the distance of the primary channel, offers additional opportunity for fish to find slow water refuge.

Comparison of aquatic habitat in Catherine Creek 1991-1995 and 2010

The Aquatic Inventories Project conducted stream habitat surveys on Catherine Creek in the early 1990's and in 2010. Different portions of Catherine Creek were surveyed in 1991 and 1995; these were combined into one, continuous survey. The 2010 survey began at the confluence of Catherine Creek and State Ditch while the 1991-95 survey did not survey the lower 17km. In order to compare these surveys, Catherine Creek was split into three major sections, a lower (survey start to Davis Dam), middle (Davis Dam to Brinkler Creek), and an upper section (Brinkler Creek to North Fork and South Fork Catherine Creeks) (Figure 4).

Catherine Creek has changed little between the two surveys. The lower section of the creek continues to be a meandering stream constrained by terraces and agricultural activities with little undercut, riparian shading, or large wood. The substrate and bank material is fine sediment (Figure 6) and some of which is actively eroding. Percent active erosion may have decreased since 1995 simply due to increased shrub growth, which in turn better anchored the substrate. Water visibility is low. The middle section transitions from an agriculture landscape to a section with agriculture and urban land uses. The creek has five dams and diversions in this section. Streamside shade, coarse substrate, and stream gradient increases in the middle section. The upper reach maintains the riffle/pool habitat ratio of the middle section. However, the character of the upper section changes dramatically with a sharp increase in the number of multiple channels. The secondary and off-channel habitat increases from approximately 600 meters in the middle section to close to 5000 meters in the upper section (Figure 7). The primary channel to secondary channel area and length is similar between surveys (Table 1). The channel geomorphology and dimensions, habitat types, and substrate composition changed little between survey years (Table 2). Approximately half-as-much wood was observed during the 1991-95 survey in contrast to the 2010 survey, although the amount was still low (Table 3). The upper section had the most wood and the most opportunity for wood contribution.

There was a high water event in early June, prior to the 2010 survey start. The water flow reached more than 1200 cubic feet per second (cfs) in early June; a month later at the start of the survey the water flow had dropped to 140 cfs (Water Resources Department, http://apps2.wrd.state.or.us/apps/sw/hydro_report/data_Results.aspx?station_nbr=13320000&start_date=9/30/1980&end_date=9/30/2010&record_type=mdfMonthly_monthly_statistics_complete&tolerance=0&fdcCase=usgs&record_status=PUB&nbr_days=14&nbr_max=10). Normal flow at this time of year (June) ranges from 100-700 cfs. The high terraces on either side of Catherine Creek contained much of the high water, though many tributaries and oxbows flooded. Large wood data was higher in 2010 than the 1991-95 habitat survey. It is unclear as to how much wood was washed downstream or had been present prior to the high water event. The percent of pools was similar for both surveys, though there were more deep pools and more complex pools (deep pools with large wood) in 2010. Part of this may be attributed to the high water event and earlier time of survey; July – early September versus September and October for the 1991-95 survey. The total distance of secondary channels remained more or less the same. In the upper section, an unconstrained portion had been reworked by the Creek during the spring high water event. Gravel and wood were piled and channels had been formed, altering the available habitat.

Habitat quality relative to life stage requirements

We used a model (HabRate; Burke et al. 2010) to integrate habitat attributes as a method to assess overall habitat quality relative to freshwater life stages of Chinook and steelhead. We described the habitat quality for 1) spawning, egg survival, and emergence, 2) summer rearing, and 3) winter rearing. HabRate incorporates the habitat attributes collected in Catherine Creek during the summer of 2010. We collected information on stream substrate (fine sediment, gravel, and cobble), habitat unit type (scour, beaver, and off channel pools), cover (large wood, undercut banks), and channel morphology (secondary channels, gradient). The model combined attributes using logic equations, and provides a overall rating of habitat quality in a stepwise fashion. The ratings can be used as an additional tool to consider limiting factors for salmonid productivity in the system. Our assessment does not include water quality or quantity, although those factors can be added to the model for consideration. Model output ranks physical habitat quality from 1 to 3: poor, fair, and good.

We generated ratings from the 1991-95 and 2010 surveys. The conclusions concerning physical habitat were similar between survey years at the scale of the three long sections so we will focus on the output of the 2010 survey. The ratings are described here for the three sections, followed by a more detailed analysis for the 22 reaches.

Appendix B contains the habitat criteria for Chinook salmon and Steelhead trout life stages.

HabRate model results for Catherine Creek 2010: Spring Chinook Salmon

The availability and quality of spawning habitat did not change in the three sections (lower, middle, and upper) between 1991-95 and 2010. Appendix C illustrates the following summary for Chinook salmon. Spawning habitat is poor in the lower section and fair in the middle and upper sections. The abundance of fines and lack of coarse material lowers the quality of the few riffles that are present in the lower section. Riffles are prevalent in the middle and upper sections and the substrate has few fines and more gravel, but little cobble.

Overall, the lower section rated fair for 0+ Summer Rearing and Overwintering. Pools were scarce and cover was low. However the very few pools had good complexity which created an overly optimistic average rating for the reach. The middle section and upper sections also rated as fair on average (Figure 8). The sections lacked suitable pool area, undercut banks, large wood, and cobble substrate. Due to a decrease in fines and an increase in gravel, the substrate rating increased to good. The quantity of boulders also increased the cover rating.

HabRate model results for Catherine Creek 2010: Summer Steelhead Trout

HabRate comparisons for summer Steelhead generated the similar values for the 2010 surveys for each of the six categories (Appendix D). The lower section contains poor habitat for steelhead spawning, incubation and emergence. Substrate availability and quality precludes areas for spawning and survival to emergence were steelhead to successfully spawn. Spawning habitat quantity and quality is fair in the middle and upper sections.

Habitat quality for summer and winter rearing of age-0 and age-1 juvenile steelhead was poor in the lower section and fair in the middle and upper sections. Habitat was uniform with few pools and structurally-simple in the lower section. The middle and upper sections had few pools, although they had adequate depth and structure. The substrate complexity increase in the middle and upper sections, which provided better conditions for juvenile steelhead.

Reach detail of Catherine Creek 2010 survey data

Maintaining the original 22 reaches of the 2010 Catherine Creek survey allows for a finer scale of detail (Figure 2). Detailed examination of the 22 reaches shows the variety within the overall pattern in the middle and upper reaches (Appendices E and F). Selected reaches which met the good level of Chinook salmon and steelhead spawning, incubation, and emergence are 12, 13, 16, 20, and 21. The percent of pools achieved a good level in Reach 12 and fair in Reaches 18 and 20, and Reaches 20-22 had substantially higher amount of secondary channel as well. These attributes increase the quality of rearing habitat for juvenile steelhead and Chinook at all life stages. High quality Summer Rearing habitat for 1+ summer Steelhead is less widely available than overwintering habitat. No reach achieved a good rating. Generally, pool area, depth in fast water units, undercut, and large wood was low. Reaches 1-11 ranked poor; Reaches 12-22 ranked fair. Summer habitat water depth in fast water units ranged from 0.13-0.33m, which is lower than the preferred > 0.45m. Reaches 13, 14, 16, and 19-22 had better winter rearing conditions for steelhead because of a combination of cover factors – boulders, undercut, and/or wood availability.

References

- Burke, J. L., K. K. Jones, and J. M. Dambacher. 2010. Habstrate: A Limiting Factors Model for Assessing Stream Habitat Quality for Salmon and Steelhead in the Deschutes River Basin. Information Report 2010-03, Oregon Department of Fish and Wildlife, Corvallis.
- Grant, G. E. 1988. Morphology of high gradient streams at different spatial scales, Western Cascades, Oregon. Pages 1-12 in Shizouka Symposium on Geomorphic change and the control of Sedimentary Load in Devastated Streams, Oct 13-14, 1988. Shizouka university, Shizouka, Japan.
- Gregory, S. V., F. J. Swanson, and W. A. McKee. 1991. An ecosystem perspective of riparian zones. *BioScience* 40: 540-551.
- Hankin, D. G. 1984, Multistage sampling designs in fisheries: applications in small streams. *Can. J. Fish. Aquat. Sci.* 41: 1575-1591.
- Hankin, D. G. and G. H. Reeves. 1988. Estimating total fish abundance and total habitat area in small streams based on visual estimation methods. *Can. J. Fish. Aquat. Sci.* 45: 834-844.
- Jones, K.K., R.L. Flitcroft, and B.A. Thom. 2001. Spatial patterns of aquatic habitat in Oregon. Pages 266–280 In *First International Symposium on GIS in Fisheries Science*. T. Nishida, Editor.
- Kuchenbecker, L. 2010. Grande Ronde Model Watershed. Personal communication.
- Moore, K. M. and S. V. Gregory. 1989. Geomorphic and riparian influences on the distribution and abundance of salmonids in a Cascade Mountain Stream. Pages 256-261 in D. Abell, ed., *Proceedings of the California Riparian Systems Conference*; 1988 September 22-24, 1988; Davis, CA Gen. Tech. Rep. PSW-110. Berkeley CA: Pacific Southwest Forest Range and Experiment Station, U.S.D.A.
- Moore, K. M. S., K. K. Jones, J. M. Dambacher, and Charles Stein. 2010. Methods for stream habitat surveys. Oregon Department of Fish and Wildlife, Corvallis.
- Rosgen, D. L. 1994. "A Classification of Natural Rivers", *Catena*, Vol. 22, pp. 169-199
- Yanke, J. A., B. M. Alfonse, K. W. Bratcher, S. D. Favrot, J. P. Kimbro, J. W. Steele, I. P. Wilson, B. C. Jonasson, R. W. Carmichael. 2009. Investigations into the early life history of naturally produced spring Chinook salmon and summer steelhead in the Grande Ronde River Subbasin. Annual Report. Oregon Department of Fish and Wildlife.

Tables

Table 1. Catherine Creek 1991-95 and Catherine Creek 2010 consolidated into three sections for comparison of reach features.

Survey	Reach	Primary channel length (m)	Secondary channel length (m)	Valley type*	Channel type**	Wetted width (m)	Active Channel width (m)	Terrace width (m)	Land use*		Vegetation type**		Gradient (%)
									dominant	subdominant	dominant	subdominant	
Catherine Creek 9195	lower	34,752	20	WF	US	12.3	19.7	30.4	AG		G	D3	0
Catherine Creek 9195	middle	12,925	563	CT	CT	9	14.3	17	AG		D3	S	0.5
Catherine Creek 9195	upper	14,679	3,783	CT	CT	7.4	11.4	14.1	LG		M50		1.2
Catherine Creek 2010	lower	55,945	868	CT	CT	14.6	18.9	31.6	AG		S	G	0
Catherine Creek 2010	middle	20,169	582	CT	CT	9	16.2	26.4	LG	AG	G		0.6
Catherine Creek 2010	upper	13,296 89,410	4,864	CT	CT	7.5	17	30.4	LG	ST	G	D3	1.3

* Valley type codes: WF - wide floodplain; CT - constrained by high terraces
** Channel type codes: US - unconstrained single channel; CT - constrained by high terraces
* Land use codes: AG - agricultural crop or dairy land; LG - light grazing pressure; ST - second-growth timber (15-30cm dbh)
** Vegetation type - G - annual grasses; S - shrubs; D3 - deciduous trees 3-15cm dbh; M50 - mixed conifer/deciduous trees 50-90cm dbh

Table 2. Catherine Creek 1991-95 and Catherine Creek 2010 consolidated into three sections for comparison of habitat unit-scale features.

Survey	Reach	Percent Substrate						Percent wetted area (habitat)						number of pools	number of pools >=1m deep	Pool summary number of complex pools	pool frequency (channel widths/pool)
		organic	sand	gravel	cobble	boulder	bedrock	backwater	scour	pool	glide	riffle	rapid				
Catherine Creek 9195	lower	59	41	0	0	0	0	0	3.09	96.05	0	0	19	17	N/A *	93	
Catherine Creek 9195	middle	8	21	40	35	5	2	15	15	10	57	12	125	19	N/A *	7	
Catherine Creek 9195	upper	15	3	28	44	9	0	1.6	12	2	51	31	199	7	N/A *	8.2	
Catherine Creek 2010	lower	42	27	2	0	0	28	1	0	98	1	0	7	0	2	428	
Catherine Creek 2010	middle	5	5	45	35	7	3	2	11	9	51	1	90	44	19	14.2	
Catherine Creek 2010	upper	8	9	31	42	8	2	0	12	0	73	11	110	30	28	9.7	

N/A *: Complex pools were not calculated at the time of the survey.

Table 3. Catherine Creek 1991-95 and Catherine Creek 2010 consolidated into three sections for comparison of reach-scale features including bank condition and large woody debris (lwd).

Survey	Reach	Percent active erosion	Percent undercut banks	Number of pieces lwd	Pieces lwd/100m	Volume of lwd	Volume lwd/100m	Key pieces of lwd	Key pieces lwd/100m
Catherine Creek 9195	middle	29	1	387	3	118	0.9	N/A *	N/A *
Catherine Creek 9195	upper	16	1	516	3.5	306	2.1	N/A *	N/A *
Catherine Creek 2010	lower	6	1	340	0.6	84	0.2	1	0
Catherine Creek 2010	middle	9	3	639	3.2	347	1.7	7	0
Catherine Creek 2010	upper	17	7	1142	8.6	784	5.9	34	0.3

N/A *: Key pieces were not calculated at the time of the survey.

Table 4. Life history ratings for Chinook salmon and Steelhead trout for Catherine Creek based on 2010 habitat survey data.

Stream	Reach	Chinook Salmon Habitat			Steelhead trout Habitat				
		Spawning to Emergence	0+ Summer	0+ Winter	Spawning to Emergence	0+ Summer	0+ Winter	1+ Summer	1+ Winter
Catherine Creek	1	1	2	2	1	1	1	1	1
Catherine Creek	2	1	2	2	1	1	1	1	1
Catherine Creek	3	1	2	2	1	1	1	1	1
Catherine Creek	4	1	2	2	1	1	1	1	1
Catherine Creek	5	1	2	2	1	1	1	1	1
Catherine Creek	6	1	2	2	1	1	1	1	1
Catherine Creek	7	1	2	2	1	1	1	1	1
Catherine Creek	8	1	2	2	1	1	1	1	1
Catherine Creek	9	1	2	2	1	1	1	1	1
Catherine Creek	10		unsurveyed				unsurveyed		
Catherine Creek	11	1	2	2	1	2	1	1	1
Catherine Creek	12	3	3	2	3	3	2	2	2
Catherine Creek	13	3	2	2	3	2	3	2	3
Catherine Creek	14	2	2	2	2	2	3	2	3
Catherine Creek	15		unsurveyed				unsurveyed		
Catherine Creek	16	3	2	2	3	2	3	2	3
Catherine Creek	17	2	2	2	2	2	3	2	3
Catherine Creek	18	3	2	2	1	2	2	2	2
Catherine Creek	19	2	2	2	2	2	3	2	3
Catherine Creek	20	3	2	2	3	3	3	2	3
Catherine Creek	21	3	2	2	3	2	3	2	3
Catherine Creek	22	2	2	2	2	2	3	2	3

Figures

Figure 1. Catherine Creek Watershed within the Grande Ronde River Basin (HU 17060104)




Figure 2. Catherine Creek reach breaks based on 2010 habitat survey data
Note that Reaches 10 and 15 were not surveyed




Figure 3. Catherine Creek 2010 habitat survey split into three sections: lower, middle, upper.




Figure 4. Catherine Creek divided into three sections (lower, middle, upper) for comparison of 1991-1995 and 2010 habitat survey data.




Figure 5. Catherine Creek gradient based on 2010 habitat survey data




Figure 6. Catherine Creek divided into three sections for comparison of Percent Fine Sediment based on 1991-1995 and 2010 habitat survey data.




Figure 7. Catherine Creek divided into three sections for comparison of Percent Secondary Channel Length based on 1991-1995 and 2010 habitat survey data.





Figure 8. Catherine Creek 2010 habitat survey data applied to Chinook salmon HabRate life history ratings



Figure 9. Catherine Creek 2010 habitat survey data applied to Steelhead trout HabRate life history ratings



Appendix A

Catherine Creek 2010 Habitat Survey

ODFW AQUATIC INVENTORY PROJECT
STREAM REPORT

STREAM: Catherine Creek LLID: 1178722453139
BASIN: Grande Ronde River HUC NUMBER: 17060104
DATES: July 7 – September 22, 2010
SURVEY CREW: Ryan Lande and Ashley Davidson
REPORT PREPARED BY: Staci Stein and Peggy Kavanagh
USGS MAPS: Imbler, Gassett Bluff, Cove, Conley, Craig Mt., Union, Little Catherine Creek
ECOREGION: Blue Mountain Basin and Upland

GENERAL DESCRIPTION:

The Catherine Creek habitat survey began at the confluence with State Ditch and continued upstream 89.4 kilometers to end at the confluence of North Fork and South Fork Catherine Creek. Twenty-two reaches were designated based on major tributary junctions and change in land ownership. The river channel was primarily constrained by high terraces. There were 6,313 meters of secondary channel habitat. The land uses were agriculture and light grazing in the lower reaches and light grazing, large trees (30-50cm dbh), and second growth timber (15-30cm dbh) in the upper reaches. Fine sediments (36%), cobble (24%), and gravel (23%) were the primary stream substrates. The stream habitats were predominately glides (70%) and riffles (19%). Large wood volume ranged from 0-8.9m³/100m per reach. Active bank erosion ranged from 0-28 percent of the stream reach length. The trees observed most frequently along the riparian zones were hardwoods ranging from 3-15cm dbh (based on 78 riparian transects). The crew walked or canoed to conduct the survey, as water level varied from low flow to high flow.

REACH DESCRIPTIONS:

- Reach 1: (T02S-R39E-S10NW) Length 11,900 meters. Reach 1 began at the confluence with State Ditch. The channel was constrained by terraces in a broad valley floor. The valley width index was 20.0. There were 244 meters of secondary channel habitat. Land use was agriculture. The primary vegetation classes were shrub and grass. The average unit gradient was 0.0 percent. The stream habitat was 99% glides. Fine sediments (58%) and hardpan clay (35%) were the stream substrates. No active bank erosion was noted. There was no large wood debris present. The composition of the riparian zones were shrubs, grasses, and hardwood trees 3-15cm dbh (based on 12 riparian transects). Vegetation included willow, hawthorns, thistle, wild rose, grass, and wheat fields.
- Reach 2: (T02S-R39E-S13SW) Length 8,315 meters. Reach 2 began after the confluence with Nye Creek. The channel was constrained by terraces in a broad valley floor. The valley width index was 20. There were 317 meters of secondary channel habitat. Land use was agriculture. The primary vegetation classes were shrub and grass. The average unit gradient was 0.0 percent. The stream habitat was 98% glides. Fine sediments (66%) and hardpan (32%) comprised the stream substrates. Active bank erosion was not noted. Large wood debris volume was 0.3m³/100m. The trees found most frequently in the riparian zones were hardwoods 3-30cm dbh (based on 9 riparian transects). Alfalfa and agricultural grass fields were noted.

Catherine Creek (continued)

- Reach 3: (T02S-R40E-S30NW) Length 9,855 meters. Reach 3 began at Elmer's Dam and continued upstream to Warm Creek confluence. The channel was constrained by high terraces in a broad valley floor. The valley width index (VWI) was 20. Land uses were agriculture and light grazing. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.0 percent. The stream habitat was composed of glides. Ninety-one percent of the stream substrate was silt and fine organic material. There was neither active bank erosion nor large wood noted. The vegetation found most frequently in the riparian zones were agricultural grass and wheat fields. Hardwood trees 3-15cm dbh were also noted (based on 11 riparian transects). Due to the water depth, the crew had difficulty determining and measuring active channel and flood prone dimensions; metric measurements were modified. Active channel and flood prone were not measured. Terrace height measurements were based on the height from the water surface to the terrace lip. The terrace width and VWI were collected per usual.
- Reach 4: (T03S-R40E-S05NW) Length 5,762 meters. Reach 4 began after the confluence with Warm Creek and continued upstream to Old Grande Ronde channel junction. The channel was constrained by terraces within a broad valley floor. The valley width index (VWI) was 20. The land uses were agriculture and light grazing. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.0 percent. One hundred percent of the stream habitat was glide. Fine sediments (85%) and hardpan clay (15%) were the stream substrates. While there were countable pieces of large wood, wood volume was too low to be calculated. The trees found most frequently in the riparian zones were hardwoods 3-15cm dbh (based on four riparian transects). Shrubs and grasses were also noted which included corn, wheat, and agricultural fields. Due to the water depth, the crew had difficulty determining and measuring active channel and flood prone dimensions; metric measurements were modified. Active channel and flood prone were not measured. Terrace height measurements were based on the height from the water surface to the terrace lip. The terrace width and VWI were collected per usual.
- Reach 5: (T03S-R40E-S18SW) Length 2,989 meters. Reach 5 began after the confluence with Old Grande Ronde channel and continued upstream to Mill Creek tributary. The channel was constrained by terraces in a broad valley floor. The valley width index was 20.0. The land uses were agriculture and light grazing. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.0 percent. One hundred percent of the stream habitats were glides. Stream substrates were fine sediments (57%) and hardpan (43%). Active bank erosion was 23% for the reach length. Wood volume was very low at less than $0.1\text{m}^3/100$ meters. The trees found most frequently in the riparian zones were hardwoods 3-15cm dbh (based on two riparian transects). Grasses were also noted.
- Reach 6: (T03S-R39E-S13SW) Length 4,148 meters. Reach 6 began after the confluence with Mill Creek and continued upstream to Godly Lane bridge crossing. The channel was constrained by terraces in a broad valley floor. The valley width index was 20.0. The land uses were agriculture and light grazing. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.0 percent. Stream habitat was 99% glide. The stream substrates were hardpan (63%) and fine sediment (37%). Twenty-four percent of the reach length was actively eroding. Wood volume was very low at less than $0.1\text{m}^3/100$ meters. Agricultural grass fields and hardwood trees 3-15cm dbh were the dominant vegetation found in the riparian zones (based on four riparian transects).

Catherine Creek (continued)

- Reach 7: (T03S-R39E-S15SW) Length 4,609 meters. Reach 7 began at the Godly Lane bridge crossing and continued upstream to McAlister Slough. The channel was an unconstrained channel in a wide floodplain. The valley width index was 20.0. Land uses were light grazing and agriculture. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.0 percent. The stream habitat was primarily glides (92%); either percent of the habitat was dry. Sand (64%) and hardpan (32%) were the stream substrates. Eighteen percent of the bank was actively eroding. Large wood debris volume was $0.1\text{m}^3/100\text{m}$. The trees found most frequently in the riparian zones were conifers 3-15cm dbh (based on four riparian transects). Agricultural grass fields were the predominant vegetation in the riparian.
- Reach 8: (T03S-R39E-S28NE) Length 3,489 meters. Reach 8 began after the confluence with McAlister Slough and continued upstream to Ladd Creek tributary. The channel was unconstrained within a wide floodplain. The valley width index was 20.0. The land uses were light grazing and agriculture. The primary vegetation classes were grasses and deciduous trees 3-15cm dbh. The gradient was 0 percent. Ninety-seven percent of the stream habitat was glide. Sand (76%) and hardpan clay (21%) were the stream substrates. Active bank erosion was 12% of the reach length. Large wood volume was $0.8\text{m}^3/100\text{m}$. The trees found most frequently in the riparian zones were hardwoods 3-30cm dbh (based on three riparian transects). Agricultural grasses were the major vegetation in the riparian.
- Reach 9: (T04S-R39E-S03NW) Length 4,878 meters. Reach 9 began at Ladd Creek tributary and ended at Lower Davis Dam. The channel was terrace-constrained in a broad valley floor. The valley width index was 20.0. Land use was heavy grazing. The primary vegetation classes were grasses and shrubs. The average unit gradient was 0.0 percent. The stream habitats were glides (86%) and riffles (13%). The stream substrate was predominately sand (66%) and hardpan (24%). Large wood debris volume was $0.4\text{m}^3/100\text{m}$. The riparian zones were predominately composed of agricultural grasses and pastures (based on five riparian transects). Hardwoods 3-15cm dbh were also noted.
- Reach 10: (T04S-R39E-S03W) Length 3,389 meters. Reach 10 began at Lower Davis Dam and continued upstream to Miller Lane bridge crossing. This section was not surveyed and no data were collected due to difficult access and time constraints.
- Reach 11: (T04S-R39E-S15NE) Length 514 meters. Reach 11 began at Miller Lane bridge crossing and ended at Pyles Creek tributary. There were 66 meters of secondary channel habitat. The channel was constrained by terraces in a broad valley floor. Land uses were light grazing and agriculture. The primary vegetation classes were grasses and deciduous trees 30-50cm dbh. The average unit gradient was 0.3 percent. The stream habitat was dominantly (99.5%) glides. The stream substrates were hardpan clay (43%), fine sediments (36%), and cobble (18%). Active bank erosion was 14% of the reach length. Large wood debris volume was $0.9\text{m}^3/100\text{m}$. No riparian zone transect was conducted.
- Reach 12: (T04S-R39E-S15NE) Length 3,888 meters. Reach 12 began at the confluence with Pyles Creek and ended at the edge of Union. The channel was constrained by terraces in a broad valley floor. The valley width index was 20.0. Land uses were heavy grazing and agriculture. The primary vegetation classes were grass and deciduous trees 50-90cm dbh. The average unit gradient was 0.4 percent. Scour pools (43%), glides (34%), and riffles (20%) were the stream habitats. The stream substrate was composed of gravel (68%), cobble (16%), and fine sediments (12%). Active bank erosion was 20% of the reach length. Large wood debris volume was $1.7\text{m}^3/100\text{m}$. Agricultural grass fields were the dominant riparian vegetation. Few hardwood trees 3-15cm dbh were also noted (based on four riparian transects).

Catherine Creek (continued)

- Reach 13: (T04S-R39E-S13SE) Length 2,713 meters. Reach 13 began at the edge of the town of Union and ended upstream from Swackhammer diversion. The channel was constrained by high terraces across a broad valley floor. The valley width index was 20.0. Land use was urban land. The primary vegetation classes were grass and deciduous trees 15-30cm dbh. The average unit gradient was 0.8 percent. Stream habitat was primarily riffles (75%). The stream substrate consisted of cobble (46%), gravel (35%), and boulder (15%). Large wood debris volume was 0.8m³/100m. The trees found in the riparian zones were hardwoods 3-30cm dbh (based on four riparian transects). Residential yard grass and horse pastures were also noted.
- Reach 14: (T04S-R40E-S19NE) Length 3,788 meters. Reach 14 began upstream of Swackhammer diversion. The channel was constrained by terraces in a broad valley floor. The average valley width index was 17.6 (range: 11.0-20.0). The land use was light grazing. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.8 percent. Riffle (93%) was the dominant stream habitat. Stream substrate was composed of cobble (51%), gravel (30%), and boulder (11%). Large wood debris volume was 3.0m³/100m. The trees found most frequently in the riparian zones were hardwoods 3-15cm dbh (based on four riparian transects). Grasses and shrubs were also noted. A roadbed, private yard, and cow pasture were within the riparian transect zone.
- Reach 15: (T04S-R40E-S28SW) Length 1,819 meters. Reach 15 was not surveyed. This was private property on Southern Cross Ranch. No data were collected.
- Reach 16: (T04S-R40E-S33NE) Length 4,059 meters. Reach 16 began after Southern Cross private property boundary and ended at Brinkler Creek tributary junction. The channel was constrained by terraces in a broad valley floor. The average valley width index was 12.9 (range: 3.0-20.0). There were 364 meters of secondary channel habitat. Land uses were light grazing and second growth timber. The primary vegetation classes were grass and deciduous trees 3-15cm dbh. The average unit gradient was 0.5 percent. The stream habitat was predominately riffles (80%). The primary stream substrates were cobble (43%) and gravel (38%). Active bank erosion was 20% of the reach length. Large wood debris volume was 3.4m³/100m. The composition of the riparian zones were hardwoods 3-15cm dbh, shrubs, and grasses (based on two riparian transects). A cow pasture was noted.
- Reach 17: (T05S-R40E-S06SW) Length 3,000 meters. Reach 17 began at the confluence with Brinkler Creek and ended at the Catherine Creek State Park boundary. The channel was constrained by terraces in a broad valley floor. The average valley width index was 5.9 (range: 1.0-14.5). There were 487 meters of secondary channel habitat. Land uses were light grazing and second growth timber. The primary vegetation classes were grasses and deciduous trees 3-15cm dbh. The average unit gradient was 0.8 percent. Riffles (85%) were the primary stream habitat. Stream substrate was composed mostly of cobble (47%) and gravel (27%). Large wood debris volume was 4.0m³/100m. The trees found most frequently in the riparian zones were hardwoods 3-30cm dbh (based on two riparian transects). Highway 213 and cow pastures were within the riparian transect zone.
- Reach 18: (T05S-R41E-S07NW) Length 621 meters. Reach 18 spanned Catherine Creek State Park. The channel was constrained by alternating high terraces and hillslopes in a broad valley floor. The valley width index was 11.0. There were 288 meters of secondary channel habitat. Land uses were greenway and old growth forest. The primary vegetation classes were hardwoods 3-15cm and conifers 30-50cm dbh. The average unit gradient was 1.0 percent. The stream habitat was mostly riffle (73%). Gravel (33%), fine sediments (32%), and cobble (28%) were the predominant stream substrates. Large wood debris volume was 5.8m³/100m. The trees found most frequently in the riparian zones were hardwoods 3-15cm dbh (based on one riparian transect). Various sizes of conifers were noted.

Catherine Creek (continued)

- Reach 19: (T05S-R41E-S07NW) Length 1,920 meters. Reach 19 began at the Catherine Creek State Park east boundary and ended at the confluence with Little Catherine Creek. The channel was constrained by alternating high terraces and hillslopes in a broad valley floor. The average valley width index was 3.5 (range: 3.0-4.0). There were 119 meters of secondary channel habitat. Land uses were large trees and second growth timber. The primary vegetation classes were grasses and deciduous trees 3-15cm dbh. The average unit gradient was 1.2 percent. Riffles (89%) dominated the stream habitat. The stream substrate was a mix of cobble (48%), gravel (25%), fine sediments (16%), and boulder (11%). Seven percent of the reach length had actively eroding banks. Large wood debris volume was 1.5m³/100m. Hardwoods and conifers 3-15cm dbh were the trees found most frequently in the riparian zones (based on two riparian transects).
- Reach 20: (T05S-R41E-S08SW) Length 339 meters. Reach 20 began at the confluence with Little Catherine Creek and ended at the Milk Creek tributary junction. The channel was constrained by terraces in a broad valley floor. The valley width index was 16.0. There were 368 meters of secondary channel habitat. Land uses were light grazing and large trees. The primary vegetation classes were grasses and deciduous trees 3-15cm dbh. The average unit gradient was 1.0 percent. The stream habitat was composed of riffles (45%), scour pools (35%), and rapids (11%). The stream substrate was primarily gravel (37%), cobble (35%), and fine sediments (18%). Active bank erosion was 28% of the reach length. Large wood debris volume was 3.5m³/100m. No riparian transects were conducted.
- Reach 21: (T05S-R41E-S08SW) Length 5,725 meters. Reach 21 began at the confluence Milk Creek and ended at Scout Creek tributary. The channel was constrained by terraces in a broad valley floor. The average valley width index was 14.2 (range: 6.5-20.0). There were 3,071 meters of secondary channel habitat. Land uses were light grazing and second growth timber. The primary vegetation classes were grasses and deciduous trees 3-15cm dbh. The average unit gradient was 1.3 percent. The stream habitats were predominately riffles (70%) and scour pools (16%). The stream substrate was a combination of cobble (42%), gravel (34%), and fine sediments (18%). Active bank erosion was 24% of the reach length. Large wood debris volume was 8.9m³/100m. The trees found most frequently in the riparian zones were hardwoods 3-15cm dbh (based on four riparian transects). Conifers of various sizes were also recorded. The riparian had evidence of cattle presence.
- Reach 22: (T05S-R41E-S22SE) Length 1,690 meters. Reach 22 began at the Scout Creek tributary junction and ended at the confluence of North and South Fork Catherine Creek. The channel was constrained by terraces in a broad valley floor. The average valley width index was 8.8 (range: 7.5-10.0). There were 530 meters of secondary channel habitat. Land uses were second growth timber and large trees. The primary vegetation classes were deciduous trees 3-15cm and conifers 15-30cm dbh. The average unit gradient was 2.4 percent. The stream habitats were riffles (48%) and rapids (43%). The stream substrate was a composition of cobble (47%), gravel (25%), boulder (17%), and fine sediments (10%). Active bank erosion was 15% of the reach length. Large wood debris volume was 4.5m³/100m. Conifers and hardwoods 3-15cm dbh were the trees found most frequently in the riparian zones (based on one riparian transect).

Catherine Creek (continued)

COMMENTS:

The crew surveyed upstream and downstream, by canoe and foot, and generally moved around as water levels and land owner availability dictated. Heavy spring rains, water retention due to in-stream construction, and water withdrawals impacted the ability to survey the creek. The crew surveyed Catherine Creek via canoe in Reaches 1 – 4 and part of Reach 5; the stream was too deep to survey by foot. In the remainder of the reaches, the crew conducted the survey by foot.

Water levels were considered high flow in Reaches 3 and 4, low flow in Reaches 7, 8, and 9, and moderate flow for the remaining stream reaches.

Fish were noted throughout the survey. The last fish was observed at unit 1084 (89,410m). A fish presence/absence survey was not conducted. While there are a number of diversion dams on the creek, none were thought to be passage barriers to adult fish. However, they could hinder upstream passage for juveniles. Most of the diversion ditches encountered were screened. The town of Union had four diversions, each a different configuration of fish ladder, pool-step-sequences, and by-pass to irrigation canal. Since the time of the survey, the Main Street diversion (unit 571, 65,032m) has been rebuilt.

In Reaches 1 – 3, oxbows were present and tended to be connected to the mainstem via a culvert. The crew didn't evaluate each oxbow and its connection to Catherine Creek, more often they noted the presence and gps reading of the oxbow entrance and/or exit. It was undetermined if the culverts were barriers to fish movement.

Much of the substrate from Reaches 1 through 12 was composed of hardpan clay. This is denoted as bedrock in the substrate composition. Refer to the Comment Summary for individual units with hardpan clay.

The crew identified numerous fish during the survey: salmonids included juvenile, adult, and jack Chinook salmon, redband trout, and bull trout; other fishes included Mountain whitefish, catfish, northern pike minnow, carp, redband shiner, brown bullhead, and small mouth bass.

Wildlife observations included the following: American bullfrog, western toad, Columbia spotted toad, green tree frog, tadpoles, turtle, nutria, beaver, river otter, muskrats, mule deer, adult and calf elk, and raccoon. There was a large diversity of birds observed during the survey: great blue herons, great horned owls, red-winged blackbirds, mallard ducks, cinnamon teal ducks, barn owls, cormorants, and hawk. Domestic livestock, mostly cows and horses, were also observed throughout the survey.

There was evidence of beaver throughout the survey in the form of chewed sticks and dens.

The named tributaries that entered the Catherine Creek stream survey included: Warm Creek (unit 221, 30,070m); Old Grande Ronde (unit 261, 35,832m); Mill Creek (unit 283, 38,822m); McAlister Slough (unit 361, 47,557m); Ladd Creek (unit 389, 51,067m); Pyles Creek (unit 448, 59,848m); Little Creek (unit 622, 69,104m); Brinker Creek (unit 713, 76,115m); Little Catherine Creek (unit 813, 81,656m); Milk Creek (unit 845, 81,995m); Scout Creek (unit 1044, 87,721m); North and South Fork Catherine Creek confluence (unit 1084, 89,410m).

The crew maintained a log book during the survey; the transcription of their survey observations are summarized in the following section. Efforts were made to present the notes as though the crew surveyed upstream. Since they surveyed as water conditions and landowner permission allowed, the dates of the notes reflect the actual survey date. The units had to be renumbered to be sequential.

Transcription of the Aquatic Inventories Project stream habitat survey crew's field notebooks from Catherine Creek July 7 – September 22, 2010

Note: Reaches and units mentioned in the following notes were updated to the final reach and unit calls, based on the survey being conducted continuously from the mouth to the headwaters, as the final report reads. While in the field, the crew surveyed as water levels and land owner access dictated. Miscellaneous notes (tally of work hours, notes to supervisor, etc.) were not included.

Reach 1

7/7/10 -- flow @ Union ~140cfs

Water is fairly swift making it somewhat difficult to maneuver in the canoe. Water is very turbid (impossible to see the bottom). Substrate seemed to be entirely mud. Had to estimate substrate by prodding depth staff and dragging it around. It would be helpful to be able to scoop up some substrate to help determine composition. Riparian transects and metrics are taking longer than they should because the mud is very deep. Also, we sink up to our knees in some places. The current is swift and carries the boat downstream when measuring the active channel.

Along the way we encountered a diversion pump along the stream bank which did not appear to be running at this time.

There were lots of carp swimming and rising around the boat. We saw a dead black bullhead catfish.

There was a 'pipe' hanging over the left bank that was made of steel drums welded together. Not sure of its purpose.

7/8/10 – flow ~139cfs

The creek seems to be dropping quickly. We took a temperature reading at 12:30pm, and it was 21°C.

We saw close to 20 adult bullfrogs in the afternoon and we heard several others calling.

There is little woody debris in the stream. Perhaps there is more, but due to the turbidity we can not see it.

In several places, large berms have been built on the terraces to constrain the stream. In most cases, there are agricultural fields on the other side. The terraces are sufficient to constrain the stream; hence, the stream is constrained by terraces not land use.

7/12/10 – flow ~69.24cfs

There is a huge diversity of birds, great blue herons, great horned owls, red-winged blackbirds, and several others. There has also been a lot of wildlife, including elk, deer, and either nutria or muskrat.

7/13/10 – flow ~85.9cfs – water 23°C

The riparian zone is starting to become wider and more densely vegetated.

Overall, lots of carp and bull frog activity.

Beyond riparian transcript at U36 on the right bank was another berm/raised parcel of land.

These seem relatively common and are usually beyond the natural terraces.

We found a culvert draining. Water was coming out of the smashed culvert coming from what appeared to be an old channel or swamp. It's draining from the left bank. It is very marshy from where it's draining. The other end of the culvert could not be found. This is near U37 or 38.

While putting the coordinates on the map, we found they don't intersect the creek. We are marking the closet point on the map.

According to the map, a trib should have come in on the left bank between riparian transects 5 and 6 but one was never found.

There is little countable wood in the stream.

7/14/10

Where we ended the day there is a large alcove on the right bank ~10m from the creek. The oxbow is ~220m long with very high banks. At the upstream end, the AL is separated from another AL by a small berm. The second AL appears to come off of the creek upstream. These AL are connected to Catherine Creek by a man-made ditch. Just downstream of the AL there is an old oxbow cut off by a berm. The oxbow has a pump draining water from it on the upstream side. There is lots of irrigation piping lying around and one line travels several hundred meters to an irrigator that is currently not running.

22°C

WL = rodents

A lot of pipes – farmers are using water from it. Both an entrance and exit. CE/. Grasses and wheat and some shrubs on each side of oxbow 11T 0429534E, 5026426N

No pictures, as camera got wet and doesn't function.

U63 – downstream end of oxbow comes in forming an island. There is a berm separating the creek from the oxbow.

U69 – strange notch in terrace. On right bank, it looks almost like an alcove or old channel rather than a secondary channel. Calling this U70 AL dry. 20% silt and 80% matchhead veg. Still connected to main channel. Connection to mainstem is maintained. 244m long. It sits between the HT that the field is on and the HT along Catherine Creek.

7/15/10 - flow ~65.4cfs

U73 - has a bridge crossing. There are boulders under the bridge for stabilization. Lots of swallows nesting on bridge. Debris on bottom of bridge from high flow event. 11T 0430467E, 5026640N

U75 - CE/, culvert has 0.6m diameter. Spilling some water into creek. Water from culvert is 22°C. The width in this unit increases considerably. Culvert has a vertical drop of 0.7m. It has a cover that appears if pushed down would close off culvert. 11T 0430625E, 5026652N

Unidentified amphibian. Also, water seeping in through berm from oxbow on this unit.

U85 - There are cattle grazing up to the stream and the riparian is much thinner on right bank.

Reach 2

7/19/10 – flow ~33.6cfs

Called a reach changed because Ryan and I switched data sheets.

U89 – downstream end of oxbow enters on the left bank. The max width at the oxbow is 36m. We made this unit short to only encompass the area influenced by the oxbow. There are a lot of old culvert materials lying around near active channel. 11T 0431794E, 5025987N.

U91 – upstream end of oxbow. 11T 0430815E, 502587N

We were able to walk across the creek to do our metrics in U96. Also, we were able to walk almost the entire length of the unit.

Saw a small mouth bass.

Switched PDA to WSG 84 at Market Lane.

7/20/10

U104 - dead catfish

Saw a hatchery spring Chinook that looked like it might die soon.

U110 - riparian 11T 0432084E, 5025301E, 22.5°C

Saw a surveyor from GRMW who said that behind U110 the levy will be pushed back and the oxbow upstream may be opened back up again and riparian work will be done.

U111 – seep from an oxbow that appears someone tried to plug it up with a bunch of bricks.

U112 – in the middle is an oxbow which is blocked off on the upstream side. We called it an AL and surveyed 2 units. Downstream coordinates at U112 are 11T 0432040E, 5025159N;

upstream coordinates at U116 are 11T 043998E, 5025130N

U116 – WL trail left bank and 2 great horned owls.

7/21/10

U120 - Estimated right bank due to dense vegetation

U126 – found dead hatchery Chinook female with 3 punches on left opercle

U127 – metrics and rip estimated due to dense shrubbery and steep bank on left. BC is middle of unit

Since start of the survey at Alicel bridge/State Ditch, the riparian has consisted mostly of willows and hawthorns. The riparian has started to be thicker/more dense.

In areas of high willow density, there appears to be a lot of beaver activity.

7/22/10 – flow ~32.7cfs

Starting a few units back from U141, there are intermittent sections of stream that have a different cross section than what we've seen. There is a width near the middle of the stream where substrate is built up and at which the depth is shallow and then it gets deeper on each side near the two banks. We are also starting to see the channel width become less uniform. There will be little peninsulas coming out of the bank that are obviously covered/submerged when the flows are at active channel height.

U142 – There are 2 CE on the right bank, Culvert 1 – 0.45m diameter, 1.0m drop – has a valve of sorts on the end of it. Culvert 2 – 0.45m diameter, 1.25m drop. Neither has water flowing through it and no indication on the map of an oxbow. There is a low spot beyond the terrace which is a field. Culvert 1 drains excess water, and Culvert 2 is attached to a pump that pumps water from the field into the creek. The low spot looked like a really old stream channel. The terraces appear to be eroding on the right bank starting in U142. There is not active erosion at active or flood levels.

U149 – Reach 2 ends at Elmer's dam – 11T 0432394E, 5024236N – dam dimensions: spillway 5m wide, step height 2m, depth ~0.2m, made of concrete with wooden slats; fishway is 0.6m wide and 0.9m tall with 0.3m step to the water. Fishway is dewatered. 2 pumps built in on top of dam. Two rock jetties 20m downstream of dam. Fishway 1.5m wide and 0.55m step, stair-stepping up to damp pool.

Lots of juvenile fish – carp, small mouth bass, whitefish, redbreast shiners, few Chinook.

Reach 3

9/16/10

We spoke with Phil Hassinger and he said he usually lets the boards out of his dam by now but left them in because Anderson Perry is doing work downstream. Otherwise, Phil has no use for the water. The wood slats will be taken out in a few weeks.

We are going to continue to survey the Elmers pool but just collect modified metric data since the AC and FP are submerged.

9/20/10

We are still working our way downstream to Elmer's dam. There is a lot of erosion on the banks within the FP but above AC. There are large chunks of land with grass falling into the creek.

It appeared that an oxbow came in on the left bank but when we got to it, it appeared to be an old channel fed by Warm Creek and another trib/irrigation canal and they both feed this channel which then feeds into Catherine Creek. It contributes ~10% of the flow. The channel kind of looks like a smaller version of Catherine Creek and the point where Warm Creek and the other trib come together is quite away from the 1st unit of the trib. Reach 4 starts upstream of this tributary.

9/21/10

U201 – Oxbow has an outlet/downstream end with a /CE 11T 0433797E, 5021288N. CE diameter of 0.4m and has a flapper valve on it. No upstream entry could be found in the bank. There was another oxbow on the left bank near this one, but here wasn't an exit/entry apparent on the bank. We got on the terrace to look and it was a 2-3ft deep depression with an AG field on it. It appears that it rarely has water in it.

Through Reaches 3 and 4, there have been depressions in the bank that look kind of like oxbow entries but they appear to be well-used animal trails that have made depressions in the banks in several places. Water may be able to bypass the high terraces in these areas since it's lower than the terrace.

Difficult to feel substrate with depth staff, plus the water isn't clear enough to see through. We will estimate the data, but recall we are estimating. We're using both the depth staff and lead ball with string to get depths.

U182 – There is an irrigation canal with a culvert that is ~20m away from Catherine Creek but the culvert entry is blocked off by a bunch of rocks and concrete. It almost looks like the rocks and concrete caved in. Also, there is a cormorant acting disoriented and is perhaps blind in one eye.

Reach 4

9/16/10

U261 – Metric/Riparian was conducted where Rob's profile was done, according to the river mile map. No stakes or flagging could be found to know exactly where his profile was done. 11T 0431749E, 5018396N

We are going to continue to collect modified metric data since the AC and FP are submerged.

Reach 5

9/7/10

Started ~1000m above the Geckler Lane bridge and continuing to work downstream.

U277 – metric has same coordinates as the entry of a culvert on the left bank. The riparian transect on the 3rd zone hits an oxbow. The oxbow essentially has an entry and exit point at the same point so it circles around and enters and exits through the same spot which is a spot that looks almost like another channel because it is well scoured out.

U276 – oxbow enters

U263 – we stopped surveying at the end of this unit because we reached the influence of Elmer's dam pool. We thought this because the active channel feature was submerged. It had been getting progressively deeper. This is ~100m upstream of Old Grande Ronde River channel diversion – 11T 0431673E, 5018232N

Reach 5 starts after the Old Grande Ronde diversion. Here, the old channel is cut off from Catherine Creek via berm but there is a diversion w/ a headgate and a SD that pumps water into the old GR channel. The headgate is ~2m wide.

Reach 7

8/3/10

U362 - Culvert on McAlister Slough plugged with debris. Perhaps from all the beaver activity. Culvert 0.65m diameter. Doesn't contribute water, but instead takes water from Catherine Creek. This Slough ends Reach 7.

Mostly dry downstream of slough – both Catherine and McAlister are 23.5°C.

U330 – CE/ 0.4m diameter, corrugated steel with door. 6m step prior to CE then SS. Flow ~1%.

SD and juvenile carp in unit.

Just downstream of diversion of CE on the mainstem, there are plywood slats on 2X4s acting as homemade diversion or dam.

Reach 8

7/28/10

U388 – Ladd Creek enters on the right, ACW = 2.55m. End Reach 8 after Ladd enters.

Running along behind terrace on left bank is a marsh that runs parallel to Catherine Creek.

7/29/10

Working downstream from Ladd Creek

A lot of cattle along both banks. Right bank starting to become a large flood plain.

8/3/10

Water dropped significantly since last week.

Cows on left bank – heavy grazing

Morning water temp 20°C

Seen some dead fish (juvenile carp)

Very heavy cattle use and light to heavy grazing. More activity on left bank than right, but still use on both.

Reach 9

7/28/10

Started ~1/2mi upstream of Wilkinson Lane bridge. We are starting to see some very large willows along the riparian but otherwise there is heavy grazing in riparian and heavy cattle use on both sides of the creek.

On map, just upstream of Wilkinson Lane bridge showed there was a channel that stopped in a marshy area but appears to have been clocked off since it's not connected to Catherine Creek.

Start upstream of Ladd Creek

Reach 11

9/13/10

About halfway through the day we finished the section of Catherine creek from Miller Lane up to the downstream end of Union, where we had begun earlier in August. Just downstream from the wastewater treatment plant we found 1 adult female Chinook building a redd and 1 jack salmon.

Reach 13

8/4/10

Starting just downstream of the town of Union and surveying upstream.

Below first diversion there are three separate lines of boulders piled across the channel to slow the water going through the diversion. On the diversion there is a fish ladder that is 13.7m long with 4 steps. The downstream end of the ladder is closed off, presumably to keep water loss down, by a wooden slat. The fish ladder is 1.8m wide and there is a 0.4m step to the entrance. We broke the diversion into a series of steps (over structure) and plunge pools. On the upstream step is a dam created by putting planks in slots across the channel. The dam is ~0.65m high and diverts water into an irrigation canal. On the canal, there are 2 head gates – 1 partially open and 1 fully open. Culvert dimensions are 0.75m in diameter. The diversion comes off of the dam pool created by the dam on U559.

U548 and 549 have CE made of PVC and each contributes ~2% flow. They appear to be overflow pipes for the diversion upstream.

U554 – We came to a diversion = below and above were pools so we weren't able to do a metric. This is why there are 18 units between metrics, though the distance is ~1000m. There were also bridge crossings and diversions keeping us from finding an uninfluenced spot.

A new diversion is built on U567. The stream has been somewhat channelized by retaining wall and sandbags to keep some water away from the construction area.

8/5/10 – flow ~5.95cfs

Today we started at the Main Street bridge diversion and worked upstream end of Reach 13 to the Swackhammer diversion.

Yesterday we talked with Rick Poe at the first diversion. The fishway was closed off so fish were unable to get by/over the boards. Rick told us that people were fishing in the fishway itself.

Throughout this reach, there have been numerous rock dams built by kids to pool the water. U581 – The landowner was actively dumping concrete blocks in the creek to stabilize the stream bank.

U583+584 – Unit had logs embedded in the stream bank somewhat diagonally in relation of the stream that appeared to be put there to slow water flow and thus stabilize the stream bank.

Reach 13

The diversion below the Main Street bridge in Union is kind of odd; our habitat units don't exactly describe what is happening. We called a SS but the water doesn't flow over. The dam is made of wooden planks placed on a concrete spillway to back up the water so that the water is deep enough to push in to the diversion on the right bank. The diversion is open but is in very deep water. It appears to be the same size as the diversions downstream.

U584 – There are numerous logs buried in the bank with cut ends. Obviously placed to stabilize the bank and likely to slow the water coming out of the Swackhammer diversion dam, which is upstream of town.

/CE – has water flowing out of it. It is likely coming off one of the irrigation canals coming off of the diversion. The culvert is made of PVC pipe and has a 0.6m step to Catherine Creek. It is ~0.25m diameter.

Small water source coming in on the right. According to the map, it appears to be a small trib.

Just downstream of Swackhammer, there is another PVC culvert (0.25m diameter with a 0.4m drop to AC) on the left bank presumably coming off of the irrigation canal coming off above the diversion. The culvert contributes a fair amount of water and even has kind of created a channel itself within the active channel.

Just upstream of the PVC pipe is the Swackhammer diversion. The diversion is a series of concrete steps without plunge pools between. The steps act as the fish ladder itself. The canal comes off of the left side above the diversion. The total width of the diversion is 2.5m and each head gate has a width of 1.5m. The depth going into each head gate is 0.3m. The total draw of the diversion is very significant, drawing ~20% of the total volume of Catherine Creek. ~30m downstream on the irrigation canal it appears that there is a juvenile fish bypass with numerous water wheels operating.

Reach 14

8/11/10

We are starting at the Swackhammer diversion just outside of Union. There is one sections ~6 tenths of a mile that we won't be able to survey due to a lack of property access permission.

This is tax lot 04540E05000 owner Short, Marcia M Trustee. Operator is Deborah Eyre. Owns both sides of the creek.

U589 – There are 2 culvert entries on the right bank coming off of an irrigation canal and an old head gate to the irrigation canal that does not appear to be functioning. All of this is happening within ~10m of the Hwy 203 bridge above town. The head gate entry is 1.25m wide and 1.35m tall. The entry to the head gate is 0.6m above the water surface (dry). The first culvert is made of PVC and has a diameter of 1.27m. The step from the culvert to the water surface is ~1.12m.

The excess water is coming from an irrigation canal. The outflow of the pipe flows onto rocks and would likely kill any juvenile fish that might pass through the pipe. This secondary culvert is 0.55m diameter and is made of corrugated galvanized steel. The step to the water surface is about 0.9m and also lands on rocks. It also leaves the irrigation canal.

There appears to be an artesian well along the left bank of the stream on U590. It is contributing a fair amount of water 0.5-1% of total volume. 17°C water from well.

Three spots appear to be old redds. The gravel is not freshly turned, so likely not a spring Chinook redd.

U593 – there is a culvert on left bank flowing out of an agriculture field w cows in it on the other side of Hwy 203. The water is dark brown and smell like bovine fecal matter.

U601 – Constrained by land use (road) on left side and hillslope on the right.

U614 – There are two PVC culvert entries on the left bank. The first culvert has a diameter of 0.18m with a 0.4m drop to the water surface. There is barely a trickle coming out of it. The second culvert has a 0.3m diameter and a 0.8m drop. The returning water is coming from a fish bypass downstream of a diversion. The culvert is returning a fair amount of water. The returning water is bouncing off of a concrete slab.

U615 – There is a diversion dam with an irrigation canal on the left side that has 2 head gates. There is a very nice new fishway on the right bank. The entry to the fishway is 0.3m wide and has a series of steps up to the dam pool. The SS appears to be permanent concrete structure with boards added to it to raise the water level. The head gates are both 1.25m wide. They have wooden slats closing them off but a decent amount of water is flowing down the canal.

8/12/10

Today we started surveying at a diversion on city of Union property. The Umatilla tribe also has a weir here where they separate hatchery and wild fish. Bob Judy owns the land directly upstream of the weir and has been contracted to dredge out the plunge pools on the diversion and the dam pool directly upstream. The plunge pools on the diversion have already been dredged and are too deep to wade. Due to the depth and active operations going on at the diversion, we decided to estimate the step heights, unit lengths, and plunge pool depths. We could see into the plunge pools on the weir and tell that they are at least 2.5m deep if not more. There are numerous large piles of gravel and sediment near the weir that had been removed prior to us surveying the plunge pools. There is a fish ladder on the left side of the diversion which has a trap on it so that fish can be sorted. It is currently closed off using wooden planks preventing any upstream migrations of fish. There is a weir on the bottom side of the diversion that is currently lifted, fish can therefore migrate upstream over the diversion dam itself.

Upstream of the diversion about 85m there is a headgate on the left bank opening into a canal. It is unscreened. The head gate is ~0.8m wide and the water flowing in is ~0.5m deep.

U640 – There is an irrigation canal that a farmer has dug. There is a head gate that is ~0.6m across; it is currently closed. It appears that it has been dredged. There is a point extending into the stream to divert water in the canal. It appears that there is a fish bypass on the canal. We surveyed upstream from the diversion to the Southern Cross Ranch, which denied us access.

Reach 16

8/12/10

We jumped out of the stream and went around their property and jumped back in on the Smith's property which is operated by Roger Huffman. Roger Huffman is their nephew. We started on Smith's property where there is a large wide gravel bar with an O2 channel to the right and an O3 channel to the left. On the O3 channel there is a diversion that appears to have been washed out by the high flows earlier this spring. The diversion is sitting in a deep pool sideways and is not operational. It appears that the landowners have been attempting to work on the washed out diversion. The pool in which the diversion sits in is created by a rock dam immediately downstream of the diversions. Upstream, the landowners are currently digging a new irrigation canal.

8/16/10

U672 – Deep pool with two large bull trout in it. One is ~75cm and the other is ~60cm.

U673 – Culvert entry left bank coming from a juvenile fish bypass. Culvert has a little bit of flow, 0.55m drop and 0.27m diameter PVC culvert.

There have been several 1+m deep lateral pools and each has contained at least one if not two adult bull trout in the 60-75cm class.

U679 – There is a small rock dam built up to divert water into an irrigation canal. There is a juvenile fish bypass downstream. The canal does not appear to be drawing much water. It is ~1.5m wide and ~0.4m deep.

U685 – Culvert entry right bank appears to be a return from a juvenile fish bypass on a canal. The diameter is 0.27m and flows directly into the stream. Above the fence crossing there is a small irrigation canal with a head gate that is 0.45m in diameter and is partially open. There is a juvenile fish bypass downstream.

8/17/10

U698 – The hillslopes come up to the stream on both sides. We decided not to break out a new reach because ~600-700m upstream Brinker Creek enters. We will break a new reach there.

There is a culvert entry from a fish bypass. The culvert is 0.27m diameter and has a 0.4m drop to the water. No water is flowing out of the culvert.

Reach 17

8/19/10

U753 – Start of an O2 channel with an ACW of 3.8m.

U756 – Heading upstream, the unit starts to form several small channels that appear to be below ACH. These are part of one single channel upstream. It essentially functions like a big floodplain. The secondary channel has a large amount of shade; however, the water quality is not good. There is heavy use of the O2 by cattle and there are cow prints and patties all over. Lots of countable wood pieces. There is a presence of juvenile fish. The way the unit is braided is probably due to the fact that the left bank of the main channel is a wide floodplain.

Reach 18

8/19/10

U765 – A tributary enters the main channel on the left bank. We originally thought this was an O3 channel when we first walked its length. However, we discovered that this was the old

channel that got locked off by gravel on the upstream side (well above AC). Although this channel is blocked on the upstream side in U783, there is a tributary draining into the old channel as well as a spring seep. Both of these water sources are being backed up by beaver dams forming large pools and a somewhat floodplain like area. Both of these water sources essentially drain into the main creek channel through this old channel.

8/23/10

Over the weekend, temperatures at night dropped into the mid to upper 30s. The water temperature has dropped and the spring Chinook have started spawning in the area of Catherine Creek State Park.

Reach 19

8/24/10

U805 – The first metric was a broad valley floor, and there are road beds on both sides of the creek acting as the constraining features. The two roads are Hwy 203 and USFS Road 2036. We decided to use the channel form CL and valley form CT. Though CT is not very representative because the roads, not HT, are the constraining features.

Reach 20

8/24/10

U817 – There are 02 and 01 channels. The 02 channel comes off of the mainstem Catherine Creek and flows into Little Catherine Creek ~20m downstream. When we surveyed the 02 channel, we decided to add the section of Little Catherine to the 02 channel from their confluence downstream to mainstem Catherine.

Reach 21

8/25/10

U862 – We encountered a habitat type that we had difficulty calling. There is a 'channel' that comes in that eventually disappears into a field on the Hall Ranch. On the upstream end, there is a channel as well. In between, the water has jumped out of any sort of defined channel and deposited sand across the field ~30m wide. This spring, when the water was at its extreme high, it was pushed out of the main channel by a large log jam upstream and pushed into the fields outside of the AC. The length that the water would have flowed through the 'channel' and field is ~600m. The area in the field where the water flowed in the high water event is well above AC and FP. There are large pine trees in the area with wand deposited around them. If the creek were at active flow, this area would likely fill with water until it approaches where the channel just disappears ~400m upstream, then the water would have no where to go unless a major flood occurs. It also functions like a BW because it is not connected to the main channel upstream. The upstream side has a defined channel for ~300m and then it disappears downstream. We decided to survey this as a ~650m 02 that just disappears in the middle and comes back together up and downstream.

8/26/10

U888- Started here today

U891 – There is a series of DJ as you move upstream on the 05 channel. There is a very large DJ on U892. It appears that in the high flow even this year, these debris jams were formed and as a result, the flow of the main channel spread out over a very wide area and deposited large amounts of sand, gravel, and cobble. The DJ basically fills a ~55m wide FP area. It extends across almost the entire width and reaches the 01. These jams appear to have deposited a large amount of sand in the surrounding forest. Also, there are channels that appear to be formed recently everywhere. They are just mud and permanent vegetation that don't indicate previous impact from water.

U908 – There is a series of channels all less than ACH. There are several new channels that were likely formed during the year's high flow event, because these channels only have silt/organic substrate and run around several tree root systems and older (30-50dbh) conifers that wouldn't have grown had there had water been inundating the area. Only a few of the channels have gravel and cobble in addition to a scour line. Essentially, it appears that as the water came down, it hit a log jam and sent water out into the surrounding forest on the right bank, resulting in a new, very wide AC in this unit. It essentially blew through, widened out, and created new channels.

U915 – The right bank becomes almost level with water level and all the channels come back together.

8/30/10

Today there have been another series of DJ and multiple channels around U928. This is still in the Hall Ranch area. Also, we have found several Chinook adult mortalities as well as several spawning adults and redds.

8/31/10

U1011-1015 – The channel has been dammed by a series of small rock dams created by kids at a church camp adjacent to the left bank. There are also several logs cabled to boulders along the stream to stabilize the bank so it won't destroy buildings near the stream.

In this area, there are lots of spawning spring Chinook at the tail of the man-made pools.

Reach 22

9/2/10

U1075 – There is a corrugated steel culvert entering on the left bank. There is only a tiny bit of water trickling through it. On the other side of Catherine Creek Lane there is a marsh which is where the other end of the culvert comes from. The culvert is oval and 1.45 X 0.45m diameter. All around the culvert is new rip rap placed to channelize the 03 channel. There is not a step, only a 0.7m cascade to the water surface.


9/2/10



Around 1 mile from the forks (NF and SF Catherine Creeks), the road was built up on the left bank ~6ft above the water level. Likely, the road had been impacted by the spring flood.



9/6/10



We finished the upper reaches of Catherine Creek to the North and South Fork confluences. Today, we are starting at Godley Lane bridge since the water has dropped since we were there last. We plan to work downstream until the water level is too high to survey (above AC) due to the influence of Elmer's dam.



CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010


















REACH 1

T02S-R39E-S10NW

REACH 1

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	11,900	277,109	0
Secondary	244	2,440	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 12	<u>First Terrace</u> n = 11
Width: 23.2	Width: 27.3	47.9 (19.6 - 157.75)	43.5 (24.2 - 76.95)
Depth: 1.16	Height: 1.7	3.4 (2.8 - 3.9)	4.3 (3.35 - 7.5)

W:D ratio: 16.4

Stream Flow Type: MF

Average Unit Gradient: 0.0%

Water temperature (°C): 18.0 - 18.0

Entrenchment (ACW:FPW ratio): 1.7

Habitat Units/100m (total channel length): 0.7

Habitat Units/100m (primary channel length): 0.7

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	AG	
Riparian Vegetation:	S	G

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	0%	Reach avg: 22%
Undercut Banks:	0%	Range: 6 - 36

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	23	0.2
Volume (m ³):	4	0.0
Key pieces (>=12m x 0.60m):	0	0.0

REACH 2

T02S-R39E-S13SW

REACH 2

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	8,315	142,625	0
Secondary	317	3,291	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 9	<u>First Terrace</u> n = 9
Width: 16.9	Width: 19.2	31.2 (27.35 - 47.5)	37.4 (29.95 - 50.3)
Depth: 0.81	Height: 1.5	3.0 (2.8 - 3.28)	4.3 (3.16 - 6.96)

W:D ratio: 12.7

Entrenchment (ACW:FPW ratio): 1.7

Stream Flow Type: MF

Habitat Units/100m (total channel length): 0.8

Average Unit Gradient: 0.0%

Habitat Units/100m (primary channel length): 0.8

Water temperature (°C): 22.8 - 22.8

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	AG	
Riparian Vegetation:	S	G

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	0%	Reach avg: 29%
Undercut Banks:	0%	Range: 11 - 42

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	88	1.1
Volume (m ³):	25	0.3
Key pieces (>=12m x 0.60m):	0	0.0

REACH 3

T02S-R40E-S30NW

REACH 3

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	9,855	203,708	0
Secondary	150	1,025	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 0	<u>First Terrace</u> n = 11
Width: 20.3	Due to deep water, active channel and flood prone dimensions were not measured. Terrace height was measured from water surface to terrace lip.		28.7 (1.25 - 41.6)
Depth: 1.63			3.3 (1.15 - 18.1)

W:D ratio: Entrenchment (ACW:FPW ratio):
Stream Flow Type: HF Habitat Units/100m (total channel length): 0.7
Average Unit Gradient: 0.0% Habitat Units/100m (primary channel length): 0.7
Water temperature (°C): 16.6 - 16.6

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	AG	LG
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:		Reach avg: 22%
Undercut Banks:		Range: 11 - 39

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	30	0.3
Volume (m ³):	5	0.0
Key pieces (>=12m x 0.60m):	0	0.0

REACH 4

T03S-R40E-S05NW

REACH 4

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	5,762	84,508	0
Secondary	0	0	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 0	<u>First Terrace</u> n = 5
Width: 14.6	Due to deep water, active channel and flood prone dimensions were not measured. Terrace height was measured from water surface to terrace lip.		17.7 (15.51 - 21.3)
Depth: 1.31			1.3 (1 - 1.5)

W:D ratio: Entrenchment (ACW:FPW ratio):
Stream Flow Type: HF Habitat Units/100m (total channel length): 0.7
Average Unit Gradient: 0.0% Habitat Units/100m (primary channel length): 0.7
Water temperature (°C): 17.8 - 17.8

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	AG	LG
Riparian Vegetation:	D3	G

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	2%	Reach avg: 30%
Undercut Banks:	0%	Range: 19 - 36

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	9	0.2
Volume (m ³):	1	0.0
Key pieces (>=12m x 0.60m):	0	0.0

REACH 5

T03S-R40E-S18SW

REACH 5

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	2,989	35,611	0
Secondary	64	128	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 2	<u>First Terrace</u> n = 2
Width: 11.5	Width: 12.9	20.6 (14.8 - 26.45)	23.1 (18.12 - 28.05)
Depth: 0.87	Height: 1.2	2.3 (2 - 2.62)	2.5 (2.2 - 2.72)

W:D ratio: 11.5
Stream Flow Type: MF
Average Unit Gradient: 0.0%
Water temperature (°C): 15.0 - 15.0

Entrenchment (ACW:FPW ratio): 1.6
Habitat Units/100m (total channel length): 0.7
Habitat Units/100m (primary channel length): 0.7

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	AG	LG
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	23%	Reach avg: 36%
Undercut Banks:	2%	Range: 22 - 47

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	8	0.3
Volume (m ³):	1	0.0
Key pieces (>=12m x 0.60m):	0	0.0

REACH 6

T03S-R39E-S13SW

REACH 6

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	4,148	38,529	0
Secondary	0	0	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 4	<u>First Terrace</u> n = 4
Width: 9.4	Width: 10.8	14.3 (12.25 - 16.49)	16.2 (12.85 - 18.64)
Depth: 0.74	Height: 1.2	2.5 (2.4 - 2.5)	2.8 (2.48 - 3.11)

W:D ratio: 8.8
Stream Flow Type: MF
Average Unit Gradient: 0.0%
Water temperature (°C): 15.5 - 15.5

Entrenchment (ACW:FPW ratio): 1.3
Habitat Units/100m (total channel length): 0.7
Habitat Units/100m (primary channel length): 0.7

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	AG	LG
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	24%	Reach avg: 23%
Undercut Banks:	2%	Range: 14 - 47

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	10	0.2
Volume (m ³):	1	0.0
Key pieces (>=12m x 0.60m):	0	0.0

REACH 7

T03S-R39E-S15SW

REACH 7

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	0%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	100%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	100%
Bedrock	0%	Multiple Channel	0%
Terrace	0%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	4,609	23,161	15
Secondary	32	130	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 5	<u>First Terrace</u> n = 2
Width: 4.5	Width: 14.9	70.0 (14.15 - 118.2)	32.9 (16.35 - 49.52)
Depth: 0.24	Height: 1.3	2.6 (2 - 3.32)	2.8 (2.5 - 3.05)

W:D ratio: 11.7
Stream Flow Type: LF
Average Unit Gradient: 0.0%
Water temperature (°C): 34.5 - 34.5

Entrenchment (ACW:FPW ratio): 4.6
Habitat Units/100m (total channel length): 1.0
Habitat Units/100m (primary channel length): 1.0

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	AG
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	18%	Reach avg: 25%
Undercut Banks:	0%	Range: 8 - 39

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	32	0.7
Volume (m ³):	3	0.1
Key pieces (>=12m x 0.60m):	0	0.0

REACH 9

T04S-R39E-S03NW

REACH 9

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	4,878	37,184	0
Secondary	44	86	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 5	<u>First Terrace</u> n = 4
Width: 7.1	Width: 14.5	44.6 (18.7 - 120)	30.4 (24.5 - 42.6)
Depth: 0.31	Height: 1.3	2.5 (2.2 - 2.74)	3.4 (2.75 - 4.09)

W:D ratio: 11.6

Stream Flow Type: LF

Average Unit Gradient: 0.0%

Water temperature (°C): 21.8 - 21.8

Entrenchment (ACW:FPW ratio): 3.3

Habitat Units/100m (total channel length): 1.0

Habitat Units/100m (primary channel length): 1.0

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	HG	
Riparian Vegetation:	G	S

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	6%	Reach avg: 21%
Undercut Banks:	4%	Range: 6 - 89

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	73	1.5
Volume (m ³):	18	0.4
Key pieces (>=12m x 0.60m):	0	0.0

REACH 10

T04S-R39E-S03NW

REACH 10

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	0%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index		VWI Range: -	

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	0%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	3,389	33,890	0
Secondary	0	0	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 0	<u>First Terrace</u> n = 0
Width: 10.0	Width:	(-)	(-)
Depth:	Height:	(-)	(-)

W:D ratio: Entrenchment (ACW:FPW ratio):
Stream Flow Type: Habitat Units/100m (total channel length): 0.0
Average Unit Gradient: 0.2% Habitat Units/100m (primary channel length): 0.0
Water temperature (°C): -

Riparian, Bank, and Wood Summary

Primary Secondary

Land Use:
Riparian Vegetation:

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	0%	Reach avg: 22%
Undercut Banks:	0%	Range: 22 - 22

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	0	
Volume (m ³):	0	
Key pieces (>=12m x 0.60m):	0	

REACH 11

T04S-R39E-S15NE

REACH 11

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index		VWI Range: -	

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	514	5,763	0
Secondary	66	79	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 0	<u>First Terrace</u> n = 0
Width: 7.3	Width:	(-)	(-)
Depth: 0.51	Height:	(-)	(-)

W:D ratio: Entrenchment (ACW:FPW ratio):
Stream Flow Type: MF Habitat Units/100m (total channel length): 1.6
Average Unit Gradient: 0.3% Habitat Units/100m (primary channel length): 1.8
Water temperature (°C): 12.0 - 12.0

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	AG
Riparian Vegetation:	G	D30

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	14%	Reach avg: 16%
Undercut Banks:	1%	Range: 11 - 39

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	11	2.1
Volume (m ³):	5	0.9
Key pieces (>=12m x 0.60m):	0	0.0

REACH 12

T04S-R39E-S15NE

REACH 12

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	3,888	33,707	0
Secondary	36	78	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 9	<u>First Terrace</u> n = 7
Width: 7.6	Width: 17.6	47.4 (12.45 - 120.2)	33.9 (13.65 - 70.65)
Depth: 0.58	Height: 0.9	1.7 (1.48 - 1.94)	2.1 (1.86 - 2.32)

W:D ratio: 20.4

Stream Flow Type: MF

Average Unit Gradient: 0.4%

Water temperature (°C): 13.0 - 13.0

Entrenchment (ACW:FPW ratio): 2.6

Habitat Units/100m (total channel length): 2.4

Habitat Units/100m (primary channel length): 2.4

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	HG	AG
Riparian Vegetation:	G	D50

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	20%	Reach avg: 41%
Undercut Banks:	4%	Range: 8 - 100

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	147	3.8
Volume (m ³):	65	1.7
Key pieces (>=12m x 0.60m):	1	0.0

REACH 13

T04S-R39E-S13SE

REACH 13

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	20.0	VWI Range:	20 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	2,713	25,385	0
Secondary	77	430	1

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 4	<u>First Terrace</u> n = 3
Width: 8.7	Width: 14.3	64.6 (12.8 - 209.55)	19.5 (16 - 22.61)
Depth: 0.34	Height: 0.6	1.1 (0.96 - 1.3)	1.7 (1.52 - 1.8)

W:D ratio: 25.7
 Stream Flow Type: MF
 Average Unit Gradient: 0.8%
 Water temperature (°C): 22.9 - 22.9

Entrenchment (ACW:FPW ratio): 3.7
 Habitat Units/100m (total channel length): 1.8
 Habitat Units/100m (primary channel length): 1.8

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	UR	
Riparian Vegetation:	D15	G

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	1%	Reach avg: 55%
Undercut Banks:	4%	Range: 22 - 97

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	61	2.2
Volume (m ³):	23	0.8
Key pieces (>=12m x 0.60m):	0	0.0

REACH 14

T04S-R40E-S19NE

REACH 14

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	17.6	VWI Range:	11 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	3,788	44,081	0
Secondary	40	71	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 6	<u>First Terrace</u> n = 5
Width: 11.2	Width: 14.5	51.1 (14.3 - 214)	19.9 (16.5 - 24.98)
Depth: 0.57	Height: 0.7	1.3 (1 - 1.66)	1.7 (1.42 - 1.9)

W:D ratio: 22.4
Stream Flow Type: MF
Average Unit Gradient: 0.8%
Water temperature (°C): 16.4 - 16.4

Entrenchment (ACW:FPW ratio): 3.4
Habitat Units/100m (total channel length): 1.4
Habitat Units/100m (primary channel length): 1.5

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	
Riparian Vegetation:	D3	G

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	3%	Reach avg: 44%
Undercut Banks:	6%	Range: 19 - 69

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	129	3.4
Volume (m ³):	114	3.0
Key pieces (>=12m x 0.60m):	2	0.1

REACH 15

T04S-R40E-S28SW

REACH 15

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	0%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index		VWI Range: -	

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	0%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	1,819	18,190	0
Secondary	0	0	0

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 0	<u>First Terrace</u> n = 0
Width: 10.0	Width:	(-)	(-)
Depth: 0.20	Height:	(-)	(-)

W:D ratio: Entrenchment (ACW:FPW ratio):
Stream Flow Type: Habitat Units/100m (total channel length): 0.1
Average Unit Gradient: 0.5% Habitat Units/100m (primary channel length): 0.1
Water temperature (°C): -

Riparian, Bank, and Wood Summary

Primary Secondary

Land Use:
Riparian Vegetation:

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	0%	Reach avg: 53%
Undercut Banks:	0%	Range: 53 - 53

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	0	
Volume (m ³):	0	
Key pieces (>=12m x 0.60m):	0	

REACH 16

T04S-R40E-S33NE

REACH 16

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	12.9	VWI Range:	3 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	4,059	49,937	0
Secondary	364	1,136	5

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 5	<u>First Terrace</u> n = 4
Width: 9.3	Width: 17.3	45.2 (17.08 - 129.29)	26.6 (19.75 - 35.15)
Depth: 0.49	Height: 0.6	1.2 (1.12 - 1.3)	1.3 (1.22 - 1.45)

W:D ratio: 29.0

Entrenchment (ACW:FPW ratio): 2.5

Stream Flow Type: MF

Habitat Units/100m (total channel length): 1.5

Average Unit Gradient: 0.5%

Habitat Units/100m (primary channel length): 1.7

Water temperature (°C): 16.0 - 16.0

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	ST
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	20%	Reach avg: 32%
Undercut Banks:	3%	Range: 6 - 92

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	291	7.2
Volume (m ³):	140	3.4
Key pieces (>=12m x 0.60m):	4	0.1

REACH 17

T05S-R40E-S06SW

REACH 17

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	5.9	VWI Range:	1 - 14.5

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	3,000	35,540	0
Secondary	487	1,545	2

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 4	<u>First Terrace</u> n = 3
Width: 8.9	Width: 20.2	36.8 (15.85 - 63.16)	46.2 (31.92 - 67.6)
Depth: 0.42	Height: 0.6	1.1 (1 - 1.16)	3.1 (1.1 - 6.76)

W:D ratio: 36.2
Stream Flow Type: MF
Average Unit Gradient: 0.8%
Water temperature (°C): 15.9 - 15.9

Entrenchment (ACW:FPW ratio): 1.8
Habitat Units/100m (total channel length): 1.3
Habitat Units/100m (primary channel length): 1.5

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	ST
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	8%	Reach avg: 40%
Undercut Banks:	5%	Range: 19 - 100

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	159	5.3
Volume (m ³):	121	4.0
Key pieces (>=12m x 0.60m):	5	0.2

REACH 18

T05S-R41E-S07NW

REACH 18

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	11.0	VWI Range:	11 - 11

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	0%	Braided Channel	0%
Alt. Terrace/Hill	100%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	621	8,080	0
Secondary	288	1,013	2

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 1	<u>First Terrace</u> n = 1
Width: 6.2	Width: 14.8	16.3 (16.33 - 16.33)	16.7 (16.73 - 16.73)
Depth: 0.38	Height: 0.7	1.3 (1.3 - 1.3)	1.3 (1.32 - 1.32)

W:D ratio: 22.8

Stream Flow Type: MF

Average Unit Gradient: 1.0%

Water temperature (°C): 18.0 - 18.0

Entrenchment (ACW:FPW ratio): 1.1

Habitat Units/100m (total channel length): 2.5

Habitat Units/100m (primary channel length): 3.7

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	GN	OG
Riparian Vegetation:	D3	C30

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	4%	Reach avg: 62%
Undercut Banks:	4%	Range: 19 - 100

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	47	7.6
Volume (m ³):	36	5.8
Key pieces (>=12m x 0.60m):	3	0.5

REACH 19

T05S-R41E-S07NW

REACH 19

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	3.5	VWI Range:	3 - 4

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	0%	Braided Channel	0%
Alt. Terrace/Hill	100%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	1,920	22,683	0
Secondary	119	244	5

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 2	<u>First Terrace</u> n = 2
Width: 9.7	Width: 16.8	24.0 (21.65 - 26.3)	29.2 (23 - 35.3)
Depth: 0.35	Height: 0.6	1.2 (1.22 - 1.22)	2.1 (1.52 - 2.72)

W:D ratio: 27.5
Stream Flow Type: MF
Average Unit Gradient: 1.2%
Water temperature (°C): 10.5 - 10.5

Entrenchment (ACW:FPW ratio): 1.5
Habitat Units/100m (total channel length): 1.6
Habitat Units/100m (primary channel length): 1.7

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LT	ST
Riparian Vegetation:	D3	S

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	7%	Reach avg: 56%
Undercut Banks:	2%	Range: 36 - 89

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	58	3.0
Volume (m ³):	29	1.5
Key pieces (>=12m x 0.60m):	0	0.0

REACH 20

T05S-R41E-S08SW

REACH 20

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	16.0	VWI Range:	16 - 16

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	339	3,179	0
Secondary	368	1,343	5

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 1	<u>First Terrace</u> n = 1
Width: 5.4	Width: 21.3	38.3 (38.27 - 38.27)	49.5 (49.52 - 49.52)
Depth: 0.35	Height: 0.4	0.9 (0.86 - 0.86)	1.2 (1.16 - 1.16)

W:D ratio: 49.4
 Stream Flow Type: MF
 Average Unit Gradient: 1.0%
 Water temperature (°C): 12.0 - 12.0

Entrenchment (ACW:FPW ratio): 1.8
 Habitat Units/100m (total channel length): 4.7
 Habitat Units/100m (primary channel length): 9.7

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	LT
Riparian Vegetation:	G	D3

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	28%	Reach avg: 36%
Undercut Banks:	8%	Range: 17 - 94

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	26	7.7
Volume (m ³):	12	3.5
Key pieces (>=12m x 0.60m):	0	0.0

REACH 21

T05S-R41E-S08SW

REACH 21

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	14.2	VWI Range:	6.5 - 20

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	5,725	65,612	0
Secondary	3,071	8,034	33

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 10	<u>First Terrace</u> n = 8
Width: 7.2	Width: 16.5	39.9 (12.22 - 165)	24.3 (14.15 - 46)
Depth: 0.36	Height: 0.6	1.1 (0.98 - 1.3)	1.5 (1.22 - 1.96)

W:D ratio: 29.2

Stream Flow Type: MF

Average Unit Gradient: 1.3%

Water temperature (°C): 11.0 - 11.0

Entrenchment (ACW:FPW ratio): 2.5

Habitat Units/100m (total channel length): 2.2

Habitat Units/100m (primary channel length): 3.4

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	LG	ST
Riparian Vegetation:	D3	S

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	24%	Reach avg: 49%
Undercut Banks:	9%	Range: 11 - 94

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	705	12.3
Volume (m ³):	509	8.9
Key pieces (>=12m x 0.60m):	24	0.4

REACH 22

T05S-R41E-S22SE

REACH 22

Valley and Channel Summary

Valley Characteristics (Percent Reach Length)

<u>Narrow Valley Floor</u>		<u>Broad Valley Floor</u>	
Steep V-shape	0%	Constraining Terraces	100%
Moderate V-shape	0%	Multiple Terraces	0%
Open V-shape	0%	Wide Floodplain	0%
Valley Width Index	8.8	VWI Range:	7.5 - 10

Channel Morphology (Percent Reach Length)

<u>Constrained</u>		<u>Unconstrained</u>	
Hillslope	0%	Single Channel	0%
Bedrock	0%	Multiple Channel	0%
Terrace	100%	Braided Channel	0%
Alt. Terrace/Hill	0%		
Landuse	0%		

Channel Characteristics

<u>Type</u>	<u>Length (m)</u>	<u>Area (m2)</u>	<u>Dry Units</u>
Primary	1,690	16,641	0
Secondary	530	2,839	1

Channel Dimensions (m)

<u>Wetted</u>	<u>Active</u>	<u>Floodprone</u> n = 2	<u>First Terrace</u> n = 2
Width: 7.7	Width: 11.7	24.0 (23.1 - 24.95)	29.3 (24.45 - 34.15)
Depth: 0.37	Height: 0.6	1.3 (1.28 - 1.3)	1.6 (1.5 - 1.68)

W:D ratio: 18.2

Stream Flow Type: MF

Average Unit Gradient: 2.4%

Water temperature (°C): 9.5 - 9.5

Entrenchment (ACW:FPW ratio): 2.1

Habitat Units/100m (total channel length): 1.8

Habitat Units/100m (primary channel length): 2.4

Riparian, Bank, and Wood Summary

	<u>Primary</u>	<u>Secondary</u>
Land Use:	ST	LT
Riparian Vegetation:	D3	C15

Bank Condition and Shade

<u>Bank Status</u>	<u>Percent Reach Length</u>	<u>Shade (% of 180)</u>
Actively Eroding:	15%	Reach avg: 48%
Undercut Banks:	4%	Range: 28 - 100

Large Wood Debris

	<u>Total</u>	<u>Total / 100m primary channel</u>
All pieces (>=3m x 0.15m):	147	8.7
Volume (m ³):	76	4.5
Key pieces (>=12m x 0.60m):	2	0.1

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

7/7/2010

REACH 1

T02S-R39E-S10NW

REACH 1

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	84	11,900	23.3	1.18	277,109	11	57	4	3	0	0	36
POOL-ALCOVE	1	244	10.0	0.00	2,440	0	100	0	0	0	0	0
Total:	85	12,144	23.2	1.16	279,549	11	Avg: 58	4	3	0	0	35

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	1	244	10.0	0.00	2,440	0.87%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	84	11,900	23.3	1.18	277,109	99.13%	11	0.0
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	1	0.1	0.1
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	444.6		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

7/14/2010

REACH 2

T02S-R39E-S13SW

REACH 2

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	62	8,315	17.4	0.84	142,624	56	51	14	1	0	0	33
POOL-ALCOVE	2	317	6.4	0.15	3,291	0	100	0	0	0	0	0
STEP/STRUCTURE	1	0	5.0	0.20	1	0	20	0	0	40	40	0
Total:	65	8,633	16.9	0.81	145,915	56	Avg: 52	14	1	1	1	32

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	2	317	6.4	0.15	3,291	2.26%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	62	8,315	17.4	0.84	142,624	97.74%	56	0.0
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	1	0	5.0	0.20	1	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	2	0.2	0.2
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	225.1		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/16/2010

REACH 3

T02S-R40E-S30NW

REACH 3

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area						
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk	
GLIDE	71	10,005	20.3	1.63	204,733	0	91	0	0	0	0	0	9
Total:	71	10,005	20.3	1.63	204,733	0	Avg: 91	0	0	0	0	0	9

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	71	10,005	20.3	1.63	204,733	100.00		
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/16/2010

REACH 4

T03S-R40E-S05NW

REACH 4

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	40	5,762	14.6	1.31	84,508	0	68	17	0	0	0	15
Total:	40	5,762	14.6	1.31	84,508	0	Avg: 68	17	0	0	0	15

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	40	5,762	14.6	1.31	84,508	100.00		
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/17/2010

REACH 5

T03S-R40E-S18SW

REACH 5

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	22	3,053	11.5	0.87	35,739	0	23	34	0	0	0	43
Total:	22	3,053	11.5	0.87	35,739	0	Avg: 23	34	0	0	0	43

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	22	3,053	11.5	0.87	35,739	100.00		
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total	Total of all Channel Lengths # / Km	Primary Channel Length # / Km
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/17/2010

REACH 6

T03S-R39E-S13SW

REACH 6

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	29	4,118	9.3	0.78	38,186	0	10	29	0	0	0	60
RIFFLE	1	28	11.5	0.21	325	0	0	15	0	0	0	85
STEP/BEAVER DAM	1	2	11.5	0.15	17	0	0	0	0	0	0	100
Total:	31	4,148	9.4	0.74	38,529	0	Avg: 9	28	0	0	0	63

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	29	4,118	9.3	0.78	38,186	99.11%	0	0.0
Riffles	1	28	11.5	0.21	325	0.84%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	1	2	11.5	0.15	17	0.04%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/3/2010

REACH 7

T03S-R39E-S15SW

REACH 7

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
DRY UNIT	1	48	9.0	0.00	428	0	0	100	0	0	0	0
GLIDE	33	3,574	5.6	0.31	21,349	13	3	53	2	0	0	42
PUDDLED UNIT	14	1,020	1.6	0.08	1,514	0	0	88	2	0	0	10
Total:	48	4,641	4.5	0.24	23,291	13	Avg: 2	64	2	0	0	32

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	33	3,574	5.6	0.31	21,349	91.66%	13	0.1
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	15	1,067	2.1	0.07	1,942	8.34%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/3/2010

REACH 8

T03S-R39E-S28NE

REACH 8

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area						
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk	
GLIDE	24	3,242	7.8	0.32	26,289	19	0	79	2	0	0	0	18
RIFFLE	4	262	2.4	0.14	841	0	8	75	0	0	0	0	18
STEP/BEAVER DAM	1	0	2.3	0.11	1	0	5	0	0	0	0	0	95
Total:	29	3,505	6.9	0.28	27,131	19	Avg: 2	76	2	0	0	0	21

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	24	3,242	7.8	0.32	26,289	96.90%	19	0.1
Riffles	4	262	2.4	0.14	841	3.10%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	1	0	2.3	0.11	1	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

7/28/2010

REACH 9

T04S-R39E-S03NW

REACH 9

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	31	4,200	7.6	0.37	32,077	20	0	65	4	0	0	30
POOL-BACKWATER	3	44	2.0	0.32	86	0	10	90	0	0	0	0
POOL-PLUNGE	1	8	13.0	0.85	104	34	0	85	5	5	5	0
RIFFLE	7	633	7.1	0.13	4,771	10	0	82	3	1	0	14
STEP/BEDROCK	1	5	5.8	0.12	29	0	0	15	0	0	0	85
STEP/COBBLE	3	26	4.9	0.04	137	70	0	52	20	18	10	0
STEP/STRUCTURE	1	6	10.9	0.01	65	0	19	0	27	0	54	0
Total:	47	4,922	7.1	0.31	37,270	134	Avg: 1	66	5	2	2	24

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	3	44	2.0	0.32	86	0.23%	0	0.0
Scour Pools	1	8	13.0	0.85	104	0.28%	34	32.7
Glides	31	4,200	7.6	0.37	32,077	86.07%	20	0.1
Riffles	7	633	7.1	0.13	4,771	12.80%	10	0.2
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	5	37	6.3	0.05	232	0.62%	70	30.2
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	4	0.8	0.8
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	2	0.4	0.4
Pool frequency (channel widths/pool):	85.0		
Residual pool depth (avg):	0.75		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/21/2010

Survey Date:

9/8/2010

REACH 10

T04S-R39E-S03NW

REACH 10

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
MIX OF HABITATS	1	3,389	10.0		33,890	0	17	17	17	17	17	17
Total:	1	3,389	10.0		33,890	0	Avg: 17	17	17	17	17	17

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	0	0			0	0.00%	0	0.0
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/8/2010

REACH 11

T04S-R39E-S15NE

REACH 11

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	8	576	7.3	0.58	5,813	4	18	22	2	9	1	48
STEP/COBBLE	1	4	7.3	0.01	29	0	0	0	5	95	0	0
Total:	9	580	7.3	0.51	5,842	4	Avg: 16	20	3	18	1	43

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	0	0			0	0.00%	0	0.0
Scour Pools	0	0			0	0.00%	0	0.0
Glides	8	576	7.3	0.58	5,813	99.50%	4	0.1
Riffles	0	0			0	0.00%	0	0.0
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	1	4	7.3	0.01	29	0.50%	0	0.0
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	0	0.0	0.0
Pools >=1m deep:	0	0.0	0.0
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/8/2010

REACH 12

T04S-R39E-S15NE

REACH 12

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
GLIDE	13	1,136	9.8	0.24	11,532	14	6	18	57	13	0	7
POOL-BACKWATER	1	12	2.0	0.35	24	0	0	15	85	0	0	0
POOL-ISOLATED	2	24	1.9	0.52	55	0	0	25	73	3	0	0
POOL-LATERAL SCOUR	24	1,275	8.5	1.19	11,234	104	5	8	66	17	2	3
POOL-STRAIGHT SCOUR	12	424	7.5	1.28	3,272	14	5	15	65	12	1	2
RAPID/BOULDERS	2	35	4.8	0.08	152	25	0	0	63	15	23	0
RIFFLE	22	915	7.8	0.14	6,868	61	1	3	70	21	2	3
STEP/COBBLE	17	104	6.1	0.11	649	4	0	5	79	14	2	0
Total:	93	3,924	7.6	0.58	33,786	222	Avg: 3	9	68	16	2	3

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	3	36	1.9	0.46	78	0.23%	0	0.0
Scour Pools	36	1,699	8.2	1.22	14,505	42.93%	118	0.8
Glides	13	1,136	9.8	0.24	11,532	34.13%	14	0.1
Riffles	22	915	7.8	0.14	6,868	20.33%	61	0.9
Rapids	2	35	4.8	0.08	152	0.45%	25	16.4
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	17	104	6.1	0.11	649	1.92%	4	0.6
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	39	9.9	10.0
Pools >=1m deep:	23	5.9	5.9
Complex pools (LWD pieces>=3):	9	2.3	2.3
Pool frequency (channel widths/pool):	5.7		
Residual pool depth (avg):	1.03		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/1/2010

REACH 13

T04S-R39E-S13SE

REACH 13

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
DRY CHANNEL	1	45	8.0	0.00	360	6	50	5	15	30	0	0
GLIDE	3	107	10.3	0.18	1,087	112	0	0	38	57	5	0
POOL-BACKWATER	2	22	3.0	0.36	65	12	50	0	8	40	3	0
POOL-DAMMED	4	263	9.7	1.12	2,364	193	0	1	50	46	3	0
POOL-LATERAL SCOUR	3	173	8.9	0.58	1,624	54	0	0	55	42	3	0
POOL-PLUNGE	4	27	12.4	0.70	329	9	0	0	31	59	11	0
POOL-STRAIGHT SCOUR	1	26	8.0	0.70	205	59	0	0	20	35	45	0
RIFFLE	21	2,096	8.4	0.21	19,452	1,999	0	0	41	49	10	0
STEP/BOULDERS	4	5	8.7	0.16	47	86	0	0	6	21	73	0
STEP/COBBLE	1	10	6.5	0.13	62	15	0	0	15	75	10	0
STEP/STRUCTURE	5	16	8.3	0.13	221	0	0	0	29	42	17	11
Total:	49	2,789	8.7	0.34	25,816	2,545	Avg: 3	0	35	46	15	1

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	6	285	7.4	0.87	2,429	9.41%	205	8.4
Scour Pools	8	226	10.5	0.65	2,158	8.36%	122	5.7
Glides	3	107	10.3	0.18	1,087	4.21%	112	10.3
Riffles	21	2,096	8.4	0.21	19,452	75.35%	1,999	10.3
Rapids	0	0			0	0.00%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	10	31	8.3	0.14	329	1.28%	101	30.7
Dry	1	45	8.0	0.00	360	1.39%	6	1.7
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	14	5.0	5.2
Pools >=1m deep:	3	1.1	1.1
Complex pools (LWD pieces>=3):	2	0.7	0.7
Pool frequency (channel widths/pool):	13.9		
Residual pool depth (avg):	0.60		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/5/2010

REACH 14

T04S-R40E-S19NE

REACH 14

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
POOL-BACKWATER	2	15	1.6	0.45	23	5	5	0	30	55	3	8
POOL-DAMMED	1	45	15.0	1.10	669	30	0	5	45	50	0	0
POOL-ISOLATED	2	17	1.2	0.35	20	0	0	90	8	3	0	0
POOL-LATERAL SCOUR	2	58	8.5	0.95	483	23	0	2	27	66	5	0
POOL-PLUNGE	6	58	14.5	2.27	822	16	0	0	55	45	0	0
POOL-STRAIGHT SCOUR	2	65	7.3	0.81	468	61	0	0	22	39	33	7
RAPID/BOULDERS	1	19	15.0	0.40	288	9	0	0	20	75	5	0
RIFFLE	28	3,519	11.2	0.29	41,028	2,366	0	0	24	60	13	2
STEP/BOULDERS	1	0	12.4	0.33	5	14	0	0	5	5	90	0
STEP/COBBLE	3	30	9.9	0.24	317	12	0	0	22	68	10	0
STEP/STRUCTURE	7	2	15.0	0.26	30	0	0	2	45	29	0	24
Total:	55	3,828	11.2	0.57	44,153	2,536	Avg: 0	4	30	51	11	5

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	5	77	4.1	0.54	712	1.61%	35	4.9
Scour Pools	10	180	11.9	1.71	1,772	4.01%	100	5.6
Glides	0	0			0	0.00%	0	0.0
Riffles	28	3,519	11.2	0.29	41,028	92.92%	2,366	5.8
Rapids	1	19	15.0	0.40	288	0.65%	9	3.1
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	11	32	13.4	0.26	352	0.80%	26	7.4
Dry	0	0			0	0.00%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	15	3.9	4.0
Pools >=1m deep:	8	2.1	2.1
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	17.6		
Residual pool depth (avg):	1.29		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/21/2010

Survey Date:

8/12/2010

REACH 15		T04S-R40E-S28SW					REACH 15					
HABITAT DETAIL												
Habitat Type	Number	Total	Avg	Avg	Total	Large	Substrate					
	Units	Length	Width	Depth	Area	Boulders	Percent Wetted Area					
		(m)	(m)	(m)	(m ²)	(>0.5m)	S/O	Snd	Grvl	Cbl	Bldr	Bdrk
MIX OF HABITATS	1	1,819	10.0	0.20	18,190	0	17	17	17	17	17	17
Total:	1	1,819	10.0	0.20	18,190	0	Avg: 17	17	17	17	17	17

HABITAT SUMMARY									
Habitat Group	Number	Total	Avg	Avg	Wetted Area		Large Boulders		
	Units	Length	Width	Depth	(m ²)	Percent	Number	(# / 100m ²)	
		(m)	(m)	(m)					
Dammed & BW Pools	0	0			0	0.00%	0	0.0	
Scour Pools	0	0			0	0.00%	0	0.0	
Glides	0	0			0	0.00%	0	0.0	
Riffles	0	0			0	0.00%	0	0.0	
Rapids	0	0			0	0.00%	0	0.0	
Cascades	0	0			0	0.00%	0	0.0	
Step/Falls	0	0			0	0.00%	0	0.0	
Dry	0	0			0	0.00%	0	0.0	
Culverts	0	0			0	0.00%	0	0.0	

POOL SUMMARY			
	<u>Total</u>	Total of all Channel Lengths	
		<u># / Km</u>	
		Primary Channel Length	
		<u># / Km</u>	
All Pools:	0	0.0	
Pools >=1m deep:	0	0.0	
Complex pools (LWD pieces>=3):	0	0.0	
Pool frequency (channel widths/pool):	0.0		
Residual pool depth (avg):			

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/21/2010

Survey Date:

8/16/2010

REACH 16

T04S-R40E-S33NE

REACH 16

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate					
							Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
CASCADE/BOULDERS	1	10	0.6	0.01	6	4	0	0	5	65	25	5
DRY CHANNEL	2	55	1.7	0.00	102	5	0	20	55	25	0	0
DRY UNIT	1	38	3.6	0.00	138	0	0	0	50	50	0	0
GLIDE	1	81	9.0	0.21	732	85	0	0	40	60	0	0
POOL-ALCOVE	1	4	0.7	0.30	3	0	95	0	0	5	0	0
POOL-BACKWATER	2	26	5.0	0.63	139	0	90	0	8	3	0	0
POOL-DAMMED	1	34	8.0	1.23	272	0	30	5	35	30	0	0
POOL-ISOLATED	4	56	1.2	0.40	61	4	65	8	11	16	0	0
POOL-LATERAL SCOUR	12	460	10.3	1.20	5,323	87	1	3	58	36	2	0
POOL-STRAIGHT SCOUR	2	85	7.0	0.88	647	1	0	45	43	13	0	0
PUDDLED UNIT	2	27	1.5	0.09	44	1	40	8	30	23	0	0
RAPID/BOULDERS	2	243	8.0	0.26	1,946	523	0	0	20	48	33	0
RIFFLE	31	3,274	11.9	0.33	41,281	1,313	0	0	38	54	7	0
STEP/BEAVER DAM	1	2	5.5	0.41	11	0	0	0	10	5	85	0
STEP/COBBLE	4	27	13.5	0.17	370	7	0	0	36	61	3	0
Total:	67	4,422	9.3	0.49	51,073	2,030	Avg: 10	3	38	43	6	0

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	8	120	2.9	0.55	474	0.93%	4	0.8
Scour Pools	14	545	9.8	1.15	5,970	11.69%	88	1.5
Glides	1	81	9.0	0.21	732	1.43%	85	11.6
Riffles	31	3,274	11.9	0.33	41,281	80.83%	1,313	3.2
Rapids	2	243	8.0	0.26	1,946	3.81%	523	26.9
Cascades	1	10	0.6	0.01	6	0.01%	4	66.7
Step/Falls	5	29	11.9	0.22	381	0.75%	7	1.8
Dry	5	120	2.0	0.03	284	0.56%	6	2.1
Culverts	0	0			0	0.00%	0	0.0

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/21/2010

Survey Date:

8/12/2010

REACH 16

T04S-R40E-S33NE

REACH 16

POOL SUMMARY

	<u>Total</u>	Total of all Channel Lengths <u># / Km</u>	Primary Channel Length <u># / Km</u>
All Pools:	22	5.0	5.4
Pools >=1m deep:	10	2.3	2.5
Complex pools (LWD pieces>=3):	8	1.8	2.0
Pool frequency (channel widths/pool):	11.6		
Residual pool depth (avg):	0.82		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/16/2010

REACH 17

T05S-R40E-S06SW

REACH 17

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
CASCADE/BOULDERS	1	10	0.4	0.01	4	0	0	0	0	0	0	100
POOL-BACKWATER	3	54	2.3	0.44	119	1	33	58	8	0	0	0
POOL-ISOLATED	1	9	2.0	0.21	17	0	0	0	85	15	0	0
POOL-LATERAL SCOUR	8	255	6.8	1.04	1,848	1	6	8	45	41	0	0
POOL-STRAIGHT SCOUR	1	20	5.0	1.50	101	4	0	10	60	20	10	0
PUDDLED UNIT	2	231	2.0	0.11	462	0	10	10	5	70	5	0
RAPID/BOULDERS	6	331	8.9	0.22	3,189	577	0	2	9	40	49	0
RIFFLE	24	2,579	11.8	0.26	31,346	1,796	2	2	27	59	10	0
Total:	46	3,487	8.9	0.42	37,085	2,379	Avg: 5	7	27	47	12	2

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	4	62	2.3	0.39	136	0.37%	1	0.7
Scour Pools	9	275	6.6	1.09	1,949	5.25%	5	0.3
Glides	0	0			0	0.00%	0	0.0
Riffles	24	2,579	11.8	0.26	31,346	84.52%	1,796	5.7
Rapids	6	331	8.9	0.22	3,189	8.60%	577	18.1
Cascades	1	10	0.4	0.01	4	0.01%	0	0.0
Step/Falls	0	0			0	0.00%	0	0.0
Dry	2	231	2.0	0.11	462	1.24%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	<u>Total</u>	<u># / Km</u>	<u># / Km</u>
All Pools:	13	3.7	4.3
Pools >=1m deep:	4	1.1	1.3
Complex pools (LWD pieces>=3):	1	0.3	0.3
Pool frequency (channel widths/pool):	13.3		
Residual pool depth (avg):	0.83		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/18/2010

REACH 18

T05S-R41E-S07NW

REACH 18

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
DRY CHANNEL	1	65	1.0	0.00	65	0	0	50	30	20	0	0
POOL-ISOLATED	1	2	1.5	0.20	3	0	0	50	5	45	0	0
POOL-LATERAL SCOUR	6	153	7.0	0.59	1,419	55	33	17	24	23	3	0
POOL-STRAIGHT SCOUR	3	73	11.2	1.12	997	23	20	7	47	15	8	3
PUDDLED UNIT	1	10	0.7	0.05	7	0	95	0	5	0	0	0
RAPID/BOULDERS	1	6	1.5	0.05	8	0	5	0	70	25	0	0
RIFFLE	9	600	6.8	0.17	6,594	273	11	6	40	41	3	0
STEP/BEDROCK	1	0	0.8	0.09	0	0	0	0	0	0	0	100
Total:	23	909	6.2	0.38	9,093	351	Avg: 20	12	33	28	3	5

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	1	2	1.5	0.20	3	0.03%	0	0.0
Scour Pools	9	226	8.4	0.77	2,416	26.57%	78	3.2
Glides	0	0			0	0.00%	0	0.0
Riffles	9	600	6.8	0.17	6,594	72.52%	273	4.1
Rapids	1	6	1.5	0.05	8	0.09%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	1	0	0.8	0.09	0	0.00%	0	0.0
Dry	2	75	0.9	0.03	72	0.79%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	10	11.0	16.1
Pools >=1m deep:	3	3.3	4.8
Complex pools (LWD pieces>=3):	3	3.3	4.8
Pool frequency (channel widths/pool):	6.1		
Residual pool depth (avg):	0.53		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/19/2010

REACH 19

T05S-R41E-S07NW

REACH 19

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
DRY CHANNEL	1	10	1.7	0.00	17	0	0	50	5	45	0	0
DRY UNIT	2	53	1.2	0.00	64	1	50	42	0	5	3	0
GLIDE	1	33	12.0	0.30	396	15	0	0	35	65	0	0
POOL-BACKWATER	1	5	5.0	0.32	26	4	0	40	5	30	25	0
POOL-LATERAL SCOUR	2	89	9.5	1.10	861	22	0	3	78	13	8	0
POOL-STRAIGHT SCOUR	3	77	10.4	1.13	811	35	0	13	23	52	12	0
PUDDLED UNIT	2	24	1.2	0.23	29	1	98	0	0	0	3	0
RAPID/BOULDERS	1	16	10.0	0.25	164	5	0	0	10	60	30	0
RIFFLE	17	1,721	11.4	0.24	20,376	643	0	0	29	64	8	0
STEP/BEAVER DAM	1	1	15.5	0.15	16	2	0	0	5	5	90	0
STEP/COBBLE	1	11	15.5	0.06	169	12	0	0	15	65	20	0
Total:	32	2,040	9.7	0.35	22,927	740	Avg: 9	7	25	48	11	0

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	1	5	5.0	0.32	26	0.11%	4	15.4
Scour Pools	5	166	10.0	1.12	1,672	7.29%	57	3.4
Glides	1	33	12.0	0.30	396	1.73%	15	3.8
Riffles	17	1,721	11.4	0.24	20,376	88.87%	643	3.2
Rapids	1	16	10.0	0.25	164	0.72%	5	3.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	2	12	15.5	0.11	184	0.80%	14	7.6
Dry	5	87	1.3	0.09	109	0.48%	2	1.8
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	6	2.9	3.1
Pools >=1m deep:	4	2.0	2.1
Complex pools (LWD pieces>=3):	0	0.0	0.0
Pool frequency (channel widths/pool):	20.3		
Residual pool depth (avg):	0.78		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

8/24/2010

REACH 20

T05S-R41E-S08SW

REACH 20

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
DRY CHANNEL	1	20	5.8	0.00	115	0	95	0	5	0	0	0
DRY UNIT	1	30	1.0	0.00	30	0	0	0	50	50	0	0
POOL-BACKWATER	1	3	1.3	0.43	3	0	95	0	5	0	0	0
POOL-LATERAL SCOUR	9	204	7.0	0.80	1,516	5	1	7	62	21	0	10
POOL-STRAIGHT SCOUR	2	26	3.5	0.36	88	0	85	0	3	13	0	0
PUDDLED UNIT	3	54	0.6	0.11	43	0	30	0	48	22	0	0
RAPID/BOULDERS	1	31	16.4	0.09	508	0	0	0	25	75	0	0
RIFFLE	11	312	5.5	0.19	2,042	8	7	1	29	53	1	9
STEP/BEDROCK	1	0	2.0	0.10	0	0	0	0	0	0	0	100
STEP/COBBLE	3	28	6.2	0.19	176	7	0	0	40	53	7	0
Total:	33	707	5.4	0.35	4,522	20	Avg: 16	2	37	35	1	9

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	1	3	1.3	0.43	3	0.07%	0	0.0
Scour Pools	11	230	6.4	0.72	1,604	35.47%	5	0.3
Glides	0	0			0	0.00%	0	0.0
Riffles	11	312	5.5	0.19	2,042	45.15%	8	0.4
Rapids	1	31	16.4	0.09	508	11.24%	0	0.0
Cascades	0	0			0	0.00%	0	0.0
Step/Falls	4	28	5.1	0.17	176	3.90%	7	4.0
Dry	5	104	1.7	0.06	188	4.17%	0	0.0
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	12	17.0	35.4
Pools >=1m deep:	3	4.2	8.8
Complex pools (LWD pieces>=3):	1	1.4	2.9
Pool frequency (channel widths/pool):	2.8		
Residual pool depth (avg):	0.42		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/21/2010

Survey Date:

9/1/2010

REACH 21

T05S-R41E-S08SW

REACH 21

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate					
							Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
CASCADE/BOULDERS	4	46	5.7	0.15	297	22	0	0	13	49	33	6
DRY CHANNEL	2	97	3.6	0.00	349	0	0	38	38	25	0	0
DRY UNIT	12	546	4.1	0.00	1,700	2	0	25	48	27	0	0
POOL-BACKWATER	8	120	2.4	0.38	269	5	23	56	7	11	3	2
POOL-BEAVER DAM	1	3	2.0	0.47	5	0	95	0	5	0	0	0
POOL-DAMMED	1	12	9.0	1.10	108	15	0	5	30	55	10	0
POOL-ISOLATED	2	9	1.5	0.30	13	0	50	18	28	5	0	0
POOL-LATERAL SCOUR	38	1,115	7.5	0.82	9,286	86	7	14	47	30	2	1
POOL-STRAIGHT SCOUR	11	294	7.9	0.73	2,424	25	3	9	42	42	4	0
PUDDLED UNIT	19	1,087	1.4	0.18	1,200	14	17	29	28	25	0	0
RAPID/BOULDERS	14	722	6.9	0.26	5,333	195	3	1	20	60	15	1
RIFFLE	63	4,563	9.5	0.23	50,754	738	1	4	34	53	8	0
RIFFLE W/ POCKETS	2	69	11.0	0.34	755	120	0	0	19	58	23	0
STEP/BEAVER DAM	3	3	10.3	0.12	31	0	32	0	2	67	0	0
STEP/BOULDERS	1	0	11.0	0.50	4	8	0	0	0	10	90	0
STEP/COBBLE	16	113	9.9	0.15	1,120	4	0	1	33	64	2	0
Total:	197	8,796	7.2	0.36	73,647	1,234	Avg: 6	12	34	42	6	0

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	12	144	2.8	0.44	395	0.54%	20	5.1
Scour Pools	49	1,408	7.6	0.80	11,710	15.90%	111	0.9
Glides	0	0			0	0.00%	0	0.0
Riffles	65	4,632	9.6	0.23	51,509	69.94%	858	1.7
Rapids	14	722	6.9	0.26	5,333	7.24%	195	3.7
Cascades	4	46	5.7	0.15	297	0.40%	22	7.4
Step/Falls	20	116	10.0	0.16	1,155	1.57%	12	1.0
Dry	33	1,729	2.5	0.10	3,248	4.41%	16	0.5
Culverts	0	0			0	0.00%	0	0.0

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/21/2010

Survey Date:

8/24/2010

REACH 21

T05S-R41E-S08SW

REACH 21

POOL SUMMARY

	<u>Total</u>	Total of all Channel Lengths <u># / Km</u>	Primary Channel Length <u># / Km</u>
All Pools:	61	6.9	10.7
Pools >=1m deep:	13	1.5	2.3
Complex pools (LWD pieces>=3):	20	2.3	3.5
Pool frequency (channel widths/pool):	8.7		
Residual pool depth (avg):	0.52		

OREGON DEPARTMENT OF FISH AND WILDLIFE

CATHERINE CREEK

HABITAT INVENTORY

Report Date: 12/7/2010

Survey Date:

9/1/2010

REACH 22

T05S-R41E-S22SE

REACH 22

HABITAT DETAIL

Habitat Type	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Large Boulders (#>0.5m)	Substrate Percent Wetted Area					
							S/O	Snd	Grvl	Cbl	Bldr	Bdrk
CASCADE/BOULDERS	2	37	13.5	0.24	506	10	0	0	5	90	5	0
POOL-BACKWATER	2	17	1.8	0.36	29	0	88	0	10	3	0	0
POOL-LATERAL SCOUR	3	51	8.0	1.01	478	13	0	10	28	50	12	0
POOL-STRAIGHT SCOUR	3	63	8.0	0.92	497	5	0	8	56	31	2	3
PUDDLED UNIT	1	35	2.3	0.16	81	3	19	0	75	6	0	0
RAPID/BOULDERS	14	1,006	7.9	0.25	8,401	597	0	1	18	48	31	2
RIFFLE	14	1,001	7.8	0.28	9,388	299	0	9	27	51	14	0
STEP/COBBLE	1	10	10.0	0.21	100	0	0	0	10	85	5	0
Total:	40	2,220	7.7	0.37	19,480	927	Avg: 5	5	25	47	17	1

HABITAT SUMMARY

Habitat Group	Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Wetted Area		Large Boulders	
					(m ²)	Percent	Number	(# / 100m ²)
Dammed & BW Pools	2	17	1.8	0.36	29	0.15%	0	0.0
Scour Pools	6	114	8.0	0.97	975	5.01%	18	1.8
Glides	0	0			0	0.00%	0	0.0
Riffles	14	1,001	7.8	0.28	9,388	48.19%	299	3.2
Rapids	14	1,006	7.9	0.25	8,401	43.12%	597	7.1
Cascades	2	37	13.5	0.24	506	2.60%	10	2.0
Step/Falls	1	10	10.0	0.21	100	0.51%	0	0.0
Dry	1	35	2.3	0.16	81	0.41%	3	3.7
Culverts	0	0			0	0.00%	0	0.0

POOL SUMMARY

	Total of all Channel Lengths		Primary Channel Length
	Total	# / Km	# / Km
All Pools:	8	3.6	4.7
Pools >=1m deep:	3	1.4	1.8
Complex pools (LWD pieces>=3):	3	1.4	1.8
Pool frequency (channel widths/pool):	23.7		
Residual pool depth (avg):	0.56		







STREAM SUMMARY

CATHERINE CREEK







Number Units	Total Length (m)	Avg Width (m)	Avg Depth (m)	Total Area (m ²)	Substrate						Large Boulders (#>0.5m)
					Percent Wetted Area						
					S/O	Snd	Grvl	Cbl	Bldr	Bdrk	
1084	95,724	10.7	0.62	1,256,167	21	15	23	23	5	13	13,221

Habitat Group	Wetted Area	
	(m ²)	Percent
Dammed & BW Pools	10,103	0.80%
Scour Pools	44,835	3.57%
Glides	882,173	70.23%
Riffles	235,820	18.77%
Rapids	19,989	1.59%
Cascades	813	0.06%
Step/Falls	3,609	0.29%
Dry	6,746	0.54%
Culverts	0	0.00%
Unsurveyed	52,080	4.15%







CATHERINE CREEK: HABITAT DISTRIBUTION







CATHERINE CREEK: HABITAT DISTRIBUTION



CATHERINE CREEK: HABITAT DISTRIBUTION



CATHERINE CREEK: HABITAT DISTRIBUTION



50	LF	1	HT	10	15	40	5	Conifer Hardwood		55% BARE DIRT
50	LF	2	HT	5	40	50	60	Conifer Hardwood		SMALL WILLOWS; GRASS GRASS
50	LF	3	HT	27	20	10	90	Conifer Hardwood	1	
50	RT	1	HT	45	95	90	0	Conifer Hardwood	7	10% BARE MUD
50	RT	2	HT	5	10	10	90	Conifer Hardwood		
50	RT	3	HT	0	0	0	100	Conifer Hardwood		
57	LF	1	LT	0	30	60	10	Conifer Hardwood		40% BARE
57	LF	2	HT	15	0	10	90	Conifer Hardwood		TRANSITION BTWN FP AND TERR GRASS
57	LF	3	HT	0	0	10	90	Conifer Hardwood		
57	RT	1	LT	14	45	0	15	Conifer Hardwood	30	WILLOWS; 85% BARE DIRT
57	RT	2	LT	12	85	40	60	Conifer Hardwood	25	HAWTHORNS
57	RT	3	HT	5	5	0	30	Conifer Hardwood		70% WHEAT FIELD
64	LF	1	FP	12	95	0	50	Conifer Hardwood	50	WILLOW THICKET; 50% BARE GRASS
64	LF	2	LT	4	0	0	100	Conifer Hardwood		
64	LF	3	HT	0	0	0	100	Conifer Hardwood		TRANSITION
64	RT	1	HT	0	65	75	0	Conifer Hardwood	3	25% BARE MUD
64	RT	2	HT	0	0	0	100	Conifer Hardwood		WILD GRASSES
64	RT	3	HT	0	0	0	0	Conifer Hardwood		100% WHEAT FIELD
72	LF	1	HT	15	70	60	0	Conifer Hardwood	10	40% MUD; TRANSITION; BRUSHY-EST EST-BRUSHY
72	LF	2	HT	0	10	10	90	Conifer Hardwood		
72	LF	3	HT	0	0	0	100	Conifer Hardwood		GRASS- NATURAL
72	RT	1	HT	2	30	50	5	Conifer Hardwood	10	45% BARE MUD, WILLOWS
72	RT	2	HT	7	0	0	100	Conifer Hardwood		

72	RT	3	HT	-25	0	0	100	Conifer Hardwood			TERR TRANSITION
79	LF	1	HT	29	5	15	70	Conifer Hardwood			15% MUD; TRANSITION
79	LF	2	HT	0	70	0	90	Conifer Hardwood	2	4	10% BARE
79	LF	3	HT	0	0	0	100	Conifer Hardwood			GRASS
79	RT	1	HT	40	0	20	30	Conifer Hardwood			50% BARE MUD; TRANSITION
79	RT	2	HT	0	0	0	0	Conifer Hardwood			PLOWED FIELD
79	RT	3	HT	0	0	0	0	Conifer Hardwood			PLOWED FIELD

RIPARIAN ZONE VEGETATION

Reach 2

Reach 2

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
86	LF	1	HT	28	95	75	0	Conifer							5% BARE DIRT; TRANSITION
								Hardwood							
86	LF	2	HT	2	50	60	35	Conifer							5% BARE DIRT
								Hardwood	5	3					
86	LF	3	HT	0	0	0	100	Conifer							GRASS
								Hardwood	10	6					
86	RT	1	HT	32	55	30	40	Conifer							30% BARE DIRT; TRANSITION
								Hardwood	5	9					
86	RT	2	HT	0	0	0	100	Conifer							GRASS FIELD
								Hardwood							
86	RT	3	HT	0	0	0	100	Conifer							GRASS AG FIELD
								Hardwood							
96	LF	1	LT	10	5	10	10	Conifer							75% BARE DIRT
								Hardwood							
96	LF	2	HT	0	100	95	0	Conifer							EST
								Hardwood							
96	LF	3	HT	0	100	95	0	Conifer							
								Hardwood							
96	RT	1	HT	70	50	40	5	Conifer							5% BARE DIRT; TRANSITION
								Hardwood							
96	RT	2	HT	0	0	0	100	Conifer							GRASS AG FIELD
								Hardwood							
96	RT	3	HT	0	0	0	100	Conifer							GRASS AG FIELD
								Hardwood							
103	LF	1	HT	30	90	60	0	Conifer							40% BARE DIRT-TRANSITION
								Hardwood	6						
103	LF	2	HT	0	60	50	20	Conifer							30% BARE DIRT
								Hardwood	13	2					
103	LF	3	HT	0	0	0	100	Conifer							ALFALFA FIELD
								Hardwood							
103	RT	1	HT	45	0	25	70	Conifer							5% BARE DIRT; GRASS, WHEAT
								Hardwood							
103	RT	2	HT	6	0	0	95	Conifer							5% BARE DIRT
								Hardwood							
103	RT	3	HT	0	0	0	100	Conifer							GRASS-WHEAT
								Hardwood							
110	LF	1	HT	33	0	5	90	Conifer							5% BARE DIRT; TRANSITION
								Hardwood							

110	LF	2	RB	0	0	0	95	Conifer Hardwood					FARM ACCESS RD; 5% BARE GRASS-AG FIELD
110	LF	3	HT	0	0	0	100	Conifer Hardwood					
110	RT	1	HT	27	80	80	0	Conifer Hardwood	3	6			20% BARE DIRT, TRANSITION
110	RT	2	HT	6	95	60	0	Conifer Hardwood	20	10	2		
110	RT	3	HT	0	5	5	85	Conifer Hardwood					5% BARE DIRT, GRASS- WHEAT
120	LF	1	HT	50	55	75	20	Conifer Hardwood		2			5% BARE DIRT; TRANSITION
120	LF	2	HT	23	5	0	85	Conifer Hardwood					10% BARE DIRT; GRASS- AG
120	LF	3	HT	0	0	0	95	Conifer Hardwood					5% BARE DIRT
120	RT	1	HT	30	50	90	10	Conifer Hardwood					TRANSITION
120	RT	2	HT	0	0	10	90	Conifer Hardwood					GRASS-AG FIELD; EST
120	RT	3	HT	0	0	0	100	Conifer Hardwood					GRASS-AG FIELD
127	LF	1	HT	40	100	75	0	Conifer Hardwood		10			25% BARE DIRT; TRANSITION
127	LF	2	HT	0	0	10	90	Conifer Hardwood					GRASS-AG
127	LF	3	HT	0	0	0	100	Conifer Hardwood					GRASS-AG
127	RT	1	HT	53	0	95	0	Conifer Hardwood					5% BARE DIRT; TRANSITION
127	RT	2	HT	0	0	0	100	Conifer Hardwood					GRASS-AG
127	RT	3	HT	0	0	0	100	Conifer Hardwood					GRASS-AG FIELD
134	LF	1	HT	88	0	5	70	Conifer Hardwood					30% BARE DIRT; TRANSITION
134	LF	2	HT	0	0	0	95	Conifer Hardwood					5% BARE DIRT
134	LF	3	HT	0	0	0	95	Conifer Hardwood					5% BARE DIRT
134	RT	1	FP	3	5	95	0	Conifer Hardwood					5% BARE DIRT
134	RT	2	HT	28	0	40	55	Conifer Hardwood					5% BARE DIRT; TRANSITION
134	RT	3	HT	-5	0	0	100	Conifer Hardwood					GRASS- WHEAT FIELD

141	LF	1	FP	10	50	30	60	Conifer Hardwood		10% BARE DIRT; GRASS
141	LF	2	HT	2	5	5	90	Conifer Hardwood		HAWTHORN; 5% BARE DIRT
141	LF	3	HT	0	50	50	50	Conifer Hardwood		
141	RT	1	HT	78	5	10	80	Conifer Hardwood		10% BARE DIRT; TRANSITION
141	RT	2	HT	0	0	0	100	Conifer Hardwood		GRASS-AG
141	RT	3	HT	0	0	0	100	Conifer Hardwood		GRASS-AG FIELD
148	LF	1	HT	40	90	90	0	Conifer Hardwood	2	BRUSHY, STEEP TRANSITION;
148	LF	2	HT	0	100	95	0	Conifer Hardwood		5% BARE
148	LF	3	HT	0	0	10	90	Conifer Hardwood		GRASS- LAWN, YARD
148	RT	1	FP	0	85	85	5	Conifer Hardwood		10% BARE DIRT; GRASS- NATURAL
148	RT	2	FP	0	100	100	0	Conifer Hardwood		EST-DENSE SHRUBRY
148	RT	3	FP	0	100	100	0	Conifer Hardwood		

RIPARIAN ZONE VEGETATION

Reach 3

Reach 3

Unit	Side	Zone	Surface	Slope	Cover (percent)			Diameter class (cm)					Notes					
					Canopy	Shrub	Grass	3-15	15-30	30-50	50-90	>90						
152	LF	1	HT	0	0	0	100											
																		Conifer Hardwood
152	LF	2	HT	0	0	0	100											Conifer Hardwood
152	LF	3	HT	0	0	0	100											Conifer Hardwood
152	RT	1	HT	0	0	0	100											Conifer Hardwood
152	RT	2	HT	0	0	0	100											Conifer Hardwood
152	RT	3	HT	0	0	0	100											Conifer Hardwood
159	LF	1	HT	0	5	0	100											Conifer Hardwood
159	LF	2	HT	0	0	0	100											Conifer Hardwood
159	LF	3	HT	0	0	0	100											Conifer Hardwood
159	RT	1	FP	3	0	0	100											Conifer Hardwood
159	RT	2	HT	0	0	0	100											Conifer Hardwood
159	RT	3	HT	0	0	0	20											Conifer Hardwood
166	LF	1	FP	5	0	0	100											Conifer Hardwood
166	LF	2	HT	0	0	0	100											Conifer Hardwood
166	LF	3	HT	0	0	0	100											Conifer Hardwood
166	RT	1	HT	0	0	0	100											Conifer Hardwood
166	RT	2	HT	0	0	0	100											Conifer Hardwood
166	RT	3	HT	0	0	0	100											Conifer Hardwood
170	LF	1	HT	0	0	0	100											Conifer Hardwood

FP MAY BE HT

AG FIELD;
80% BARE
DIRT

AG FIELD

AG FIELD

AG FIELD

170	LF	2	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
170	LF	3	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
170	RT	1	HT	0	0	10	90	Conifer		
								Hardwood		
170	RT	2	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
170	RT	3	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
178	LF	1	HT	0	0	0	100	Conifer		
								Hardwood		
178	LF	2	HT	0	0	0	20	Conifer		60% PAVEMENT; 20% BARE-RB 70% BARE
								Hardwood		
178	LF	3	HT	0	0	0	30	Conifer		
								Hardwood		
178	RT	1	FP	46	10	0	100	Conifer	1	
								Hardwood		
178	RT	2	HT	0	0	0	20	Conifer		80% DIRT
								Hardwood		
178	RT	3	HT	0	0	0	0	Conifer		00% DIRT
								Hardwood		
184	LF	1	FP	27	0	0	100	Conifer		
								Hardwood		
184	LF	2	HT	-2	0	0	100	Conifer		AG FIELD
								Hardwood		
184	LF	3	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
184	RT	1	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
184	RT	2	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
184	RT	3	HT	0	0	0	100	Conifer		AG FIELD
								Hardwood		
192	LF	1	HT	0	40	80	20	Conifer		
								Hardwood	2	
192	LF	2	HT	0	0	0	100	Conifer		
								Hardwood		
192	LF	3	HT	0	0	0	100	Conifer		
								Hardwood		
192	RT	1	FP	20	0	0	100	Conifer		
								Hardwood		
192	RT	2	HT	-3	0	0	60	Conifer		40% BARE
								Hardwood		
192	RT	3	HT	0	0	0	0	Conifer		100% BARE DIRT
								Hardwood		

199	LF	1	FP	14	0	0	100	Conifer Hardwood	
199	LF	2	HT	-2	0	0	100	Conifer Hardwood	AG FIELD
199	LF	3	HT	0	0	0	100	Conifer Hardwood	AG FIELD
199	RT	1	HT	0	5	0	100	Conifer Hardwood	6
199	RT	2	HT	0	0	0	100	Conifer Hardwood	
199	RT	3	HT	0	0	0	100	Conifer Hardwood	
206	LF	1	HT	0	5	0	100	Conifer Hardwood	TRANSITION
206	LF	2	HT	0	0	0	100	Conifer Hardwood	
206	LF	3	HT	0	0	0	100	Conifer Hardwood	
206	RT	1	HT	10	0	0	100	Conifer Hardwood	2 DEER IN RIP
206	RT	2	HT	10	5	0	100	Conifer Hardwood	2
206	RT	3	HT	0	0	0	100	Conifer Hardwood	GRASS WHEAT
213	LF	1	HT	0	30	45	55	Conifer Hardwood	BV
213	LF	2	HT	0	40	60	40	Conifer Hardwood	
213	LF	3	HT	0	70	0	100	Conifer Hardwood	5
213	RT	1	HT	0	0	5	95	Conifer Hardwood	TRANSITION
213	RT	2	HT	0	0	0	100	Conifer Hardwood	
213	RT	3	HT	0	0	0	100	Conifer Hardwood	
220	LF	1	HT	30	0	0	100	Conifer Hardwood	
220	LF	2	HT	0	0	0	100	Conifer Hardwood	
220	LF	3	HT	0	0	0	100	Conifer Hardwood	
220	RT	1	HT	5	0	0	100	Conifer Hardwood	ANIMAL TRAIL
220	RT	2	HT	0	75	0	40	Conifer Hardwood	9 3 60% BARE DIRT

RIPARIAN ZONE VEGETATION

Reach 4

Reach 4

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
231	LF	1	HT	0	20	100	0	Conifer							EST-STEEP BANK; HAWTHORN
								Hardwood	10	5					
231	LF	2	HT	0	0	0	100	Conifer							
								Hardwood							
231	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
231	RT	1	HT	5	35	50	50	Conifer							ANIMAL TRAIL
								Hardwood	13	3					
231	RT	2	HT	3	75	40	60	Conifer							
								Hardwood	16	4					
231	RT	3	HT	-2	80	30	70	Conifer							
								Hardwood	16	3					
238	LF	1	HT	0	0	0	100	Conifer							60% CORN; TRANSITION
								Hardwood							
238	LF	2	HT	0	0	0	100	Conifer							100% CORN
								Hardwood							
238	LF	3	HT	0	0	0	100	Conifer							100% CORN
								Hardwood							
238	RT	1	HT	5	80	50	50	Conifer							
								Hardwood							
238	RT	2	HT	10	0	100	0	Conifer							
								Hardwood	10						
238	RT	3	HT	0	0	0	100	Conifer							
								Hardwood							
252	LF	1	HT	0	0	10	90	Conifer							
								Hardwood							
252	LF	2	HT	30	30	90	10	Conifer							
								Hardwood							
252	LF	3	HT	0	0	0	100	Conifer							20 HARVESTED WHEAT TRANSITION
								Hardwood							
252	RT	1	HT	60	0	0	100	Conifer							
								Hardwood							
252	RT	2	HT	0	0	0	95	Conifer							5% BARE; GRASS=HARV EST WHEAT
								Hardwood							
252	RT	3	HT	0	0	0	100	Conifer							
								Hardwood							
259	LF	1	HT	0	0	85	15	Conifer							
								Hardwood							

259	LF	2	HT	0	0	100	0	Conifer	
								Hardwood	
259	LF	3	HT	0	0	100	0	Conifer	
								Hardwood	
259	RT	1	FP	24	0	90	10	Conifer	
								Hardwood	
259	RT	2	HT	0	0	0	100	Conifer	AG FIELD
								Hardwood	
259	RT	3	HT	0	0	0	100	Conifer	AG FIELD
								Hardwood	

RIPARIAN ZONE VEGETATION

Reach 5

Reach 5

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
270	LF	1	HT	0	10	20	80	Conifer							
								Hardwood	5						
270	LF	2	HT	0	0	0	100	Conifer							
								Hardwood							
270	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
270	RT	1	HT	22	40	0	100	Conifer							
								Hardwood							
270	RT	2	HT	1	85	0	100	Conifer							
								Hardwood	22						
270	RT	3	HT	1	35	0	70	Conifer						30% BARE	
								Hardwood	9						
277	LF	1	FP	0.5	0	90	10	Conifer							
								Hardwood							
277	LF	2	HT	5	0	50	50	Conifer							
								Hardwood							
277	LF	3	SC	0	0	30	70	Conifer						ZONE	
								Hardwood						3=OXBOW	
277	RT	1	HT	0	0	0	100	Conifer							
								Hardwood							
277	RT	2	HT	0	0	0	100	Conifer							
								Hardwood							
277	RT	3	HT	0	5	0	100	Conifer							
								Hardwood	3						

RIPARIAN ZONE VEGETATION

Reach 6

Reach 6

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
285	LF	1	HT	0	0	0	100	Conifer							AG FIELD
								Hardwood							
285	LF	2	HT	0	0	0	100	Conifer							AG FIELD
								Hardwood							
285	LF	3	HT	0	0	0	100	Conifer							AG FIELD
								Hardwood							
285	RT	1	HT	57	0	0	100	Conifer							BV
								Hardwood							
285	RT	2	HT	0	0	10	90	Conifer							
								Hardwood	4						
285	RT	3	HT	0	65	10	90	Conifer							
								Hardwood	21						
292	LF	1	HT	55	0	10	90	Conifer							
								Hardwood							
292	LF	2	HT	0	0	0	100	Conifer							
								Hardwood							
292	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
292	RT	1	HT	38	5	5	95	Conifer							
								Hardwood							
292	RT	2	HT	2	0	0	100	Conifer							
								Hardwood							
292	RT	3	HT	0	0	0	100	Conifer							
								Hardwood							
301	LF	1	FP	19	15	50	50	Conifer							
								Hardwood	25						
301	LF	2	HT	0	0	0	100	Conifer							
								Hardwood							
301	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
301	RT	1	HT	0	0	0	95	Conifer							5% BARE; AG FIELD
								Hardwood							
301	RT	2	HT	0	0	0	100	Conifer							
								Hardwood							
301	RT	3	HT	0	0	0	100	Conifer							
								Hardwood							
308	LF	1	HT	33	0	5	95	Conifer							AG FIELD
								Hardwood							

308	LF	2	HT	0	0	5	95	Conifer	
								Hardwood	
308	LF	3	HT	0	0	0	100	Conifer	
								Hardwood	
308	RT	1	HT	0	5	10	0	Conifer	5% BARE; TRANSITION
								Hardwood	
308	RT	2	HT	0	0	0	100	Conifer	AG FIELD
								Hardwood	
308	RT	3	HT	0	0	0	100	Conifer	AG FIELD
								Hardwood	

355	LF	2	FP	0	0	5	70	Conifer	25% BARE
								Hardwood	
355	LF	3	FP	0	0	0	100	Conifer	
								Hardwood	
355	RT	1	FP	0	0	0	100	Conifer	COW PATH
								Hardwood	AND PRINTS
355	RT	2	HT	0	0	2	98	Conifer	
								Hardwood	
355	RT	3	HT	0	0	0	100	Conifer	
								Hardwood	

RIPARIAN ZONE VEGETATION

Reach 8

Reach 8

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
365	LF	1	HT	0	0	0	100	Conifer							GRASS-AG
								Hardwood							
365	LF	2	HT	0	0	0	100	Conifer							GRASS-AG
								Hardwood							
365	LF	3	HT	0	0	0	100	Conifer							GRASS-AG
								Hardwood							
365	RT	1	FP	9	85	0	80	Conifer							GRASS, 20% BARE DIRT
								Hardwood	2	4	1				
365	RT	2	FP	-8	65	0	65	Conifer							GRASS, 35% BARE DIRT
								Hardwood							
365	RT	3	FP	5	80	0	65	Conifer							35% BARE DIRT, GRASS
								Hardwood			1	2	1		
373	LF	1	FP	0	85	0	5	Conifer							95% BARE DIRT
								Hardwood	6	2	2	2	2		85% BARE DIRT
373	LF	2	FP	0	100	0	15	Conifer							NATURAL GRASSES
								Hardwood							
373	LF	3	FP	0	0	0	100	Conifer							NATURAL GRASSES
								Hardwood							
373	RT	1	FP	-6	10	0	100	Conifer							
								Hardwood				1			
373	RT	2	HT	12	0	0	100	Conifer							TRANSITION, GRASSES
								Hardwood							
373	RT	3	HT	-23	0	0	100	Conifer							NATURAL GRASSES
								Hardwood							
382	LF	1	FP	0	45	0	100	Conifer							NATURAL GRASSES
								Hardwood							
382	LF	2	FP	0	90	0	100	Conifer							NATURAL GRASSES
								Hardwood							
382	LF	3	HT	-20	0	0	100	Conifer							NATURAL GRASSES
								Hardwood							
382	RT	1	FP	-2	80	0	95	Conifer							5% BARE DIRT;
								Hardwood	3						GRASSES MARSHY AREA,
382	RT	2	FP	-5	40	0	100	Conifer							GRASSES MARSHY AREA,
								Hardwood							GRASSES MARSHY AREA,
382	RT	3	FP	0	60	0	100	Conifer							GRASSES
								Hardwood	5						

419	LF	2	FP	1	0	0	100	Conifer			
								Hardwood			
419	LF	3	FP	14	0	0	100	Conifer			
								Hardwood			
419	RT	1	FP	7	15	0	100	Conifer			
								Hardwood	1		
419	RT	2	FP	-1	15	0	100	Conifer			
								Hardwood		1	
419	RT	3	FP	40	0	0	80	Conifer			20% BARE
								Hardwood			DIRT
429	LF	1	HT	65	0	5	95	Conifer			TRANSITION
								Hardwood			
429	LF	2	HT	28	0	0	100	Conifer			
								Hardwood			
429	LF	3	HT	0	0	0	100	Conifer			
								Hardwood			
429	RT	1	HT	28	0	0	95	Conifer			CATTLE USE;
								Hardwood			5% BARE
429	RT	2	HT	-22	0	0	100	Conifer			DIRT
								Hardwood			
429	RT	3	HT	0	0	0	100	Conifer			
								Hardwood			

RIPARIAN ZONE VEGETATION

Reach 12

Reach 12

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
449	LF	1	HT	9	0	0	100	Conifer							BV ACTIVITY
								Hardwood							
449	LF	2	HT	2	0	0	100	Conifer							AG FIELD
								Hardwood							
449	LF	3	HT	0	0	0	100	Conifer							AG FIELD
								Hardwood							
449	RT	1	HT	0	0	0	100	Conifer							AG FIELD
								Hardwood							
449	RT	2	HT	0	0	0	100	Conifer							AG FIELD
								Hardwood							
449	RT	3	HT	0	0	0	100	Conifer							
								Hardwood							
472	LF	1	FP	0	0	0	100	Conifer							EST DUE TO NO ACCESS
								Hardwood							
472	LF	2	FP	0	0	0	100	Conifer							PVT PROP-HEFNER
								Hardwood							
472	LF	3	FP	0	0	0	100	Conifer							
								Hardwood							
472	RT	1	FP	0	35	0	100	Conifer							
								Hardwood							
472	RT	2	FP	2	0	0	100	Conifer							
								Hardwood					2		
472	RT	3	FP	7	0	0	100	Conifer							
								Hardwood							
504	LF	1	FP	0	90	5	95	Conifer							EST DUE TO NO ACCESS
								Hardwood	2		3				
504	LF	2	FP	0	0	0	100	Conifer							HEFNER PVT PROP
								Hardwood							
504	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
504	RT	1	FP	0	35	10	90	Conifer							GOATS GRAZING IN RIPARIAN
								Hardwood							
504	RT	2	FP	0	0	0	100	Conifer							
								Hardwood							
504	RT	3	FP	0	0	0	100	Conifer							
								Hardwood							
525	LF	1	HT	0	20	0	100	Conifer							DIANE HEFNER PROP-EST.
								Hardwood							

525	LF	2	HT	0	10	0	100	Conifer					
								Hardwood					
525	LF	3	HT	0	0	0	100	Conifer					
								Hardwood					
525	RT	1	FP	10	95	20	20	Conifer					60% BARE SAND
								Hardwood	7	3	2		
525	RT	2	HT	0	0	0	100	Conifer					COW PASTURE
								Hardwood					
525	RT	3	HT	0	0	0	100	Conifer					COW PASTURE
								Hardwood					

RIPARIAN ZONE VEGETATION

Reach 13

Reach 13

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
542	LF	1	FP	0	50	5	95	Conifer							
								Hardwood	2	6					
542	LF	2	FP	0	45	5	95	Conifer							
								Hardwood	4						
542	LF	3	FP	0	85	30	70	Conifer							
								Hardwood	4						
542	RT	1	FP	4	5	10	90	Conifer							
								Hardwood	2						
542	RT	2	FP	0	0	0	100	Conifer							HORSE PASTURE
								Hardwood							
542	RT	3	FP	0	0	0	100	Conifer							HORSE PASTURE
								Hardwood							
560	LF	1	HT	20	40	0	10	Conifer							TRANSITION, 90% GRV, CBL, BLDR
								Hardwood	5	3	1				YARD GRASS
560	LF	2	HT	0	0	0	100	Conifer							
								Hardwood							
560	LF	3	HT	0	0	0	100	Conifer							YARD GRASS
								Hardwood							
560	RT	1	HT	20	25	0	70	Conifer							TRANSITION, PARTIALLY
								Hardwood							YARD
560	RT	2	HT	0	0	0	0	Conifer							HOUSE
								Hardwood							
560	RT	3	HT	0	0	0	0	Conifer							HOUSE
								Hardwood							
573	LF	1	HT	0	85	0	40	Conifer							60% CBL,, YARD;
								Hardwood	1	1			1		TRANSITON
573	LF	2	HT	0	50	0	60	Conifer							YARD, HOUSE,
								Hardwood							PARKING
573	LF	3	HT	0	40	0	45	Conifer							55% YARD, HOUSE
								Hardwood							
573	RT	1	HT	0	90	5	0	Conifer							TRANSITION, WILD ROSE,
								Hardwood							95% GRAV
573	RT	2	HT	0	0	0	5	Conifer							STREET, PARKING LOT
								Hardwood							
573	RT	3	HT	0	0	0	5	Conifer							STREET, PARKING LOT
								Hardwood							
582	LF	1	HT	0	5	5	0	Conifer							BOTH BANKS RESIDENTIAL
								Hardwood							

582	LF	2	HT	0	0	0	0	Conifer		
								Hardwood		
582	LF	3	HT	0	0	0	0	Conifer		
								Hardwood		
582	RT	1	FP	10	60	5	5	Conifer		
								Hardwood	9	
582	RT	2	HT	0	0	0	0	Conifer		100% BARE
								Hardwood		
582	RT	3	HT	0	0	0	0	Conifer		100% GRV
								Hardwood		

RIPARIAN ZONE VEGETATION

Reach 14

Reach 14

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
591	LF	1	HT	5	90	90	0	Conifer							10% ROADBED
								Hardwood	2	3					
591	LF	2	RB	0	0	0	15	Conifer							
								Hardwood							
591	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
591	RT	1	HT	1	5	20	75	Conifer							5% GRV
								Hardwood	6	1					
591	RT	2	HS	65	5	80	20	Conifer							
								Hardwood							
591	RT	3	HS	90	0	5	95	Conifer							
								Hardwood							
601	LF	1	RB	0	0	0	0	Conifer							100% GRV-PAVEMENT
								Hardwood							
601	LF	2	HT	0	0	0	100	Conifer							COW PASTURE
								Hardwood							
601	LF	3	HT	0	0	0	100	Conifer							COW PASTURE
								Hardwood							
601	RT	1	HS	45	85	75	5	Conifer						1	20% BARE
								Hardwood	6	3					
601	RT	2	HS	85	5	5	95	Conifer							
								Hardwood							
601	RT	3	HS	85	5	5	95	Conifer							
								Hardwood							
620	LF	1	HT	0	95	10	90	Conifer						6	
								Hardwood	1		3				
620	LF	2	HT	0	95	5	95	Conifer							YARD ZONE 2+3
								Hardwood							
620	LF	3	HT	0	40	0	100	Conifer							YARD
								Hardwood							
620	RT	1	HS	80	80	60	0	Conifer						3	40% BARE AND DIRT
								Hardwood	7						
620	RT	2	HS	90	0	100	0	Conifer							
								Hardwood							
620	RT	3	HS	90	0	100	0	Conifer							
								Hardwood							
645	LF	1	RB	0	45	10	75	Conifer							BEYOND FENCE INTO PVT
								Hardwood	5						

645	LF	2	HT	0	0	0	100	Conifer		PASTURE
								Hardwood		
645	LF	3	HT	0	0	0	100	Conifer		PASTURE
								Hardwood		
645	RT	1	HS	100	5	65	30	Conifer		5% BARE
								Hardwood		
645	RT	2	HS	80	15	90	10	Conifer	1	
								Hardwood		
645	RT	3	HS	80	0	90	10	Conifer	3	
								Hardwood		

RIPARIAN ZONE VEGETATION

Reach 16

Reach 16

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
661	LF	1	FP	9	5	5	75	Conifer							20% BARE, CBL, GRV
								Hardwood							
661	LF	2	HT	0	0	5	95	Conifer							COW PASTURE
								Hardwood							
661	LF	3	HT	0	0	0	100	Conifer							COW PASTURE
								Hardwood							
661	RT	1	FP	5	45	75	20	Conifer							5% SAND
								Hardwood			4				
661	RT	2	HT	0	5	50	50	Conifer							
								Hardwood			2				
661	RT	3	HT	0	0	0	100	Conifer							
								Hardwood							
695	LF	1	FP	0	0	0	100	Conifer							LEFT BANK HEAVILY GRAZED CATTLE USE
								Hardwood							
695	LF	2	FP	0	0	0	100	Conifer							
								Hardwood							
695	LF	3	FP	0	0	0	100	Conifer							
								Hardwood							
695	RT	1	HS	57	90	90	100	Conifer							CATTLE USE
								Hardwood	45	2					
695	RT	2	HS	40	0	0	100	Conifer							CATTLE USE
								Hardwood							
695	RT	3	HS	40	0	0	100	Conifer							CATTLE USE
								Hardwood							

RIPARIAN ZONE VEGETATION

Reach 17

Reach 17

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
717	LF	1	RB	0	0	0	10	Conifer							HWY 203, 90% BARE
								Hardwood							
717	LF	2	HS	50	5	0	100	Conifer				1			
								Hardwood							
717	LF	3	HS	50	0	0	100	Conifer							
								Hardwood							
717	RT	1	HS	85	50	90	10	Conifer							
								Hardwood	5						
717	RT	2	HS	40	35	90	10	Conifer			1		1		
								Hardwood							
717	RT	3	HS	40	35	90	10	Conifer				2			
								Hardwood							
743	LF	1	HT	-4	10	5	95	Conifer							
								Hardwood	1	6	3				
743	LF	2	RB	0	0	0	0	Conifer							100% GRV, HWY 203, PAVEMENT
								Hardwood							
743	LF	3	HT	0	0	50	50	Conifer							
								Hardwood							
743	RT	1	HS	11	65	80	10	Conifer							HEAVY CATTLE USE ALL ZONES
								Hardwood	3						
743	RT	2	HS	25	95	100	0	Conifer							
								Hardwood	3						
743	RT	3	HS	25	95	100	0	Conifer							
								Hardwood							

RIPARIAN ZONE VEGETATION

Reach 18

Reach 18

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
767	LF	1	HT	0	35	70	30	Conifer	1						
								Hardwood	2						
767	LF	2	HT	0	70	70	30	Conifer							
								Hardwood	4						
767	LF	3	HT	0	65	80	20	Conifer				1			
								Hardwood							
767	RT	1	HS	90	40	60	0	Conifer							40% MOSS
								Hardwood							
767	RT	2	HS	90	85	100	0	Conifer				1			
								Hardwood							
767	RT	3	HS	90	85	100	0	Conifer				2			
								Hardwood							

RIPARIAN ZONE VEGETATION

Reach 19

Reach 19

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
790	LF	1	HT	0	25	20	20	Conifer			1				YARD, 60% PINE NEEDLES
								Hardwood							
790	LF	2	HT	0	50	0	50	Conifer							YARD; 50% PINE NEEDLES
								Hardwood	5						
790	LF	3	HT	0	45	0	50	Conifer							YARD, 50% PINE NEEDLES
								Hardwood							
790	RT	1	HS	50	40	70	0	Conifer	6						30% MOSS
								Hardwood							
790	RT	2	HS	50	95	45	5	Conifer	8	1					50% MOSS
								Hardwood							
790	RT	3	HS	50	95	90	0	Conifer	10				1		10% PINE NEEDLES
								Hardwood							
805	LF	1	FP	-3	80	20	80	Conifer							BV
								Hardwood	17	1					
805	LF	2	FP	3	40	30	40	Conifer			1				FS RD 2036; 30% BLDR, CONCRETE
								Hardwood	24						100% BLDR, CONCRETE
805	LF	3	RB	0	0	0	0	Conifer							
								Hardwood							
805	RT	1	RB	0	0	0	5	Conifer							HWY 203
								Hardwood							
805	RT	2	RB	0	0	0	0	Conifer							100% GRV, CONCRETE
								Hardwood							
805	RT	3	HS	-26	10	5	95	Conifer							
								Hardwood							

RIPARIAN ZONE VEGETATION

Reach 21

Reach 21

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes	
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90		
880	LF	1	HT	0	10	0	100	Conifer	1		1				
								Hardwood							
880	LF	2	HT	0	0	5	95	Conifer							
								Hardwood							
880	LF	3	HT	0	0	0	100	Conifer							
								Hardwood							
880	RT	1	FP	3	75	0	100	Conifer	1	3				BV, CATTLE TRAMPLING	
								Hardwood	12	1					
880	RT	2	FP	-2	80	0	100	Conifer		1	2			BV, CATTLE TRAMPLED	
								Hardwood	6						
880	RT	3	FP	0	70	20	70	Conifer			2			BV, CATTLE TRAMPLED	
								Hardwood	17						
926	LF	1	FP	0	5	30	70	Conifer							
								Hardwood	7						
926	LF	2	HS	55	5	60	40	Conifer	1						
								Hardwood	5						
926	LF	3	HS	55	15	55	45	Conifer							
								Hardwood							
926	RT	1	HT	0	0	50	50	Conifer							
								Hardwood							
926	RT	2	HT	0	0	50	50	Conifer							
								Hardwood							
926	RT	3	HT	0	0	50	50	Conifer							
								Hardwood							
985	LF	1	SC	0	0	0	0	Conifer						EST DUE TO DENSE VEG	
								Hardwood	3						
985	LF	2	HT	0	60	100	0	Conifer							
								Hardwood							
985	LF	3	HT	0	60	100	0	Conifer							
								Hardwood							
985	RT	1	FP	2	65	60	0	Conifer						40% BARE DIRT	
								Hardwood	1	3					
985	RT	2	FP	0	80	90	0	Conifer			2			BV, 10% BARE	
								Hardwood	4		4				
985	RT	3	FP	0	55	90	0	Conifer						10% BARE	
								Hardwood							
1017	LF	1	FP	0	60	60	5	Conifer			1			35% BARE	
								Hardwood	9						

1017	LF	2	HT	0	90	80	0	Conifer	2				20% BARE
								Hardwood	10	2	1		
1017	LF	3	HT	0	100	100	0	Conifer					
								Hardwood					
1017	RT	1	HS	100	35	100	0	Conifer	1				
								Hardwood	1				
1017	RT	2	HS	100	55	100	0	Conifer	4		1	1	
								Hardwood					
1017	RT	3	HS	100	70	100	0	Conifer	4	3	2		
								Hardwood					

RIPARIAN ZONE VEGETATION

Reach 22

Reach 22

Unit	Side	Zone	Surface	Slope	Cover (percent)				Diameter class (cm)					Notes
					Canopy	Shrub	Grass		3-15	15-30	30-50	50-90	>90	
1054	LF	1	HT	-2	90	60	5	Conifer	2		2			35% BARE
								Hardwood	7					
1054	LF	2	RB	0	0	10	5	Conifer						85% PAVEMENT
								Hardwood						
1054	LF	3	HS	95	20	20	20	Conifer	2					60% BARE DIRT
								Hardwood						
1054	RT	1	FP	6	55	90	10	Conifer	2					
								Hardwood	7					
1054	RT	2	HT	1	5	5	90	Conifer						5% BARE, CBL
								Hardwood			2			
1054	RT	3	RB	0	0	0	80	Conifer						OLS RD, 20% BARE, CBL
								Hardwood						

RIPARIAN ZONE VEGETATION SUMMARY

REACH 1

REACH 1

Summary of Riparian Zone (0-30m)

12 transects

Total hardwoods/1000	1199
Total conifers/1000 ft	15
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1		Zone 2		Zone 3		Zones 1-3	
	0-10 meters		10 - 20 meters		20 - 30 meters		0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.3	12.8	0.0	4.5	0.0	1.4	0.3	18.8
15-30cm	0.0	0.3	0.0	0.5	0.0	0.1	0.0	0.9
30-50cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.3	13.2	0.0	5.0	0.0	1.5	0.1	6.6

Canopy closure and ground cover

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	33		24		14	
Shrub cover	31		18		12	
Grass/forb cover	23		63		65	

Predominant landform in each zone

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	0		0		0	
High terrace	71		88		96	
Low terrace	8		8		0	
Floodplain	21		4		4	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	0		0		0	
Riprap	0		0		0	
Surface slope (%)	22		4		-1	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 2	REACH 2
Summary of Riparian Zone (0-30m) 9 transects	
Total hardwoods/1000	711
Total conifers/1000 ft	61
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.3	2.8	0.0	4.2	0.0	1.1	0.3	8.1
15-30cm	0.7	1.0	0.0	1.7	0.0	0.7	0.7	3.3
30-50cm	0.0	0.0	0.0	0.2	0.0	0.0	0.0	0.2
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	1.0	3.8	0.0	6.1	0.0	1.8	0.3	3.9

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	45	29	14
Shrub cover	54	29	14
Grass/forb cover	26	64	84

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	78	89	94
Low terrace	6	0	0
Floodplain	17	6	6
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	6	0
Riprap	0	0	0
Surface slope (%)	37	4	0

RIPARIAN ZONE VEGETATION SUMMARY

REACH 3

REACH 3

Summary of Riparian Zone (0-30m)

11 transects

Total hardwoods/1000	200
Total conifers/1000 ft	6
Total conifers >20" dbh/1000 ft	6
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1		Zone 2		Zone 3		Zones 1-3	
	0-10 meters		10 - 20 meters		20 - 30 meters		0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	0.7	0.0	1.0	0.0	1.0	0.0	2.7
15-30cm	0.0	0.0	0.0	0.3	0.0	0.3	0.0	0.5
30-50cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50-90cm	0.1	0.0	0.0	0.0	0.0	0.0	0.1	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.1	0.7	0.0	1.3	0.0	1.3	0.0	1.1

Canopy closure and ground cover

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	4		5		6	
Shrub cover	6		3		0	
Grass/forb cover	94		85		83	

Predominant landform in each zone

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	0		0		0	
High terrace	73		100		100	
Low terrace	0		0		0	
Floodplain	27		0		0	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	0		0		0	
Riprap	0		0		0	
Surface slope (%)	7		0		0	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 4

REACH 4

Summary of Riparian Zone (0-30m) 4 transects

Total hardwoods/1000	1219
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	5.8	0.0	6.5	0.0	4.0	0.0	16.3
15-30cm	0.0	2.0	0.0	1.0	0.0	0.8	0.0	3.8
30-50cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.0	7.8	0.0	7.5	0.0	4.8	0.0	6.7

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	17	13	10
Shrub cover	48	41	16
Grass/forb cover	52	58	84

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	88	100	100
Low terrace	0	0	0
Floodplain	13	0	0
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	12	5	0

RIPARIAN ZONE VEGETATION SUMMARY

REACH 5	REACH 5
Summary of Riparian Zone (0-30m) 2 transects	
Total hardwoods/1000	1189
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	2.5	0.0	11.0	0.0	6.0	0.0	19.5
15-30cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
30-50cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.0	2.5	0.0	11.0	0.0	6.0	0.0	6.5

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	13	21	10
Shrub cover	28	13	8
Grass/forb cover	73	88	85

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	75	100	75
Low terrace	0	0	0
Floodplain	25	0	0
Wetland/meadow	0	0	0
Stream channel	0	0	25
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	6	2	0

RIPARIAN ZONE VEGETATION SUMMARY

REACH 6

REACH 6

Summary of Riparian Zone (0-30m) 4 transects

Total hardwoods/1000	762
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	6.3	0.0	1.0	0.0	5.3	0.0	12.5
15-30cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
30-50cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.0	6.3	0.0	1.0	0.0	5.3	0.0	4.2

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	3	0	8
Shrub cover	10	2	1
Grass/forb cover	78	98	99

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	88	100	100
Low terrace	0	0	0
Floodplain	13	0	0
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	25	0	0

RIPARIAN ZONE VEGETATION SUMMARY

REACH 7	Summary of Riparian Zone (0-30m)	REACH 7
		4 transects
Total hardwoods/1000	0	
Total conifers/1000 ft	152	
Total conifers >20" dbh/1000 ft	0	
Total conifers >35" dbh/1000 ft	0	

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	2.5	0.0	0.0	0.0	0.0	0.0	2.5	0.0
15-30cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
30-50cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	2.5	0.0	0.0	0.0	0.0	0.0	0.8	0.0

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	2	0	0
Shrub cover	18	2	0
Grass/forb cover	78	94	99

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	38	50	63
Low terrace	0	0	0
Floodplain	63	50	38
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	2	0	2

RIPARIAN ZONE VEGETATION SUMMARY

REACH 8

REACH 8

Summary of Riparian Zone (0-30m) 3 transects

Total hardwoods/1000	691
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	3.7	0.0	0.0	0.0	1.7	0.0	5.3
15-30cm	0.0	2.0	0.0	0.0	0.0	0.0	0.0	2.0
30-50cm	0.0	1.0	0.0	0.0	0.0	0.3	0.0	1.3
50-90cm	0.0	1.0	0.0	0.0	0.0	0.7	0.0	1.7
>90cm	0.0	0.7	0.0	0.0	0.0	0.3	0.0	1.0
Total/100m2	0.0	8.3	0.0	0.0	0.0	3.0	0.0	3.8

Canopy closure and ground cover

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	51		49		23	
Shrub cover	0		0		0	
Grass/forb cover	80		80		94	

Predominant landform in each zone

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	0		0		0	
High terrace	17		33		50	
Low terrace	0		0		0	
Floodplain	83		67		50	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	0		0		0	
Riprap	0		0		0	
Surface slope (%)	0		0		-6	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 9

REACH 9

Summary of Riparian Zone (0-30m)

5 transects

Total hardwoods/1000	207
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	0.2	0.0	0.0	0.0	2.2	0.0	2.4
15-30cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
30-50cm	0.0	0.0	0.0	0.2	0.0	0.4	0.0	0.6
50-90cm	0.0	0.0	0.0	0.0	0.0	0.2	0.0	0.2
>90cm	0.0	0.0	0.0	0.0	0.0	0.2	0.0	0.2
Total/100m2	0.0	0.2	0.0	0.2	0.0	3.0	0.0	1.1

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	11	5	18
Shrub cover	2	0	7
Grass/forb cover	94	95	90

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	40	70	70
Low terrace	0	0	0
Floodplain	60	30	30
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	11	0	-4

RIPARIAN ZONE VEGETATION SUMMARY

REACH 12

REACH 12

Summary of Riparian Zone (0-30m)

4 transects

Total hardwoods/1000	290
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	2.3	0.0	0.0	0.0	0.0	0.0	2.3
15-30cm	0.0	0.8	0.0	0.0	0.0	0.0	0.0	0.8
30-50cm	0.0	1.3	0.0	0.0	0.0	0.0	0.0	1.3
50-90cm	0.0	0.0	0.0	0.5	0.0	0.0	0.0	0.5
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.0	4.3	0.0	0.5	0.0	0.0	0.0	1.6

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	34	1	0
Shrub cover	4	0	0
Grass/forb cover	88	100	100

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	0	0	0
High terrace	38	50	63
Low terrace	0	0	0
Floodplain	63	50	38
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	2	1	1

RIPARIAN ZONE VEGETATION SUMMARY

REACH 13

REACH 13

Summary of Riparian Zone (0-30m) 4 transects

Total hardwoods/1000	594
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	4.8	0.0	1.0	0.0	1.0	0.0	6.8
15-30cm	0.0	2.5	0.0	0.0	0.0	0.0	0.0	2.5
30-50cm	0.0	0.3	0.0	0.0	0.0	0.0	0.0	0.3
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.3	0.0	0.0	0.0	0.0	0.0	0.3
Total/100m2	0.0	7.8	0.0	1.0	0.0	1.0	0.0	3.3

Canopy closure and ground cover

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)	(%)	(%)	(%)	(%)	(%)
Canopy closure	45		12		16	
Shrub cover	4		1		4	
Grass/forb cover	39		45		40	

Predominant landform in each zone

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)	(%)	(%)	(%)	(%)	(%)
Hillslope	0		0		0	
High terrace	63		75		75	
Low terrace	0		0		0	
Floodplain	38		25		25	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	0		0		0	
Riprap	0		0		0	
Surface slope (%)	7		0		0	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 14

REACH 14

Summary of Riparian Zone (0-30m) 4 transects

Total hardwoods/1000	564
Total conifers/1000 ft	213
Total conifers >20" dbh/1000 ft	168
Total conifers >35" dbh/1000 ft	152

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	6.8	0.0	0.0	0.8	0.0	0.8	6.8
15-30cm	0.0	1.8	0.0	0.0	0.0	0.0	0.0	1.8
30-50cm	0.0	0.8	0.0	0.0	0.0	0.0	0.0	0.8
50-90cm	0.0	0.0	0.3	0.0	0.0	0.0	0.3	0.0
>90cm	2.5	0.0	0.0	0.0	0.0	0.0	2.5	0.0
Total/100m2	2.5	9.3	0.3	0.0	0.8	0.0	1.2	3.1

Canopy closure and ground cover

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	51		15		6	
Shrub cover	41		35		25	
Grass/forb cover	34		54		75	

Predominant landform in each zone

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	38		50		50	
High terrace	38		38		50	
Low terrace	0		0		0	
Floodplain	0		0		0	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	25		13		0	
Riprap	0		0		0	
Surface slope (%)	29		40		43	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 16

REACH 16

Summary of Riparian Zone (0-30m)

2 transects

Total hardwoods/1000	1615
Total conifers/1000 ft	0
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	22.5	0.0	0.0	0.0	0.0	0.0	22.5
15-30cm	0.0	1.0	0.0	0.0	0.0	0.0	0.0	1.0
30-50cm	0.0	2.0	0.0	1.0	0.0	0.0	0.0	3.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.0	25.5	0.0	1.0	0.0	0.0	0.0	8.8

Canopy closure and ground cover

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Canopy closure	35	1	0
Shrub cover	43	14	0
Grass/forb cover	74	86	100

Predominant landform in each zone

	Zone 1 0-10 meters (%)	Zone 2 10 - 20 meters (%)	Zone 3 20 - 30 meters (%)
Hillslope	25	25	25
High terrace	0	50	50
Low terrace	0	0	0
Floodplain	75	25	25
Wetland/meadow	0	0	0
Stream channel	0	0	0
Roadbed/Railroad	0	0	0
Riprap	0	0	0
Surface slope (%)	18	10	10

RIPARIAN ZONE VEGETATION SUMMARY

REACH 17 **REACH 17**

Summary of Riparian Zone (0-30m) 2 transects

Total hardwoods/1000	640
Total conifers/1000 ft	152
Total conifers >20" dbh/1000 ft	61
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1		Zone 2		Zone 3		Zones 1-3	
	0-10 meters		10 - 20 meters		20 - 30 meters		0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.0	4.5	0.0	1.5	0.0	0.0	0.0	6.0
15-30cm	0.0	3.0	0.5	0.0	0.0	0.0	0.5	3.0
30-50cm	0.0	1.5	0.0	0.0	1.0	0.0	1.0	1.5
50-90cm	0.0	0.0	1.0	0.0	0.0	0.0	1.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	0.0	9.0	1.5	1.5	1.0	0.0	0.8	3.5

Canopy closure and ground cover

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	31		34		33	
Shrub cover	44		48		60	
Grass/forb cover	31		28		40	

Predominant landform in each zone

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	50		75		75	
High terrace	25		0		25	
Low terrace	0		0		0	
Floodplain	0		0		0	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	25		25		0	
Riprap	0		0		0	
Surface slope (%)	23		29		29	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 18

REACH 18

Summary of Riparian Zone (0-30m)

1 transects

Total hardwoods/1000	366
Total conifers/1000 ft	305
Total conifers >20" dbh/1000 ft	61
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters		Zones 1-3 0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	1.0	2.0	0.0	4.0	0.0	0.0	1.0	6.0
15-30cm	0.0	0.0	0.0	0.0	2.0	0.0	2.0	0.0
30-50cm	0.0	0.0	1.0	0.0	0.0	0.0	1.0	0.0
50-90cm	0.0	0.0	0.0	0.0	1.0	0.0	1.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	1.0	2.0	1.0	4.0	3.0	0.0	1.7	2.0

Canopy closure and ground cover

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	38		78		75	
Shrub cover	65		85		90	
Grass/forb cover	15		15		10	

Predominant landform in each zone

	Zone 1 0-10 meters		Zone 2 10 - 20 meters		Zone 3 20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	50		50		50	
High terrace	50		50		50	
Low terrace	0		0		0	
Floodplain	0		0		0	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	0		0		0	
Riprap	0		0		0	
Surface slope (%)	45		45		45	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 19 **REACH 19**

Summary of Riparian Zone (0-30m) 2 transects

Total hardwoods/1000	1433
Total conifers/1000 ft	853
Total conifers >20" dbh/1000 ft	30
Total conifers >35" dbh/1000 ft	30

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1		Zone 2		Zone 3		Zones 1-3	
	0-10 meters		10 - 20 meters		20 - 30 meters		0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	3.0	8.5	4.0	14.5	5.0	0.0	12.0	23.0
15-30cm	0.0	0.5	1.0	0.0	0.0	0.0	1.0	0.5
30-50cm	0.5	0.0	0.0	0.0	0.0	0.0	0.5	0.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.5	0.0	0.5	0.0
Total/100m2	3.5	9.0	5.0	14.5	5.5	0.0	4.7	7.8

Canopy closure and ground cover

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	36		46		38	
Shrub cover	28		19		24	
Grass/forb cover	26		24		36	

Predominant landform in each zone

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	25		25		50	
High terrace	25		25		25	
Low terrace	0		0		0	
Floodplain	25		25		0	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	25		25		25	
Riprap	0		0		0	
Surface slope (%)	12		13		6	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 21

REACH 21

Summary of Riparian Zone (0-30m) 4 transects

Total hardwoods/1000	1311
Total conifers/1000 ft	503
Total conifers >20" dbh/1000 ft	15
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1		Zone 2		Zone 3		Zones 1-3	
	0-10 meters		10 - 20 meters		20 - 30 meters		0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	0.8	8.3	1.8	6.3	1.0	4.3	3.5	18.8
15-30cm	1.0	1.0	0.3	0.5	0.8	0.0	2.0	1.5
30-50cm	0.3	0.0	1.3	1.3	1.0	0.0	2.5	1.3
50-90cm	0.0	0.0	0.3	0.0	0.0	0.0	0.3	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	2.0	9.3	3.5	8.0	2.8	4.3	2.8	7.2

Canopy closure and ground cover

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	31		46		46	
Shrub cover	38		61		64	
Grass/forb cover	41		36		33	

Predominant landform in each zone

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	13		25		25	
High terrace	25		50		50	
Low terrace	0		0		0	
Floodplain	50		25		25	
Wetland/meadow	0		0		0	
Stream channel	13		0		0	
Roadbed/Railroad	0		0		0	
Riprap	0		0		0	
Surface slope (%)	13		19		19	

RIPARIAN ZONE VEGETATION SUMMARY

REACH 22	REACH 22
Summary of Riparian Zone (0-30m)	
	1 transects
Total hardwoods/1000	975
Total conifers/1000 ft	488
Total conifers >20" dbh/1000 ft	0
Total conifers >35" dbh/1000 ft	0

Average number of trees in a 5-meter wide band

Diameter class (cm)	Zone 1		Zone 2		Zone 3		Zones 1-3	
	0-10 meters		10 - 20 meters		20 - 30 meters		0-30 meters	
	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood	Conifer	Hardwood
3-15cm	4.0	14.0	0.0	0.0	2.0	0.0	6.0	14.0
15-30cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
30-50cm	2.0	0.0	0.0	2.0	0.0	0.0	2.0	2.0
50-90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
>90cm	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total/100m2	6.0	14.0	0.0	2.0	2.0	0.0	2.7	5.3

Canopy closure and ground cover

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Canopy closure	73		3		10	
Shrub cover	75		8		10	
Grass/forb cover	8		48		50	

Predominant landform in each zone

	Zone 1		Zone 2		Zone 3	
	0-10 meters		10 - 20 meters		20 - 30 meters	
	(%)		(%)		(%)	
Hillslope	0		0		50	
High terrace	50		50		0	
Low terrace	0		0		0	
Floodplain	50		0		0	
Wetland/meadow	0		0		0	
Stream channel	0		0		0	
Roadbed/Railroad	0		50		50	
Riprap	0		0		0	
Surface slope (%)	2		1		48	

Summary of Riparian Zone (0-30m) for all reaches**78 transects****Summary of riparian zone (0-100 feet) extrapolated to 1,000 feet along stream**

Total hardwoods/1000	720
Total conifers/1000 ft	91
Total conifers >20" dbh/1000 ft	13
Total conifers >35" dbh/1000 ft	9

Average number of trees in a 5-m wide band

Diameter class (cm)	Zones 1-3	
	<u>0-30 meters</u>	
	<u>Conifer</u>	<u>Hardwood</u>
3-15cm	0.8	9.9
15-30cm	0.2	1.3
30-50cm	0.2	0.4
50-90cm	0.1	0.1
>90cm	0.1	0.1

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
1	1	GL	00	150	FC	427154E/5028752N; RIP 1	START 427154/5028752
1	2	GL	00	300		T=18C	BEDROCK=HARDPAN
1	4	GL	00	600			HARDPAN
1	5	GL	00	750	CS/, SD/	CS-/BLDRS, SD/-PUMP	PLACED BOULDERS
1	8	GL	00	1150	AM	AM=W.TOAD; RIP 2; 427737/5028610	WESTERN TOAD
1	10	GL	00	1450	WL	WL-NUTRIA/OTTER?	NUTRIA
1	11	GL	00	1600	AM	BULLFROG	NUTRIA HOLE IN BANK
1	12	GL	00	1750			HARDPAN
1	15	GL	00	2150		428223E/5028118N; RIP 3	
1	16	GL	00	2300			HARDPAN
1	17	GL	00	2450	AM	AM-BULLFROG	FROG; HARDPAN
1	18	GL	00	2600			HARDPAN
1	19	GL	00	2750			HARDPAN
1	20	GL	00	2900			HARDPAN
1	21	GL	00	3000			HARDPAN
1	22	GL	00	3150	BV	BV-CHEWS; 428462E/5027148N; RIP 4	HARDPAN
1	23	GL	00	3300	AM	BULLFROG (BF)	BF, W.TOAD; HARDPAN
1	24	GL	00	3450	AM, WL	MUSKRAT	BF; MUSKRAT; HARDPAN
1	25	GL	00	3600	AM, WL	BULLFROG CALL	BF; GREAT HORNED OWL; HARDPAN
1	27	GL	00	3900			HARDPAN
1	28	GL	00	4000			HARDPAN
1	29	GL	00	4150	AM	11T 428590E/5027772N; RIP 5	HARDPAN, BULLFROGS
1	30	GL	00	4300			HARDPAN
1	31	GL	00	4450	WL	HORSE IN RIP, HARDPAN	MALLARD, CINNAMON TEAL
1	32	GL	00	4600		WILLOWS ALONG BANK	HORSES NEAR STREAM; HARDPAN
1	33	GL	00	4750		SOME MARSHY AREAS	HP=HARDPAN
1	34	GL	00	4900			HP
1	35	GL	00	5000			HP
1	36	GL	00	5150		11T 428837E/5028133N; RIP 6	HP
1	37	GL	00	5300	CE/		HP
1	38	GL	00	5450			HP
1	39	GL	00	5600	WL		CALF ELK, HP
1	40	GL	00	5750	AM	BF	HP
1	41	GL	00	5900			HP
1	42	GL	00	6000			HP
1	43	GL	00	6150	WL	11T 429208E/5028066N; RIP 7	BARN OWL; HP
1	44	GL	00	6300			HP
1	45	GL	00	6450			HP
1	46	GL	00	6600			HP
1	47	GL	00	6750			HP
1	48	GL	00	6900			HP
1	49	GL	00	7000			HP
1	50	GL	00	7150	AM	11T 429275E/5027386N; RIP 8; BF	HP'; INVASIVE LILLY IN RIP ZONE
1	51	GL	00	7300		WATER TEMP 23°C	HP
1	52	GL	00	7450			HP
1	53	GL	00	7600			HP
1	54	GL	00	7750			HP
1	55	GL	00	7900			HP
1	56	GL	00	8000		DEAD CARP	HP
1	57	GL	00	8150		11T 0428908E/5026636N; RIP 9	
1	59	GL	00	8450	BV		CHEWED STICKS
1	61	GL	00	8750			HP
1	62	GL	00	8800			HP
1	63	GL	00	8930	CE/	DWNSTRM END OF OXBOW	HEADGATE ON OXBOW; HP
1	64	GL	00	9080	WL	1T 429607E/5026329N; RIP 10	HP, RACCOON

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
1	65	GL	00	9230			HP
1	66	GL	00	9380			HP
1	67	GL	00	9530			HP
1	68	GL	00	9680			HP
1	69	GL	01	9830			HP
1	70	AL	10			DRY, 80% GRASS; SEASONALLY WET	
1	71	GL	00	9930			HP
1	72	GL	00	10080	WL	WL TRAIL; 11T 430177E/5026638N	HP, MULE DEER DOE, RIP 11
1	73	GL	00	10240	BC, /CS	MARKET LANE; HP; PLACED BOULDERS	
1	75	GL	00	10450	CE/, SS	CE/-SPILLING FLOW	.7M DROP FROM CULVERT
1	76	GL	00	10600	BV, WL	BEDDED DOE; BV	CHEWED STICKS
1	77	GL	00	10750	WL	WL TRAIL/	GAME TRAIL; HP
1	79	GL	00	11050		11T 430388E/5026278N; RIP 12	HP
1	80	GL	00	11200			HP
1	81	GL	00	11350			HP
1	82	GL	00	11500	WL		GAME TRAIL; HP
1	83	GL	00	11650	FC		OPERATING WELL ON RT BANK
1	84	GL	00	11800		CATTLE USE ON BANK; DEAD NORTHERN PIKE MINNOW; RIP 19	
1	85	GL	00	11900		CATTLE IN STREAM	END REACH
2	86	GL	00	12050		11T 430408E/5026048N; RIP 13	SIGN OF CATTLE IN RIP; HP
2	87	GL	00	12200	BV,WL		OLD BRIDGE XING
2	88	GL	00	12260			HP
2	89	GL	00	12290		OXBOW LF BANK ENTRY	OLD CULVERT MATERIAL DWNSTRM
2	90	GL	00	12380			HP
2	91	GL	00	12410		OXBOW EXIT	OXBOW; HP
2	92	GL	00	12560			HP
2	93	GL	00	12710			SIGN OF CATTLE IN RIPARIAN
2	94	GL	00	12860	FC		CATTLE IN RIPARIAN
2	95	GL	00	12960			HP
2	96	GL	00	13110		11T 430598E/5025357N; RIP 14	HP
2	97	GL	00	13260	AM		BF
2	98	GL	00	13410	WL		DEER ON BANK
2	99	GL	00	13560	BV		CHEWED STICKS
2	100	GL	00	13710	SS,WL		NUTRIA HOLES IN BANK
2	102	GL	00	13960		T=24°C	HP
2	103	GL	00	14110	WL	11T 431290E/5025310N; RIP 15	GAME TRAIL; 3 BARN OWLS
2	104	GL	00	14260			HP
2	105	GL	00	14410		CATTLE USE NEXT TO STREAM	
2	107	GL	00	14710	WL		GAME TRAIL
2	110	GL	00	15110	BV, FC	RIP 16	HP
2	111	GL	00	15225		11T 432084E/5025301N-RIP	
2	112	GL	01	15260			HP
2	113	AL	10			11T 432040E/5025159N; OXBOW BLOCKED UPSTRM	
2	114	AL	10		AM		MANY BF TADPOLES
2	115	GL	00	15305	WL		GAME TRAIL; HP
2	116	GL	00	15455	WL	OXBOW UPSTRM; 431998/5025130	MUSKRAT BURROW; HP
2	117	GL	00	15605	WL		3 GREAT HORNED OWL; HP
2	118	GL	00	15755	WL		GREAT HORNED OWL; HP
2	120	GL	00	16065		11T 431371E/5025087N; RIP 17	
2	121	GL	00	16215	WL		MUSKRAT
2	122	GL	00	16365	BV		HP
2	123	GL	00	16515	BV, /SS		HP
2	124	GL	00	16665	WL		MUSKRAT; HP
2	125	GL	00	16815			HP
2	126	GL	00	16915	AM		W.TOAD; HP

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
2	127	GL	00	17065	BV, AM	11T 430909E/5024744N; RIP 18	FROG; HP
2	128	GL	00	17215	BV, BC	BC 11T 430947/5024701	HP
2	129	GL	00	17365			HP
2	130	GL	00	17515	WL	DEAD ELK IN RIP	DEAD ELK LF BANK; HP
2	131	GL	00	17665	WL, BV		ANIMAL TRAIL; HP
2	132	GL	00	17815	AM		BULLFROG; HP
2	133	GL	00	17915	WL		GAME TRAIL; HP
2	134	GL	00	18065	WL	T=22.5°C; RIP 19	GAME TRAIL; HP
2	135	GL	00	18215	BV	11T 431512E/5024629N-NAD 27	HP
2	136	GL	00	18365			HP
2	137	GL	00	18515	WL		GAME TRAIL; HP
2	138	GL	00	18665			HP
2	140	GL	00	18915	FC		
2	141	GL	00	19065		11T 431676E/5024339N; RIP 20	
2	142	GL	00	19215	/CE,BV,/SS	HIGH TERRACE ERODING	HP
2	143	GL	00	19365			HP
2	146	GL	00	19815	SS/		HP
2	147	GL	00	19915	BC	HOUSE/ WITH TREES NEAR	
2	148	GL	00	20065	BC	RIP 21	HP; WATCH TOWER
2	149	GL	00	20215	CS	T=22.5°C	
2	150	SS	00	20215	CS	H=2.0M; 432206E/5024368N	END REACH
3	151	GL	00	20303	CS/	START AT ELMER'S DAM	CONCRETE AT ELMER'S DAM
3	152	GL	00	20453	CS/		CONCRETE FROM OLD BC
3	153	GL	00	20603		T=17°C	
3	154	GL	00	20753	WL		BARN OWL
3	155	GL	00	20903	AM		BULLFROG
3	156	GL	00	21053	AM		BULLFROGS
3	157	GL	00	21203	AM		DOWNSTREAM END OF OXBOW
3	158	GL	00	21353	/CE		.5 DIAM
3	159	GL	00	21453	BV		
3	160	GL	00	21603		T=17°C	
3	161	GL	00	21753	BV,AM,CE/		.5M DIAM, 1.5M DROP; BFROGS
3	162	GL	00	21903	BV		OXBOW ON RT OF BANK
3	163	GL	00	22053	AM	11T 433715E/5023377N	BULLFROGS
3	164	GL	00	22203			DIVERSION
3	165	GL	00	22353	WL		RIVER OTTER
3	166	GL	00	22420		ROB'S TRANSECT	
3	167	GL	00	22570	AM		BULLFROG
3	168	GL	00	22720	AM		BULLFROG
3	171	GL	11			TRIB T=16°C	TRIB, OXBOW
3	172	GL	01	23170	TJ/		
3	173	GL	00	23320	AM, BV	T=15°C	BULLFROG
3	174	GL	00	23470	AM		BULLFROGS
3	175	GL	00	23620	AM		BULLFROGS
3	176	GL	00	23770	AM		MANY BULLFROGS
3	177	GL	00	23920	BC, AM		BOOTHLANE, BULLFROGS
3	178	GL	00	24020	AM	MANY BULLFROGS; SCHOOL CATFISH	
3	179	GL	00	24170	BV		
3	180	GL	00	24320	BC,WL,CE/	0.4M DIAM WITH FLAP VALVE; WOOD DUCK	
3	181	GL	00	24470	BV,CE/		0.3M DIAM WITH FLAP VALVE
3	182	GL	00	24620	BV,WL		IRRIGATION CANAL ON LEFT
3	184	GL	00	24920	AM		BIG BULLFROG
3	185	GL	00	25020	BV		SUBSTRATE ESTIMATED
3	186	GL	00	25170	BV		
3	189	GL	00	25620	AM		BULLFROGS AND TADPOLES

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
3	190	GL	00	25770	/CE		UPDTREAM END OF OXBOW-.4M DIAM
3	191	GL	00	25920	AM		LG BULLFROG
3	192	GL	00	26020	BV		
3	193	GL	00	26170			HARDPAN
3	195	GL	00	26470	BV		EST-COULD NOT FEEL BOTTOM
3	196	GL	00	26620	CE/		.4M DIAM; UPSTREAM END OXBOW
3	197	GL	00	26770	WL	GREAT BLUE HERON, HARDPAN CLAY	
3	198	GL	00	26920	BV		
3	199	GL	00	27020	BV		
3	201	GL	00	27320	AM,/CE	BULLFROG; OXBOW HAS FLAP VALVE	
3	202	GL	00	27470			HARDPAN
3	204	GL	00	27770			HARDPAN
3	205	GL	00	27920			HARDPAN
3	206	GL	00	28020	WL		2 DEER
3	208	GL	00	28320	BV		
3	209	GL	00	28470	BV		
3	210	GL	00	28620	WL,AM		DEAD FAWN; BULLFROG
3	211	GL	00	28770	BV		
3	212	GL	00	28920	BV		
3	213	GL	00	29020	BV,WL	T=17°C	HARDPAN
3	214	GL	00	29170	BV	11T 433670E/5020320N	HARDPAN
3	215	GL	00	29320	BV		
3	217	GL	00	29620			HARDPAN
3	218	GL	00	29770			HARDPAN
3	219	GL	00	29920			HARDPAN
3	220	GL	01	30070	TJ/	END REACH	TRIB
3	221	GL	11			TRIB T=15°C	TRIB, UNNAMED FROM WARM CR
4	222	GL	00	30182			HARDPAN
4	223	GL	00	30332		T=17°C	HARDPAN
4	224	GL	00	30482	WL		2 BARN OWLS
4	226	GL	00	30782			HARDPAN
4	227	GL	00	30932			HARDPAN
4	228	GL	00	31082	WL		BARN OWL
4	229	GL	00	31232	BV		
4	230	GL	00	31382	BV,WL		3 BARN OWLS
4	231	GL	00	31482	BV		
4	232	GL	00	31632			HARDPAN
4	234	GL	00	31932	WL	T=18°C	BARN OWL
4	235	GL	00	32082			HARDPAN
4	236	GL	00	32232			HARDPAN
4	237	GL	00	32382		11T 432707E/5019858N	
4	238	GL	00	32482		11T 432217E/5019173N	
4	242	GL	00	33082	AM		BULLFROGS, HARDPAN
4	243	GL	00	33232			HARDPAN
4	244	GL	00	33382			HARDPAN
4	245	GL	00	33482		T=18°C	
4	246	GL	00	33632	WL		WOODDUCK, HARDPAN
4	247	GL	00	33782			HARDPAN
4	248	GL	00	33932	/BV,BC,CS/CS		COVE HWY, CS/CS-CONCRETE
4	249	GL	00	34082	BV,AM		BULLFROG, HARDPAN
4	250	GL	00	34232			HARDPAN
4	251	GL	00	34382		11T 432014E/5018728N	
4	252	GL	00	34482	BV		
4	253	GL	00	34632		T=17°C	HARDPAN
4	254	GL	00	34782	BV		

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
4	255	GL	00	34932			HARDPAN
4	256	GL	00	35082			HARDPAN
4	258	GL	00	35382			HARDPAN
4	260	GL	00	35682	BV		
4	261	GL	00	35832	TJ	END REACH, OLD GRANDE RONDE	HARDPAN
5	262	GL	00	35922	SD/	11T 432067E/5017936N	HARDPAN
5	263	GL	00	36022	BV		HARDPAN
5	264	GL	00	36172	BV		HARDPAN
5	265	GL	00	36322	BV		HARDPAN
5	266	GL	00	36472	BV		HARDPAN
5	267	GL	00	36622	BV		HARDPAN
5	268	GL	00	36772	BV		HARDPAN
5	269	GL	00	36922	BV,WL		GREAT HORNED OWL
5	270	GL	00	37022	BV,WL	T=15°C; 11T 432021E/5017253N	GREAT HORNED OWL
5	271	GL	00	37172	BV		OXBOW/
5	272	GL	00	37322	BV		HARDPAN
5	273	GL	00	37472	BV		HARDPAN
5	274	GL	00	37622	WL,BV		TRAILS, CORMORANT, HARDPAN
5	275	GL	00	37772	BV		
5	276	GL	00	37922	BV	GPS OXBOW	OXBOW ENTERS ON RT
5	277	GL	00	38072	WL	T=14.5	DEER IN RIP; HARDPAN
5	278	GL	00	38222	BV	11T 432995E/5016594N	GEKELER LANE
5	279	GL	00	38372	BV		
5	280	GL	00	38522	BV		HARDPAN
5	281	GL	00	38672	BV		HARDPAN
5	282	GL	01	38822	TJ	HAWTHORN, MILL CR, END REACH	MILL CR, HARDPAN
5	283	GL	11		TJ/	11T 432086E/5016661N; T=14.5°C-MILL °CR	
6	284	GL	00	38955	BV,WL		TURTLE, HARDPAN
6	285	GL	00	39055	BV		HARDPAN
6	286	GL	00	39205	BV,WL	11T 431472E/5016513N	TURTLE-ORANGE ON BACK
6	287	GL	00	39355	BV		HARDPAN
6	288	GL	00	39505	BV		HARDPAN
6	289	GL	00	39655	BV,AM		BULLFROG, TADPOLES
6	290	GL	00	39805	BV		HARDPAN
6	291	GL	00	39955	BV		GARBAGE IN CR; HARDPAN
6	292	GL	00	40035	BV		HARDPAN
6	293	GL	00	40185	BV		DEAD JUV CARP, BV DEN; HARDPAN
6	294	RI	00	40213	BV		HARDPAN
6	295	SD	00	40215	BV		BV DAM
6	296	GL	00	40370	BV		BV DAM, HARDPAN
6	297	GL	00	40520	BV		HARDPAN
6	298	GL	00	40670	WL,BV		GREAT HORNED OWL; HARDPAN
6	299	GL	00	40820			HARDPAN
6	300	GL	00	40970	BV	T=17.5; 11T 430797E/5016607N	HARDPAN
6	301	GL	00	41070	WL		HAWK AND OWL; HARDPAN
6	302	GL	00	41220	WL		DEER IN RIP
6	303	GL	00	41370			HARDPAN
6	304	GL	00	41520	BV		HARDPAN
6	305	GL	00	41670	BV		HARDPAN
6	306	GL	00	41820	WL,BV	T=14°C	BV DEN, OWL, HARDPAN
6	307	GL	00	41970	WL	GREAT HORNED OWL,CINNAMON TEAL, 11T 430520E/5016666N	
6	308	GL	00	42070			HARDPAN
6	309	GL	00	42220	WL		GREAT HORNED OWL, HARDPAN
6	310	GL	00	42370			HARDPAN
6	311	GL	00	42520	WL,BV		GREAT HORNED OWL

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
6	312	GL	00	42670	SD,BV		HARDPAN
6	313	GL	00	42820			HARDPAN
6	314	GL	00	42970	WL,BV	END REACH	MUSKRAT, HARDPAN
7	315	GL	00	43120	/CS,BC	GODLEY LANE BRIDGE	HARDPAN, BOULDERS
7	316	PD	00	43236			ACW=10; .1 AT DEEPEST
7	317	GL	00	43335		T=28°C	HARDPAN
7	318	GL	00	43485			DEAD MUSKRAT, DEAD JUV CARP
7	319	PD	00	43536			HARDPAN
7	320	GL	00	43592			HARDPAN
7	321	GL	00	43742	BV		HARDPAN
7	322	GL	00	43892	BV,AM	MANY LARGE FEMALE BULLFROGS	8-10 BULLFROGS
7	323	PD	00	43957			ACW=10.5; LARGE CATTLE AREA
7	324	GL	00	44052			HARDPAN
7	325	PD	00	44115		11T 0430022E/50164994N	ACW=9.3M
7	326	GL	00	44265	BV		DEAD JUV, CARP, HARDPAN
7	327	GL	00	44365			HARDPAN
7	328	GL	00	44515			HARDPAN
7	330	GL	00	44815	/SD,CE,CS		HARDPAN, CATTLE PATH
7	331	GL	00	44965	BV		HARDPAN
7	332	GL	00	45085			HARDPAN
7	333	PD	00	45149	BV		ACW=9.5M
7	334	GL	00	45266	BV	11T 429447E/5016910N	T=27°C
7	335	GL	00	45343	AM		ACW=9; BULLFROGS
7	336	GL	00	45489	WL, BV	T=34°C	GREAT HORNED OWL, HARDPAN
7	337	GL	00	45639	BV		HARDPAN
7	338	PD	00	45707			ACW=9M
7	339	GL	00	45768	/WL		MUSKRAT HOLES, HARDPAN
7	340	PD	00	45816			ACW=8; .1 DEEPEST
7	341	GL	00	45915	WL		TRAIL, HARDPAN
7	342	PD	00	46015			HARDPAN
7	343	GL	00	46080			HARDPAN
7	344	PD	00	46132		11T 429028E/5016572N	
7	345	GL	00	46316	BV	BULLHEAD CATFISH	BROWN BULLHEAD; DEAD CARP
7	346	GL	00	46380		T=35C; 11T 0428423E/5016755N	CATTLE/
7	347	GL	00	46460			DEEP POCKET; 1.1 DEEP
7	348	PD	00	46542		11T 428427E/5016751N-PDA	
7	350	GL	00	46757			DEAD CARP; HARDPAN
7	351	PD	00	46823			MAX D=0.28; ACW=9.5
7	352	GL	00	46856			HARDPAN
7	353	GL	00	46920			HARDPAN
7	355	GL	00	47115	BV		OVERFLOW PIPE INTO CR
7	356	PD	00	47163		T=33°C	ACW=8.5; MAX D=.4
7	358	GL	00	47359	BV	BV DEN ON RT BANK	BV DEN; HARDPAN
7	359	DU	00	47407			ACW=9M
7	360	PD	00	47557	TJ	MCALISTER SLOUGH	ACW=9M
7	361	GL	11		/TJ	MCALISTER SLOUGH TAKES WATER	MCCALISTER SLOUGH; HARDPAN
7	362	GL	01	47579	BV	FROM CATHERINE, END REACH, LOTS OF BV ACTIVITY	
8	363	GL	00	47708			HARDPAN
8	364	GL	00	47858		11T 428097E/5017030N	HARDPAN
8	365	RI	00	47907			METRIC
8	366	GL	00	48042		N. PIKEMINNOW; T=24°C	N. PIKEMINNOW
8	367	GL	00	48192	WL	GREAT BLUE HERON, DEAD CARP, HARDPAN	
8	368	RI	00	48333	BV,WL		GREAT HORNED OWL; 3 DEAD CARP
8	369	GL	00	48402			HARDPAN
8	370	GL	00	48552	DJ		HARDPAN

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
8	371	RI	00	48617		COWS IN STREAM	DEAD JUV °CARP; T=20°C
8	372	GL	00	48767	FC	11T 427860E/5016683N	
8	373	GL	00	48917	/CS	FLOOD EST-VERY WIDE	HARDPAN, CONCRETE SLABS
8	374	GL	00	49017		T=23.5°C; 11T 427657E/5015770N	HARDPAN
8	375	GL	00	49167		CORMORANTS, EGRETS, ROOKERY HERONS, HARDPAN CLAY	
8	376	GL	00	49317	/CS		HERON, CORMORANT; BLDRS
8	377	GL	00	49467	DJ,FC	CORMORANTS, HERONS	CORMORANT, ROOKERY
8	378	GL	00	49617	BV		
8	380	GL	00	49917	BV	SEVERAL DEAD JUV CARP	DEAD CARP, HARDPAN
8	381	GL	00	50067	BV	FPW EST- VERY WIDE	DEAD CARP, HARDPAN
8	382	GL	00	50167	WL,AM		TREE FROG, BARN OWL
8	383	GL	00	50317		2 BARN OWLS	
8	384	GL	00	50467			CATTLE TRAIL/
8	386	GL	00	50767	BV		HARDPAN
8	387	GL	00	50917	BV,AM	DEAD CATFISH; TRASH	BULLFROG, HARDPAN
8	388	GL	01	51067	/TJ	END REACH	LADD CREEK
8	389	GL	11			ACW=2.55M	LADD CREEK
8	390	RI	11			T=24°C	HARDPAN
8	391	SD	11		BV	STEP H=.4M	HARDPAN
9	392	GL	00	51187	BV	FPW EST-VERY WIDE	BEAVER DEN
9	393	GL	00	51337	BV	BV DEN/	3 BV DENS
9	394	GL	00	51487			DEAD CARP, HARDPAN
9	395	GL	00	51637			HARDPAN
9	396	GL	00	51787			HARDPAN
9	397	GL	00	51937		BC=WILKINSON LANE	
9	398	RI	00	51966	BC,CS/	426578E/5014429N	BOULDERS, HARDPAN
9	400	RI	01	52116			HARDPAN
9	401	RI	00	52266	AM	NAD 27-11T 426973E/5013574N; COWS IN CR, TREE FROG, HARDPAN	
9	403	GL	00	52544	DJ,/BV		HARDPAN
9	404	GL	00	52694	AM		TREE FROG
9	405	GL	00	52844		GREAT HORNED OWL	HARDPAN
9	406	RI	00	52909			HARDPAN
9	407	GL	00	53041			HARDPAN
9	408	GL	00	53191		T=22.5°C	HARDPAN=BEDROCK
9	410	GL	00	53431		11T 427312E/5012690N-NAD 27	HARDPAN
9	412	RI	00	53630		T=21°C; COWS IN CREEK	HARDPAN
9	413	SR	00	53635		HARDPAN	STEP OVER HARDPAN
9	415	GL	00	53836			HARDPAN
9	416	GL	00	53986			DEAD REDSIDE SHINER
9	417	GL	00	54136	DJ		HARDPAN
9	418	GL	00	54286	/SS,AM		CATTLE, TREE FROG
9	419	GL	00	54436			HARDPAN, METRIC
9	420	GL	00	54586			CATTLE TRAIL/
9	421	RI	00	54627		T=21.5°C	
9	422	BW	10		WL		GREAT HORNED OWL
9	425	GL	00	54768	BV	11T 427573E/5012010N; POSSIBLY BLUEGILL	
9	426	GL	00	54918	CS/		HARDPAN
9	427	GL	00	55068	BC,CE/,CS/	DEAD ADULT CHINOOK	BLDRS
9	428	GL	00	55218	/SS		HARDPAN
9	429	GL	00	55318			HARDPAN, T=22°C METRICS
9	430	GL	00	55468		11T 427108E/5011321N	HARDPAN
9	431	GL	00	55618		DEAD JUV. MALLARD	DEAD JUV MALLARD, HARDPAN
9	432	GL	00	55768			HARDPAN, SMALL MOUTH BASS
9	435	GL	01	55921	BV		HARDPAN, CLAMS, MUSSELLS
9	436	SC	00	55931		T=22°C	

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
9	437	PP	00	55939			MANY JUV FISH
9	438	SS	00	55945	SS,CS/CS	LOWER DAVIS DAM	END REACH
10	439	MX	00	59334		DAVIS DAM-MILLER LANE	NOT SURVEYED
11	440	GL	00	59484	FC		BRK=HARDPAN
11	441	GL	00	59634	/CS		CONCRETE SLAB, HARDPAN
11	442	GL	00	59784	BV		HARDPAN
11	443	GL	00	59793			HARDPAN
11	444	GL	00	59806	BV,WL		MUSKRAT HOLE, HARDPAN
11	445	GL	00	59836	BV		HARDPAN
11	446	SC	00	59840	BV		
11	447	GL	01	59848	/TJ,CS/CS	11T 428197E/5007735N	PYLES CR, RIPRAP, END REACH
11	448	GL	11		BV	T=18°C	PYLES CREEK
12	449	GL	00	59998	BV		BV DEN, HARDPAN
12	450	GL	00	60148			HARDPAN
12	451	GL	00	60308	BV		DEBRIS PILE W/JUV FISH
12	452	RI	00	60327	BV		
12	453	GL	00	60387	BV		
12	455	GL	00	60425		T=13.5C	
12	457	GL	00	60513	CS/		CONCRETE
12	458	RI	00	60555		11T 428508E/5007564N	
12	459	SP	00	60576	/CS		CARS AND RIPRAP; DEPTH EST.
12	460	RI	00	60637	BV		HARDPAN
12	461	SP	00	60660	AM	GREEN TREE FROG	TREE FROG, IRRIGATION DITCH/
12	462	RI	00	60714			HARDPAN
12	463	LP	00	60818	BV		
12	465	SP	00	60850	AM		TREE FROG
12	466	RI	01	60887	CS/		CONCRETE
12	468	BW	10		CS/,AM	COLUMBIA SPOTTED FROG	COLUMBIA SPOTTED FROG
12	469	GL	00	60946			HARDPAN
12	470	SC	00	60950	FC		
12	471	LP	00	61034	UD/,CS/		CONCRETE
12	473	LP	00	61114	CS/	EST-LEFT BANK HEFFNER PROP	CONCRETE; DEPTH EST.
12	474	RI	00	61129		NO ACCESS	
12	475	LP	00	61170	CS/BV		RIPRAP
12	476	SC	00	61175	BV		
12	477	LP	00	61227	BC,CS/CS	11T 428903E/5007349N	PRIVATE BC; RIPRAP
12	478	RI	00	61246	BV	T=14°C; FLOW-MF	
12	479	LP	00	61278	BV		
12	480	SC	00	61288	BV	AGRICULTURE (AG)/HEAVY GRAZING (HG) ,GRASS/HARDWOOD 50-90CM DBH	
12	481	LP	00	61347	/CS		OIL DRUMS AND COBBLE
12	482	RI	00	61368		FLOOD EST	
12	483	LP	00	61437		LF BANK HEFFNER	DEPTH EST.
12	484	SC	00	61441	BV	ALFALFA RT BANK	
12	485	LP	00	61563	CS/	FIELD	CABLED LOGS, BLDRS, CONCRETE
12	486	RI	00	61643	BV		
12	487	LP	00	61715			HARDPAN
12	488	GL	00	61786	SD/	11T 429185E/5007232N; T=14°C, FLOW=MF	
12	489	SP	00	61846		SALMON BUILDING REDD	REDD AND ADULT SALMON
12	490	SC	00	61857	/CS	HG/AG; GRASS/DECIDUOUS 3-15CM DBH, BOULDERS	
12	491	SP	00	61904	/CS		HARDPAN, BOULDERS
12	492	SC	00	61912		T=14°C; FLOW-MF; 11T 429507E/5006927N	
12	493	SP	00	61950			DEPTH EST
12	494	RI	00	61983	CS/		BLDRS
12	495	LP	00	62056	CS/CS		BLDRS
12	497	SP	00	62125	DJ		MANY JUV FISH

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
12	500	SC	00	62193		HG/AG; US/WF	
12	501	LP	00	62226	/CS		BLDRS
12	502	RI	00	62274	/CS	G/S	LOGS AND CONCRETE
12	503	LP	00	62336	AM	LG FEMALE BULLFROG	LG BULL FROG
12	504	SC	00	62342		FLOODPRONE ESTIMATED LEFT-NO ACCESS	
12	505	LP	00	62373			HARDPAN
12	506	RI	00	62413	/CS		CONCRETE
12	507	GL	00	62460		RIGHT BANK ESTIMATED - BARBED WIRE FENCE	
12	508	SC	00	62463	BV	11T 429694E/5006677N; T=12°C	
12	509	GL	00	62522	BV,CS/	BOULDERS, GOATS AND SHEEP IN RIPARIAN	
12	510	SP	00	62574		HG/AG; G/D30-50	IRRIGATION DITCH ON RT
12	511	RI	00	62598		IRRIGATION DITCH ENTERS ON RIGHT	
12	512	GL	00	62736			HARDPAN
12	513	RI	00	62786		TERRACE-CONSTRAINED; DEAD SALMON	
12	514	GL	00	62881			DEAD ADULT CHINOOK
12	517	SP	00	62978	/CS		HARDPAN, CONCRETE
12	518	LP	00	63009	/CS	T=12°C; 11T 430222E/5006626N	CONCRETE, BOULDERS (BLDRS)
12	523	SP	00	63127		CT/CT	
12	524	LP	00	63162	CS/		4-6" TROUT, BLDRS
12	526	LP	00	63244	CS/	HG/AG, D30-50/G	REDD, JACK AND ADULT SALMON
12	528	LP	00	63275		13°C, LOW FLOW, 11T 430349E/5006792N, JUVENILE WHITEFISH	
12	529	RB	00	63296	/SS,/CS		RIPRAP
12	530	LP	00	63331		RT BANK WASTE WATER TREATMENT PLANT	
12	533	RI	00	63465	CS/CS		BLDRS, RIPRAP
12	534	LP	00	63510	CS/		BLDRS, CONCRETE
12	535	SC	00	63519	CS/		BLDRS, CONCRETE
12	536	SP	00	63559	CS/	RR/HG, D15-30/G	CONCRETE BLDRS
12	537	RB	00	63572	CS/		CONCRETE
12	538	LP	00	63601	/CS	14°C, LOW FLOW; 11T 430612E/5006925N, LOGS AND BOULDERS	
12	539	RI	00	63658	/CS	END REACH	CONCRETE, BLDRS
13	542	LP	00	63820	CS/CS	11T 0430781E/5006830N; FP EST	BOULDERS
13	543	RI	00	63928	/CS	LIGHT GRAZING/URBAN, GRASS/DECIDUOUS 30-50CM, BOULDERS	
13	545	RI	00	64090	/CS		BLDR, CONCRETE SLABS
13	546	LP	00	64149	SD,/CS/		CONCRETE SLABS
13	547	GL	00	64197	CS/		CONCRETE SLABS
13	548	RI	00	64347	BC,CS,GS,CE	BC=10TH STREET	CE, BLDRS
13	549	RI	00	64422	CS,/CE/		OVERFLOW FROM CULVERT, BLDRS
13	550	SB	00	64425	CS/CS	T=22.5°C	BLDRS
13	551	SP	00	64451	CS/CS		BLDRS
13	552	SB	00	64453	CS/CS	T=22°C	BLDRS
13	553	PP	00	64462	CS/CS	DIVERSION #1-SEE NOTEBOOK	BLDRS
13	554	SS	00	64462	CS/CS	H=.15M	CONCRETE WALL
13	555	PP	00	64468	CS/CS		CONCRETE WALL
13	556	SS	00	64468	CS/CS	H=.3; 11T 431705E/5006841N	CONCRETE WALL
13	557	PP	00	64474	CS/CS		CONCRETE WALL
13	558	SS	00	64477	CS/CS	H=.37M	CONCRETE WALL
13	559	DP	00	64536	/CS		BLDRS
13	560	RI	00	64686	BC,/CS	BC=5TH STREET	CONCRETE SLABS, BLDRS
13	561	RI	00	64711	CS/		BLDRS
13	563	RI	01	64793	CS/CS		BLDRS, CONCRETE WALL
13	564	BW	10			RETAINING WALL CREATES BW	MADE BY DIVERSION CONSTRUCTION
13	565	RI	01	64850		DIVERSION CONSTRUCTION	DIVERSION CONSTRUCTION
13	566	DC	02				02 CHNL
13	567	DP	00	64990	/CE,/CS	CREATED BY RETAINING WALL	PTC CAUSED BY SANDBAGS
13	570	PP	00	65031	UD	PP CAUSED BY DIVERSION DAM	CONCRETE

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
13	571	SS	00	65032	PA	H=.85; MAIN STREET DIVERSION	CONCRETE
13	572	DP	00	65071	/CS		CONCRETE, BLDRS
13	573	RI	00	65144	CS/CS		
13	574	GL	00	65181	CS/CS	URBAN LAND USE	BLDRS
13	575	RI	00	65331	CS/CS,BC	11T 432094E/5006609N; BC=BELLWOOD	
13	576	RI	00	65481	CS/CS		CONCRETE SLABS
13	577	RI	00	65509	CS/		CONCRETE
13	578	SB	00	65509	CS/	H 0.25M	CONCRETE SLABS
13	579	RI	00	65621	CS,/BV	LANDOWNER STABILIZED BANK	BLDRS, CONCRETE
13	580	SB	00	65622	/CS,BV	T=16°C, H=0.3M	BOULDERS
13	581	DP	00	65646	/CS	CREATED BY ROCK DAM	BOULDERS
13	582	RI	00	65796	/CS		CONCRETE
13	583	RI	01	65946	/TJ.CS/,CE		PLACED LOGS
13	584	RI	11			T=17°C	ACW=1.1
13	585	RI	01	66096	CS/CS		BOULDERS, CONCRETE
13	587	RI	00	66136	CS, CE/		PVC, BLDRS, CONCRETE
13	588	SS	00	66149	CS/CS	SWACKHAMMER, HWY 203 BC	CONCRETE WALLS
13	589	RI	00	66299	SD,UD,CE,BC		BC, CS,
13	590	RI	00	66449	CS/CS	11T 432530E/506670N; T=17°C	BOULDERS, END REACH
14	591	RI	00	66545	CS/		BOULDERS
14	592	SB	00	66545		11T 433165E/5006366N; H=.15M	
14	593	LP	00	66561	/UD,/CS		BOULDERS
14	594	RI	00	66711	/CS		BOULDERS
14	595	RI	00	66861	CS,CE		AG FIELD DUMPING IN CR
14	596	RI	00	67011	CS/CS		BOULDERS
14	597	RI	00	67161	CS/CS		BOULDERS
14	598	RI	00	67311	CS/CS,WL		DEER, BLDRS
14	599	RI	00	67461	CS/CS,WL		BLDRS, DEER
14	600	RI	00	67541	CS/CS,WL		BLDRS, DEER
14	601	RI	01	67691	CS/CS		
14	602	BW	10		CS/	11T 433806E/5005632N, 2D, FRY IN BACKWATER, BOULDERS	
14	603	RI	00	67724	CS/	T=17°C	BOULDERS
14	604	SC	00	67730		LIGHT GRAZING	
14	605	RI	00	67811	CE/		SEEPING AG FIELD
14	607	RB	00	67862	CS/		BOULDERS
14	608	RI	00	68012	CS/		BOULDERS
14	609	RI	00	68162	/WL		CATTLE IN RIP
14	610	RI	00	68312	CS/		BOULDERS
14	611	RI	00	68462		FLOOD PRONE EST.	
14	612	RI	00	68522		11T 434204E/5004956N, 3D	
14	613	SP	00	68555		T=19°C	
14	614	RI	00	68705	CE/*2	UNCONSTRAINED	.3M DIAM, .18 DIAM
14	615	SS	00	68705		H=1.0M	H=1.0M; DAM DIVERSION, WD SLAT
14	616	DP	00	68749	UD,CS/CS		BLDRS, CONCRETE
14	618	LP	00	68804	CS/CS		CARS, BLDRS
14	619	RI	00	68954	BC,CS/CS		BLDRS, CONCRETE, SLABS
14	620	RI	01	69104	TJ/	TJ/	LITTLE CREEK
14	622	RI	11		FC	T=18°C	ACW=3.5M
14	623	RI	00	69227	WL	BIRD	
14	624	SS	00	69228	CS/CS	H=.35M	CONCRETE WALLS
14	625	PP	00	69233	CS		
14	626	SS	00	69233	CS	H=.25M	
14	627	PP	00	69239	CS	S/D15-30	
14	628	SS	00	69239	CS	H=.3M	
14	629	PP	00	69245	CS	T=18.5°C	

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
14	630	SS	00	69245	CS	11T 434804E/5004571N; H=.3M	
14	631	PP	00	69250	CS		
14	632	SS	00	69251	CS/CS	11T 434979E/5004347N, H=.3M-WEIR	CONCRETE WALLS
14	633	PP	00	69256	CS		
14	634	SS	00	69257		H=.3M	
14	635	PP	00	69287			FISH BYPASS,TRAP
14	636	RI	00	69437	UD/		
14	637	RI	00	69587			
14	638	RI	01	69737		T=13°C; DRY IRRIGATION CANAL/	
14	639	IP	10			FRY IN ISOLATED POOL	FISH
14	640	RI	00	69887	CS/	DIVERSION	BOULDERS
14	641	RI	01	70004	CS/CS,FC		CONCRETE, BLDRS
14	642	IP	10			FISH IN IP, LG/RR, D30-50/S	JUV FISH
14	643	SC	00	70016	WL		TRAIL, GRAZING
14	644	RI	00	70166	CE/	11T 435320E/5003727N	POND DRAINING INTO CREEK
14	645	RI	00	70237	CS/	END REACH	BOULDERS
15	646	MX	00	72056		SHORT/SOUTHERN CROSS RANCH PRC	11T 435320E/5003727N-NO ACCESS
16	647	RI	01	72206		T=16°C, CA/CT	11T 436463E/5002628N
16	648	BW	10		BV		
16	650	SC	03				SET UP MANMADE ROCK PILE
16	651	DP	03				WASHED OUT DIVERSION
16	655	PD	02				ACW=3.1M
16	656	DU	02			FLOWING THROUGH ROCKS	ACW=3.6
16	662	LP	00	72394		11T 436673E/5002455N	IRRIGATION CANAL/
16	663	RI	00	72544	CS/,/SS	HEAVY GRAZING	
16	667	RI	01	72674	CS/		CONCRETE SLABS
16	668	AL	10			T=16°C, HARDWOODS 30-50CM DBH AND GRASS	
16	669	SP	00	72725		MULTIPLE TERRACES	
16	671	RI	00	72812		DECIDUOUS TREES 30-50CM DBH/GRASS, T=18C	
16	672	LP	00	72842		2 LG BULLTROUT	30+ TROUT/SALMONID
16	673	RI	00	72958	BV,CE/CS		REDD, BLDR
16	674	LP	00	72996		LIGHT GRAZING, EXCLOSURE	BULLTROUT
16	676	IP	10				MANY JUV FISH
16	677	LP	00	73040		LARGE BULLTROUT	~25" BULLTROUT
16	678	RI	00	73078	CS/		CONCRETE
16	679	SD	00	73080	BV	11T 437085E/5002195N	BLDR, CONCRETE STEP
16	680	RI	00	73120	BV,UD		FISH BYPASS-OVERFLOW CULVERT
16	681	LP	00	73188	CS/	SPRING CHINOOK	BOULDER, WHITEFISH
16	682	RI	00	73255		11T 437211E/5001816N	
16	683	LP	00	73301	BV	2 CHINOOK SALMON	OTTER, CHINOOK
16	684	SC	00	73305		S/D30-50	
16	685	RI	00	73455	FC./CE./UD		
16	686	RI	00	73605			COWS IN CR
16	687	RI	00	73755	BV,SD/		
16	688	RI	00	73905		DEEP POCKETS LEFT BANK	
16	689	RI	00	73975		T=20°C, CA/CT	
16	690	LP	00	74006	CS/	REDD ON TAILOUT	BOULDERS
16	691	RI	00	74134	CS/		BOULDERS
16	692	LP	00	74202		HG/RR, G/D3-15	BOULDERS
16	693	RI	00	74352	CS/,BV		BOULDERS
16	694	RI	00	74491	CS/CS,BC	11T 437857E/5001073N	KIRBY'S PROP
16	695	RI	01	74526			COWS IN CREEK
16	696	IP	10			UNCONSTRAINED	
16	697	RI	00	74676		DECAYED SALMON CARCASS	
16	698	RI	00	74826	SD/,CE/		0.3M DIAM

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
16	699	RI	00	74976	CS/		
16	700	RB	00	75069	BV,CS/	T=15°C	BOULDERS
16	701	RI	01	75219	SS/		UNDER HWY 203
16	702	DC	02			11T 438406E/5000394N	ACW=1.4
16	703	RI	00	75287	WL	BIRD	
16	704	LP	00	75328	DJ	SALMON IN POOL	REDBAND
16	705	RI	00	75478	/SS,BV	T=18.5°C	30" BULLTROUT
16	706	RB	00	75628	/CS		
16	707	GL	00	75710	BV	3 SALMON IN GLIDE	3 CHINOOK
16	708	RI	01	75860	AM,BV		FROG
16	709	PD	02		AM		ACW=1.6M, FROG
16	710	RI	01	76010	BV,BC,CS/CS	BC	ACW=2.0
16	711	DC	02			2 SM PUDDLES	
16	712	RI	01	76115	WL,BV,/TJ	T=14.5°C, END REACH	BRINKER CR
16	713	CB	11			T=18°C, BRINKER CR	ACW=0.8M, HARDPAN
17	714	RI	00	76265	GS,WL	T=20°C	
17	716	RB	00	76565	CS/		BLDRS
17	717	RB	00	76646	CS/	NO TERRACES, HILLSLOPE	BLDRS
17	718	RI	00	76778	CS/	REDD, CH/MV	REDD, BLDRS
17	719	RB	00	76828	SS,/CS/	6 SALMON; G/D30-50	CH
17	720	RI	00	76978	CS/	11T 439408E/5000513N, SALMON	CH
17	721	RI	00	77128	BC,CS/CS	BC PRIVATE	BLDRS, CONCRETE
17	722	RI	01	77278	/TJ		TREEFROG
17	723	CB	11			T=15°C	ACW=1.2M
17	724	RI	00	77428		CHINOOK	
17	725	RI	00	77578	WL, SS/		DOE
17	726	RI	00	77728	CS,BC,WL	6 CHINOOK	SNAKE, 11T 440180E/5000085N
17	727	RI	01	77833	/TJ		UNNAMED TRIBUTARY
17	728	RI	11			T=17°C	ACW=1.0M
17	729	BW	10		WL, CS/	CT/CT	BLDRS, PRINTS
17	730	LP	00	77875		11T 440287E/500009N; CHINOOK IN POOL	
17	731	RI	00	78025	BV,CS/	CHINOOK	BLDRS, CONCRETE
17	732	RI	00	78036			
17	735	LP	00	78113		T=18°C	
17	736	RI	01	78188	BV		
17	737	IP	10				JUV FISH
17	738	LP	00	78213			DEPTH ESTIMATED
17	739	RI	00	78273	BV		
17	740	RI	01	78333	/CS	11T 440781E/5000024N	BLDRS
17	743	RI	00	78506	/CE	OLD BROKEN CONCRETE CULVERT, OLD IRRIGATION	
17	744	RI	01	78626		CHINOOK PAIR IN SIDE CHANNEL	CHINOOK
17	747	RI	01	78820			ADULT CHINOOK
17	748	RI	01	78840			CATTLE IN CR
17	749	BW	10				JUVENILE CHINOOK
17	750	LP	01	78867	DJ	2 ADULT CHINOOK	ADULT CHINOOK
17	751	RI	01	79017		DEAD CHINOOK PAIR	JUVENILE CHINOOK - DEAD
17	752	RI	01	79094	AM		TREE FROG, SNAKE
17	753	LP	02			11T 441363E/5000090N	
17	754	RB	02			HG/ST; 30/G	
17	756	PD	02			DENSE HAWTHORN; T=14°C	JUVENILE FISH
17	758	PD	02		BV	FISH IN PUDDLES	JUVENILE FISH
17	759	RI	0	79265		END REACH	
18	760	RI	00	79265	BV	REACH BREAK=STATE PARK	
18	761	RI	00	79419	BV	11T 0441470E/5000172	STACKED ROCKS BY PARK POOLING
18	762	SP	00	79443	DJ	GREENWAY/OLD GROWTH; 11T 441853E/5000084N	

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
18	763	RI	01	79505	BV		
18	764	LP	01	79590	BV	T=18C, TWO SALMON REDDS	2 REDDS
18	765	RI	02		TJ/	D3-15/C30-50	(5) SALMON
18	766	LP	11		BV		JUV FISH, ACW=18M
18	768	SP	01	79736		2 SALMON, REDD	SALMON, REDD
18	770	LP	04				JUVENILE CHINNOK, SNAKE
18	775	LP	04		BV		
18	776	RI	04		BV		
18	777	SR	03			H=.15M	HARDPAN
18	778	RI	03		BV, DJ		ACW=1.8M, JUVENILE FISH
18	779	PD	05		DJ		ACW=2.0M
18	780	LP	03		BV		
18	781	DC	06				ACW=1.0M
18	782	SP	03		BV,DJ	END CATHERINE CREEK STATE PARK	END REACH
19	783	RI	00	79812	BV	11T 0442212E/4999702N	REDD
19	784	BW	10		BV		
19	785	SP	00	79836			SM ROCK DAM BUILT BY SWIMMERS
19	786	SD	00	79837	BV	H=.5M	STEP FORMED BY CAMPERS
19	787	RI	00	79987	BV,BC	11T 442374E/4999556N	FOOTBRIDGE
19	788	RI	00	80137		OG/UR	REDD
19	789	RI	00	80287	BV,SD	T=11°C	
19	790	RI	00	80410	SD		
19	793	PD	02				ACW=1.2M
19	797	RI	00	80743	BV		
19	799	RI	00	81043	BV		
19	800	RI	00	81100	BV, AM	TREE FROG	LARGE TREES CHEWED, TREE FROG
19	801	SP	00	81130	/SS	JUV CHINOOK	
19	802	RI	00	81280	CS/,BV	ARTISAN WELL LF BANK	
19	803	RI	00	81305		LT/ST; T=10°C	
19	804	SP	00	81327		11T 443200E/4998985N; 3 ADULT CHINOOK	
19	805	RI	00	81477	BC,CS/CS		HWY 203, BLDRS
19	807	SC	00	81508		CL/CT	
19	809	LP	00	81604	BV	3 SALMON IN POOL	ADULT CHINOOK
19	810	RB	00	81620		2 REDDS	REDDS, SALMON
19	811	LP	00	81648		5 SALMON	REDD, ADULT CHINOOK
19	812	RI	01	81656	/TJ	T=12°C, END REACH	LITTLE CATHERINE CR
19	813	DC	11			11T 443278E/4998798N	UNNAMED JUNCTION ON TOPO
19	814	RI	11			T=10.5°C, LITTLE CATHERINE CR	LITTLE CATHERINE; ACW=7.6M
20	815	RI	01	81689	BV	T=11°C	
20	817	RB	01	81734	BV		
20	818	LP	01	81767		11T 443340E/4998695N; 1 REDD	
20	819	RI	01	81809	BV	LIGHT GRAZING / LARGE TIMBER	
20	820	RI	02				ACW=8.0M
20	822	SC	02		BV		
20	823	LP	02			LITTLE CATHERINE CONFLUENCE	
20	824	RI	02		TJ/		LITTLE CATHERINE
20	826	RI	02		BV,TJ/	UNNAMED TRIB	
20	827	DC	11				ACW=0.75M
20	828	SR	03			H=.25M	HARDPAN
20	829	RI	03				HARDPAN
20	831	LP	04				ACW=2.0M, CLAY
20	833	LP	01	81850			2 ADULT CHINOOK
20	834	SC	01	81860			2 ADULT CHINOOK, REDD
20	835	LP	01	81900		2 SALMON, LARGE REDD	REDD
20	837	PD	02		BV		02 CHNL, ACW=8.0

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
20	838	DU	02		BV		02 CHNL
20	839	PD	03				03 CHNL, ACW=1.7
20	840	PD	04				04 CHNL, ACW=1.1
20	841	LP	01	81947			JUVENILE CHINOOK
20	842	RI	01	81995	BV	MILK CREEK OFF SIDE CHANNEL, BUT HERE FOR DISTANCE-SAKE	
20	843	SC	05		BV		05 CHNL
20	844	LP	05		BV		05 CHNL
20	845	RI	05		/CS,BV./TJ		
20	846	SP	11		BV	END REACH; T=15°C, ACW=3.3M	MILK CREEK, ACW=3.3
20	847	RI	05		BV	T=17°C	
21	848	LP	01	82025	BV	REDD	
21	849	RI	01	82053	BV		
21	850	LP	06				JUVENILE FISH
21	851	RI	06				ACW=13.0
21	854	PD	06				ACW=1.5
21	855	LP	01	82109		SALMON	LARGE REDDS, 2 ADULTS
21	856	RI	01	82153	BV,DJ	SALMON	ADULT CHINOOK
21	857	DU	06		BV		ACW=2.6
21	858	PD	06		BV		ACW=2.2
21	859	RI	05		BV	REDD	REDD
21	860	SP	05		BV		
21	861	RI	00	82303	BV/FC	DEEP POCKETS W/ 5 SALMON	MAIN CHNL
21	862	RI	01	82386		11T 443677E/4998266N; T=10°C, SALMOI MANY CATTLE IN RIP	
21	863	LP	01	82404	BV	LIGHT GRAZING, SECOND GROWTH TIMBER	
21	864	RI	01	82496	BV		
21	865	LP	01	82541	BV		
21	867	RI	03		BV		03 CHNL
21	868	LP	03			CT/CT	
21	869	SC	03		BV	D3-15/G	
21	870	LP	03		AM		COLUMBIA SPOTTED FROG
21	871	RI	03		BV		
21	872	LP	01	82600	DJ		
21	873	RI	01	82633	FC		
21	874	DU	04		WL	T=17°C	ACW=5.2, GROUSE
21	875	PD	04		DJ	US/WF	PTC GOES TO DRY UNIT
21	878	LP	01	82685		11T 443995E/4998187N	REDD, ADULT CH
21	879	SC	01	82690	BV		ADULT CH
21	880	LP	01	82713	BV	TAKEN ON PTC	REDD
21	881	SC	01	82721	BV		
21	882	LP	01	82753	BV	REDD, 2 SALMON	REDD, 2 ADULT CH
21	884	SP	01	82769	BV		
21	885	RI	01	82822	BV		
21	886	BW	10		BV		
21	887	PD	06		BV		ACW=2.3M
21	888	PD	05		BV,AM	COLUMBIA SPOTTED FROG	CATTLE TRAFFIC
21	889	DU	05		BV		HEAVY CATTLE TRAFFIC
21	890	PD	05		DJ,BV		ACW=2.7M
21	891	LP	05		DJ		
21	892	PD	05		DJ,BV		ACW=4.0M
21	895	LP	01	82891			REDD, 4 ADULT CHINOOK
21	896	RI	01	82986	BV,DJ	4 REDDS, 2 SALMON	WILD CHINOOK ON REDD
21	897	DU	06		BV		ACW=1.5M
21	898	PD	06				ACW=3.8M
21	902	LP	01	83017		2 SALMON, 1 REDD	BULL TROUT
21	903	RI	01	83074		REDD	REDD

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010


REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
21	906	SP	01	83108			REDD, SEVERAL TROUT
21	907	SC	01	83109	BV	LIGHT GRAZING, LARGE TIMBER	
21	908	RI	01	83184	BV,DJ	4 SALMON, 2 REDDS	MULTIPLE CHANNELS
21	909	LP	01	83207		11T 444281E/4997811N	POST SPAWN HATCHERY MORTALITY
21	910	SC	01	83215			
21	911	LP	01	83243		REDD	REDD AT PTC; SALMON
21	912	PD	02		BV		ACW=1.7M
21	914	PD	02				CATTLE TRAFFIC
21	915	RI	00	83393	DJ,BV		2 REDDS, 4 SALMON, 1 JACK
21	916	RI	00	83503	BV	3 ADULT CHINOOK, JACK, REDD	REDDS
21	917	RB	00	83526		REDD, SALMON	ADULT SALMON
21	919	BW	10				HATCHERY MALE CHINOOK
21	920	RI	01	83730	BV	3 SALMON, 2 REDDS	
21	921	IP	10				HEAVY CATTLE TRAFFIC
21	922	BW	10			LG/ST; T=8C; CT/CT	ADULT CHINOOK
21	923	RI	01	83772		ST, CT/CT, REDD, SALMON	
21	924	IP	10			S/G	MANY JUV FISH
21	925	LP	00	83786		11T 444659E/4997401N; SALMON	REDD, SALMON
21	928	LP	01	83919	DJ	3 SALMON BUILDING REDDS	REDD, ADULT CHINOOK
21	931	RI	01	84068	BV,/SS		
21	934	LP	02			5 REDDS, MANY SALMON	REDD ON PTC
21	935	SC	02				ACW=9.0M
21	938	PD	03		BV		
21	939	DC	04			2 SALMON, 2 REDDS	ACW=4.0M
21	940	RI	03				ADULT HATCHERY CHINOOK
21	941	LP	03		BV	REDD	
21	942	SP	01	84114		2 SALMON, 2 REDDS	ADULT CHINOOK
21	943	PD	05		DJ	DEAD SALMON	ACW=4.0M, CHINOOK
21	944	RI	01	84163	FC		MALE ADULT CHINOOK CARCASS
21	945	LP	01	84180		2 REDDS, 1 SALMON	REDDS
21	946	RI	01	84298	BV		4 REDDS, SALMON
21	947	BW	10		WL		TRACKS
21	948	BW	10		BV, DJ	6 REDDS, MANY SALMON	
21	949	PD	06				ACW=7.0M
21	951	LP	06		ACW=2.9M		
21	952	DU	06		ACW=5.5M	LARGE AND SECOND-GROWTH TIMBER	
21	953	LP	01	84326		1 REDD, 2 SALMON	REDD
21	954	RI	01	84429	FC,/CS		BOULDERS
21	955	PD	05			11T 444980E/4996923N	
21	956	DU	05		FC	T=9.5°C	
21	957	LP	00	84453	BV,/CS	2 SALMON, 1 REDD	REDD, BOULDERS
21	958	RI	01	84561	CS/	1 REDD	REDD, BOULDERS
21	959	RB	02			TERRACES	
21	960	RI	00	84648		5 SALMON, 3 REDDS	MULTIPLE REDDS, ADULTS
21	961	LP	00	84679		3 SALMON, 2 REDDS	
21	962	RB	01	84721	/CS		REDD, ADULT CH
21	963	LP	01	84750		DEAD SALMON-SPAWNED	MORTALITY - POST SPAWN FEMALE
21	964	SC	02		BV		
21	965	LP	02		BV		
21	967	RI	01	84900			2 JACKS, 2 ADULT CH
21	968	DC	03		BV	2 JACKS, 5 ADULTS, 2 REDDS	ACW=3.2M
21	970	RB	01	84969		1 SALMON	
21	971	RB	02		CE,/CS/	BOULDERS, UMATILLA ACCLIMATION POND	
21	972	SP	00	85004		2 SALMON, 1 REDD	JACK
21	973	RB	00	85022		LARGE AND SECOND-GROWTH TIMBER	

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
21	974	SP	00	85043	BC,CS/CS	T=7.5°C; 3 SALMON, 2 REDDS	REDDS, 3 ADULT CHINOOK
21	976	RI	00	85343	BV	T=7.5°C	
21	977	RI	00	85359			2 REDDS
21	978	SP	00	85384		2 SALMON, 1 REDD	ADULT CHINOOK
21	979	RI	00	85505		SPAWNED HEN CHINOOK	SALMON CARCASS
21	980	RP	00	85548		445476E/4996747N	
21	981	RI	00	85651		REDD, SPAWNED MALE	CHINOOK CARCASS
21	982	RP	00	85676	CS/	2 REDDS	REDDS, CARCASS
21	983	SB	00	85677	CS/	ST/LT; S/D3-15; H=.32	BOULDERS
21	984	RI	00	85716	CS/	11T 445985E/4996372N	BOULDERS
21	985	RI	01	85787	WL	3 REDDS, 2 SALMON	PILEATED WOODPECKER
21	987	LP	01	85871	BV	2 REDDS, 4 SALMON, 1 JACK	CHINOOK CARCASS
21	988	RI	02		TJ/	T=10.5°C; 7 SALMON, 3 REDDS	5 CH SALMON
21	989	RI	11		BV	T=15°C;11T 445982E/4996376N	ACW=1.3M
21	990	RB	01	85944		1 SALMON, 1 REDD	
21	991	LP	03		BV,WL		
21	992	RI	04		DJ,BV		
21	993	SD	04		BV	H=.15M	WATER RUNS UNDER BV DAM
21	994	BP	04		BV		DRY BV DAM
21	995	RI	03		BV		
21	1000	RI	00	86091	BV	4 SALMON, 3 REDDS	JACK MORT
21	1002	RB	00	86166		RR/LT; D3-15/S	
21	1005	RI	00	86343		3 REDDS, 2 SALMON	
21	1006	RI	01	86385			REDD, SALMON
21	1008	LP	00	86421		2 REDDS, 2 DEAD SALMON	REDD, SALMON
21	1010	RI	00	86468		1 REDD, 3 SALMON, 11T 446429E/4996201N	
21	1011	SD	00	86468		H=.25M	DAM BUILT BY ROCK PILES
21	1012	DP	00	86480	CS/CS,BC	SPRUCE, GRAND FIR	FOOTBRIDGE, REDD
21	1013	RI	00	86516	CS/CS	6 SALMON, 3 REDDS	CABLED LOGS
21	1014	SD	00	86518	CS/CS	H=.37M	CABLED LOGS, BLDRS
21	1015	RI	00	86668	CS/CS	3 REDDS	REDDS, 2 ADULT CH
21	1017	RI	01	86879	TJ/	T=9C	UNNAMED TRIB
21	1018	RB	11			11T 446926E/4996094N; T=12C	ACW=3.5M
21	1020	SP	01	86906		ST/LT; D3-15/C30-50	
21	1021	RB	01	86999			2 CH CARCASSES
21	1023	LP	02		BV		
21	1025	RI	00	87149	/SS	REDD	JACK MORT
21	1027	BW	10		AM	2 SALMON, 1 REDD, 2 C.SPOTTED FROG	COLUMBIA SPOTTED FROG
21	1028	RI	01	87372	AM		TREE FROG, HATCHERY CH
21	1030	LP	01	87392	BV		
21	1032	SC	00	87397		11T 447415E/4995823N	
21	1033	RI	00	87491	BV	2 REDDS, 2 SALMON	2 REDDS, SALMON
21	1034	RB	01	87630	/TJ,/SS	D3-15/S; LT/ST	
21	1035	CB	11		WL	447509E/4995854N	
21	1036	BW	10			T=11C	
21	1038	RI	02		CS/		BLDRS
21	1039	RB	02		CS/		BLDRS
21	1040	RI	02		CS/	REDD, T=9.5°C	BLDRS
21	1041	LP	00	87684			CH SALMON, CARCASS
21	1043	RI	01	87721	/TJ		SCOUT CREEK
21	1044	CB	11			SCOUT CR, T=10.5°C	END REACH
22	1045	RI	00	87871	BC,CS/CS	BC,11T 447667E/4995925N	CARCASS
22	1051	RI	00	88099	CS/		BLDRS
22	1052	LP	00	88126		REDD; D3-15/C15-30; ST/LT	
22	1054	RI	00	88192			CH CARCASS

CATHERINE CREEK (GRANDE RONDE RIVER BASIN) - SUMMER 2010

REACH	UNIT#	TYPE	CHAN	DIST.(m)	COMMENTS	NOTE_ESTIMATOR	NOTE_NUMERATOR
22	1055	RB	00	88326	WL	REDD	CH CARCASS
22	1056	RB	01	88438		REDDS	
22	1057	RI	02			11T 447909E/4996265N	
22	1058	LP	02			REDD	REDD
22	1060	RB	02			T=11°C	
22	1063	RB	01	88502	BV	DEEP POCKET-10M LONG	
22	1064	RB	01	88603	DJ		HEN CH CARCASS
22	1065	RI	04		DJ		
22	1067	SP	01	88617			REDD, SALMON
22	1068	RB	01	88641			MALE CH CARCASS
22	1069	SP	01	88661	BV		CHINOOK CARCASS
22	1072	SP	01	88699		11T 448491E/4996438N; T=8°C	REDDS
22	1073	RI	01	88820	/SS	2 REDDS	
22	1074	RI	03		CS/,CE/	BOUDERS, CORRUGATED CULVERT	
22	1075	RB	03		CS,,CE/,SS		
22	1077	RB	03		BV		
22	1078	PD	05		BV		
22	1079	RI	00	88970	CE/	ST/LG; D3-15	TWO CULVERT ENTRIES
22	1080	RI	00	89066		REDD	REDD
22	1081	RB	00	89216	CE/		MALE CH CARCASS, 3 REDDS
22	1082	RB	01	89366	CE/		CHINOOK CARCASS
22	1084	RB	00	89410		END SURVEY, 11T 449053E/4996458N; CONF SF AND NK CATHERINE	




Copyright (C) 1996, Earthvisions, Inc.

Name: IMBLER (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.


CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN

Copyright (C) 1996, Earthvisions, Inc. 2010 SUMMER



Name: COVE (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 SUMMER 2010




Copyright (C) 1996, Earthvisions, Inc.

Name: COVE (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 SUMMER 2010

Copyright (C) 1996, Earthvisions, Inc.




Copyright (C) 1996, Earthvisions, Inc.

Name: CONLEY (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 SUMMER 2010

Copyright (C) 1996, Earthvisions, Inc.




Copyright (C) 1996, Earthvisions, Inc.

Name: CONLEY (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN

Copyright (C) 1996, Earthvisions, Inc. SUMMER 2010




Copyright (C) 1996, Earthvisions, Inc.

Name: CONLEY (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 SUMMER 2010

Copyright (C) 1996, Earthvisions, Inc.




Name: CRAIG MT (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 SUMMER 2010

Copyright (C) 1996, Earthvisions, Inc.

Copyright (C) 1996, Earthvisions, Inc.





Copyright (C) 1996, Earthvisions, Inc.

Name: CRAIG MT (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 SUMMER 2010

Copyright (C) 1996, Earthvisions, Inc.






Copyright (C) 1996, Earthvisions, Inc.

Name: UNION (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 2010 SUMMER

Copyright (C) 1996, Earthvisions, Inc.




Copyright (C) 1996, Earthvisions, Inc.

Name: UNION (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN
 2010 SUMMER


Copyright (C) 1996, Earthvisions, Inc.



Name: LITTLE CATHERINE CREEK (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN

Copyright (C) 1996, Earthvisions, Inc. 2010 SUMMER



Copyright © 1996, Earthvisions, Inc.

Name: MEDICAL SPRINGS (OR)
 Date: 12/21/10
 Scale: 1 inch = 2,000 ft.

CATHERINE CREEK HABITAT SURVEY
 GRANDE RONDE RIVER BASIN

Copyright (C) 1996, Earthvisions, Inc. 2010 SUMMER

CATHERINE CREEK 2010 STREAM HABITAT PHOTOS



Catherine Creek- Reach 1 unit 1 - Glide -
Looking Upstream



Catherine Creek- Reach 1 unit 8 - Glide - Left
Riparian



Catherine Creek- Reach 3 unit 159 - Glide -
Right Riparian



Catherine Creek- Reach 3 unit 178 - Glide - Left
Riparian



Catherine Creek- Reach 3 unit 178 - Glide -
Right Riparian



Catherine Creek- Reach 3 unit 182 - Irrigation
Material

CATHERINE CREEK 2010 STREAM HABITAT PHOTOS



Catherine Creek- Reach 3 unit 206 - Glide –
Right Riparian



Catherine Creek- Reach 3 unit 220 - Glide –
Right Riparian



Catherine Creek- Reach 3 unit 220 - Glide –
Looking Upstream



Catherine Creek- Reach 4 unit 245 - Glide –
Right Riparian



Catherine Creek- Reach 4 unit 259 - Glide – Left
Riparian



Catherine Creek- Reach 5 unit 262 - Glide –
Looking Upstream

CATHERINE CREEK 2010 STREAM HABITAT PHOTOS



Catherine Creek- Reach 6 unit 292 - Glide – Left Riparian



Catherine Creek- Reach 6 unit 295 – Beaver Dam and Ryan




Catherine Creek- Reach 6 unit 301 - Glide – Looking Upstream



Catherine Creek- Reach 7 unit 326 - Glide – Right Riparian



Catherine Creek- Reach 12 unit 449 - Glide – Looking Upstream



Catherine Creek- Reach 12 unit 514 - Right Riparian

CATHERINE CREEK 2010 STREAM HABITAT PHOTOS



Catherine Creek- Reach 13 unit 551 – Scour Pool - Looking Downstream



Catherine Creek- Reach 13 unit 553 – Looking Upstream at Diversion



Catherine Creek- Reach 13 unit 559 – Culverts Diverting Water



Catherine Creek- Reach 13 unit 590 – Riffle - Looking Upstream



Catherine Creek- Reach 14 unit 624 – Umatilla Fish Trap Weir



Catherine Creek- Reach 14 unit 645 – Right Riparian

CATHERINE CREEK 2010 STREAM HABITAT PHOTOS



Catherine Creek- Reach 16 unit 661 – Riffle -
Right Riparian



Catherine Creek- Reach 17 unit 717 – Rapid -
Looking Upstream



Catherine Creek- Reach 17 unit 743 – Riffle -
Right Riparian



Catherine Creek- Reach 19 unit 817 – Rapid -
Left Riparian



Catherine Creek- Reach 21 unit 861 – Riffle -
Right Riparian



Catherine Creek- Reach 21 unit 908 – Riffle -
Left Riparian

CATHERINE CREEK 2010 STREAM HABITAT PHOTOS



Catherine Creek- Reach 21 unit 975 – Riffle -
Right Riparian



Catherine Creek- Reach 22 unit 1045 – Riffle -
Looking Upstream



Catherine Creek- Reach 22 unit 1054 – Riffle -
Right Riparian



Catherine Creek- Reach 22 unit 1073 – Riffle -
Right Riparian

Steelhead Trout Input Values

1 Spawning, egg survival, emergence

Attribute	Criteria and Rating		
	3	2	1
Fines (%)	≤ 10	> 10 and ≤ 20	> 20
Gravel (%)	≥ 30	< 30 and ≥ 15	< 15
Cobble (%)	≥ 10 and ≤ 30	> 30 and ≤ 60	< 10 or > 60
Pool area (% pools)	≥ 40 and ≤ 60	≥ 20 and < 40	< 20 or > 60
Residual Pool Depth (m)	≥ 0.2		< 0.2

2 Summer Rearing 0+

Attribute	Criteria and Rating		
	3	2	1
Fines (%)	≤ 10	> 10 and ≤ 30	> 30
Cobble and boulders (%)	≥ 20	< 20 and ≥ 10	< 10
Pool Area (% pools)	≥ 40 and ≤ 60	< 40 and ≥ 20	< 20 or > 60
Cover			
Undercut (%)	≥ 15	< 15 and ≥ 10	< 10
Pieces of large woody debris / 100m	≥ 20	< 20 and ≥ 10	< 10
Number of boulders / 100m	≥ 20	< 20 and ≥ 5	< 5

3 Overwintering 0+

Attribute	Criteria and Rating		
	3	2	1
Fines (%)	≤ 10	> 10 and ≤ 30	> 30
Cobble and boulders (%)	≥ 20	< 20 and ≥ 10	< 10
Pool Area (% pools)	≥ 40 and ≤ 60	< 40 and ≥ 20	< 20 or > 60
Pool complexity		See below	
Cover			
Undercut (%)	≥ 15	< 15 and ≥ 10	< 10
Pieces of large woody debris / 100m	≥ 20	< 20 and ≥ 10	< 10
Number of boulders / 100m	≥ 20	20 and ≥ 5	< 5
Gradient (%)	< 4	≥ 4	

4 Summer Rearing 1+

Attribute	Criteria and Rating		
	3	2	1
Fines (%)	≤ 10	> 10 and ≤ 30	> 30
Cobble and boulders (%)	≥ 20	> 20 and ≥ 10	< 10
Pool Area (% pools)	≥ 40 and ≤ 60	< 40 and ≥ 20	< 20 or > 60
Depth in fast water units (m)	≥ 0.5		< 0.5
Additional Cover			
Undercut (%)	≥ 15	< 15 and ≥ 10	< 10
Pieces of large woody debris / 100m	≥ 20	< 20 and ≥ 10	< 10
Number of boulders / 100m	≥ 20	< 20 and ≥ 5	< 5

5 Overwintering 1+ life history

Attribute	Criteria and Rating		
	3	2	1
Fines (%)	≤ 10	> 10 and ≤ 30	> 30
Cobble and boulder (%)	≥ 25	< 25 and ≥ 10	< 10
Pool Area (% pools)	≥ 40 and ≤ 60	< 40 and ≥ 20	< 20 or > 60
Pool complexity		See Below	
Cover			
Undercut (%)	≥ 20	< 20 and ≥ 10	< 10
Pieces large woody debris / 100m	≥ 20	< 20 and ≥ 10	< 10
Number of boulders / 100m	≥ 20	< 20 and ≥ 5	< 5

6 Pool Complexity

Attribute	Criteria and Rating		
	3	2	1
Scour Pool Depth (m) (<i>min. at summer flow</i>)			
Wetted width ≤ 10m	> 0.6	≤ 0.6 and ≥ 0.6	< 0.6
Wetted width > 10m	> 1	≤ 1 and ≥ 0.6	< 0.6
Large woody debris (LWD)			
Keypieces of LWD / 100m	≥ 0.6	< 0.6 and > 0	= 0
Pieces of LWD / 100m	≥ 2 or	< 2 and > 0	= 0 and

Appendix C

HabRate models for Catherine Creek Chinook salmon based on 2010 data split into three sections: lower, middle, upper.

HabRate model for Catherine Creek 2010 habitat survey data for Chinook salmon habitat availability at Spawning, Incubation, and Emergence.

Stream	Reach	Fines	Gravel	Cobble	Substrate	Pool Area	Residual Pool		Morphology	Rating
							Depth	Gradient		
CATHERINE CREEK 2010	1	1	1	1	1	1	3	3	3	1
CATHERINE CREEK 2010	2	3	3	1	2	1	3	3	3	2
CATHERINE CREEK 2010	3	2	3	1	2	1	3	3	3	2

HabRate model for Catherine Creek 2010 habitat survey data for Chinook salmon habitat availability for 0+ Summer Rearing.

Stream	Reach	Fines	Gravel	Cobble and boulders	Substrate	Pool Area	Pool Complexity	Cover					Rating
								Undercut	Large woody debris/100m	Large Boulders/100m	Cover	Gradient	
CATHERINE CREEK 2010	1	1	1	1	1	1	3	1	1	1	1	3	2
CATHERINE CREEK 2010	2	3	3	1	2	1	3	1	1	3	2	3	2
CATHERINE CREEK 2010	3	2	3	1	2	1	3	1	1	3	2	3	2

HabRate model for Catherine Creek 2010 habitat survey data for Chinook salmon habitat availability for 0+ Winter Rearing.

Stream	Reach	Fines	Cobble and boulders	Interstices	Pool Area	Pool Complexity	Cover					Rating
							Undercut	Large woody debris/100m	Large Boulders/100m	Cover	Gradient	
CATHERINE CREEK 2010	1	1	1	1	1	3	1	1	1	1	3	2
CATHERINE CREEK 2010	2	3	1	1	1	3	1	1	3	2	3	2
CATHERINE CREEK 2010	3	2	1	1	1	3	1	1	3	2	3	2

Appendix D

HabRate models for Catherine Creek Steelhead trout based on 2010 data split into three sections: lower, middle, upper.

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout habitat availability at Spawning, Incubation, and Emergence.

Stream	Reach					Pool	Residual	Rating
		Fines	Gravel	Cobble	Substrate	Area	Pool Depth	
CATHERINE CREEK 2010	1	1	1	1	1	1	3	1
CATHERINE CREEK 2010	2	3	3	1	2	1	3	2
CATHERINE CREEK 2010	3	2	3	1	2	1	3	2

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout habitat availability at 0+ Summer Rearing.

Stream	Reach					Pool	Cover			Cover	Rating
		Fines	Cobble and boulders	Substrate	Area	Undercut	Large woody debris/100m	Boulders/100m			
CATHERINE CREEK 2010	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK 2010	2	3	1	2	1	1	1	3	2	2	2
CATHERINE CREEK 2010	3	2	1	2	1	1	1	3	2	2	2

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout habitat availability at 0+ Winter Rearing.

Stream	Reach					Pool	Cover			Pool Complexity	Pool Habitat	Gradient	Rating
		Fines	Cobble and boulders	Interstices	Area	Undercut	Large woody debris/100m	Boulders/100m	Cover				
CATHERINE CREEK 2010	1	1	1	1	1	1	1	1	1	2	2	3	1
CATHERINE CREEK 2010	2	3	1	1	1	1	1	3	2	3	2	3	2
CATHERINE CREEK 2010	3	2	1	1	1	1	1	3	2	3	2	3	2

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout habitat availability at 1+ Summer Rearing.

Stream	Reach					Pool	Depth in fast	Cover			Cover	Rating
		Fines	Cobble and boulders	Interstices	Area	water units	Undercut	Large woody debris/100m	Boulders/100m			
CATHERINE CREEK 2010	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK 2010	2	3	1	2	1	1	1	1	1	3	2	2
CATHERINE CREEK 2010	3	2	1	2	1	1	1	1	1	3	2	2

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout habitat availability at 1+ Winter Rearing.

Stream	Reach	Fines	Cobble and boulders	Interstices	Pool Area	Pool Complexity	Pool Habitat	Cover			Cover	Rating
								Undercut	Large woody debris per 100m	Boulders per 100m		
CATHERINE CREEK 2010	1	1	1	1	1	2	2	1	1	1	1	1
CATHERINE CREEK 2010	2	3	1	1	1	3	2	1	1	3	2	2
CATHERINE CREEK 2010	3	2	1	1	1	3	2	1	1	3	2	2

Appendix E

HabRate models for Catherine Creek Chinook salmon based on 2010 data

HabRate model for Catherine Creek 2010 habitat survey data for Chinook salmon habitat availability at Spawning, Incubation, and Emergence. Rating is the final rating for the reach based on the attributes in the table.

Stream	Reach	Residual							Morphology	Rating
		Fines	Gravel	Cobble	Substrate	Pool Area	Pool Depth	Gradient		
CATHERINE CREEK	1	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	2	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	3	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	4	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	5	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	6	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	7	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	8	1	1	1	1	1	1	3	1	1
CATHERINE CREEK	9	1	1	1	1	1	3	3	3	1
CATHERINE CREEK	10						unsurveyed			
CATHERINE CREEK	11	1	1	2	1	1	1	3	1	1
CATHERINE CREEK	12	2	3	2	3	3	3	3	3	3
CATHERINE CREEK	13	3	3	2	3	1	3	3	3	3
CATHERINE CREEK	14	3	2	2	2	1	3	3	3	2
CATHERINE CREEK	15						unsurveyed			
CATHERINE CREEK	16	2	3	2	3	1	3	3	3	3
CATHERINE CREEK	17	2	2	2	2	1	3	3	3	2
CATHERINE CREEK	18	1	3	3	3	2	3	3	3	3
CATHERINE CREEK	19	2	2	2	2	1	3	3	3	2
CATHERINE CREEK	20	2	3	3	3	2	3	3	3	3
CATHERINE CREEK	21	2	3	2	3	1	3	3	3	3
CATHERINE CREEK	22	3	2	2	2	1	3	3	3	2

HabRate model for Catherine Creek 2010 habitat survey data for Chinook salmon 0+ Summer Rearing habitat availability.

Stream	Reach	Reach Cover											Gradient	Rating
		Fines	Gravel	Cobble and boulders	Substrate	Pool Area	Pool Complexity	Undercut	Large woody debris/100m	Large Boulders/100m	Cover			
CATHERINE CREEK	1	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	2	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	3	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	4	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	5	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	6	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	7	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	8	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	9	1	2	1	2	1	3	1	1	1	1	1	3	2
CATHERINE CREEK	10													
CATHERINE CREEK	11	1	1	3	2	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	12	2	3	3	2	3	3	1	1	2	2	2	3	3
CATHERINE CREEK	13	3	3	3	3	1	3	1	1	3	2	3	3	2
CATHERINE CREEK	14	3	3	3	3	1	3	1	1	3	2	3	3	2
CATHERINE CREEK	15													
CATHERINE CREEK	16	2	3	3	2	1	3	1	1	3	2	3	3	2
CATHERINE CREEK	17	2	3	3	2	1	3	1	1	3	2	3	3	2
CATHERINE CREEK	18	1	3	3	2	2	3	1	1	3	2	3	3	2
CATHERINE CREEK	19	2	3	3	2	1	3	1	1	3	2	3	3	2
CATHERINE CREEK	20	2	3	3	2	2	3	1	1	2	2	3	3	2
CATHERINE CREEK	21	2	3	3	2	1	3	1	2	3	2	3	3	2
CATHERINE CREEK	22	3	3	3	3	1	3	1	1	3	2	3	3	2

HabRate model for Catherine Creek 2010 habitat survey data for Chinook salmon 0+ Overwintering habitat availability.

Stream	Reach	Reach Cover									Cover	Gradient	Rating
		Fines	Cobble and boulders	Interstices	Pool Area	Pool Complexity	Undercut	Large woody debris/100m	Large Boulders/100m				
CATHERINE CREEK	1	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	2	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	3	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	4	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	5	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	6	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	7	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	8	1	1	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	9	1	1	1	1	3	1	1	1	1	1	3	2
CATHERINE CREEK	10						unsurveyed						
CATHERINE CREEK	11	1	3	1	1	1	1	1	1	1	1	3	2
CATHERINE CREEK	12	2	3	3	3	3	1	1	2	2	2	3	2
CATHERINE CREEK	13	3	3	3	1	3	1	1	3	2	3	2	2
CATHERINE CREEK	14	3	3	3	1	3	1	1	3	2	3	2	2
CATHERINE CREEK	15						unsurveyed						
CATHERINE CREEK	16	2	3	3	1	3	1	1	3	2	3	2	2
CATHERINE CREEK	17	2	3	3	1	3	1	1	3	2	3	2	2
CATHERINE CREEK	18	1	3	1	2	3	1	1	3	2	3	2	2
CATHERINE CREEK	19	2	3	3	1	3	1	1	3	2	3	2	2
CATHERINE CREEK	20	2	3	3	2	3	1	1	2	2	3	2	2
CATHERINE CREEK	21	2	3	3	1	3	1	2	3	2	3	2	2
CATHERINE CREEK	22	3	3	3	1	3	1	1	3	2	3	2	2

Appendix F

HabRate models for Catherine Creek Steelhead trout based on 2010 data

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout Spawning, Incubation, and Emergence habitat availability.

Stream	Reach						Residual Pool		Rating
		Fines	Gravel	Cobble	Substrate	Pool Area	Depth		
CATHERINE CREEK	1	1	1	1	1	1	1	1	
CATHERINE CREEK	2	1	1	1	1	1	1	1	
CATHERINE CREEK	3	1	1	1	1	1	1	1	
CATHERINE CREEK	4	1	1	1	1	1	1	1	
CATHERINE CREEK	5	1	1	1	1	1	1	1	
CATHERINE CREEK	6	1	1	1	1	1	1	1	
CATHERINE CREEK	7	1	1	1	1	1	1	1	
CATHERINE CREEK	8	1	1	1	1	1	1	1	
CATHERINE CREEK	9	1	1	1	1	1	3	1	
CATHERINE CREEK	10				unsurveyed				
CATHERINE CREEK	11	1	1	3	1	1	1	1	
CATHERINE CREEK	12	2	3	3	3	3	3	3	
CATHERINE CREEK	13	3	3	2	3	1	3	3	
CATHERINE CREEK	14	3	2	2	2	1	3	2	
CATHERINE CREEK	15				unsurveyed				
CATHERINE CREEK	16	2	3	2	3	1	3	3	
CATHERINE CREEK	17	2	2	2	2	1	3	2	
CATHERINE CREEK	18	1	3	3	1	2	3	1	
CATHERINE CREEK	19	2	2	2	2	1	3	2	
CATHERINE CREEK	20	2	3	2	3	2	3	3	
CATHERINE CREEK	21	2	3	2	3	1	3	3	
CATHERINE CREEK	22	3	2	2	2	1	3	2	

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout 0+ Summer Rearing habitat availability.

Stream	Reach	Cover								Rating
		Fines	Cobble and boulders	Substrate	Pool Area	Undercut	Large woody debris/100m	Boulders/100m	Cover	
CATHERINE CREEK	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	2	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	3	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	4	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	5	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	6	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	7	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	8	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	9	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	10				unsurveyed					
CATHERINE CREEK	11	1	2	2	1	1	1	1	1	2
CATHERINE CREEK	12	2	2	2	3	1	1	2	2	3
CATHERINE CREEK	13	3	3	3	1	1	1	3	2	2
CATHERINE CREEK	14	3	3	3	1	1	1	3	2	2
CATHERINE CREEK	15				unsurveyed					
CATHERINE CREEK	16	2	3	3	1	1	1	3	2	2
CATHERINE CREEK	17	2	3	3	1	1	1	3	2	2
CATHERINE CREEK	18	1	3	2	2	1	1	3	2	2
CATHERINE CREEK	19	2	3	3	1	1	1	3	2	2
CATHERINE CREEK	20	2	3	3	2	1	1	2	2	3
CATHERINE CREEK	21	2	3	3	1	1	2	3	2	2
CATHERINE CREEK	22	3	3	3	1	1	1	3	2	2

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout 0+ Overwintering habitat availability.

Stream	Reach	Cover										Pool Habitat	Gradient	Rating
		Fines	Cobble and boulders	Interstices	Pool Area	Undercut	Large woody debris/100m	Boulders/100m	Cover	Pool Complexity				
CATHERINE CREEK	1	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	2	1	1	1	1	1	1	1	1	1	1	2	3	1
CATHERINE CREEK	3	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	4	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	5	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	6	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	7	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	8	1	1	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	9	1	1	1	1	1	1	1	1	1	3	2	3	1
CATHERINE CREEK	10						unsurveyed							
CATHERINE CREEK	11	1	2	1	1	1	1	1	1	1	1	1	3	1
CATHERINE CREEK	12	2	2	2	3	1	1	2	2	3	3	3	3	2
CATHERINE CREEK	13	3	3	3	1	1	1	3	2	3	2	3	3	3
CATHERINE CREEK	14	3	3	3	1	1	1	3	2	3	2	3	3	3
CATHERINE CREEK	15						unsurveyed							
CATHERINE CREEK	16	2	3	3	1	1	1	3	2	3	2	3	3	3
CATHERINE CREEK	17	2	3	3	1	1	1	3	2	3	2	3	3	3
CATHERINE CREEK	18	1	3	1	2	1	1	3	2	3	3	3	3	2
CATHERINE CREEK	19	2	3	3	1	1	1	3	2	3	2	3	3	3
CATHERINE CREEK	20	2	3	3	2	1	1	2	2	3	3	3	3	3
CATHERINE CREEK	21	2	3	3	1	1	2	3	2	3	2	3	3	3
CATHERINE CREEK	22	3	3	3	1	1	1	3	2	3	2	3	3	3

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout 1+ Summer Rearing habitat availability.

Stream	Reach	Cover										Cover	Rating
		Fines	Cobble and boulders	Interstices	Pool Area	Depth in fast water units	Undercut	Large woody debris/100m	Boulders /100m				
CATHERINE CREEK	1	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	2	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	3	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	4	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	5	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	6	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	7	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	8	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	9	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	10						unsurveyed						
CATHERINE CREEK	11	1	2	2	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	12	2	2	2	3	1	1	1	2	2	2	2	2
CATHERINE CREEK	13	3	3	3	1	1	1	1	3	2	2	2	2
CATHERINE CREEK	14	3	3	3	1	1	1	1	3	2	2	2	2
CATHERINE CREEK	15						unsurveyed						
CATHERINE CREEK	16	2	3	3	1	1	1	1	3	2	2	2	2
CATHERINE CREEK	17	2	3	3	1	1	1	1	3	2	2	2	2
CATHERINE CREEK	18	1	3	2	2	1	1	1	3	2	2	2	2
CATHERINE CREEK	19	2	3	3	1	1	1	1	3	2	2	2	2
CATHERINE CREEK	20	2	3	3	2	1	1	1	2	2	2	2	2
CATHERINE CREEK	21	2	3	3	1	1	1	2	3	2	2	2	2
CATHERINE CREEK	22	3	3	3	1	1	1	1	3	2	2	2	2

HabRate model for Catherine Creek 2010 habitat survey data for Steelhead trout 1+
Overwintering habitat availability.

Stream	Reach	Cover										Cover	Rating
		Fines	Cobble and boulders	Interstices	Pool Area	Pool Complexity	Pool Habitat	Undercut	Large woody debris/100m	Boulders/ 100m			
CATHERINE CREEK	1	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	2	1	1	1	1	2	2	1	1	1	1	1	1
CATHERINE CREEK	3	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	4	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	5	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	6	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	7	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	8	1	1	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	9	1	1	1	1	3	2	1	1	1	1	1	1
CATHERINE CREEK	10						unsurveyed						
CATHERINE CREEK	11	1	2	1	1	1	1	1	1	1	1	1	1
CATHERINE CREEK	12	2	2	2	3	3	3	1	1	2	2	2	2
CATHERINE CREEK	13	3	3	3	1	3	2	1	1	3	2	3	3
CATHERINE CREEK	14	3	3	3	1	3	2	1	1	3	2	3	3
CATHERINE CREEK	15						unsurveyed						
CATHERINE CREEK	16	2	3	3	1	3	2	1	1	3	2	3	3
CATHERINE CREEK	17	2	3	3	1	3	2	1	1	3	2	3	3
CATHERINE CREEK	18	1	3	1	2	3	3	1	1	3	2	2	2
CATHERINE CREEK	19	2	3	3	1	3	2	1	1	3	2	3	3
CATHERINE CREEK	20	2	3	3	2	3	3	1	1	2	2	3	3
CATHERINE CREEK	21	2	3	3	1	3	2	1	2	3	2	3	3
CATHERINE CREEK	22	3	3	3	1	3	2	1	1	3	2	3	3