

Η

OPCC Lake Kachess Inactive Storage

APPENDIX H.1

OPCC Lake Kachess Inactive Storage - Alternative 1

Yakima River Basin Water Storage Study Kachess Inactive Storage Alternate 1 - Tunnel to Yakima

US Department of the Interior Bureau of Reclamation Pacific Northwest Region

HDR Engineering, Inc

9/20/2010

Appraisal 3rd Qtr 2010 Union Open Competition

This Feature involves modifying the existing natural lake reservoir so that water can be taken at depths below the current minimum pool elevation. This would be the equivalent of enlarging the reservoir without requiring additional land to be inundated, allows the current reservoir to remain operational during much of the construction process, and is less costly than enlarging the existing reservoir. Alternative one would be a tunnel aligned from the portal next to the lake approximately 24,200 If southeast and downstream to a discharge into the Yakima River through a portal next to the river. A 20 cfs pump station would be constructed in the lakeside portal as a minimum in stream flow to the Kachess River.



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Feature Estimate Summary Report

Page 2 10/4/2010 4:57 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Labor	Material	Subcontract	Equipment	Other	Total
Description		Quantity		Amount	Amount	Amount	Amount	Amount	Amount
01_TUNNEL	LAKE KACHESS OUTLET TO PUMP STATION	2,900.00	LF	355,388	2,730,509	9,441,731	381,771		12,909,399
02_PUMP STATION	PUMP STATION_20 CFS	1.00	LS	1,619,413	3,833,789	9,581,981	187,327	106,000	15,328,510
03_PIPELINE	PIPELINE_20" FROM PUMP STATION TO KACHESS RIVER DISCHARGE	1.00	LS	1,088,045	645,082		1,389,124		3,122,252
04_TUNNEL	TUNNEL FROM PUMP STATION TO YAKIMA RIVER	24,200.00	LF			85,996,593			85,996,593
05_YR DISCHARGE	YAKIMA RIVER DISCHARGE STRUCTURE	1.00	LS	1,904,497	1,700,480		884,402		4,489,379
06_KR DISCHARGE	KACHESS RIVER DISCHARGE STRUCTURE	1.00	LS	129,571	106,138	326,620	23,981		586,311



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Feature Estimate Summary Report

Estimate Totals

Description	Amount	Totals	Rate	
Labor Material Subcontract Equipment Other	5,096,915 9,015,998 105,346,925 2,866,606 106,000			
Subtotal		122,432,444		
Contractor's Fld Ovhd	4,897,298		4.000 %	
Mobilization	2,448,649		2.000 %	
Subtotal w/ mobilization		129,778,391		
Unlisted Items Minor	4,862,604		4.000 %	
Design and Scope Changes Minor	4,862,604		4.000 %	
Cost Est Refinements Minor	2,431,302		2.000 %	
Contractor's Fee	11,354,792		8.000 %	
Contractor's Bonds & Insurance	2,129,023		1.500 %	
Procurement Strategy-Open Comp				
Contract Cost		155,418,716		
Contingencies	38,854,679		25.000 %	
Field Cost		194,273,395		
Sales Tax Estimate (Mat & Eq) Escal to NTP (NOTINCL)	969,982		8.200 %	



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Feature Estimate Summary Report Page 4A 10/4/2010 4:57 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

Estimate Totals

Forecasted Feature Bid

195,243,377

Yakima River Basin Water Storage Study Kachess Inactive Storage Alternate 1 - Tunnel to Yakima

US Department of the Interior Bureau of Reclamation Pacific Northwest Region

HDR Engineering, Inc

9/20/2010

Appraisal 3rd Qtr 2010 Union Open Competition

This Feature involves modifying the existing natural lake reservoir so that water can be taken at depths below the current minimum pool elevation. This would be the equivalent of enlarging the reservoir without requiring additional land to be inundated, allows the current reservoir to remain operational during much of the construction process, and is less costly than enlarging the existing reservoir. Alternative one would be a tunnel aligned from the portal next to the lake approximately 24,200 If southeast and downstream to a discharge into the Yakima River through a portal next to the river. A 20 cfs pump station would be constructed in the lakeside portal as a minimum in stream flow to the Kachess River.

989-WA-YAKIMA

LTD	ONE COMPANY Many Solutions®
	Many Solutions®

Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 2 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

			Total	
Description		Quantity	Unit Cost	Amoun
01_TUNNEL	LAKE KACHESS	OUTLET TO PUMP STATIO	DN .	
DIVISION 02	SITE CONSTRUCTION			
02400.100	Tunneling Lake Inlet to Pump Station	1.00 ls	9,216,731.00 /ls	9,216,731
Tunnel from Lake Kacl	hess Outlet to Pump Station; includes but	not limited to shaft, tunnel, rock tra	ap, and rock plug	
DIVISION 02 SITE CO	NSTRUCTION		9,216,731.00 /ls	9,216,731
1.00 l	s			
DIVISION 13	SPECIAL CONSTRUCTION			
13300.000	Fish Screens - SS Wedge Wire	1,000.00 cfs	3,692.67 /cfs	3,692,668
1000cfs fish screen. 7'	Cylinders dia x 26' long(4ea), mounted on 20' dia. S	SS Pipe arouted into rock lake botto	om	
DIVISION 13 SPECIAL			3,692,668.38 /ls	3,692,668
1.00 l	5			
7,936.000 L	abor hours			
7,936.000 L	-			
7,936.000 L 3,392.00 E	abor hours		4,451.52 /LF	12,909,399
7,936.000 L 3,392.00 E	abor hours Equipment hours		4,451.52 /LF	12,909,399
7,936.000 L 3,392.00 E 01_TUNNEL LAK	abor hours Equipment hours		4,451.52 /LF	12,909,399
7,936.000 L 3,392.00 E 01_TUNNEL LAK PUMP STATION 2,900.00 L 7,936.000 L	Labor hours Equipment hours E KACHESS OUTLET TO LF Labor hours		4,451.52 /LF	12,909,399
7,936.000 L 3,392.00 E 01_TUNNEL LAK PUMP STATION 2,900.00 L 7,936.000 L	Labor hours Equipment hours E KACHESS OUTLET TO LF		4,451.52 /LF	12,909,399
7,936.000 L 3,392.00 E 01_TUNNEL LAK PUMP STATION 2,900.00 L 7,936.000 L	abor hours Equipment hours E KACHESS OUTLET TO LF abor hours Equipment hours	20 CFS	4,451.52 /LF	12,909,399
7,936.000 L 3,392.00 E 01_TUNNEL LAK PUMP STATION 2,900.00 L 3,392.00 E	abor hours Equipment hours E KACHESS OUTLET TO LF abor hours Equipment hours	20 CFS	4,451.52 /LF	12,909,399



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 3 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total		
Description		Quantity		Unit Cost	Amount	
02513.000	Asphaltic Concrete Vehicular Paving	2,670.00	sy	33.941/sy	90,621	
DIVISION 02 SITE	0			4,274,452.27 /ls	4,274,452	
1.00	ls					
259.19	Labor hours					
130.04	Equipment hours					
DIVISION 03	CONCRETE					
03002.111	20cfs Valve	19.00	су	401.18 /cy	7,622	
	Vault_Concrete_Foundations					
Excavation included	l in Div 15					
03002.300	Concrete_Walls Exterior	6,529.00	су	375.19 /cy	2,449,610	
03002.311	20cfs Valve	83.00	су	508.90 /cy	42,238	
	Vault_Concrete_Walls Exterior					
03002.600	Concrete_Elevated Slab	2,276.00	су	369.88 /cy	841,835	
03002.611	20cfs Valve	9.00	су	538.272/cy	4,844	
	Vault_Concrete_Elevated Slab					
03002.700	Concrete_Slab on Grade	304.00	су	338.59 /cy	102,931	
03002.825	Concrete_Stairs	32.00	су	1,075.78 /cy	34,425	
05900.000	Miscellaneous Metal	1.00	ls	4,077.83 /ls	4,078	
DIVISION 03 CONC	RETE			381.532/cy	3,487,584	
9,141.00	су					
30,771.534	Labor hours					
2,400.484	Equipment hours					
DIVISION 05	METALS					
05505.000	Metal Fabrications	1.00	LS	5,316.19 /LS	5,316	
05522.000	Aluminum Railings	550.00	LF	120.87 /LF	66,479	
DIVISION 05 META	LS			71,794.81 /ls	71,795	
1.00	s					
	Labor hours					
DIVISION 08	DOORS & WINDOWS					
08305.000	Access Doors	10.00	EA	2,939.51 /EA	29,395	



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 4 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total	
Description		Quantity		Unit Cost	Amount
083450.50	Watertight Doors	1.00	EA	23,154.57_/EA	23,155
DIVISION 08 DOOR	S & WINDOWS			52,549.62 /ls	52,550
1.00	ls				
67.56	Labor hours				
8.00	Equipment hours				
DIVISION 11	EQUIPMENT				
11065.000	Pumping Equipment: Sump	1.00	ea	168,543.32 /ea	168,543
11072.000	Pumping Equipment: Vertical Turbine (Line Shaft)	2.00	ea	472,214.19 /ea	944,428
DIVISION 11 EQUIF	PMENT			1,112,971.69 /ls	1,112,972
1.00	ls				
449.000	Labor hours				
74.833	Equipment hours				
DIVISION 13	SPECIAL CONSTRUCTION				
13020.000	Building Modules	1.00	ls	1,204,000.00 /ls	1,204,000
DIVISION 13 SPEC	IAL CONSTRUCTION			1,204,000.00 /ls	1,204,000
1.00	ls				
DIVISION 15	MECHANICAL				
02221.000	Trenching, Backfilling and	1,046.00	су	65.09 /cy	68,079
	Compacting for Utilities				
Includes excavation	for valve vault				
15062.000	Pipe: Ductile	1.00	lf	42,919.88 /lf	42,920
15103.000	Butterfly Valves	4.00	ea	8,583.42 /ea	34,334
15115.000	Water Control Gates	3.00	ea	247,225.733/ea	741,677
15190.010	Pipe Expansion Joints - Bellows Style	4.00	ea	1,856.96 /ea	7,428
DIVISION 15 MECH	-			894,437.57 /ls	894,438

1.00 ls

2,503.162 Labor hours 939.282 Equipment hours



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 5 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

			Total	
Description		Quantity	Unit Cost	Amount
DIVISION 16	ELECTRICAL			
16000.100 Pump Station Discharge (Electrical Subcontractor Control Building/ Electrical_I&C.	1.00 ls	394,150.00 /ls	394,150
16000.210	Electrical Subcontractor - Substation Power Feed with Relays	4.00 mile	950,000.00 /mile	3,800,000
		e existing source, ROW	cost is not included in the allowance. Assumed a	listance 4 miles, all
motors to be operating. 16230.000	Engine Generator: Diesel	1.00 ls	36,569.34 /ls	36,569
DIVISION 16 ELECTRICA	ncy functions not for pump operation. Pa IL	a includea.	4,230,719.34 /LS	4,230,719
51.282 Labo 10.26 Equi			15,328,509.62 /LS	15,328,510
1.00 LS 34,395.054 Labo 3,562.90 Equi	or hours pment hours			
34,395.054 Labo	or hours pment hours	I PUMP STATION	TO KACHESS RIVER DISCHARGE	
34,395.054 Labo 3,562.90 Equi	or hours pment hours PIPELINE_20" FROM GENERAL REQUIREMENTS Administrative Requirements	1 PUMP STATION	TO KACHESS RIVER DISCHARGE	21,221 21,221
34,395.054 Labo 3,562.90 Equip 03_PIPELINE DIVISION 01 01300.000	or hours pment hours PIPELINE_20" FROM GENERAL REQUIREMENTS Administrative Requirements REQUIREMENTS or hours		21,221.15 /ls	

HR ONE COMPANY Many Solutions®

Labor Rate Table - 3rd Qtr 2010 Union Equipment Rate Table -3rd Qtr 2010 City Index - 989-WA-YAKIMA

Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 6 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total	
Description	Quantity			Unit Cost	Amount
02110.000 Includes 6500LF @	Site Clearing	7.46	acre	9,059.042/acre	67,580
02930.000	Seeding, Sodding, and Landscaping	7.46	acre	974.052/acre	7,266
DIVISION 02 SITE				74,846.88 /ls	74,847
1.00	ls				
730.47	Labor hours				
559.930	Equipment hours				
DIVISION 15	MECHANICAL				
02221.000	Trenching, Backfilling and Compacting for Utilities	40,925.00	су	50.133/cy	2,051,710
Includes excavation	for valve vault				
15062.000	Pipe: Ductile	6,599.00	lf	147.67 /lf	974,474
DIVISION 15 MECH	IANICAL			3,026,183.58 /ls	3,026,184
1.00	ls				
21,067.615	Labor hours				
19,326.58	Equipment hours				
03 PIPELINE P	PIPELINE_20" FROM PUMP			3,122,251.61 /LS	3,122,252
_	ACHESS RIVER DISCHARGE				
1.00	LS				
22,195.95	Labor hours				
19,985.974	Equipment hours				
	TUNNEL FROM I	PUMP STATIO	N TO YAKIMA F	RIVER	
04_TUNNEL					
_					
DIVISION 02	SITE CONSTRUCTION	24 200 00	lf	3 553 58 /lf	85 996 593
DIVISION 02 02400.300	Tunnel Main	24,200.00	lf	3,553.58 /lf 85.996.593.000/ls	<u> </u>
DIVISION 02	Tunnel Main CONSTRUCTION	24,200.00	lf	<u>3,553.58</u> /lf 85,996,593.000/ls	<u> </u>



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 7 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total	
Description		Quantity		Unit Cost	Amoun
04_TUNNEL TU TO YAKIMA RIV 24,200.00				3,553.58 /LF	85,996,59
05_YR DISCHAR	GE YAKIMA RIVER L	DISCHARGE S	TRUCTURE		
DIVISION 02	SITE CONSTRUCTION				
02360.000	Cofferdam	3,000.00	sf	22.924/sf	68,773
DIVISION 02 SITE (CONSTRUCTION			68,773.240/Is	68,77
1.00	ls				
584.34	Labor hours				
292.17	Equipment hours				
DIVISION 03	CONCRETE				
02200.000	Earthwork	46,998.00	су	24.86 /cy	1,168,15
Hauling to stockpile	20 mile RT				
03002.100	Concrete_Foundations	4,709.00	су	391.17 /cy	1,842,00
03002.300	Concrete_Walls Exterior	1,379.00	,	740.711/cy	1,021,44
03002.600	Concrete_Elevated Slab	556.00	су	512.912/cy	285,17
03002.700	Concrete_Slab on Grade	194.00	су	383.06 /cy	74,31
03002.835 DIVISION 03 CONC	Concrete Spillway	28.00	су	1,054.304/cy 641.23 /cy	29,52 4,420,60
				011120709	4,120,00
6,894.00	су				
40,460.75	Labor hours				
10,607.31	Equipment hours				
05_YR DISCHA	RGE YAKIMA RIVER			4,489,379.10 /LS	4,489,379
DISCHARGE ST					
1.00	LS				
	Labor hours				

41,045.09 Labor hours 10,899.48 Equipment hours



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 8 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total	
Description		Quantity		Unit Cost	Amount
06_KR DISCHAR	GE KACHESS RIVER D	ISCHARGE	STRUCTURE		
DIVISION 02	SITE CONSTRUCTION				
02360.000	Cofferdam	3,000.00	sf	22.924/sf	68,773
02513.000	Asphaltic Concrete Vehicular Paving	667.50	sy	24.44 /sy	16,310
02930.000	Seeding, Sodding, and Landscaping	1.00	acre	25,250.00 /acre	25,250
DIVISION 02 SITE	CONSTRUCTION			110,333.52 /ls	110,334
1.00					
632.81 313.23	Labor hours Equipment hours				
DIVISION 03	CONCRETE				
03002.100	Concrete_Foundations	89.00	су	476.523/cy	42,411
03002.300	Concrete_Walls Exterior	77.00	су	739.94 /cy	56,975
03002.600	Concrete_Elevated Slab	44.00	су	517.06 /cy	22,751
03002.700	Concrete_Slab on Grade	59.00	су	388.992/cy	22,951
03002.835	Concrete Spillway	28.00	су	1,054.304/cy	29,521
DIVISION 03 CONC	RETE			641.94 /cy	174,607
272.00	- ,				
,	Labor hours Equipment hours				
DIVISION 13	SPECIAL CONSTRUCTION				
13020.000	Building Modules	1.00	ls	56,250.00 /ls	56,250
DIVISION 13 SPEC	IAL CONSTRUCTION			56,250.00 /ls	56,250
1.00	ls				
DIVISION 16	ELECTRICAL				
16000.100	Electrical Subcontractor				245,120
Pump Station, Disch	narge Control Building/ Electrical_I&C.				



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 9 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

		Total	Total	
Description	Quantity	Unit Cost	Amount	
DIVISION 16 ELECTRICAL			245,120	
06_KR DISCHARGE KACHESS RIVER		586,310.65 /LS	586,311	
DISCHARGE STRUCTURE				
1.00 LS				
2,748.59 Labor hours				

495.492 Equipment hours



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Estimate Totals

Description	Amount	Totals	Rate	
Labor Material Subcontract Equipment Other	5,096,915 9,015,998 105,346,925 2,866,606 106,000			
Subtotal		122,432,444		
Contractor's Fld Ovhd	4,897,298		4.000 %	
Mobilization	2,448,649		2.000 %	
Subtotal w/ mobilization		129,778,391		
Unlisted Items Minor	4,862,604		4.000 %	
Design and Scope Changes Minor	4,862,604		4.000 %	
Cost Est Refinements Minor	2,431,302		2.000 %	
Contractor's Fee	11,354,792		8.000 %	
Contractor's Bonds & Insurance	2,129,023		1.500 %	
Procurement Strategy-Open Comp				
Contract Cost		155,418,716		
Contingencies	38,854,679		25.000 %	
Field Cost		194,273,395		
Sales Tax Estimate (Mat & Eq)	969,982		8.200 %	
Upper Rang	je +40%	AACE Classification Acc	uracy Range Lower Range -20%	



Kachess Inactive Storage_Alt 1 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 11A 10/4/2010 4:56 PM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

Estimate Totals

Escal to NTP (NOTINCL) Forecasted Feature Bid

195,243,377

This Page Intentionally Left Blank

APPENDIX H.2

OPCC Lake Kachess Inactive Storage - Alternative 2

US Department of the Interior Bureau of Reclamation Pacific Northwest Region

HDR Engineering, Inc

8/16/2010

Appraisal 3rd Qtr 2010 Union Open Competition

This Feature involves modifying the existing natural lake reservoir so that water can be taken at depths below the current minimum pool elevation. This would be the equivalent of enlarging the reservoir without requiring additional land to be inundated, allows the current reservoir to remain operational during much of the construction process, and is less costly than enlarging the existing reservoir. Alternative two would be a 1000 cfs pump station located in the portal next to the lake. The pump station would pump water from the shorter lake tap tunnel through a 6500 lf pipeline aligned to the southwest to discharge in to the Kachess River downstream of the existing Kachess Dam outlet channel. The pump station would also include 20 cfs pumps to provide a minimum in stream flow to the Kachess River.



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Feature Estimate Summary Report

Page 2 10/5/2010 11:48 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Labor	Material	Subcontract	Equipment	Other	Total
Description		Quantity		Amount	Amount	Amount	Amount	Amount	Amount
01_TUNNEL	LAKE KACHESS OUTLET TO PUMP STATION	2,900.00	LF	355,388	2,730,509	9,441,730	381,771		12,909,398
02_PUMP STATION	PUMP STATION_1,000 CFS	1.00	LS	5,088,850	52,333,003	20,811,525	961,518	56,000	79,250,896
03_PIPELINE	PIPELINE_PUMP STATION TO KACHESS RIVER DISCHARGE	6,500.00	LF	2,701,729	6,641,615	650,000	4,521,180		14,514,524
04_KR DISCHARGE	KACHESS RIVER DISCHARGE STRUCTURE	1.00	LS	435,614	363,187	349,250	195,350		1,343,400



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Feature Estimate Summary Report

Page 3A 10/5/2010 11:48 AM HDR-DBI, Inc. Estimating Team ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

Estimate Totals

Description	Amount	Totals	Rate	
Labor	8,581,581			
Material	62,068,314			
Subcontract Equipment	31,252,505 6,059,818			
Other	56,000			
Subtotal		108,018,218		
Contractor's Fld Ovhd	4,320,729		4.000 %	
Mobilization	2,160,364		2.000 %	
Subtotal w/ mobilization		114,499,311		
Unlisted Items Minor	4,237,050		4.000 %	
Design and Scope Changes Minor	4,237,050		4.000 %	
Cost Est Refinements Minor	2,118,525		2.000 %	
Contractor's Fee	7,505,516		6.000 %	
Contractor's Bonds & Insurance	1,876,379		1.500 %	
Procurement Strategy-Open Comp				
Contract Cost		134,473,831		
Contingencies	33.618.458		25.000 %	
_	00,010,100	400 000 000		
Field Cost		168,092,289		
Sales Tax Estimate (Mat & Eq)	5,527,320		8.200 %	
Escal to NTP (NOTINCL)				
(\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Feature Estimate Summary Report Page 4A 10/5/2010 11:48 AM HDR-DBI, Inc. Estimating Team ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

Estimate Totals

Forecasted Feature Bid

173,619,609

US Department of the Interior Bureau of Reclamation Pacific Northwest Region

HDR Engineering, Inc

8/16/2010

Appraisal 3rd Qtr 2010 Union Open Competition

This Feature involves modifying the existing natural lake reservoir so that water can be taken at depths below the current minimum pool elevation. This would be the equivalent of enlarging the reservoir without requiring additional land to be inundated, allows the current reservoir to remain operational during much of the construction process, and is less costly than enlarging the existing reservoir. Alternative two would be a 1000 cfs pump station located in the portal next to the lake. The pump station would pump water from the shorter lake tap tunnel through a 6500 lf pipeline aligned to the southwest to discharge in to the Kachess River downstream of the existing Kachess Dam outlet channel. The pump station would also include 20 cfs pumps to provide a minimum in stream flow to the Kachess River.

989-WA-YAKIMA

HR	ONE COMPANY		
	Many Solutions®		

Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 2 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

			Total	
Description		Quantity	Unit Cost	Amoun
01_TUNNEL	LAKE KACHESS (DUTLET TO PUMP STATI	ON	
DIVISION 02 02400.100	SITE CONSTRUCTION Tunneling Lake Inlet to Pump	1.00 ls	9,216,730.00 /ls	9,216,730
Tunnel from Lake Ka DIVISION 02 SITE C	Station chess Outlet to Pump Station; includes but ONSTRUCTION	not limited to shaft, tunnel, rock	trap, and roc <u>k plug</u> 9,216,730.00 /Is	9,216,730
1.00	ls			
DIVISION 13 13300.000	SPECIAL CONSTRUCTION Fish Screens - SS Wedge Wire Cylinders 7'dia x 26' long(4ea), mounted on 20' dia. S	1.00 ls	3,692,668.38 /ls	3,692,668
	AL CONSTRUCTION	S Fipe grouted into rock lake bo	3,692,668.38 /sf	3,692,668
7,936.000	sf Labor hours Equipment hours			
01_TUNNEL LA	KE KACHESS OUTLET TO		4,451.52 /LF	12,909,398
2,900.00 7,936.000 3,392.00	LF Labor hours Equipment hours			
02_PUMP STATIC	N PUMP STATION_1	,000 CFS		
DIVISION 02	SITE CONSTRUCTION			
02400.200	Pump Station Shaft	1.00 ls	8,251,335.00 /ls	8,251,335



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 3 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total	
Description		Quantity		Unit Cost	Amount
02513.000	Asphaltic Concrete Vehicular Paving	2,670.00	sy	33.941/sy	90,621
DIVISION 02 SITE	5			8,341,956.27 /ls	8,341,956
1.00	ls				
259.19	Labor hours				
130.04	Equipment hours				
DIVISION 03	CONCRETE				
03002.300	Concrete_Walls Exterior	23,781.00	су	353.57 /cy	8,408,145
03002.600	Concrete_Elevated Slab	5,984.00	су	366.54 /cy	2,193,361
03002.700	Concrete_Slab on Grade	698.00	су	355.19 /cy	247,922
03002.825	Concrete_Stairs	32.00	су	1,075.78 /cy	34,425
DIVISION 03 CONC	RETE			357.281/cy	10,883,852
30,463.00	су				
90,754.212	Labor hours				
7,827.98	Equipment hours				
DIVISION 05	METALS				
05505.000	Metal Fabrications	1.00	ls	25,163.12 /ls	25,163
05522.000	Aluminum Railings	550.00	lf	120.87 /lf	66,479
DIVISION 05 META	LS			91,641.75 /Is	91,642
1.00	ls				
332.28	Labor hours				
5.65	Equipment hours				
DIVISION 08	DOORS & WINDOWS				
08305.000	Access Doors	10.00	ea	2,939.51 /ea	29,395
083450.50	Watertight Doors	1.00	ea	23,154.56 /ea	23,155
DIVISION 08 DOOF	RS & WINDOWS			52,549.61 /ls	52,550
1.00	ls				
67.56	Labor hours				

67.56 Labor hours

8.00 Equipment hours



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 4 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total		
Description		Quantity		Unit Cost	Amount	
DIVISION 11 11065.000 11072.000 DIVISION 11 EQUIF	EQUIPMENT Pumping Equipment: Sump Pumping Equipment: Vertical Turbine (Line Shaft)				168,543 34,394,020 	
1.00 1,889.000				34,502,505.250/15	34,302,303	
DIVISION 13 13020.000	SPECIAL CONSTRUCTION Building Modules AL CONSTRUCTION			210.00 /sf	<u>3,141,600</u> 3,141,600	
14,960.00				210.00751	3,141,000	
DIVISION 14 14305.000 DIVISION 14 CONV	CONVEYING SYSTEMS Bridge Cranes EYING SYSTEMS	1.00	ea	<u>199,441.37</u> /ea 199,441.37 /s f	<u> </u>	
1.00 153.413 12.03	Labor hours					
DIVISION 15	MECHANICAL					
02221.000	Trenching, Backfilling and Compacting for Utilities	12,007.00	су	57.872/cy	694,873	
03002.110	200cfs Valve Vault_Concrete_Foundations	178.00	CY	385.022/CY	68,534	
03002.111	20cfs Valve	19.00	су	365.48 /cy	6,944	
03002.310	Vault_Concrete_Foundations 200cfs Valve	190.00	су	737.61 /cy	140,146	
03002.311	Vault_Concrete_Walls 20cfs Valve Vault_Concrete_Walls Exterior	83.00	су	508.90 /cy	42,238	

HR ONE COMPANY Many Solutions®

Labor Rate Table - 3rd Qtr 2010 Union Equipment Rate Table -3rd Qtr 2010 City Index - 989-WA-YAKIMA

Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 5 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total	
				Total	
Description		Quantity		Unit Cost	Amount
03002.605	200cfs Valve	88.00	су	521.791/cy	45,918
	Vault_Concrete_Elevated Slab				
03002.611	20cfs Valve	9.00	су	538.272/cy	4,844
	Vault_Concrete_Elevated Slab				
15061.100	Pipe: Steel- 26" and larger	7,000.00	lf	1,298.672/lf	9,090,703
15062.000	Pipe: Ductile	100.00	lf	407.084/lf	40,708
15103.000	Butterfly Valves	16.00	ea	48,760.20 /ea	780,163
15106.000	Check Valves	6.00	ea	94,062.60 /ea	564,376
15115.000	Water Control Gates	5.00	ea	106,473.384/ea	532,367
15190.010	Pipe Expansion Joints - Fabricated	16.00	ea	31,243.70 /ea	499,899
DIVISION 15 MECH				12,511,712.94 /ls	12,511,713
1.00	ls				
14,955.743	Labor hours				
9,376.820	Equipment hours				
DIVISION 16	ELECTRICAL				
16000.100	Electrical Subcontractor	1.00	ls	5,018,590.00 /ls	5,018,590
	ubstation, Discharge Control Building/ Elect		15	5,018,590.00715	5,016,590
16000.210	Electrical Subcontractor -	4.00	mile	1,100,000.00 /mile	4,400,000
10000.210	Substation Power Feed with	4.00	TIME	1,100,000.00 /11111	4,400,000
	Relays				
Allowance assumes	the Power Supplier will perform the cut in a	at the existing sour	ce ROW cost is r	not included in the allowance Assumed d	istance 4 miles all
motors to be operati		a are existing sour			istarios + miles, all
16230.000	Engine Generator: Diesel	1.00	ea	46,988.71 /ea	46,989
	nergency functions not for pump operation.		ou	10,000.11,00	10,000
DIVISION 16 ELECT		r aa moladoa.		9,465,578.710/Is	9,465,579
DIVISION IN LELO	INICAL			3,403,570.71013	3,403,373
1.00					
	Labor hours				
12.903	Equipment hours				
02_PUMP STAT	TION PUMP STATION_1,000 CFS			79,250,896.330/LS	79,250,896
1.00	LS				

 1.00
 LS

 108,475.904
 Labor hours

 17,688.25
 Equipment hours

Image: Constraint of the second systemONE COMPANY Many Solutions*Labor Rate Table - 3rd Qtr 2010 UnionEquipment Rate Table - 3rd Qtr 2010City Index - 989-WA-YAKIMA	Yakima	ess Inactive Storage_Alt 2 a River Basin Water Storage Study YRSS PN Appraisal stimate Pay Item Report		Page 10/5/2010 11:49 A HDR-DBI, Inc. Estimate Rep ESTIMATORS: HDR Estimating Te ESTIMATE VERSION	
		Total			
Description	Quantity	Unit Cost	Amount		
03_PIPELINE PIPELINE_PUMI	P STATION TO KACHES	S RIVER DISCHARGE			
DIVISION 01 GENERAL REQUIREMENT 01300.000 Administrattive Requirements DIVISION 01 GENERAL REQUIREMENTS	S 1.00 ls	44,488.79 /ls 44,488.79 /ls	44,489 44,489		
1.00Is836.853Labor hours149.213Equipment hours					
DIVISION 02 SITE CONSTRUCTION 02110.000 Site Clearing 02930.000 Seeding, Sodding, and Landscaping	11.19 acre 11.19 acre	9,058.64 /acre 973.922/acre	101,366 10,898		
DIVISION 02 SITE CONSTRUCTION		112,264.35 /Is	112,264		
1.00Is1,095.65Labor hours839.853Equipment hours					
DIVISION 15 MECHANICAL 02221.000 Trenching, Backfilling and Compacting for Utilities	93,167.00 cy	75.474/cy	7,031,661		
15061.100 Pipe: Steel- 26" and larger DIVISION 15 MECHANICAL	6,500.00 lf	1,127.094/lf 14,357,770.49 /ls	7,326,110 14,357,770		
1.00 Is 54,088.45 Labor hours 84,921.804 Equipment hours					
03_PIPELINE PIPELINE_PUMP STATION TO KACHESS RIVER DISCHARGE 6,500.00 LF 56,020.95 Labor hours 85,910.87 Equipment hours		2,233.004/LF	14,514,524		



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 7 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

				Total		
Description		Quantity		Unit Cost	Amount	
04_KR DISCHAR	GE KACHESS RIVER D	ISCHARGE	STRUCTURE			
DIVISION 02	SITE CONSTRUCTION					
02360.000	Cofferdam	4,160.00	sf	37.37 /sf	155,443	
02513.000	Asphaltic Concrete Vehicular	667.50	sy	33.02 /sy	22,041	
	Paving					
02950.000	Site Restoration & Rehabilitation	1.00	ls	25,250.00 /ls	25,250	
DIVISION 02 SITE (CONSTRUCTION			202,733.72 /ls	202,734	
1.00	ls					
1,284.32	Labor hours					
642.27	Equipment hours					
DIVISION 03	CONCRETE					
02200.000	Earthwork	8,634.00	су	31.954/cy	275,887	
03002.100	Concrete_Foundations	354.00	cy	373.76 /cy	132,311	
03002.300	Concrete_Walls Exterior	300.00	су	705.86 /cy	211,758	
03002.600	Concrete_Elevated Slab	177.00	су	512.194/cy	90,658	
03002.700	Concrete_Slab on Grade	119.00	су	395.06 /cy	47,012	
03002.835	Concrete Spillway	56.00	су	1,054.304/cy	59,041	
DIVISION 03 CONC	RETE			85.17 /cy	816,667	
9,589.00	су					
7,977.87	Labor hours					
2,781.79	Equipment hours					
DIVISION 13	SPECIAL CONSTRUCTION					
13020.000	Building Modules	375.00	sf	210.00 /sf	78,750	
DIVISION 13 SPEC	IAL CONSTRUCTION			210.00 /sf	78,750	
					,	
375.00	sf					
DIVISION 16	ELECTRICAL					
16000.100	Electrical Subcontractor	1.00	ls	245,250.00 /ls	245,250	
Pump Station, PS S	ubstation, Discharge Control Building/ Electric	al_I&C.				

AACE Classification Accuracy Range

Lower Range -20%



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 8 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

		Total	
Description	Quantity	Unit Cost	Amount
DIVISION 16 ELECTRICAL		245,250.00 /ls	245,250
1.00 Is			
04_KR DISCHARGE KACHESS RIVER DISCHARGE STRUCTURE		1,343,400.24 /LS	1,343,400
1.00 LS 9,262.185 Labor hours 3,424.06 Equipment hours			



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Estimate Totals

Description	Amount	Totals	Rate	
Labor Material	8,581,581 62,068,314			
Subcontract	31,252,505			
Equipment	6,059,818			
Other	56,000			
Subtotal		108,018,218		
Contractor's Fld Ovhd	4 220 720		4.000 %	
Mobilization	4,320,729		4.000 % 2.000 %	
	2,160,364		2.000 %	
Subtotal w/ mobilization		114,499,311		
Unlisted Items Minor	4,237,050		4.000 %	
Design and Scope Changes Minor	4,237,050		4.000 %	
Cost Est Refinements Minor	2,118,525		2.000 %	
Contractor's Fee	7,505,516		6.000 %	
Contractor's Bonds & Insurance	1,876,379		1.500 %	
Procurement Strategy-Open Comp	.,			
Contract Cost		134,473,831		
Contingencies	33 618 /58		25.000 %	
-	55,010,450		23.000 /0	
Field Cost		168,092,289		
Sales Tax Estimate (Mat & Eq)	5,527,320		8.200 %	
		AACE Classification Acc	uracy Range	

Upper Range +40%



Kachess Inactive Storage_Alt 2 Yakima River Basin Water Storage Study YRSS PN Appraisal Estimate Pay Item Report

Page 10A 10/5/2010 11:49 AM HDR-DBI, Inc. Estimate Report ESTIMATORS: HDR Estimating Team ESTIMATE VERSION: 1

Estimate Totals

Escal to NTP (NOTINCL) Forecasted Feature Bid

173,619,609