

Yakima River Basin Integrated Water Resource Management Plan

Technical Memorandum Reconciled Opinion of Probable Construction Cost, Kachess Drought Relief Pumping Plant - Floating Pumping Plant Alternative

U.S. Bureau of Reclamation

Contract No. R13PC10006 ID/IQ

Draft

Prepared by

HDR Engineering, Inc.
Orion Marine Group
Glosten
Shannon & Wilson



**U.S. Department of the Interior
Bureau of Reclamation
Pacific Northwest Region
Columbia-Cascades Area Office**



**State of Washington
Department of Ecology
Office of Columbia**

December 21, 2017

MISSION STATEMENTS

U.S. Department of the Interior

Protecting America's Great Outdoors and Powering our Future.

The U.S. Department of the Interior protects America's natural resources and heritage, honors our cultures and Tribal communities, and supplies the energy to power our future.

Bureau of Reclamation

The mission of the Bureau of Reclamation is to manage, develop, and protect water and related resources in an environmentally and economically sound manner in the interest of the American public.

Washington State Department of Ecology

The Mission of the Washington State Department of Ecology is to protect, preserve and enhance Washington's environment, and promote the wise management of our air, land, and water for the benefit of current and future generations.

If you need this document in a format for the visually impaired, call the Office of Columbia River at (509) 575-2490. Persons with hearing loss can call 711 for Washington Relay Service. Persons with a speech disability can call 877-833-6341.

Contents

1.0	Background and Purpose	1
1.0	Approach	1
2.0	Separation of Costs for Deferred Future Construction from Initial Construction	7
3.0	Results	9

List of Tables

Table 1.	OPCC Comparison	2
Table 2.	Reconciled OPCC	5
Table 3.	Deferred Costs – Narrows Upstream Fish Passage Structure.....	8
Table 4.	Deferred Costs – Public Boat Ramp	8
Table 5.	Floating Pumping Plant Alternative Costs (in 2020\$)	9

Attachments

Attachment A Drawings

Attachment B HDRC OPCC

Attachment C Orion Marine Group OPCC

Attachment D Construction Schedule

This page intentionally left blank.

1.0 Background and Purpose

Under contract to the US Bureau of Reclamation (Reclamation), HDR Engineering, Inc. (HDR) has recently prepared an updated conceptual design for the Kachess Drought Relief Pumping Plant, Floating Pumping Plant Alternative. In late 2016, HDR, along with subconsultant Orion Marine Group (OMG) prepared an opinion of probable construction cost (OPCC) for an earlier conceptual design for this alternative. The purpose of this technical memorandum is to document the approach used and results of the HDR Team's preparation of an updated OPCC reflecting the additional information developed during update of the conceptual design. The current updated OPCC has been prepared based on the attached set of thirty (30) drawing sheets (Attachment A) that present the updated conceptual design.

In addition to the development of the drawing set, on Wednesday, October 25, 2017 the senior members of the design team met and held a Construction Plan Workshop. The significant challenge of constructing fixed project features on the floor of the reservoir was discussed, along with discussions of how to construct the floating project features on a reservoir whose water surface elevation can experience changes of up to 80 vertical feet each year. Major construction activities, durations and sequences were developed along with an estimation of the number of "spreads" that would be needed to accomplish the marine construction activities.

A spread is the temporary barge structure that is assembled on-site for construction purposes and consists of a crane located atop a set of floats that is used on the water during construction and subsequently disassembled and removed from the project site once construction is completed. It was determined that two separate spreads would be required for construction of this project alternative. A 2-year-long Construction Schedule is envisioned for this alternative and this schedule is presented in Attachment D.

1.0 Approach

For this current OPCC development effort, HDR and OMG each prepared an independent OPCC based on the attached conceptual design drawing sheets. The independently prepared OPCC by HDR Constructors and OMG are contained in Attachments B and C, respectively. A summary comparison of the two OPCCs is contained in Table 1.

Table 1. OPCC Comparison

Bid Item	Description	QTY	Unit	LH	ORION	LH	HDR	DELTA
1000	MOBILIZATION	1	LS	10,060	\$4,450,000	-	\$2,966,070	\$(1,483,930)
	Mobilization Total				\$4,450,000		\$2,966,070	
2000	CIVIL							
2100	CIVIL: LS-3 EAST SHORE PARKING AREA (3 ACRES)	1	LS		\$325,000		\$384,682	\$59,682
2200	CIVIL: LS-3 EAST SHORE BOAT RAMP (20 X 600 LF)	1	LS		\$700,000		\$382,305	\$(317,695)
2300	CIVIL: LS-2 CONTROL BUILDING AREA (5000 SF)	1	LS		\$100,000		\$698,325	\$598,325
2400	CIVIL: LS-3 EXTEND BOAT RAMP (20X400 LF) LOW POOL	1	LS		\$1,500,000		\$1,500,000	-
2500	CIVIL: LS-3 ACCESS ROAD TO FLOW CONTROL STRUCTURE	1	LS		\$350,000		\$258,228	\$(91,772)
	Civil Total			6,125	\$2,975,000	7,927	\$3,223,540	-
3000	MARINE							
3100	MARINE: RESERVOIR DREDGING	1	LS		\$325,000		\$204,797	\$(120,203)
3200	MARINE: FLOW CONTROL STRUCTURE (W/ 4 GATES)	1	LS		\$3,175,000		\$2,079,270	\$(1,095,730)
3300	MARINE: OUTLET CHANNEL	1	LS		\$1,615,000		\$1,615,813	\$813
3400	MARINE: PIPE BRIDGE STRUCTURES, RIGID	1	LS		\$975,000		\$262,764	\$(712,236)
3500	MARINE: PIPE BRIDGE STRUCTURES, FLEXIBLE	1	LS		\$2,400,000		\$1,175,454	\$(1,224,546)
3600	MARINE: PUMP BARGE FACILITIES	1	LS		\$7,000,000		\$8,137,943	\$1,137,943
3700	MARINE: BARGE ANCHORING	1	LS		\$1,200,000		\$865,589	\$(334,411)
	Marine Total			21,425	\$16,690,000	22,650	\$14,341,630	-
4000	MECHANICAL							
4100	MECHANICAL: VERTICAL TURBINE PUMPS	1	LS		\$10,900,000		\$11,652,489	\$752,489
4200	MECHANICAL: RIGHT ANGLE DRIVES	1	LS		\$3,800,000		\$4,558,924	\$758,924
4300	MECHANICAL: MOTORS	1	LS		\$1,800,000		\$2,121,424	\$321,424
4400	MECHANICAL: DISCHARGE PIPING	1	LS		\$2,150,000		\$2,340,896	\$190,896
	Mechanical Total			5,830	\$18,650,000	10,500	\$20,673,733	
5000	ELECTRICAL							

Bid Item	Description	QTY	Unit	LH	ORION	LH	HDR	DELTA
5100	ELECTRICAL: INTERCONNECTION TO PSE 115 KV	1	LS		\$250,000		\$135,844	\$(114,156)
5200	ELECTRICAL: LAKE EASTON STEPDOWN SUBSTATION	1	LS		\$2,500,000		\$1,834,481	\$(665,519)
5300	ELECTRICAL: TWIN 34.5 KV BURIED TRANSMISSION LINES	1	LS		\$2,750,000		\$2,447,125	\$(302,875)
5400	ELECTRICAL: KACHESS RESERVOIR STEPDOWN SUBSTATION	1	LS		\$1,250,000		\$1,260,644	\$10,644
5500	ELECTRICAL: CONTROL BUILDING & ELECTRICAL EQUIPMENT	1	LS		\$3,500,000		\$4,442,083	\$942,083
5600	ELECTRICAL: MARINE CABLES TO BARGE (4)	1	LS		\$2,750,000		\$555,435	\$(2,194,565)
5700	ELECTRICAL: BARGE ELECTRICAL SYSTEMS	1	LS		\$500,000		\$123,379	\$(376,621)
	Electrical Total			1,400	\$13,500,000	13,700	\$10,798,991	
6000	FISH							
6100	NARROWS UPSTREAM FISH PASSAGE (PHASE 1)	1	LS		\$1,918,000		\$1,918,000	
6200	NARROWS UPSTREAM FISH PASSAGE (PHASE 2)	1	LS		\$21,816,000		\$21,816,000	
	Fish Total							
7000	PSE							
7100	INTERCONNECTION & TRANSMISSION SYST DESIGN/REVIEW	1	LS		\$250,000		\$250,000	
	PSE Total				\$250,000		\$250,000	
	TOTAL			44,840	\$80,249,000	54,777	\$75,987,964	\$(4,261,036)

LH = Labor Hours; LS = Lump Sum; PSE = Puget Sound Energy; QTY = Quantity;
DELTA = Difference between the 2 independent estimates.

		Orion Cost Estimate Breakdown Totals	HDR Cost Estimate Break Down Totals	Cost Delta
Direct Labor		\$3,740,000	\$4,639,160	\$899,160
Permanent Materials		\$29,640,000	\$33,351,860	\$3,711,860
Temporary Materials		\$955,000	-	\$(955,000)
Equipment		\$7,860,000	\$2,649,123	\$(5,210,877)
Subcontract (OMG's * Costs accounted here)		\$37,990,000	\$11,760,428	\$(26,229,572)
Other		\$64,000	-	\$(64,000)
(HDR's * Costs accounted here)		-	\$21,816,000	
Subtotal Const. Direct Costs		\$80,249,000	\$74,216,571	\$(6,032,429)
Project Indirect (Overhead)		\$2,620,000	\$3,954,760	\$1,334,760
Project Indirect (GC's)		\$2,420,000	\$2,471,725	\$51,725
Construction Contingency	25%	\$21,322,250	25% \$20,160,764	\$(1,161,486)
Escalation Project (2020)	5%	\$4,264,450	5% \$4,032,153	\$(232,297)
Subtotal Field Const. Indirect Costs		\$30,626,700	\$30,619,402	\$(7,298)
Contractor's Alternative Delivery Fee	12%	\$13,305,084	12% \$12,580,317	\$(724,767)
Contractor's Bonds & Insurance	1.50%	\$1,862,712	2% \$2,348,326	\$485,614
Washington State Sales Tax	8.0%	\$10,083,480	8.0% \$9,581,169	\$(502,310)
B&O Tax	0.5%	\$680,635	0.5% \$646,729	\$(33,906)
Builders Risk Insurance		\$1,500,000	\$1,500,000	-
Subtotal Other Const. Indirect Costs		\$27,431,910	\$26,656,541	\$(775,370)
Total Construction Cost w/ Tax		\$138,307,610	\$131,492,513	\$(6,815,097)
Orion Marine Design Assist		\$430,000	\$430,000	
HDR Design & Management Fee		\$11,500,000	\$11,500,000	
Total Project Cost		\$150,237,610	\$143,422,513	\$(6,815,097)

* = Contains deferred future costs for construction of the lower portion of the Narrows Fish Passage Structure and the Public Boat Ramp.

On January 23, 2018, the lead estimators from HDR and OMG met with the HDR project manager to reconcile the differences between the two independently prepared OPCC's. Together, they collectively conducted an in-person reconciliation exercise by comparing the two independently prepared OPCCs. Each line item of each OPCC was compared, reviewed and discussed. If a large difference existed for a given line item, then the group closely examined how the number was developed and discussed what assumptions were used in the development of the line item cost. If there was a cost that was reasonably supported by both parties but the resulting cost was different; either the average of the costs was used or the bid item cost was reevaluated to identify the difference in the costs. In several instances the final cost that was reconciled was different, but not necessarily larger than either of the estimates. Additionally, there were assumptions that were identified which moved costs from one bid item to another. Table 2 – reconciled OPCC presents the final results of the fully reconciled OPCC.

Table 2. Reconciled OPCC

Bid Item	Description	QTY	UNIT	RECONCILED
1000	MOBILIZATION	1	LS	\$4,450,000
2000	CIVIL			
2100	CIVIL: LS-3 EAST SHORE PARKING AREA (3 ACRES)	1	LS	\$355,000
2200	CIVIL: LS-3 EAST SHORE BOAT RAMP (20 X 600 LF) PHASE 1	1	LS	\$700,000
2300	CIVIL: LS-2 CONTROL BUILDING AREA (5000 SF)	1	LS	\$100,000
2400	CIVIL: LS-3 EXTEND BOAT RAMP (20X400 LF) PHASE 2	1	LS	Future Cost
2500	CIVIL: LS-3 ACCESS ROAD TO FLOW CONTROL STRUCTURE	1	LS	\$300,000
3000	MARINE			
3100	MARINE: RESERVOIR DREDGING	1	LS	\$325,000
3200	MARINE: FLOW CONTROL STRUCTURE (W/ 4 GATES)	1	LS	\$3,175,000
3300	MARINE: OUTLET CHANNEL	1	LS	\$1,615,000
3400	MARINE: PIPE BRIDGE STRUCTURES, RIGID	1	LS	\$730,000
3500	MARINE: PIPE BRIDGE STRUCTURES, FLEXIBLE	1	LS	\$3,250,000
3600	MARINE: PUMP BARGE FACILITIES	1	LS	\$7,325,000
3700	MARINE: BARGE ANCHORING	1	LS	\$1,200,000
4000	MECHANICAL			
4100	MECHANICAL: VERTICAL TURBINE PUMPS	1	LS	\$11,000,000
4200	MECHANICAL: RIGHT ANGLE DRIVES	1	LS	\$4,500,000
4300	MECHANICAL: MOTORS	1	LS	\$2,000,000
4400	MECHANICAL: DISCHARGE PIPING	1	LS	\$2,350,000
5000	ELECTRICAL			
5100	ELECTRICAL: INTERCONNECTION TO PSE 115 KV	1	LS	\$140,000
5200	ELECTRICAL: LAKE EASTON STEPDOWN SUBSTATION	1	LS	\$1,800,000
5300	ELECTRICAL: TWIN 34.5 KV BURIED TRANSMISSION LINES	1	LS	\$2,200,000
5400	ELECTRICAL: KACHESS RESERVOIR STEPDOWN SUBSTATION	1	LS	\$1,110,000
5500	ELECTRICAL: 4160V CABLES, KRSS TO CONTROL BLDG	1	LS	\$2,132,000
5600	ELECTRICAL: ENCLOSED GENERATOR SET	1	LS	\$125,000
5700	ELECTRICAL: CONTROL BUILDING & EQUIPMENT	1	LS	\$5,000,000
5800	ELECTRICAL: MARINE CABLES, CONTROL BLDG TO MOTORS	1	LS	\$7,519,000

Bid Item	Description	QTY	UNIT	RECONCILED
5900	ELECTRICAL: ON BARGE ELECTRICAL	1	LS	\$200,000
6000	FISH			
6100	NARROWS UPSTREAM FISH PASSAGE (PHASE 1)	1	LS	\$1,918,000
6200	NARROWS UPSTREAM FISH PASSAGE (PHASE 2)	1	LS	Future Cost
7000	PSE			
7100	INTERCONNECTION & TRANSMISSION SYST DESIGN/REVIEW	1	LS	\$250,000
	TOTAL DIRECT COSTS			\$65,769,000

TOTAL DIRECT COSTS		\$65,769,000
PROJECT INDIRECT COSTS		
Project Indirect (Overhead)	7.5%	\$4,932,675
Project Indirect (GC's)	5.0%	\$3,288,450
SUBTOTAL DIRECT PLUS INDIRECT COSTS		\$73,990,125
OTHER INDIRECT COSTS		
Contractor's Alternative Delivery Fee	12.0%	\$8,878,815
Contractor's Bonds & Insurance	2.0%	\$1,479,803
WA State Sales Tax (unincorporated Kittitas Co)	8.0%	\$5,919,210
B&O Tax	0.5%	\$369,951
Builders Risk Insurance	1.0%	\$739,901
SUBTOTAL OTHER INDIRECT COSTS		\$17,387,679
TOTAL ALL DIRECT + INDIRECT COSTS		\$91,377,804
Engineering and Design Costs (2018)	12.0%	\$10,965,336
Construction Contingency (2020)	25.0%	\$24,237,963
Escalation of Project to Midpoint Construction ^A (2020)	6.1%	\$5,574,046
Total Project Cost ^B		\$132,155,149

^A The inflation factor used in the reconciled OPCC is 6.1 percent versus a 5 percent inflation factor used in the two un-reconciled OPCCs. The author believes the 6.1 percent inflation factor is more representative of current inflation estimates.

^B Does not include the deferred future costs required to construct the lower portion of the Narrows Fish Passage Structure (\$43.4 M in 2020\$) and the lower portion of the Public Boat Ramp (\$3.0 M in 2020\$). However, these costs must be taken into consideration for project economics and financing as these two features must be built; but at an as-yet unknown time in the future.

2.0 Separation of Costs for Deferred Future Construction from Initial Construction

There are two future construction actions that cannot be constructed during the initial construction of the drought relief pumping plant project. The two future construction actions that must be deferred are:

1. Extension of the Public Boat Ramp on the east shore of the reservoir.
2. Extension of the Volitional Fish Passage Structure located at the downstream end of the Narrows.

The reason these two construction actions cannot be accomplished during the initial construction phase lies in the fact that the reservoir cannot be physically lowered below the elevation of the existing gravity outlet works (El 2192.75) until after:

1. The drought relief pumping plant has been constructed and is operational.
2. An actual drought occurs and is officially declared to be such. Also, it will most likely require a multi-year drought to occur for both the Public Boat Ramp and the Volitional Fish Passage Structure to be completed in their entireties to their deepest elevations in the reservoir (down to elevation 2113.0).

It is not possible to know in advance if either a single year drought or a multi-year drought will occur. Thus, it will not be possible to schedule out with any certainty when the completion of these two project features will occur in the future. For this reason, the line item costs for these two items have been removed from the original construction contract of this OPCC; as it represents the estimated costs for the initial construction contract only.

Table 2 does not include the deferred costs for construction of the lower portion of either the Narrows Fish Passage Structure (\$43.4 M in 2020\$) or the lower portion of the Public Boat Ramp (\$3.0 M in 2020\$). However, these costs must be taken into consideration for project economics and financing as these two features must be built; but at an as-yet unknown date in the future.

Tables 3 and 4 present calculation of the deferred costs for the lower portion of the Narrows Fish Passage Structure and the lower portion of the Public Boat Ramp, respectively.

Table 3. Deferred Costs – Narrows Upstream Fish Passage Structure

TOTAL DIRECT COSTS (HDR, M. Garelo)		<u>\$21,816,000</u>
PROJECT INDIRECT COSTS		
Project Indirect (Overhead)	7.5%	\$1,636,200
Project Indirect (GC's)	5.0%	\$1,090,800
SUBTOTAL DIRECT PLUS INDIRECT COSTS		<u>\$24,543,000</u>
OTHER INDIRECT COSTS		
Contractor's Alternative Delivery Fee	12.0%	\$2,945,160
Contractor's Bonds & Insurance	2.0%	\$490,860
WA State Sales Tax (unincorporated Kittitas Co)	8.0%	\$1,963,440
B&O Tax	0.5%	\$122,715
Builders Risk Insurance	1.0%	\$245,430
SUBTOTAL OTHER INDIRECT COSTS		<u>\$5,767,605</u>
TOTAL ALL DIRECT + INDIRECT COSTS		<u>\$30,310,605</u>
Engineering and Design Costs (2018)	12.0%	\$3,637,273
Construction Contingency (2020)	25.0%	\$7,577,651
Escalation of Project to Midpoint Construction (2020)	6.1%	\$1,848,947
Total Deferred Narrows Upstream Fish Passage Structure Costs		<u>\$43,374,476</u>

Table 4. Deferred Costs – Public Boat Ramp

TOTAL DIRECT COSTS (OMG, C. Bruneau)		<u>\$1,500,000</u>
PROJECT INDIRECT COSTS		
Project Indirect (Overhead)	7.5%	\$112,500
Project Indirect (GC's)	5.0%	\$75,000
SUBTOTAL DIRECT PLUS INDIRECT COSTS		<u>\$1,687,500</u>
OTHER INDIRECT COSTS		
Contractor's Alternative Delivery Fee	12.0%	\$202,500
Contractor's Bonds & Insurance	2.0%	\$33,750
WA State Sales Tax (unincorporated Kittitas Co)	8.0%	\$135,000
B&O Tax	0.5%	\$8,438
Builders Risk Insurance	1.0%	\$16,875
SUBTOTAL OTHER INDIRECT COSTS		<u>\$396,563</u>
TOTAL ALL DIRECT + INDIRECT COSTS		<u>\$2,084,063</u>
Engineering and Design Costs (2018)	12.0%	\$250,088
Construction Contingency (2020)	25.0%	\$521,016
Escalation of Project to Midpoint Construction (2020)	6.1%	\$127,128
Total Deferred Public Boat Ramp Costs		<u>\$2,982,295</u>

3.0 Results

The reconciled OPCC resulting from the discussions at the reconciliation meeting held on January 23, 2018 along with additional line item input that resulted from a few follow-up activities that were determined to be needed during the meeting are presented in Table 2. The calculated Total Construction Cost for the reconciled OPCC for the project without the costs of the deferred future construction actions is \$132.2 million in 2020 dollars.

At the current level of design, this OPCC is considered a Class 4 cost estimate (i.e. having a maturity level of project definition ranging from 1 percent to 15 percent). A Class 4 cost estimate will have an expected accuracy range having a Low that falls between -15 percent to -30 percent; and a High that falls between +20 percent to +50 percent. The authors place the maturity level of project definition for the Floating Pumping Plant Alternative at approximately 10 percent at present. Correspondingly, the authors have applied an expected range of accuracy to the calculated OPCC of a Low of -25 percent and a High of +40 percent. The basis of this range of accuracy is the AACE International Recommended Practice No. 18R-97, Cost Estimate Classification System – as Applied in Engineering, Procurement and Construction for the Process Industry (Revised March 1, 2016). Applying these accuracy ranges to the calculated OPCC amount of \$132.2 million results in a cost range falling between a Low of \$99.1 million and a High of \$185.1 million.

As presented in Tables 3 and 4, the OPCC for the deferred construction contract costs is \$46.4 million in 2020 dollars. Applying the same accuracy ranges (a Low of -25 percent and a High of +40 percent) to the deferred construction costs results in a cost range for the deferred construction costs falling between a low of \$34.8 million and a high of \$65.0 million.

Table 5 presents the results of the OPCC estimate contained in this memorandum for: 1) the original construction contract costs only; 2) the deferred construction contract costs only; and, 3) the original construction contract costs plus the deferred construction contract costs (all in 2020 dollars).

Table 5. Floating Pumping Plant Alternative Costs (in 2020\$)

OPCC Name	Original Construction Contract Only (\$Million)	Deferred Construction Contract Costs Only (\$Millions)	Original Plus Deferred Construction Contract Costs (\$Millions)
Low Range OPCC	\$99.1	\$34.8	\$133.9
Computed OPCC	\$132.2	\$46.4	\$178.6
High Range OPCC	\$185.1	\$65.0	\$250.1

This page intentionally left blank.

Attachment A Drawings


This page intentionally left blank.




WASHINGTON STATE
SCALE: NO SCALE



VICINITY MAP
SCALE: NO SCALE



LOCATION MAP
SCALE: NO SCALE




INDEX OF DRAWINGS

- | | | |
|----|------|---|
| 1 | G-01 | PLAN - OVERALL PROJECT |
| 2 | G-02 | SITE PLAN - ON RESERVOIR |
| 3 | G-03 | FPPA - MAXIMUM POOL (GRAVITY DISCHARGE) |
| 4 | G-04 | FPPA - MINIMUM POOL (GRAVITY DISCHARGE) |
| 5 | G-05 | FPPA - MAXIMUM POOL (DROUGHT RELIEF PUMPING) |
| 6 | G-06 | FPPA - MINIMUM POOL (DROUGHT RELIEF PUMPING) |
| 7 | M-01 | PLAN PUMPING SYSTEM |
| 8 | M-02 | PROCESS AND INSTRUMENTATION DIAGRAM |
| 9 | M-03 | PROFILE - GRAVITY OPERATION |
| 10 | M-04 | PROFILE - DROUGHT RELIEF PUMPING OPERATION |
| 11 | S-01 | FLOW CONTROL STRUCTURE |
| 12 | S-02 | SECTION - COMBI-WALL |
| 13 | S-03 | DETAILS - COMBI-WALL AND PIPE BRIDGE |
| 14 | S-04 | PLAN - RIGID PIPE BRIDGE |
| 15 | S-05 | PROFILE - RIGID PIPE BRIDGE |
| 16 | S-06 | SECTION - PUMP BARGE |
| 17 | E-01 | SITE PLAN - POWER SUPPLY SYSTEM |
| 18 | E-02 | PLAN - OVERHEAD 115KV TRANSMISSION LINES |
| 19 | E-03 | PLAN - LAKE EASTON SUBSTATION (115KV~34.5KV) |
| 20 | E-04 | PLAN - DISTRIBUTION LAYOUT TO I-90 |
| 21 | E-05 | PLAN-TWIN HORIZONTAL DIRECTIONAL DRILL BORING BENEATH I-90 |
| 22 | E-06 | PLAN - TWIN 34.5KV BURIED TRANSMISSION LINE |
| 23 | E-07 | PLAN - KACHESS RESERVOIR SUBSTATION (34.5 KV - 4.16 KV) |
| 24 | E-08 | PLAN - PROPOSED KACHESS RESERVOIR SUBSTATION (34.5 KV - 4.16KV) |
| 25 | E-09 | PLAN - CONTROL BUILDING, VFDs AND LOW-V STEP DOWN T AND SCADA |
| 26 | E-10 | ELECTRICAL - ONE LINE DIAGRAM |
| 27 | F-01 | NARROWS FISH PASSAGE - LOCATION MAP & PHOTO |
| 28 | F-02 | NARROWS FISH PASSAGE - ACCESS PLAN AND SITE PLAN |
| 29 | F-03 | NARROWS FISH PASSAGE - PLAN ROUGHENED CHANNEL |
| 30 | F-04 | NARROWS FISH PASSAGE - TYPICAL SECTIONS |

KEY

- | | |
|----|---|
| 1 | INTERCONNECTION TO PSE 115 kV |
| 2 | OVERHEAD 115 kV TRANSMISSION LINES |
| 3 | LAKE EASTON SUBSTATION (115 kV TO 34.5 kV) |
| 4 | BURIED, TWIN 34.5 kV TRANSMISSION LINES |
| 5 | HDD TRENCHLESS I-90 UNDER CROSSING TWIN 34.5 kV |
| 6 | KACHESS RESERVOIR SUBSTATION (34.5 kV TO 4,160 V) |
| 7 | CONTROL BUILDING |
| 8 | SUBMARINE CABLES TO PUMPING UNITS |
| 9 | FLOW CONTROL STRUCTURE |
| 10 | FLOATING PUMPING PLANT |

PLAN



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

R. KING
DESIGNED
B. MOBLEY
DRAWN
CHECKED
TECH. APPR.
APPROVED
AGENCY APPROVAL - TITLE
YAKIMA, WA YYYY-MM-DD

PLAN - OVERALL
PROJECT

ALTERNATIVE 3

G-01

SHEET 1 OF 30

AYS THINK SA

**KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE**

R. KING
DESIGNED

J. BRAMLETT
DRAWN

CHECKED

ECH. APPR.

APPROVED

EXHIBIT APPROVAL - TITLE

YAKTIMA, WA YYY-MM-DD

*FPPA - MAXIMUM POOL
(GRAVITY DISCHARGE)*

ALTERNATIVE 3

G-03


SHEET 3 OF 30

SAFETY NOTE:

THIS ALTERNATIVE HAS NUMEROUS PRINCIPAL PROJECT FEATURES LOCATED DIRECTLY ON WATER. PERSONNEL SAFETY FOR INGRESS AND EGRESS TO AND FROM THE BARGE, PERSONNEL SAFETY WHILE ON THE BARGE, AND PERSONNEL SAFETY ASSOCIATED WITH THE FLOW CONTROL STRUCTURE AND RIGID AND FLEXIBLE PIPE BRIDGES WOULD BE CRITICAL TO THE SAFE OPERATION, MAINTENANCE AND REPAIR OF THIS FACILITY.

C:\pwworking\sead1972762\G-03.dwg, G-01, 3/29/2018 9:28:35 AM, SNISHIMURA
 CAD FILENAME UNKNOWN
 AUTOCAD
 PLOTTED BY Not Ploated
 B

C:\pwworking\seald1972762\G-04.dwg, G-01, 3/29/2018 9:28:52 AM, SNISHIMURA
AUTOCAD
C:\pwworking\seald1972762\G-04.dwg, G-01, 3/29/2018 9:28:52 AM, SNISHIMURA
AUTOCAD
C:\pwworking\seald1972762\G-04.dwg, G-01, 3/29/2018 9:28:52 AM, SNISHIMURA
AUTOCAD



SAFETY NOTE:

THIS ALTERNATIVE HAS NUMEROUS PRINCIPAL PROJECT FEATURES LOCATED DIRECTLY ON WATER, PERSONNEL SAFETY FOR INGRESS AND EGRESS TO AND FROM THE BARGE, PERSONNEL SAFETY WHILE ON THE BARGE, AND PERSONNEL SAFETY ASSOCIATED WITH THE FLOW CONTROL STRUCTURE AND RIGID AND FLEXIBLE PIPE BRIDGES WOULD BE CRITICAL TO THE SAFE OPERATION, MAINTENANCE AND REPAIR OF THIS FACILITY.

RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

R. KING
DESIGNED
L. BRAMLETT
DRAWN
CHECKED
TECH. APPR.
APPROVED
JURY APPROVAL - TITLE
YAKIMA, WA YYYY-MM-DD

FPPA - MINIMUM POOL
(GRAVITY DISCHARGE)

ALTERNATIVE 3

G-04

SHEET 4 OF 30

DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITITAS DIVISION

**KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE**

AKIMA, WA

ALTERNATIVE 3

SHEET 5 OF 30

SAFETY NOTE:

THIS ALTERNATIVE HAS NUMEROUS PRINCIPAL PROJECT FEATURES LOCATED DIRECTLY ON WATER. PERSONNEL SAFETY FOR INGRESS AND EGRESS TO AND FROM THE BARGE, PERSONNEL SAFETY WHILE ON THE BARGE, AND PERSONNEL SAFETY ASSOCIATED WITH THE FLOW CONTROL STRUCTURE AND RIGID AND FLEXIBLE PIPE BRIDGES WOULD BE CRITICAL TO THE SAFE OPERATION, MAINTENANCE AND REPAIR OF THIS FACILITY.

DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
WYAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

R. KING DESIGNED L. BRAMLETT DRAWN CHECKED TECH. APPR. APPROVED ADMIN APPROVAL - TITLE YAKIMA, WA YYYY-MM-DD

FPPA - MINIMUM POOL
(DROUGHT RELIEF
PUMPING)

ALTERNATIVE 3

G-06

SHEET 6 OF 30

SAFETY NOTE:

THIS ALTERNATIVE HAS NUMEROUS PRINCIPAL PROJECT FEATURES LOCATED DIRECTLY ON WATER, PERSONNEL SAFETY FOR INGRESS AND EGRESS TO AND FROM THE BARGE, PERSONNEL SAFETY WHILE ON THE BARGE, AND PERSONNEL SAFETY ASSOCIATED WITH THE FLOW CONTROL STRUCTURE AND RIGID AND FLEXIBLE PIPE BRIDGES WOULD BE CRITICAL TO THE SAFE OPERATION, MAINTENANCE AND REPAIR OF THIS FACILITY.


C:\pw\working\sead197262\G-06.dwg, G-01, 3/29/2018 9:27:23 AM, SNISHIMURA

A B

AutoCAD
CADD FILENAME
UNKNOWN
Not Plotted
Net Plotted


DATE AND TIME PLOTTED
PLOTTER
PLOTTER BY
Not Plotted

CAD SYSTEM
CADD
CADD FILENAME
UNKNOWN



SAFETY NOTE:

THIS ALTERNATIVE HAS NUMEROUS PRINCIPAL PROJECT FEATURES LOCATED DIRECTLY ON WATER, PERSONNEL SAFETY FOR INGRESS AND EGRESS TO AND FROM THE BARGE, PERSONNEL SAFETY WHILE ON THE BARGE, AND PERSONNEL SAFETY ASSOCIATED WITH THE FLOW CONTROL STRUCTURE AND RIGID AND FLEXIBLE PIPE BRIDGES WOULD BE CRITICAL TO THE SAFE OPERATION, MAINTENANCE AND REPAIR OF THIS FACILITY.



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING
DESIGNED
R. CARPENTER
DRAWN
CHECKED
TECH. APPR.
APPROVED
FOR REVIEW - TITLE
YAKIMA, WA YYYY-MM-DD

PLAN PUMPING SYSTEM

ALTERNATIVE 3

M-01

SHEET 7 OF 30



ALWAYS THINK SAFETY



U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


I. RINCON
DESIGNED
E. PILAPIL
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL - TITLE
YAKIMA, WA YYYY-MM-DD

PROCESS AND
INSTRUMENTATION
DIAGRAM

ALTERNATIVE 3

M-02

SHEET 8 OF 30



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION


KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

R. KING
DESIGNED
R. CARPENTER
DRAWN
CHECKED
TECH. APPR.
APPROVED
JURY APPROVAL TITLE
YAKIMA, WA YYYY-MM-DD

PROFILE - GRAVITY
OPERATION

ALTERNATIVE 3

M-03
SHEET 9 OF 30



DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
WYAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


DESIGNED	R. KING
DRAWN	R. CARPENTER
CHECKED	
TECH. APPR.	
APPROVED	
ADMIN APPROVAL - TITLE	
YAKTNA, WA	YYYY-MM-DD

FLOW CONTROL STRUCTURE

ALTERNATIVE 3

S-01

SHEET 11 OF 30



PLAN COMBI-WALLFLOW CONTROL STRUCTURE

SCALE: 1"=15'

C:\pwworking\sead1972762\S-01.dwg, S-05 15 scale (USED) 3/29/2018 9:46:40 AM, SNISHIMURA

DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING
DESIGNED
R. CARPENTER
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL: TITLE
YAKIMA, WA YYYY-MM-D

SECTION - COMBI-WALL

ALTERNATIVE 3

S-02

SHEET 12 OF 30



SECTION - COMBI-WALL
SCALE: 1"=5'

C:\pwworking\seald1972762\S-02.dwg, S-02, 3/29/2018, 9:45:11 AM, SNISHIMURA, not Plotted

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING DESIGNED	
R. CARPENTER DRAWN	
CHECKED	
TECH. APPR.	
APPROVED	
ADMIN. APPROVAL - TITLE	
YAKTMA, WA	YYYY-MM-DD

DETAILS - COMBI-WALL
AND PIPE BRIDGE

ALTERNATIVE 3

S-03

SHEET 13 OF 30





DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING DESIGNED	
R. CARPENTER DRAWN	
CHECKED	
TECH. APPR.	
APPROVED	
ADMIN APPROVAL -	TITLE
YAKIMA, WA	YYYY-MM-DD

PLAN - RIGID PIPE
BRIDGE

ALTERNATIVE 3

S-04

SHEET 14 OF 30



PLAN - RIGID PIPE BRIDGE
SCALE: 1"=10'

C:\pwworking\sead\1972762\S-04.dwg, S-04, 3/29/2018 9:48:47 AM, SNISHIMURA

DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITIAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING DESIGNED	
R. CARPENTER DRAWN	
CHECKED	
TECH. APPR.	
APPROVED	
ADMIN APPROVAL -	TITLE
YAKIMA, WA	YYYY-MM-DD

PROFILE - RIGID PIPE BRIDGE

ALTERNATIVE 3

S-05

SHEET 15 OF 30



PROFILE - RIGID PIPE BRIDGE

SCALE: 1"=5'

DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING DESIGNED	
R. CARPENTER DRAWN	
CHECKED	
TECH. APPR.	
APPROVED	
ADMIN APPROVAL -	TITLE
YAKIMA, WA	YYYY-MM-DD

SECTION - PUMP BARGE

ALTERNATIVE 3

S-06

SHEET 16 OF 30



SECTION - PUMP BARGE

SCALE: 1/4" = 1'-0"

C **working** **sead** **1972762** **S-06.dwg**, **S-06**, **3/29/2018** **9:40:22 AM**, **SNISHIMURA**
 CAD FILENAME
 UNKNOWN
 AUTOCAD
 Not Potted
 Not Potted
A
B

C:\pwworking\seald\1972762E-01.dwg, LAYOUT 1, 3/29/2018 8:39:23 AM, SNISHIMURA

CAD SYSTEM
CAD USER
CAD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
3/29/2018 8:39:23 AM
PLOTTED BY
Not Plotted



SITE PLAN – POWER SUPPLY SYSTEM



RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

S. EVERETT / K. DEWEY
DESIGNED
S. BRADFORD
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL - TITLE
YAKIMA, WA YYYY-MM-DD

SITE PLAN - POWER
SUPPLY SYSTEM

ALTERNATIVE 3

E-01

SHEET 17 OF 30

C:\pwworking\seald\1972762E-02.dwg, LAYOUT 1, 3/29/2018 8:39:10 AM, SNISHIMURA

CAD SYSTEM
CADD USER
CADD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
3/29/2018 8:39:10 AM
PLOTTER BY
Not Plotted



PLAN — OVERHEAD 115 KV TRANSMISSION LINES
SCALE: 1"=30'

RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY



U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

S. EVERETT / K. DEWEY
DESIGNED
S. BRADFORD
DRAWN
J. DOHRENDORF
CHECKED

TECH. APPR.

APPROVED

ADMIN. APPROVAL

YAKIMA, WA

YYYY-MM-DD

PLAN - OVERHEAD 115kv
TRANSMISSION LINES

ALTERNATIVE 3

E-02

SHEET 18 OF 30

C:\pwworking\seald\1972762E-03.dwg, LAYOUT 1, 3/29/2018 8:35:27 AM, SNISHIMURA

CAD SYSTEM
CADDY
CADD FILENAME
UNKNOWN


DATE AND TIME PLOTTED
3/29/2018 8:35:27 AM
PLOTTER BY
Not Plotted

D

C

B

A



PLAN — LAKE EASTON SUBSTATION
SCALE: 3/32"=1'-0"

RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

K. MOUGHAMER / S. EVERETT
DESIGNED
S. BRADFORD
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL: TITLE
YAKIMA, WA YYYY-MM-DD

PLAN - LAKE EASTONS
SUBSTATION
(115KV-34.5KV)

ALTERNATIVE 3

E-03

SHEET 19 OF 30

C:\pwworking\seald\1972762E-04.dwg, LAYOUT 1, 3/29/2018 8:55:54 AM, SNISHIMURA

CAD SYSTEM
CAD USER
CAD FILENAME
UNKNOWN


DATE AND TIME PLOTTED
3/29/2018 8:55:54 AM
PLOTTER
Not Plotted

D


C

B

A



PLAN — TWIN 34.5 KV BURIED TRANSMISSION LINE ROUTE
SCALE: 1"=200'



RECLAMATION
Managing Water in the West

HR



ALWAYS THINK SAFETY



U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

S. EVERETT / K. DEWEY
DESIGNED
S. BRADFORD
DRAWN
J. DOHRENDORF
CHECKED

TECH. APPR.

APPROVED

ADMIN. APPROVAL: TITLE
YAKIMA, WA YYYY-MM-DD

PLAN - DISTRIBUTION
LAYOUT TO I-90

ALTERNATIVE 3

E-04

SHEET 20 OF 30



PLAN - TWIN HORIZONTAL DIRECTIONAL DRILL BORING BENEATH I-90
SCALE: 1"=50'

Cell ID: 1972762E-05.dwg, E-05, 3/29/2018 8:30:24 AM, SNISHIMURA
Cell status: Cell not plotted

Cell FILENAME UNKNOWN
Cell AUTOLOG

Cell A Cell B

Cell NOT PLOTTED BY NOT PLOTTED

CAD FILENAME
UNKNOWN

RECLAMATION
Managing Water in the West



 ALWAYS THINK SAFETY

DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITTTITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

S. EVERET / K. DEWEY
DESIGNED
S. BRADFORD
DRAWN
J. DOHRENDORF
CHECKED

TECH. APPR.

APPROVED

YAKIMA, WA

PLAN - TWIN HORIZONTAL
DIRECTIONAL DRILL
BORING BENEATH I-90

ALTERNATIVE 3

E-05

SHEET 21 OF 30

C:\pwworking\seald\1972762E-06.dwg, LAYOUT 1, 3/29/2018 8:37:34 AM, SNISHIMURA

CAD SYSTEM
CADD USER
CADD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
3/29/2018 8:37:34 AM

PLOTTED BY
Not Plotted

A

B

C

D



PLAN — TWIN 34.5 KV BURIED TRANSMISSION LINE
SCALE: 1"=150'

SHARED CONDUIT TRENCH DETAIL
SCALE: 1"=1'-0"



RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY



U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION
KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

S. EVERETT / K. DEWEY
DESIGNED
S. BRADFORD
DRAWN
J. DOHRENDORF
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL - TITLE
YAKIMA, WA YYYY-MM-DD

PLAN - TWIN 34.5 KV
BURIED TRANSMISSION
LINE

ALTERNATIVE 3

E-06

SHEET 22 OF 30

C:\pwworking\seald\1972762E-07.dwg, LAYOUT 1, 3/29/2018 8:37:22 AM, SNISHIMURA

CAD SYSTEM
CADD USER
CADD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
3/29/2018 8:37:22 AM
PLOTTER BY
Not Plotted



PLAN – KACHESS RESERVOIR SUBSTATION (34.5 KV – 4.16 KV)
SCALE: 1"=400'

RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION

YAKIMA PROJECT - WA

KITTITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

S. EVERETT / K. DEWEY

DESIGNED

S. BRADFORD

DRAWN

J. DOHRENDORF

CHECKED

TECH. APPR.

APPROVED

ADMIN. APPROVAL - TITLE

YAKIMA, WA

YYYY-MM-DD

PLAN - KACHESS
RESERVOIR SUBSTATION
(34.5 KV - 4.16 KV)

ALTERNATIVE 3

E-07

SHEET 23 OF 30

C:\pwworking\seald1972762\E-08.dwg, LAYOUT 1, 3/29/2018 8:36:20 AM, SNISHIMURA

CAD SYSTEM
CADDIST
CADD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
3/29/2018 8:36:20 AM
PLOTTER
Not Plotted

D

C

B

A

1

2

3


4

5



34.5 KV ~ 4,160 V PAD
MOUNT TRANSFORMER W/4'
SPILL CONTAINMENT BERM

4,160 V BURIED CONDUIT
TO CONTROL HOUSE



PLAN — PROPOSED KACHESS RESERVOIR SUBSTATION (34.5 KV — 4,160V)
SCALE: 3/32" = 1'-0"

RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY



U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

K. MOUGHAMER / S. EVERETT
DESIGNED
S. BRADFORD
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL: TITLE
YAKIMA, WA YYYY-MM-DD

PLAN - PROPOSED
KACHESS RESERVOIR
SUBSTATION (34.5 KV -
4,160V)

ALTERNATIVE 3


E-08

SHEET 24 OF 30

C:\pwworking\seald1972762\E-09.dwg, Layout, 3/29/2018 10:30:22 AM, SNISHIMURA

CAD SYSTEM
CADD USER
CADD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
3/29/2018 10:30:22 AM
PLOTTER BY
Not Plotted



RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

I. RINCON
DESIGNED
E. PILAPIL
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL
TITLE
YAKIMA, WA
YYYY-MM-DD

PLAN - CONTROL
BUILDING, VFDs AND
LOW-V STEP DOWN T
AND SCADA

ALTERNATIVE 3


E-09

SHEET 25 OF 30

C:\pwworking\sea\197262\1E-10.dwg, Layout, 3/29/2018 8:57:20 AM, SNISHIMURA

CAD SYSTEM
AUTOCAD
CAD FILENAME
UNKNOWN

DATE AND TIME PLOTTED
Not Plotted
PLOTTED BY
Not Plotted



RECLAMATION
Managing Water in the West



ALWAYS THINK SAFETY

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
YAKIMA PROJECT - WA
KITTITAS DIVISION

KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE

J. RINCON
DESIGNED
E. PILAPIL
DRAWN
CHECKED
TECH. APPR.
APPROVED
ADMIN. APPROVAL - TITLE
YAKIMA, WA YYYY-MM-DD

ELECTRICAL - ONE LINE
DIAGRAM

ALTERNATIVE 3

E-10

SHEET 26 OF 30

JK SA

U.S. DEPARTMENT OF THE INTERIOR
BUREAU OF RECLAMATION
30 OF 30
KITITAS DIVISION
KACHESS DROUGHT RELIEF PUMPING PLANT
ALT. 3 - FLOATING ALTERNATIVE


R. KING	
DESIGNED	
B. MOBLEY	
DRAWN	
CHECKED	
ECH. APPR.	
APPROVED	
WORKMAN APPROVAL - TITLE	
AKTMA, WA	YYYY-MM-DD

NARROWS FISH PASSAGE
- TYPICAL SECTIONS

ALTERNATIVE 3

-04

SHEET 30 OF 30



C:\pwworking\sead1972762\F-04.dwg, F-04, 3/29/2018 8:58:47 AM, SNISHIMURA
 CAD FILENAME UNKNOWN
 AUTOCAD
 PLOTTED BY Not Plotted
 Not Plotted
 A B

Attachment B

HDRC OPCC

This page intentionally left blank.



Roza Irrigation District

Kachess Reservoir Relief Pumping Plant

Basis of Estimate

Feasibility Study OPCC
November 30, 2017

Prepared For:





Table of Contents

Project History	2
Scope of Work.....	2
Method of Accomplishment	3
Project Schedule.....	4
Estimate Methodology/Type	4
Cost Estimate	5
Cost Basis	6
Assumptions/Exclusions.....	7
Level of Confidence.....	8
Escalation	8

Attachments:

- Summary Roll-Up Estimate Report
- Work Area Estimate Report



Project History

In response to an anticipated continuation of the 2015 drought into the 2016 irrigation year Roza Irrigation District hired HDR to complete a four week reconnaissance study to determine the feasibility and primary design features of an emergency floating pumping plant on Lake Kachess. This facility was sized at Roza's request to deliver 150,000 acre-feet of water during a 70-80 day irrigation season. Ultimately this emergency plan was not enacted, and now a permanent floating pump station is under consideration. The permanent floating pump station will provide 200,000 Acre Feet (AF) of drought relief pumping volume at a rate of 1,000 Cubic Feet per Second (FPS). The design concept proposed will allow the permanent floating pump barge to drawdown the Big Kachess reservoir to a Water Surface Elevation (WSEL) of approximately 2,113'. At that elevation the reservoir would contain a pool volume of approximately 200,000 (AF). See Figure 1.

Scope of Work

The design concept for this facility consists of a custom engineered floating steel pump barge with three (3) 5,500 HP electric fired vertical turbine pumps. These pumps will discharge to pipes contained in a flexible end (with Cardanic Joints) trussed pipe bridge that will be fixed to the barge and to a rigid pipe bridge that will be supported by pipe pile supports. These pipelines will discharge water to a concrete flow control structure with a water jet impact slab. From the new flow control structure, water will enter the existing outlet channel and will utilize the existing gravity outlet works to convey flow to the Kachess River. Access to the discharge basin would be provided by upgraded existing public access road which connects to an existing National Forest road. An East Shore Boat Ramp Parking Area will be constructed along with marina facilities for use during construction and ultimately for long term operations, maintenance, and repair activities for the floating pump plant.

Dredging of existing reservoir (approximately 6,000 cy) to a depth of approximately 25 feet lower than the maximum drawdown elevation of the reservoir will be done to ensure acceptable vertical clearance to the suction bells of the pumping units is maintained. The dredged material will be returned to the reservoir floor and not brought to the surface for upland disposal.

A volitional fish passage facility will be constructed at the Kachess Narrows to allow passage of bull trout.

Power for the emergency floating pumping plant would be provided by a proposed 115-kV transmission line to a proposed switchyard (complete with storage building & yard) and a control building. The control building will be constructed on the East end of the existing Kachess Dam which is N.W. of the proposed switchyard. Power and I&C cabling from the control building to the floating pump station will be provided via marine cable installed at the approximate centerline of the existing outlet channel.




Figure 1: Hydraulic Profile Schematic

Method of Accomplishment

This estimate is based upon a single prime contractor self-performing portions of the work. All other scopes of work will be secured utilizing competitive subcontract procurement process. Major work scopes include: Site clearing and grading, barge fabrication and field erection, supply and installation of (three) pumps and all appurtenances, building erection and building trades, fish passage, boat ramp and docks, outlet structure, electrical, and instrumentation.

The contractor will staff the project with a team of qualified Construction Managers, Project Superintendents, Safety Manager, and QA/QC manager. A full time Project Manager will manage the project from the contractor's home office with support staff as necessary.

It is assumed that all work in the reservoir will be performed at optimum water level drawdown elevations. Every effort to work in dry conditions will be made by the contractor and its subcontractors to maximum labor productivity and efficiencies.

Project Schedule

The final project duration has not been established so for the purpose of this estimate we have assumed a 2 year construction period with Notice to Proceed on or around the middle of June 2018. Procurement of long lead time items will begin soon after the NTP on or around June 18, 2018. Construction will begin on or around March 11, 2019 with Substantial Completion on or around June 08, 2020.

Description	Start	Complete
Notice to Proceed	04 Jun 2018	04 Jun 2018
Procurement	18 Jun 2018	11Mar 2019
Construction	11 Mar 2019	08 Jun 2020
Demobilization	08 Jun 2020	22 Jun 2020

Figure 2 Anticipated Milestone Schedule

Estimate Methodology/Type

This estimate is based on the “Draft – KFPPA Project Description – SDEIS Concept Text” and the “KFPP DWGS Updated BK Redlines 2016-08-22” concept drawings along with additional drawings provided on 8-22-16 and updated ALT.3 – Floating Pumping Plant drawings provided on 11-6-2017. Estimating staff performed detailed analysis of all concept drawings and narratives. Detailed quantity takeoffs were performed, where necessary, utilizing Bluebeam Software. Sage Timberline Estimating Software was utilized for all labor, material and equipment price calculations.

The estimate utilizes RS Means labor rates for Yakima, WA. See Cost Data section for clarification. Material and equipment costs are adjusted utilizing the RS Means City Cost Index for Yakima, WA as well. Major Equipment pricing was provided to HDR and included vendor budgetary quotes specific to this project.

The estimate utilizes standard productivity installation rates from RS Means. These rates have been adjusted for local and site specific conditions.

Based on AACE guidance and review of the conceptual design documents and preliminary construction schedule, the estimate meets Class V methodology standards.

Cost Estimate

Total Project			
Estimate Totals			
Description	% of Total	Amount	Totals
Labor		\$ 4,639,160	
Material		\$ 33,351,860	
Equipment		\$ 2,649,123	
Subcontract		\$ 11,760,428	
Subtotal Const Direct Costs			\$ 52,400,571
Contractor Overhead	8.0%	\$ 3,954,760	
Contractor GC's	5.0%	\$ 2,471,725	
Construction Contingency	25.0%	\$ 14,706,764	
Project Escalation (2020)	4.6%	\$ 3,382,556	
Subtotal Field Const Indirect Costs			\$ 24,515,805
Contractor Fee	12.0%	\$ 9,229,965	
Contractor's Bonds & Insurance	2.0%	\$ 1,722,927	
Washington State Sales Tax	8.0%	\$ 7,029,541	
B&O Tax	0.5%	\$ 425,287	
Subtotal Other Const Indirect Costs			\$ 18,407,720
Total Construction Cost w/Tax			\$ 95,324,096
HDR Contractor Design Assist		\$ 400,000	
HDR Design & Management Fee		\$ 11,500,000	
Total Project Cost			\$ 107,224,096

Figure 3 Construction Cost Summary

Cost Basis

This estimate utilizes the following financial data for all pricing included. The direct costs and indirect cost percentages are based on experience, current market conditions, and historical data.

Direct Cost Methodology

- A combination of HDR Constructors database pricing, similar project costs, and historical data were used to establish direct costs
- The HDRC database was indexed for Yakima, WA
- 2017 RS Means labor rates.
- All labor is done on normal 8 hour days, 5 days a week Monday thru Friday.
- Subcontractor pricing includes mark-ups of
 1. 10% Field Overhead/General Conditions
 2. 15% Home Office Overhead and Profit

Indirect Cost Methodology

- General Contractor Mobilization & Demobilization – 6%
 - Set up and removal of all temporary facilities, including contractor field office
 - Equipment necessary for self performed scopes of work
 - Mob/Demob of all necessary construction equipment
 - Training of all field and craft personnel
- General Contractor Field OH – 8%
 - Field OH includes, but is not limited to the following:
 - Field project staff and standard burden
 - Procurement
 - Project controls/scheduling
 - Full time QA/QC, safety, and environmental staffing
- General Contractor Field General Conditions – 5%
 - Field general conditions include, but are not limited to the following:
 - Site office facilities adequate for staff required to manage project site
 - Field office staff vehicles and equipment
 - SWPPP and minor maintenance of SWPPP measures
 - Project consumables
 - Temporary utilities
 - Temporary facilities
- Washington State Sales Tax – 8%
- Washington State B&O Tax – 0.484%
- General Contractor Fee – 12%
 - Profit based on:
 - Local market conditions
 - Size and scope of project
 - Contacting method
 - Project Risk

- Construction contingency – 25%
 - See Level of Confidence
- General Contractor Bonds & Insurance – 2.0%
 - Bonds & Insurance includes the following (under normal conditions):
 - 0.75% - Bonds
 - 0.75%- General Liability
 - 0.5%- Marine Construction
- The following allowances are included
 - Fish screening under barge
 - Grading Existing Rock from Turnaround to Outlet Channel
 - PSE Design/Review Fee's
 - Existing road repair at project completion
- The following 2016 budgetary pricing was provided to HDR from individual vendors for use in this estimate
 - Pumps, motors, and drives
 - VFD's (2017 Budgetary Pricing Obtained)
 - Electrical Gear
 - Barge Modules

Assumptions/Exclusions

Assumptions:

- This work will be completed uninterrupted, only one mobilization and demobilization.
- This project will be worked on a standard work week.
- Project to be competitively bid, not sole sourced with a minimum of three bids.
- All regulatory approvals will be obtained by others prior to mobilization
- Any/all environmental impact studies and associated permitting will be completed by others prior to mobilization.
- Subcontractors and trade labor can be procured locally or within a radius that does not require per diem upcharges.
- Location provides for sufficient lay-down and staging area.
- All procurements by the Joint Venture and its subcontractor's.
- All existing soils are suitable for re-use as backfill and any spoils will be spread on site.
- All start-up and testing to be done by vendors, sub-contractors under supervision of GC.
- Temporary construction power is available

Exclusions:

- Accelerated schedule costs
- All permits, regulatory fees, environmental fees or requirements and acquisition of such.
- Any off-site storage facilities.
- Around the clock site security measures
- Extended warranty costs
- Handling/disposal of any hazardous materials.
- Any rock excavation or excavation of unforeseen underground obstacles
- SWPPP and marine construction abatement costs.

Level of Confidence

This is a Class V estimate as defined by AACE. The margin of error for this estimate classification is L: -25% / H: +50. According to these guidelines and the stated classifications, construction contingency would fall between 25% - 40% based on the conceptual design documents. The estimate utilizes 2017 RS Means as a basis for labor and it is understood that labor rates may adjust in an unknown direction based on future market conditions. The estimate incorporates a 25% construction contingency to account for fluctuating market conditions, evolution of the equipment specifications, increases to the prevailing wages and general design and estimate omissions.

Escalation

Project escalation calculated for estimated procurement of long lead items (pumps) beginning one year in advance of the start of construction. Construction is currently assumed to begin in March 2019, with completion anticipated on or before June 08, 2020. The escalation for this project is calculated utilizing the Bureau of Labor Statistics cost indexes. See Figure 4.

Single Weighted Avg Escalation			
% of Year End Committed Costs	Year	Escalation	
60%	2018	2.23%	
20%	2019	6.13%	
20%	2020	10.20%	
100%			<u>4.60%</u>

Figure 4: Escalation Weighted Average



Cost Reports

November 30, 2017



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Summary Roll-Up Estimate Report

Page 1
11/30/2017
Design Stage:
Estimate Version: R00

Project name	Roza Irrigation Alt 3 Pump Station Easton WA
Labor rate table	CONC2017
Equipment rate table	CONC2017
Notes	Any opinions of probable construction cost or cost estimates provided by HDR, Inc. are made on the basis of information available to HDR, Inc. and on the basis of cost estimator's experience and qualifications, and represents its judgment as an experienced and qualified professional engineer. However, since HDR, Inc. has no control over the cost of labor, materials, equipment or services furnished by others, or over the contractor(s)' methods of determining prices, or over competitive bidding or market conditions, HDR, Inc. does not guarantee that proposals, bids or actual project or construction cost will not vary from opinions of probable cost or cost estimates prepared by HDR, Inc.
Report format	Sorted by 'WBS_MAIN/WORK AREA/MF04_DIV/HDR04SPEC' 'WORK AREA' summary Allocate addons
Cost index	989-WA-YAKIMA



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Summary Roll-Up Estimate Report

Page 2
11/30/2017
Design Stage:
Estimate Version: R00

Description	Quantity			Labor	Material	Subcontract	Equipment	Other	Total	
				Amount	Amount	Amount	Amount	Amount	Unit Cost	Amount
100 MOBILIZATION										
110 CONTACTOR MOBILIZATION/DEMOLIZATIO N	1.00	LS				2,966,070			2,966,070.05 /LS	2,966,070
100 MOBILIZATION						2,966,070			2,966,070.05 /LS	2,966,070
1.00 LS										
200 CIVIL WORK										
210 EAST SHORE PARKING	1.00	LS		53,740	91,668	200,000	39,274		384,682.10 /LS	384,682
220 EAST SHORE BOAT RAMP (In-Reservoir)	1.00	LS		50,758	291,470		40,077		382,304.54 /LS	382,305
230 CONTROL BUILDING AREA (5,000 SF)	1.00	LS		346,647	287,316	16,000	48,362		698,324.98 /LS	698,325
275 RESERVOIR ROAD TURNAROUND	1.00	LS		102,465	90,525		65,238		258,227.86 /LS	258,228
200 CIVIL WORK				553,610	760,979	216,000	192,951		1,723,539.48 /LS	1,723,539
1.00 LS										
7,927.296	Labor hours									
2,347.527	Equipment hours									
300 MARINE WORK										
310 RESERVOIR DREDGING	1.00	LS		102,134		45,000	57,664		204,797.15 /LS	204,797
320 FLOW CONTROL STRUCTURE (W/4 BULKHEADS)	1.00	LS		270,870	435,921	64,800	1,307,679		2,079,270.48 /LS	2,079,270
330 OUTLET CHANNLE IMPROVEMENTS (INSIDE & OUTSIDE CHANNEL)	1.00	LS		568,183	767,470	89,157	191,002		1,615,812.78 /LS	1,615,813
340 DISCHARGE PIPES (3) & RIGID PIPE BRIDGE STRUCTURE	1.00	LS		7,394	224,250	30,800	320		262,763.95 /LS	262,764
350 DISCHARGE PIPES (3) & FLEXIBLE PIPE BRIDGE STRUCTURE	1.00	LS		1,540	520,000	653,900	13		1,175,453.69 /LS	1,175,454
360 PUMP BARGE & BARGE SYSTEMS	1.00	LS		993,030	6,198,542	120,000	826,371		8,137,942.78 /LS	8,137,943
370 PUMP BARGE CANTANARY ANCHORAGES	1.00	LS		45,478	801,930		18,180		865,588.95 /LS	865,589
300 MARINE WORK				1,988,629	8,948,114	1,003,657	2,401,230		14,341,629.78 /LS	14,341,630
1.00 LS										
22,657.250	Labor hours									
36,059.201	Equipment hours									

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Summary Roll-Up Estimate Report

Page 3

11/30/2017

Design Stage:

Estimate Version: R00

				Labor	Material	Subcontract	Equipment	Other	Total			
Description				Quantity		Amount	Amount	Amount	Amount	Amount	Unit Cost	Amount
	410	VERTICAL TURBINE PUMPS	1.00	LS	73,965	11,562,500		16,023			11,652,488.56 /LS	11,652,489
	420	RIGHT ANGLE DRIVES	1.00	LS	49,310	4,500,000		9,614			4,558,924.150/LS	4,558,924
	430	MOTORS	1.00	LS	49,310	2,062,500		9,614			2,121,424.15 /LS	2,121,424
	440	ON-BARGE DISCHARGE PIPING	1.00	LS	872,026	1,455,990		12,881			2,340,896.48 /LS	2,340,896
400 MECHANICAL WORK					1,044,612	19,580,990		48,132			20,673,733.34 /LS	20,673,733
1.00 LS												
10,511.997 Labor hours												
1,760.001 Equipment hours												
500 ELECTRICAL WORK												
	510	INTERCONNECTION TO PSE 115KV	1.00	LS			135,844				135,843.75 /LS	135,844
	520	LAKE EASTON STEPDOWN SUBSTATION	1.00	LS			1,834,481				1,834,481.25 /LS	1,834,481
	530	TWIN 34.5 KV BUIRED TRANSMISSION LINES	1.00	LS			2,447,125				2,447,125.00 /LS	2,447,125
	540	KACHESS RESERVOIR STEP DOWN SUBSTATION	1.00	LS			1,260,644				1,260,643.75 /LS	1,260,644
	550	CONTROL BUILDING & ELECTRICAL EQUIPMENT	1.00	LS	880,959	3,554,312		6,811			4,442,082.730/LS	4,442,083
	560	MARINE CABLES TO BARDGE (4)	1.00	LS	154,019	401,416					555,434.85 /LS	555,435
	570	BARGE ELECTRICAL SYSTEMS	1.00	LS	17,331	106,048					123,379.22 /LS	123,379
500 ELECTRICAL WORK					1,052,309	4,061,777	5,678,094	6,811			10,798,990.55 /LS	10,798,991
1.00 LS												
13,714.636 Labor hours												
179.992 Equipment hours												
600 FISH PASSAGE												
	610	NARROWS VOLITIONAL UPSTREAM FISH PASSAGE (In-Reservoir) Phase 1	1.00	LS			1,646,608				1,646,607.50 /LS	1,646,608
600 FISH PASSAGE							1,646,608				1,646,607.50 /LS	1,646,608
1.00 LS												
700 PSE DESIGN/REVIEW												
	710	INTERCONNECTION & TRANSMISSION SYSTEM DESIGN/REVIEW	1.00	LS			250,000				250,000.00 /LS	250,000
700 PSE DESIGN/REVIEW							250,000				250,000.00 /LS	250,000
1.00 LS												

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Summary Roll-Up Estimate Report

Page 4A
11/30/2017
Design Stage:
Estimate Version: R00

Estimate Totals

Description	Amount	Totals	Rate
Labor	4,639,160		
Material	33,351,860		
Equipment	2,649,123		
Subcontract	11,760,428		
Subtotal Direct Project Costs	52,400,571	52,400,571	
Contractor Overhead	3,954,760		8.000 %
Contractor GC's	2,471,725		5.000 %
Field Construction Costs	6,426,485	58,827,056	
Sales Tax Estimate (GRT Below)			
Subtotal Field Const Costs		58,827,056	
Construction Contingency	14,706,764		25.000 %
Field Const w/ Contingency	14,706,764	73,533,820	
Project Escalation (2020)	3,382,556		4.600 %
Escalated Construction Costs	3,382,556	76,916,376	
Contractor Fee	9,229,965		12.000 %
Construction Cost w/ Fee	9,229,965	86,146,341	
Contractor's Bonds & Insurance	1,722,927		2.000 %
Total Construction Costs	1,722,927	87,869,268	
Washington State Sales Tax	7,029,541		8.000 %
B&O Tax	425,287		0.484 %
Total Construction Cost w/ Tax	7,454,828	95,324,096	
HDR Contractor Design Assist	400,000		
HDR Design & Management Fee	11,500,000		
Total		107,224,096	

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 1
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Project name	Roza Irrigation Alt 3 Pump Station Easton WA
Labor rate table	CONC2017
Equipment rate table	CONC2017
Notes	Any opinions of probable construction cost or cost estimates provided by HDR, Inc. are made on the basis of information available to HDR, Inc. and on the basis of cost estimator's experience and qualifications, and represents its judgment as an experienced and qualified professional engineer. However, since HDR, Inc. has no control over the cost of labor, materials, equipment or services furnished by others, or over the contractor(s)' methods of determining prices, or over competitive bidding or market conditions, HDR, Inc. does not guarantee that proposals, bids or actual project or construction cost will not vary from opinions of probable cost or cost estimates prepared by HDR, Inc.
Report format	Sorted by 'WBS_MAIN/MF04_DIV/HDR04SPEC' 'HDR04SPEC' summary Allocate addons
Cost index	989-WA-YAKIMA



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 2
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description	Quantity	Labor	Material	Subcontract	Equipment	Other	Total	Amount
		Amount	Amount	Amount	Amount	Amount	Unit Cost	
100 MOBILIZATION								
DIVISION 01 GENERAL REQUIREMENTS								
01 71 13.000	Mobilization / Demobilization			2,966,070				2,966,070
DIVISION 01 GENERAL REQUIREMENTS				2,966,070				2,966,070
100 MOBILIZATION		0	0	2,966,070	0	0	2,966,070.05 /LS	2,966,070
1.00 LS								
200 CIVIL WORK								
DIVISION 01 GENERAL REQUIREMENTS								
01 21 00.000	Allowances			200,000				200,000
DIVISION 01 GENERAL REQUIREMENTS				200,000				200,000
DIVISION 03 CONCRETE								
03.30.00.011a	Excavation for Building Slab Foundation	17,579			21,303			38,883
03.30.00.011b	Spread Footing (5'x5' wide) Storage Building	16,127	32,557		1,326			50,009
03.30.00.011c	Grade Beam (4' Tall x 1'-6" Wide) Storage Building	41,966	41,655		1,792			85,413
03.30.00.011d	Storage Bldg Slab on Grade (Assume 6" Thick)	51,838	84,738		5,875			142,452
DIVISION 03 CONCRETE		127,511	158,949		30,296			316,756
1,748.253 Labor hours								
457.258 Equipment hours								
DIVISION 04 MASONRY								
04 22 00.000	Concrete Masonry Unit	61,450	43,219		891			105,559
DIVISION 04 MASONRY		61,450	43,219		891			105,559
1,016.232 Labor hours								
43.846 Equipment hours								
DIVISION 07 THERMAL, MOISTURE PROTECTION								
07 61 13.000	Metal Roofing	15,838	18,000					33,838
07 72 33.000	Roof Hatches	1,882	2,188					4,069

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 3
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description	Quantity	Labor	Material	Subcontract	Equipment	Other	Total
		Amount	Amount	Amount	Amount	Amount	Unit Cost Amount
DIVISION 07 THERMAL, MOISTURE PROTECTION		17,720	20,188				37,908
237.312 Labor hours							
DIVISION 08 OPENINGS							
08 11 00.000 Metal Doors & Frames		5,357	7,188				12,544
08 33 23.000 Steel Rolling Overhead Doors		595	2,144				2,739
DIVISION 08 OPENINGS		5,952	9,332				15,283
88.889 Labor hours							
DIVISION 09 FINISHES							
09 29 00.000 Gypsum Board		21,639					21,639
09 53 00.000 Acoustical Suspension System		3,096	4,908				8,004
09 67 00.000 Epoxy Flooring System		8,676	12,948		328		21,952
09 91 00.000 Painting and Protective Coatings		9,563	5,000				14,563
DIVISION 09 FINISHES		42,974	22,856		328		66,158
834.208 Labor hours							
75.84 Equipment hours							
DIVISION 12 FURNISHINGS							
12 90 00.000 Other Furnishings				16,000			16,000
DIVISION 12 FURNISHINGS				16,000			16,000
DIVISION 31 EARTHWORK							
31 23 00.000 Earthwork		13,030	68,920		12,425		94,374
31 23 00.002 Clearing and Grubbing		38,786			24,442		63,229
31 23 00.202 Gravel Parking Lot (6" thick)		3,863	22,748		3,629		30,241
31.00.00.010 Temporary Erosion & Sediment Control		6,123	1,908				8,031
31.10.00.021 Topsoil Stripping, Geofabric, and Gravel Subgrade for Boat Ramp		20,729	142,019		21,720		184,469
31.30.00.010d Turn Around GeoFab and 2' Roadbase		1,979	13,488		1,920		17,387
31.30.00.010e Turn Around Slope Protection		50,050	18,529		9,490		78,069
31.30.00.010f Turn Around Road Base Fabric and 2' Sand		18,896	57,281		20,171		96,348
31.30.00.032 Turn Around Access Road Excavation		27,602			33,658		61,260
DIVISION 31 EARTHWORK		181,060	324,893		127,455		633,408
2,337.209 Labor hours							
1,460.732 Equipment hours							
DIVISION 33 UTILITIES							
33 20 00.001 Septic Tanks and Leach Field		89,101	32,773		15,625		137,499

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 4
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description	Quantity	Labor	Material	Subcontract	Equipment	Other	Total
		Amount	Amount	Amount	Amount	Amount	Unit Cost Amount
DIVISION 33 UTILITIES		89,101	32,773		15,625		137,499
1,305.194 Labor hours							
249.851 Equipment hours							
DIVISION 35 WATERWAY & MARINE CONSTRUCTION							
03 41 33.000 Precast and Prestressed Concrete		27,841	148,770		18,356		194,968
DIVISION 35 WATERWAY & MARINE CONSTRUCTION		27,841	148,770		18,356		194,968
360.00 Labor hours							
60.00 Equipment hours							
200 CIVIL WORK		553,610	760,979	216,000	192,951	0	1,723,539.46 /LS 1,723,539
1.00 LS							
7,927.296 Labor hours							
2,347.527 Equipment hours							
300 MARINE WORK							
DIVISION 01 GENERAL REQUIREMENTS							
01 50 00.001 Crawler Crane (Land Based)		66,145			247,750		313,895
01 50 00.201 Tugboat					336,971		336,971
DIVISION 01 GENERAL REQUIREMENTS		66,145			584,721		650,865
624.00 Labor hours							
1,040.00 Equipment hours							
DIVISION 03 CONCRETE							
03.30.00.015b Water Impact Slab on Grade (Assume 100'x40'x18" Thick)		78,459	105,843		7,357		191,658
03.40.00.020a Outlet Channel SOG		34,629	46,245		3,921		84,795
DIVISION 03 CONCRETE		113,087	152,088		11,278		276,453
1,502.961 Labor hours							
256.223 Equipment hours							
DIVISION 05 METALS							
05.10.00.030 Rigid Pipe Bridge		7,394	224,250	30,800	320		262,764
05.10.00.031 Flexible Pipe Bridge		1,540	520,000	653,900	13		1,175,454
DIVISION 05 METALS		8,934	744,250	684,700	334		1,438,218
87.00 Labor hours							
37.50 Equipment hours							
DIVISION 10 SPECIALTIES							
10.00.00.011 Floating Crane (for Marine Construction)		172,736	352,500		219,375		744,611

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 5
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description		Quantity	Labor	Material	Subcontract	Equipment	Other	Total
			Amount	Amount	Amount	Amount	Amount	Unit Cost Amount
10.00.00.020	Self Adjusted Barge Tensioning Anchors		5,467	453,750				459,217
10.00.00.070	Discharge Basin Dock Piles		12,684	31,413		5,074		49,170
DIVISION 10 SPECIALTIES			190,886	837,663		224,449		1,252,998
2,051.991	Labor hours							
921.152	Equipment hours							
DIVISION 13 SPECIAL CONSTRUCTION								
13 10 00.010	Chain Catenary Anchors		17,329	185,088		18,180		220,597
13 10 00.005	Barge (81' L x 90' w x 8' dp)		276,383	4,795,000	120,000	28,950		5,220,334
13 10 00.015	Cable Catenary Anchors		22,683	163,093				185,775
DIVISION 13 SPECIAL CONSTRUCTION			316,395	5,143,180	120,000	47,130		5,626,705
3,765.230	Labor hours							
1,968.000	Equipment hours							
DIVISION 31 EARTHWORK								
03.30.00.015a	Excavation & Backfill		14,628			6,322		20,950
31 23 00.000	Earthwork		134,358	84,400		26,967		245,725
31 40 00.000	Shoring & Underpinning		332,877	569,288		182,568		1,084,733
31 62 16.000	Driven Steel Piling		76,675	397,355		31,540		505,570
31.00.00.010	Temporary Erosion & Sediment Control		3,936	1,226				5,163
31.30.00.010c	Access Road Slope Protection		75,486	27,945		14,313		117,744
31.30.00.030	Discharge Basin Armoring		48,027	24,428		9,417		81,873
31.30.00.031	Stilling Basin Excavation		30,921			37,577		68,498
31.30.00.040	Outlet Channel Slope Protection		44,000	145,894		29,192		219,086
DIVISION 31 EARTHWORK			760,909	1,250,536		337,896		2,349,342
8,287.147	Labor hours							
2,926.191	Equipment hours							
DIVISION 32 EXTERIOR IMPROVEMENTS								
01 21 00.001	Regrade Existing Road				89,157			89,157
DIVISION 32 EXTERIOR IMPROVEMENTS					89,157			89,157
DIVISION 35 WATERWAY & MARINE CONSTRUCTION								
01 71 13.000	Mobilization / Demobilization		287		45,000	564		45,852
03 41 33.000	Precast and Prestressed Concrete		154,133	394,514		48,779		597,426
35 20 00.000	Waterway & Marine Construction & Equipment		101,846			57,099		158,946
35 20 00.000a	Temporary Flume at Outlet Structure		164,367	95,805		42,729		302,901
35 20 00.001	Slide Gates (8' x 10' Stainless Steel)		71,629	278,164		4,447		354,240
35 70 00.010	Cofferdam (2 each for Flow Control Structure Construction)		40,009	51,915	64,800	1,041,804		1,198,528

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 6
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description	Quantity	Labor	Material	Subcontract	Equipment	Other	Total	Amount
		Amount	Amount	Amount	Amount	Amount	Unit Cost	
DIVISION 35 WATERWAY & MARINE CONSTRUCTION		532,273	820,398	109,800	1,195,421			2,657,892
6,338.92	Labor hours							
28,910.136	Equipment hours							
300 MARINE WORK		1,988,629	8,948,114	1,003,657	2,401,230	0	14,341,629.78 /LS	14,341,630
1.00 LS								
22,657.250	Labor hours							
36,059.201	Equipment hours							
400 MECHANICAL WORK								
DIVISION 40 PROCESS INTEGRATION								
40 05 10.001	Pipe: Steel - 72" Discharge Piping	872,026	1,455,990		12,881			2,340,896
DIVISION 40 PROCESS INTEGRATION		872,026	1,455,990		12,881			2,340,896
8,495.997	Labor hours							
1,496.001	Equipment hours							
DIVISION 43 PROCESS GAS & LIQUID HANDLING, PURIFICATION & STORAGE EQUIPMENT								
43 21 07.000	Pumping Equipment: Vertical Turbine	73,965	11,562,500		16,023			11,652,489
43 21 07.005	Right Angle Drives	49,310	4,500,000		9,614			4,558,924
43 21 07.010	Pump Motors	49,310	2,062,500		9,614			2,121,424
DIVISION 43 PROCESS GAS & LIQUID HANDLING, PURIFICATION & STORAGE EQUIPMENT		172,586	18,125,000		35,251			18,332,837
2,016.00	Labor hours							
264.00	Equipment hours							
400 MECHANICAL WORK		1,044,612	19,580,990	0	48,132	0	20,673,733.34 /LS	20,673,733
1.00 LS								
10,511.997	Labor hours							
1,760.001	Equipment hours							
500 ELECTRICAL WORK								
DIVISION 13 SPECIAL CONSTRUCTION								
26 09 00.000	Instrumentation & Control for Electrical Systems	49,744	237,924					287,668

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 7
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description		Quantity	Labor Amount	Material Amount	Subcontract Amount	Equipment Amount	Other Amount	Total Unit Cost	Amount
DIVISION 13 SPECIAL CONSTRUCTION			49,744	237,924					287,668
649.627 Labor hours									
DIVISION 26 ELECTRICAL									
23 00 00.000	HVAC Basic Materials and Methods		13,344	4,829					18,174
26 00 00.000	Basic Electrical Materials and Methods		84,576	56,602					141,177
26 05 00.000	Electrical: Basic Requirements			26,250					26,250
26 05 19.000	Wire and Cable: 600 volt and below		7,767	9,776					17,543
26 05 26.000	Grounding		10,315	6,626					16,942
26 05 33.000	Raceways and Boxes		31,624	27,814					59,438
26 05 99.000	Power Distribution				2,582,969				2,582,969
26 11 16.000	Unit Substation				3,095,125				3,095,125
26 13 26.000	Variable Frequency Drives: Medium Voltage		60,630	1,773,805		1,747			1,836,182
26 27 26.000	Wiring Devices		4,403	1,638					6,041
26 50 00.000	Interior and Exterior Lighting		13,464	11,774					25,238
26.00.00.010	Electrical for Building		494,536	1,168,277		3,800			1,666,612
26.00.00.020	Motor Control Centers		53,839	179,065		375			233,280
26.30.00.010	Hook-up Electrical Generator to Building		48,014	150,495		889			199,397
26.30.00.040	Marine Cable Route		54,188	50,574					104,762
26.30.00.050	Combined Power & I/C Marine Cable		104,034	337,575					441,609
28 31 00.000	Fire Alarm System		21,831	18,752					40,583
DIVISION 26 ELECTRICAL			1,002,565	3,823,852	5,678,094	6,811			10,511,322
13,065.008 Labor hours									
179.992 Equipment hours									
500 ELECTRICAL WORK			1,052,309	4,061,776	5,678,094	6,811	0	10,798,990.56 /LS	10,798,991
1.00 LS									
13,714.636 Labor hours									
179.992 Equipment hours									

600 FISH PASSAGE

DIVISION 31 EARTHWORK									
31 23 00.035	KACHESS NARROWS FISH PASSAGE - Subcontractor (PHASE 1)				1,646,608				1,646,608



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 8
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Description	Quantity	Labor	Material	Subcontract	Equipment	Other	Total	
		Amount	Amount	Amount	Amount	Amount	Unit Cost	Amount
DIVISION 31 EARTHWORK				1,646,608				1,646,608
600 FISH PASSAGE		0	0	1,646,608	0	0	1,646,607.51 /LS	1,646,608
1.00 LS								
700 PSE DESIGN/REVIEW								
DIVISION 01 GENERAL REQUIREMENTS				250,000				250,000
01 21 00.702 PSE Design/Review Fee				250,000				250,000
700 PSE DESIGN/REVIEW		0	0	250,000	0	0	250,000.00 /LS	250,000
1.00 LS								

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%



Roza Irrigation KFPPA
Kachess Floating Pumping Plant
Work Area Estimate Report

Page 9A
11/30/2017 3:24 PM
Design Stage:
Estimate Version: R00

Estimate Totals

Description	Amount	Totals	Rate
Labor	4,639,160		
Material	33,351,860		
Equipment	2,649,123		
Subcontract	11,760,428		
Subtotal Direct Project Costs	52,400,571	52,400,571	
Contractor Overhead	3,954,760		8.000 %
Contractor GC's	2,471,725		5.000 %
Field Construction Costs	6,426,485	58,827,056	
Sales Tax Estimate (GRT Below)			
Subtotal Field Const Costs		58,827,056	
Construction Contingency	14,706,764		25.000 %
Field Const w/ Contingency	14,706,764	73,533,820	
Project Escalation (2020)	3,382,556		4.600 %
Escalated Construction Costs	3,382,556	76,916,376	
Contractor Fee	9,229,965		12.000 %
Construction Cost w/ Fee	9,229,965	86,146,341	
Contractor's Bonds & Insurance	1,722,927		2.000 %
Total Construction Costs	1,722,927	87,869,268	
Washington State Sales Tax	7,029,541		8.000 %
B&O Tax	425,287		0.484 %
Total Construction Cost w/ Tax	7,454,828	95,324,096	
HDR Contractor Design Assist	400,000		
HDR Design & Management Fee	11,500,000		
Total		107,224,096	

Upper Range +50%

AACE Classification Accuracy Range

Lower Range -25%

This page intentionally left blank.

Attachment C

Orion Marine Group OPCC

This page intentionally left blank.

Bid#	Client#	Quantity	Unit		Direct	Perm	Constr	Equip-	Sub-	Direct	Indirect	Total	Total Cost	Markup	-----Balanced Bid-----		Bid	Bid
	Bid Description			Manhours	Labor	Matl	Matl	Ment	Contr	Total	Charge	Cost	Unit Price		Total	Unit Price	Price	Total
-SUBTOTAL (MARINE)				21,777	1,797,188	10,986,100	334,976	3,805,025	1,124,011	18,047,302		18,047,302			18,047,302			18,015,000.00
4000	400	0.00																
MECHANICAL																		
4100		1.00	LS	3,521	313,328	9,250,000	282,706	1,004,042	92,647	10,942,722		10,942,722	10,942,722.49		10,942,722	10,942,722.49	F	10,900,000.00
MECHANICAL: VERTICAL TURBINE PUMPS				3,520.59														10,900,000.00
4200		1.00	LS	420	32,460	3,600,000		40,296	60,000	3,732,756		3,732,756	3,732,756.32		3,732,756	3,732,756.32	F	3,800,000.00
MECHANICAL: RIGHT ANGLE DRIVES				420.00														3,800,000.00
4300		1.00	LS	630	48,690	1,725,000		60,444		1,834,134		1,834,134	1,834,134.49		1,834,134	1,834,134.49	F	1,800,000.00
MECHANICAL: MOTORS				630.00														1,800,000.00
4400		1.00	LS	910	71,868	687,500		87,308		846,676		846,676	846,676.20		846,676	846,676.20	F	900,000.00
MECHANICAL: DISCHARGE PIPING				910.00														900,000.00
-SUBTOTAL (MECHANICAL)				5,480	466,346	15,262,500	282,705	1,192,089	152,647	17,356,289		17,356,289			17,356,289			17,400,000.00
5000	500	0.00																
ELECTRICAL																		
5100		1.00	LS						150,000	150,000		150,000	150,000.00		150,000	150,000.00	F	150,000.00
ELECTRICAL: INTERCONNECT TO PSE 115 KV																		150,000.00
5200		1.00	LS						1,850,000	1,850,000		1,850,000	1,850,000.00		1,850,000	1,850,000.00	F	1,850,000.00
ELECTRICAL: LAKE EASTON STEPDOWN SUBSTAT																		1,850,000.00
5300		1.00	LS						2,500,000	2,500,000		2,500,000	2,500,000.00		2,500,000	2,500,000.00	F	2,500,000.00
ELECTRICAL: TWIN 34.5 KV BURIED TRANSMIS																		2,500,000.00
5400		1.00	LS						1,250,000	1,250,000		1,250,000	1,250,000.00		1,250,000	1,250,000.00	F	1,250,000.00
ELECTRICAL: KACHESS RESERVOIR STEPDOWN S																		1,250,000.00
5500		1.00	LS						3,500,000	3,500,000		3,500,000	3,500,000.00		3,500,000	3,500,000.00	F	3,500,000.00
ELECTRICAL: CONTROL BUILDING & ELECTRICA																		3,500,000.00
5600		1.00	LS	1,050	81,151	1,500,000		100,740	412,500	2,094,391		2,094,391	2,094,390.79		2,094,391	2,094,390.79	F	2,100,000.00
ELECTRICAL: MARINE CABLES TO BARGE (4)				1,050.00														2,100,000.00
5700		1.00	LS						500,000	500,000		500,000	500,000.00		500,000	500,000.00	F	500,000.00
ELECTRICAL: BARGE ELECTRICAL SYSTEM																		500,000.00
-SUBTOTAL (ELECTRICAL)				1,050	81,150	1,500,000		100,740	10,162,500	11,844,390		11,844,390			11,844,390			11,850,000.00

ESTIMATE SUMMARY - COSTS & BID PRICES

Bid#	Client#	Quantity	Unit	Manhours	Direct Labor	Perm Matl	Constr Matl	Equip-Ment	Sub-Contr	Direct Total	Indirect Charge	Total Cost	Total Cost Unit Price	Markup	-----Balanced Bid-----		Bid Price	Bid Total
	Bid Description														Total	Unit Price		
6000	600	0.00																
FISH PASSAGE																		
6100		1.00	LS						1,918,000	1,918,000		1,918,000	1,918,000.00		1,918,000	1,918,000.00	F	1,918,000.00
FISH: NARROWS UPSTREAM FISH PASSAGE (PHAS																		
-SUBTOTAL (FISH PASSAGE)									1,918,000	1,918,000		1,918,000			1,918,000			1,918,000.00
6500	700	0.00																
PSE																		
6600		1.00	LS						250,000	250,000		250,000	250,000.00		250,000	250,000.00	F	250,000.00
PSE: INTERCONNECT/ TRANSMISSION SYSTEM D																		
-SUBTOTAL (PSE)									250,000	250,000		250,000			250,000			250,000.00
Totals:				41,489	3,481,357	28,555,350	1,008,160	7,741,800	14,557,850	55,344,518		55,344,518			55,344,518			55,358,000.00
[55,344,515] [0.0 %]																		
Code between Balanced Bid & Bid Price: U=Unbalanced, F=Frozen, C=Closing Biditem (item to absorb unbalancing differences).																		
[bracketed numbers represent adjusted quantities]																		
** in front of the Biditem indicates a Non-Additive item																		
Markup % is shown as a percentage of cost																		
Ins Direct (BRI) Call 4Qu		% of JB																
Ins. Indirect (Gen. Lia)		% of JB																
B&O Tax (0.50% WA + City)		% of JB																
Duty - Foreign Materials		LS																
Contingency		% of TC																
Retainage Bond (\$6.50/Tho		% of JB																
Zone Pay Adjustment		% of DH																
Markup on Resource Costs																		
***** TOTAL		JOB =====>		41,489	3,481,357	28,555,350	1,008,160	7,741,800	14,557,850	55,344,518		55,344,518			55,344,518			55,358,000.00

Spread Indirects On	TOTAL COST
Direct Labor	\$100,000
Machine Hours	\$100,000
Square Feet	\$100,000
Pounds	\$100,000
Number of Units	\$100,000

Spread Markups On TOTAL COST

Spread Addons&Bonds On	TOTAL COST
0	1000000
1	1000000
2	1000000
3	1000000
4	1000000
5	1000000
6	1000000
7	1000000
8	1000000
9	1000000
10	1000000
11	1000000
12	1000000
13	1000000
14	1000000
15	1000000
16	1000000
17	1000000
18	1000000
19	1000000
20	1000000
21	1000000
22	1000000
23	1000000
24	1000000
25	1000000
26	1000000
27	1000000
28	1000000
29	1000000
30	1000000
31	1000000
32	1000000
33	1000000
34	1000000
35	1000000
36	1000000
37	1000000
38	1000000
39	1000000
40	1000000
41	1000000
42	1000000
43	1000000
44	1000000
45	1000000
46	1000000
47	1000000
48	1000000
49	1000000
50	1000000
51	1000000
52	1000000
53	1000000
54	1000000
55	1000000
56	1000000
57	1000000
58	1000000
59	1000000
60	1000000
61	1000000
62	1000000
63	1000000
64	1000000
65	1000000
66	1000000
67	1000000
68	1000000
69	1000000
70	1000000
71	1000000
72	1000000
73	1000000
74	1000000
75	1000000
76	1000000
77	1000000
78	1000000
79	1000000
80	1000000
81	1000000
82	1000000
83	1000000
84	1000000
85	1000000
86	1000000
87	1000000
88	1000000
89	1000000
90	1000000
91	1000000
92	1000000
93	1000000
94	1000000
95	1000000
96	1000000
97	1000000
98	1000000
99	1000000
100	1000000

-----Estimate Notes-----

Bid Date: 12/01/2017

Owner:

Engineering Firm:

ESTIMATE SUMMARY - COSTS & BID PRICES

Bid#	Client#	Quantity	Unit		Direct	Perm	Constr	Equip-	Sub-	Direct	Indirect	Total	Total Cost		-----Balanced Bid-----		Bid	Bid
	Bid Description		Manhours		Labor	Matl	Matl	Ment	Contr	Total	Charge	Cost	Unit Price	Markup	Total	Unit Price	Price	Total

Estimator in Charge: 01

Desired Bid (if specified)= 0.00 Sort: Hold Acct: N Subitem: N NonAdd: N
Last Summary on 01/24/2018 at 10:13 AM.
Last Spread on 03/07/2018 at 9:34 AM.

Attachment D

Construction Schedule

This page intentionally left blank.

[illegible]

[illegible]