COLUMBIA BASIN PROJECT - IRRIGATION BLOCK 78

GRANT COUNTY, WASHINGTON

INDEX DWG. NO.	UNIT	GROSS ACRES	CLASSIFIED AREA IN ACRES: IRRIGABLE AREA (ACRES) LAND CLASS 1	2	3	4	TOTAL	NON-IRRIGABLE CLASS 6	R/W	HIGH	CLASS EQUIV.
4	1	Cancelled see Unit No. 109									
4	2	Cancelled see Unit No. 122 & 195 in Block 75									
5	3	Cancelled see Unit No. 108									
5	4	Cancelled see Unit No. 108									
5	5	Cancelled see Unit No. 119									
6	6	70.6	9.6	43.2	8.0		60.8		9.8		49.0
6	7	79.7	28.2	41.3	7.4		76.9		2.8		65.7
6	8	79.7		55.9	20.1		76.0		2.4	1.3	56.8
6	9	76.3		2.4	44.9	19.9	67.2	1.6	7.5		36.8
6	10	92.7		18.4	54.6	12.7	85.7		7.0		52.6
6	11	80.0		42.7	33.3		76.0		4.0		54.1
6	12	79.8		52.1	22.4		74.5		1.8	3.5	55.1
6	13	79.8	24.4	21.1	21.2		66.7		1.8	11.3	54.0
6	14	80.8	13.4	41.7	14.6		69.7		7.7	3.4	55.5
6	15	58.0		23.9	25.8		49.7		8.3		34.6
6	16	70.2		45.5	6.5		52.0	4.9	13.3		40.3
7	17	79.9	34.9	15.8	18.7		*69.4	2.9	7.6		58.8
7	18	Cancelled see Unit No. 115									
7	19	Cancelled see Unit No. 116									
7	20	Eliminated									
7	21	Cancelled see Unit No. 117									
7	22	Cancelled see Unit No. 130									
8	23	79.8		6.7	48.7		55.4		4.7	19.7	34.6
8	24	79.8		5.1	68.7		73.8		4.3	1.7	45.3
8	25	117.8		77.3	34.3		111.6	0.7	5.5		82.4
8	26	166.2		12.8	45.3	98.2	156.3		6.3	3.6	76.7
8	27	99.8		23.7	69.3		93.0		4.4	2.4	60.5
8	28	Cancelled see Unit No. 118									
7	29	Cancelled see Unit No. 118									
7	30	Cancelled see Unit No. 124									
7	31	Cancelled see Unit No. 124									
7	32	Cancelled see Unit No. 125									
7	33	Cancelled see Unit No. 125									
7	34	Cancelled see Unit No. 110									
7	35	Cancelled see Unit No. 111									
9	36	123.3		51.9	8.8		60.7	55.0	7.1	0.5	46.8
9	37	80.4		40.7	27.4		68.1	2.2	10.1		49.0
9	38	Cancelled see Unit No. 121									
10	39	94.9			38.6	47.8	86.4		6.0	2.5	42.3
10	40	119.2			17.7	85.8	103.5	0.5	13.2	2.0	44.9
10	41	Cancelled see Unit No. 114									
10	42	97.7				92.1	92.1		5.6		36.8
10	43	80.1			5.7	68.2	73.9		2.5	3.7	30.7
10	44	80.2			42.9	23.1	66.0	6.8	4.6	2.8	35.0
10	45	Cancelled see Unit No. 126									
10	46	Cancelled see Unit No. 126									
9	47	Cancelled see Unit No. 121									
9	48	Cancelled see Unit No. 120									
9	49	Cancelled see Unit No. 120									
9	50	80.0		19.7			19.7	57.1	3.2		15.8
9	51	80.0		63.4			63.4	13.6	3.0		50.7
9	52	80.4		69.5	8.4		*77.9	0.6	1.9		60.6
9	53	108.6						99.0	9.6		
9	54	86.9						71.3	15.6		
11	55	104.6						92.0	12.6		
11	56	60.0		5.2			5.2	54.0	0.8		4.2
11	57	40.1		20.5	10.3		30.8	1.0	8.3		22.6
11	58	80.5		45.8	29.6		75.4		5.1		54.4
11	59	71.7		3.4	41.8	12.8	58.0	1.1	9.2	3.4	32.9
11	60	88.9		24.7	46.7	10.7	82.1	1.9	4.9		52.1
11	61	80.5		26.3	48.0		74.3		6.2		49.8
11	62	60.1		9.8			9.8	45.2	5.1		7.8
11	63	59.1		15.6	2.8		18.4	30.5	10.2		14.2
11	64	45.5		31.4			31.4	5.6	8.5		25.1
11	65	80.1	14.0	47.7	3.6		65.3		8.8	6.0	54.3
11	66	40.1		39.0			39.0	0.6	0.5		31.2
11	67	40.0	5.6	30.2			35.8	0.1	4.1		29.8
11	68	80.1		49.1	24.1		73.2		6.9		53.7
11	69	80.1		46.8	31.6		78.4		1.7		56.4
12	70	160.0		60.0	65.7	17.9	143.6	4.3	7.0	5.1	94.6
12	71	Cancelled see Unit No. 127									
13	72	137.9	27.2	53.4	22.0		102.6		35.3		83.1
13	73	80.0	9.6	21.5	39.3		70.4		9.6		50.4
13	74	79.8	32.4	42.8	3.5		78.7		1.1		68.7
14	75	Cancelled see Unit No. 127									
14	76	80.3			41.0	16.4	57.4	19.1	3.8		31.2
14	77	159.8			43.4	64.6	108.0	43.0	5.7	3.1	51.9
14	78	80.2			59.2	19.3	78.5		1.7		43.2
14	79	80.4	8.3	44.8	23.8		76.9		3.5		58.4
13	80	102.6	40.9	29.9			70.8		18.7	13.1	64.8
14	81	80.3	37.5	18.9	22.5		78.9		1.4		66.1
14	82	80.1			67.4	8.1	75.5		4.6		43.7
14	83	80.2			58.6	19.4	78.0		2.2		42.9
14	84	120.2			29.2	55.8	85.0	32.9	0.2	2.1	39.8
14	85	80.4		37.5	35.5	6.8	79.8		0.6		54.0
14	86	80.3		10.2	52.7	9.8	72.7		7.6		43.7
14	87	80.0		53.8	16.2		70.0		10.0		52.8
14	88	79.8	17.2	49.6			66.8	3.5	9.5		56.9
15	89	Cancelled see Unit No. 123									
15	90	Cancelled see Unit No. 123									
15	91	94.1		88.6			88.6		5.5		70.9
15	92	100.4		79.3	8.2		87.5		7.5	5.4	68.4
15	93	81.2		77.4			77.4		3.8		61.9
15	94	81.3		70.2	8.6		78.8		2.5		61.3
15	95	78.2		14.7	44.6		59.3	0.3	13.5	5.1	38.5
16	96	161.8			75.9	78.8	154.7	2.7	4.4		77.1
16	97	114.8		21.6	76.5		98.1		13.8	2.9	63.2
16	98	120.4		9.1	65.7	35.6	110.4	8.8	1.2		60.9
16	99	113.4		62.3	39.0		101.3		9.6	2.5	73.2
16	100	96.6		50.0	24.4	11.4	85.8	4.7	6.1		59.2
16	101	103.1		44.3	39.2	7.4	90.9	3.9	7.7	1.2	61.9
16	102	160.6		46.1	56.8	11.9	114.8	36.8	9.0		75.7
17	103	150.8		12.0	81.9	18.8	112.7	27.1	10.5	0.5	66.3
17	104	161.1			38.8	47.2	86.0	75.1			42.2
17	105	77.2			61.3	6.8	68.1	2.5	6.6		39.5
17	106	160.6			47.8	82.7	130.5	29.5	0.6		61.8
17	107	164.4		13.4	87.5	28.6	129.5	16.1	18.8		74.7
5	108	168.5		42.2	102.9		145.1	1.0	19.1	3.3	95.5
4	109	Cancelled see Unit No. 122									
7	110	88.5	8.3	59.7	9.5		77.5		11.0		61.8
7	111	103.5		68.4	8.1		76.5	12.4	12.5	2.1	59.6
18	112	Cancelled see Unit No. 128 & 129									
18	113	Cancelled see Unit No. 128 & 129									
10	114	120.2			62.8	41.5	104.3		8.3	7.6	54.3
7	115	78.2		32.3	34.5		66.8	1.7	7.2	2.5	46.5
7	116	81.1		61.8	9.7		71.5	0.5	8.3	0.8	55.5
7	117	Cancelled see Unit No. 130									
7	118	143.9		75.2	44.4		119.6	0.7	10.3	13.3	86.8
5	119	158.0			84.3	5.8	*90.1	62.5	2.2	3.2	52.9
9	120	160.0		22.9	130.7		153.6		6.4		96.7
9	121	160.5		35.6	108.7		144.3	3.0	13.2		93.7
4	122	151.3		41.4	79.4		120.8	12.6	17.2	0.7	80.8
15	123	179.5		102.4	41.8		*144.2	1.2	22.8	11.3	107.0
7	124	128.0		51.0	69.9		*120.9	0.9	6.2		82.7
7	125	127.9		94.6	20.5		*115.1	4.8	8.0		88.0
10	126	168.4		17.0	51.9	86.8	155.7		12.5	0.2	79.5
12&14	127	201.8		2.3	80.8	45.7	128.8	25.4	28.1	19.5	68.6
18	128	161.9		95.6	52.8		148.4		13.5		108.2
18	129	195.4		56.6	72.7	7.3	136.6	41.2	13.3	4.3	91.8
7	130	159.4		90.0	61.2		151.2		8.2		108.7
TOTAL		9992.3	311.5	3131.4	3394.1	1206.2	8043.2	1027.6	743.9	177.6	

Revisions in Acreage after 10 year Development Period:

63		- 1.2				-1.2		+1.2	
64		- 0.4				- .4		+ .4	
101			-0.1		-.2	- .3	-.6	+.9	
102					-.3	- .3	-.6	+.9	
118		+0.4				+.4		-.4	
37	-	- .5	- .6			-1.1		+1.1	

*Includes area under high land contract

O.K.O
R.E.W

A. J. Davidson

8-3-62

REV. TO 7-31-68	CMc
REV. TO 7-29-66	CMc

I certify that this is Sheet 2 of 2 General Plan Sheets of the Fifth Revision of the final Farm Unit Plan for Block 78 in the Columbia Basin Project, as approved by the Secretary of the Interior.

H. T. Nelson

8-13-62

THIS SHEET NOT RECORDED

222-116-32565-3B