



Structural/Operational Changes Kittitas Reclamation District (KRD) Modifications

Basin Study Task 4.4

KRD Modifications Summary


- Lateral Piping
 - Pipe high loss laterals in Main Canal and South Branch Canal
 - Water savings applied to Manastash and/or Taneum Creek via KRD system (existing wasteways)
- Pumping to Manastash Creek
 - Pump to supply Manastash Creek diverters
 - Pump from Yakima River near Riverbottom Road to Manastash Creek at existing diversions

KRD Modifications


Lateral Piping

- Pipe quantities based on KRD Water Conservation Plan (CH2M Hill, 1999)
- Main Canal Lateral Piping
 - MC 4.9, MC 6.1, MC 7.7, MC 13.6, MC 16.9
 - Estimated water savings: 1,571 AF/yr
 - Pipe length: 21,127 LF
- South Branch Canal Lateral Piping
 - SB 9.9, SB 13.8, SB 14.3, SB 16.7, SB 17.6
 - Estimated water savings: 3,742 AF/yr
 - Pipe length: 66,272 LF

KRD Modifications Main Canal



KRD Modifications South Branch Canal




KRD Modifications

Lateral Piping

- Total estimated water savings: 5,312 AF/yr
 - 14.9 cfs average over irrigation season
- Continue to divert saved water; supply to tributaries
 - High priority – Taneum and Manastash Creeks
 - KRD currently has spillways that drain to these creeks
 - Use existing system to supplement flow in creeks

KRD Modifications

Lateral Piping – Existing Spillways to Tribes



KRD Modifications

Pumping to Manastash Creek

- 25 cfs pump on Yakima River
 - Near Riverbottom Road
 - Estimated WSE at Yakima River: 1490 ft
- Pump water to Manastash Creek diverters
 - Outlet at existing diversions
 - Estimated WSE at existing diversions: 2030 ft
- Convey water with pipeline
 - Estimated length: 31,000 LF

Note: Estimates preliminary and subject to change

Next Steps

- Determine whether Yakima River pump station stays in alternative
- Confirm quantities and develop cost estimates
- Define flow and other benefits

Disclaimer

- Results discussed today are working drafts
- Data and calculations are still being checked and results may be updated