

## Yakima River Basin Integrated Water Resource Management Plan

Table 1. Habitat Enhancement Projects					
Project	Proponent	Description	Funding	Benefits	Status (12/2013)
Gap-to-Gap Outfall Relocation	City of Yakima	Move the City of Yakima Regional Wastewater Treatment Plant outfall from the river channel to floodplain area	\$1,300,000	This project would provide the next step as part of the Gap-to-Gap Levee Setback Project which would lead to over 1,000 acres of floodplain connectivity in the critical Union Gap reach of the Yakima River. The project would increase spawning and rearing habitat for multiple species, improve water quality in a key juvenile and adult migration corridor, reduce river temperatures, reduce nutrient-related water quality problems, and increase floodplain storage of runoff. Multiple fish species would benefit from this project, including mid-Columbia ESU steelhead, mid-Columbia bull trout, spring Chinook salmon, rainbow trout, westslope cutthroat trout, Chinook salmon, sockeye salmon, coho salmon, and Pacific lamprey.	Working on final design, permitting documentation and preparing for construction starting in summer 2014.
Manastash – Consolidated Pipeline & Manastash Water Ditch Association (MWDA) Pipeline Construction	Kittitas County Conservation District	Replace MWDA earthen ditch with 4 miles of pipeline and remove three unscreened diversions on Manastash Creek	\$250,000	This project would permanently put 1.9 cfs of winter stock water into trust from November to March, increasing instream flows in the lower 5.6 miles of Manastash Creek, benefiting rearing for spring Chinook, steelhead, and coho. The removal of unscreened diversions would be the next step in removing all fish passage barriers in Manastash Creek which would open access to more than 20 miles of habitat.	Construction started in December with work to be completed by March 2014, in time for next irrigation season.
Toppenish Fan	Yakama Nation	Raise the water table in an area of Toppenish Creek southwest of White Swan by diverting winter flows from Toppenish Creek through existing canals for aquifer recharge	\$612,284	This project would reconnect tributary channels to the Toppenish Creek alluvial fan, increasing the alluvial water table and riparian vegetation along the alluvial fan. The project would also increase summer flows and reduce stream temperatures in Simcoe and Toppenish Creeks, improving habitat for steelhead rearing and migration.	In contracting process with work planned for summer 2014.
Bateman Island Causeway Modification Conceptual	Mid-Columbia Fisheries Enhancement Group	Develop alternatives to allow flow along the south side of Bateman Island near the confluence of the Yakima	\$100,000	This project would identify alternatives to breach a short earthen causeway that could improve salmonid migratory conditions by modifying an existing temperature barrier that can delay adult migration, and by shortening the distance	Project underway with findings available in 2014.

## Yakima River Basin Integrated Water Resource Management Plan

Table 1. Habitat Enhancement Projects					
Project	Proponent	Description	Funding	Benefits	Status (12/2013)
Design		and Columbia Rivers		traveled by outmigrating smolts and returning adults. When completed, the project is expected to improve water temperature and water quality and benefit steelhead, spring Chinook, summer Chinook, fall Chinook, coho, and sockeye.	
Bull Trout Task Force Habitat Improvements	Mid-Columbia Fisheries Enhancement Group	Address conservation needs for bull trout by implementing actions identified in recent Bull Trout Plans	\$55,000	This project would assist in various projects throughout the Yakima basin focused on the needs of bull trout, one of the ESA-listed fish species in the Yakima basin. Benefits include improving fish passage by removing recreation dams and providing temporary passage improvements during lower flow conditions, and improving understanding of bull trout density and migration timing.	Work underway with contract amendment in progress.
Gold Creek Habitat Assessment and Conceptual Design	Kittitas Conservation Trust	Investigate Gold Creek dewatering causes and associated impacts and produce conceptual designs for bull trout restoration	\$50,000	This project would identify causes of late summer and early fall dewatering in Gold Creek, which is a major bull trout limiting factor for the species in this part of the basin. Once causes are identified, conceptual designs would allow for improvement of bull trout spawning, egg incubation, and juvenile rearing in Gold Creek.	Work underway with preliminary results being evaluated, and additional analysis scheduled for 2014, and findings report by end of 2014.
Reed Diversion Dam Removal Design	Kittitas County Conservation District	Design a project that would remove the fish passage barrier at Reed Diversion on Manastash Creek	\$69,000	This project would be the first step in removing the last passage barrier on Manastash Creek, which would allow access to more than 20 miles of habitat in Manastash Creek, improving habitat for fish species including steelhead.	Select consultant early 2014, with design to be completed by fall 2014.
<b>Total</b>			<b>\$2,436,284</b>		

## Yakima River Basin Integrated Water Resource Management Plan

Table 2. Agricultural Conservation Projects					
Project	Proponent	Description	Funding	Benefits	Status (12/2013)
Kennewick Irrigation District (KID) Division IV Lining	Kennewick Irrigation District	Install 1.1 miles of geomembrane canal lining from S. Olympia Street to Olympia Siphon in the City of Kennewick	\$606,624	This project would reduce seepage from the KID. The project would allow for more reliable irrigation delivery and increase public safety by decreasing the likelihood of canal failure.	In contracting process. Work scheduled for 2013/2014 and 2014/2015 irrigation offseason.
Wapato Irrigation Project (WIP) Piping Lateral 4-414C	Yakama Nation	Replace earthen Lateral 4-414C with 1.25 miles of pipe along S. Wapato Road in the Wapato Unit	\$650,000	This project would reduce seepage from the WIP and reduce operational spill to Marion Drain, resulting in 2.24 cfs (840 af/yr) of water savings for improved water supply reliability for WIP water users. Additionally, the project would improve water quality by reducing sediment and nutrient load, and improve water management by installing measurement at pipeline turnouts.	In contracting process. Work scheduled for 2014/2015 irrigation offseason.
Wapato Irrigation Project Piping Satus East Lateral E73	Yakama Nation	Replace earthen Satus East Lateral E73 with 1.5 miles of pipe near Schuster Rd in the Satus Unit	\$300,000	This project would reduce seepage from the WIP and reduce operational spill to Toppenish Creek. 2.5 cfs (890 af/yr) of water would be saved for improved water supply reliability for WIP water users. Additionally the project would improve water quality by reducing sediment and nutrient load, and improve water management by installing measurement at pipeline turnouts.	In contracting process. Work scheduled for 2014/2015 irrigation offseason.
Manastash Creek, Anderson Diversion Irrigation Water Acquisition	Kittitas County Conservation District	Irrigation water rights off Anderson Diversion would be acquired by Trout Unlimited to provide instream flow in Manastash Creek and remove the unscreened Anderson diversion	\$356,000	This project would permanently put 2.54 cfs (894 af/yr) of water into trust, increasing instream flow from April to October in the lower 5.6 miles of Manastash Creek, a high-priority fish habitat reach. Additionally, an unscreened diversion and seasonal fish passage barrier would be removed. These elements would benefit migration and rearing for steelhead and coho as well as rearing for spring Chinook.	Project underway. Discussions are in process with the water right holder.

## Yakima River Basin Integrated Water Resource Management Plan

<b>Table 2. Agricultural Conservation Projects</b>					
<b>Project</b>	<b>Proponent</b>	<b>Description</b>	<b>Funding</b>	<b>Benefits</b>	<b>Status (12/2013)</b>
Manastash Creek Sprinkler Conversions	Kittitas County Conservation District	Convert 154 acres of rill irrigation to sprinkler irrigation along Manastash Creek	\$200,000	This project would permanently put 2 cfs (250 af/yr) of water into trust, increasing instream flow from April to October by 150 af/yr from stream mile 5.6 to 1.4 of Manastash Creek and by 250 af/yr in the lower 1.4 miles of Manastash Creek, a high-priority fish habitat area. This conversion and corresponding instream flow increase would benefit migration and rearing for steelhead and coho as well as rearing for spring Chinook.	Design and permitting work underway. Sprinkler installation planned early spring before the 2014 irrigation season. Trust water right to be determined during the design process.
Yakima-Tieton Irrigation District (YTID) Feasibility Study – Tieton to Ahtanum Exchange	Yakima-Tieton Irrigation District	Study feasibility of an enlarged YTID Main Canal and associated pipeline to carry water to the Ahtanum basin in a water exchange program to enhance instream flows for fish and supply water for irrigation	\$37,500	This project would study the potential of carrying water from the Tieton basin to the Ahtanum basin. Potential benefits of the completed project include increased instream flow in Ahtanum Creek, providing fish benefits to steelhead, bull trout, salmon, and resident trout. It also has the potential of removing stream diversions through upgraded and efficient delivery systems that would enhance habitat in the Ahtanum basin.	Project underway with findings available in 2014.
Manastash – Consolidated Pipeline & MWDA Pipeline Construction	Kittitas County Conservation District	Replace MWDA earthen ditch with 4 miles of pipeline and remove three unscreened diversions on Manastash Creek	\$250,000	This project would permanently put 1.9 cfs of winter stock water into trust from November to March, increasing instream flows in the lower 5.6 miles of Manastash Creek, benefiting rearing for spring Chinook, steelhead, and coho. The removal of unscreened diversions would be the next step in removing all fish passage barriers in Manastash Creek, which would lead to access to more than 20 miles of habitat.	Construction started in December and planned to be completed in March 2014, in time for next irrigation season.
<b>Total</b>			<b>\$2,400,124</b>		