INFORMATIONAL ROUTING

HYDRAULICS BRANCH OFFICIAL FILE COPY

Form DFC-11 (12-61) Bureau of Reclamation

~

1

WHEN BORPOWED RETURN PROMPTLY

Hamp randun

Gaief, Sydraulic Structures Srouch

Chief, Hydraulies Branch 2/38/74

R. A. Dodge

Polymary 27, 1974

Summary of data obtained during the Pobruary 19th demonstration of a mileronics, inc. water level measuring system (your memo dated 12-26-73)

John Bould John Brown of Mitronies, Inc. brought a water level measuring system
Tech Dates to the Hydraulics laboratory for demonstration and testing. Hay Thibault,
INC. Hydraulic Structures Branch, and Rudy Hogg, Electrical Branch, sociated
Denver, Co. in taking the data that are summarised in this memorandum.

The operation was briefly observed by several numbers of the Nothanical Branch. The system included an ultrasonic transducer, a transmitterreceiver (transcaiver), and electronics to provide a 4- to 20-millianpere output with zero and span (measuring range adjustments). The transceiver cands a pulse to the transducer which in turn sends an ultrasonic sound wave down to the water surface. The mature echo from the water surface is received by the transducer which sends the echo pulse to transceiver. The transceiver calculates the sound pulse travel time to the water surface and back to transducer. The transceiver then produces an analog output that is proportional to water surface elevation.

The ultrasonic transducer was mounted at the top end of a 20-foot-long 4-inch-dismeter thin-walled aluminum tube (enclosure, right margin). The tube was provided with a manounter and white face tape of 0.01-foot graduations to measure the water level. The water level was raised by filling the tube from the city water supply and lowered by a valve drain. A digital multimeter measured the milliampere output of the system.

The output of the water level system was adjusted by Brown to read 4 milliamperes with 16 feet of water in the tubing and 20 milliamperes with 1 feet of water. The full scale calibration for 15 feet of water should produce an output ratio of 0.936 foot per milliampere.

During the demonstration covering a period of about 4 hours, 29 data points of water surface elevation versus milliampere output were obtained (enclosure, left mids). The upward pointed triengles and the squares are data points in upward moving water surface sequences, read during short pauses between water surface changes.

The downward pointed triengles and hexagons were obtained in downward sequences.

Schwith 2/28

cobo 3-1 A least squares fit using the 29 data points resulted in a slope of 0.943 foot per williampers agreeing closely with the calibration slope. Reading and evaluating the deviations of data points from the graph of water surface versus milliampers output are difficult. The least squares fit equation was used to calculate deviations from measured values. The calculated deviations are assmarized in the small plot showing percent data versus deviation (enclosure, top middle). This curve indicates that 70 percent of the data obtained during the demonstration was within a \pm 0.15 foot veter band or \pm 1 percent of full scale. All the data were within \pm 0.30 foot or \pm 2 percent full scale.

For a demonstration period of about 4 hours no conclusions can be made concerning long term stability or drift characteristics of the water level measuring system.

For water surfaces below the dresser coupling shows on the test arrangement schematic, the system picked up extraneous echos. The company representative thought the echos came from miselinement of the tube ends or the tubing at the coupling. However, the data plotted in the curve below the 4.6-foot water level show that the system was able to sufficiently discriminate actual water level. After the demonstration the alimement of the pipe was measured at the dresser coupling at two places 90° spart. The total angles were the same in both directions, i.e., about 1-3/4°. It was not determined during the tests how much tube misslinement, tube joint offset, or wall roughmess can be tolerated by the water level measuring system.

R. a. Dodge

Copy to: 224

224 (Thibault)

240

243


252 (Durham)

430 (Water Systems Automation Team)

1530

1532

RADodge:baw-s



(O/P 4-65) 5010-10

OPTIONAL FORM NO. 10 MAY 1962 EDITION GSA GEN. REG. NO. 27

UNITED STATES GOVERNMENT

Memorandum

Memorandum

TO : Chief, Hydraulics Branch

Denver, Colorado DATE: December 26, 1973

THROUGH:

Chief, Division of Design 1/9/14
Director of Design and Construction

Chief, Division of General Research

FROM TO

Chief, Hydraulic Structures Branch

SUBJECT: Testing of Ultrasonic water level measuring device (UWLMD)

Two UWLMD's are now being specified for use on each of four large concrete water tanks as a part of the telemetering equipment on the Altus-Snyder Aqueducts, Mountain Park Project. We believe the ultrasonic device has several advantages over the conventional float system used in the past. The Metritape water level measuring device, originally specified for the Altus-Snyder tanks, did not perform as described in advertising literature as determined by your recent tests. Therefore, the Metritape will not be used on that project.

The second UWLMD is normally required in a regulating tank for a backup in case the first device malfunctions and for emergency high and low level alarms. We are interested in possible signal interference between the two devices when operated simultaneously.

To provide more assurance that UWLMD's will perform as advertised, you are hereby requested to test two devices in a manner similar to that used for recent Metritape tests. In cooperation with Rudy Hogg, Code 243, Extension 3382, please investigate the possiblity of obtaining two devices on loan from one of the following companies:

Sonargage - C. W. Stevens, Inc. Local Representative: Rod Street

> Goble-Sampson Associates Telephone 757-4971

Milltronics, Inc.

Local Representative: Glen Selch

B-F Sales Engineering Company

Telephone 893-1124

Funds for 10 man-days of test work are available from the Water Systems Automation Team, Job No. 102-0065-8802-012-12-0-0. If any additional time is needed it may be available from the Altus-Snyder Aqueduct, Job No. 210-0981-5527-210-04-0-0. Results of the tests are desired by



February 1, 1974, to verify use of the UWLMD's on Altus-Snyder Aqueduct structures. Specifications for these aqueducts are to be published in January 1974. A memorandum summary of test results will be adequate for Code 210 purposes.

If you have additional questions, please call R. E. Thibault, Code 224, Extension 3586.

RW. Book

Copy to: 220

224

225

240

241

243

352

430 Calhoun (2)

1500